

CLARIFICATIONS-1 Dt. Oct 10, 2011

The following queries were raised by some of the bidders during the pre-bid meeting on Oct 04, 2011. The clarifications provided are listed below:

SI No	Queries raised	Clarifications given
1	Unloaded location of components like LP rotor, HP turbine, Generator rotor etc at site is to be clarified for estimating the requirement of 100 T crane and high capacity trailer.	BHEL informed that the components are unloaded as given in the tender specification.
2	Clause 1.10.13, 1.10.15, 1.15.3 and 1.2. 1.10 of Technical Conditions of contract calls for IBR approvals. Please clarify which area needs IBR approvals.	The clauses referred for IBR requirements are generally indicated for applicable area only, However in this contract NO IBR requirements envisaged.
3	The following are required for cost estimation purpose:	
	3.1 The diameter, thickness, number of joints, quantum of NDE for Feed water storage tank shell	Feed water storage tank generally supplied in three pieces with dia 2600 mm, thickness 18mm and NDE requirement will be 100%
	3.2 The diameter of the condenser titanium tubes for consumable estimation.	32mm
	3.3 Total quantum of radiography to be done at site	Around 700 to 750 shots
	3.4 Total quantity of grouting cements.	Maximum will be around 22MT (without wastage)

For and on behalf of
BHARAT HEAVY ELECTRICALS LIMITED


/ ADDL GENERAL MANAGER / CONTRACTS