



# **PART- B**

## **List of Exhibits**

<b>1.0</b>	<b>Available land Drawing</b>
<b>2.0</b>	<b>Schematic drawing of Power evacuation system</b>
<b>3.0</b>	<b>Topographical Survey of the proposed area</b>
<b>a)</b>	<b>Topographical Survey of the proposed solar plant at PTS Stage-2</b>
<b>b)</b>	<b>Topographical Survey of the proposed solar plant at Patharmuda</b>
<b>4.0</b>	<b>Geotechnical studies of the proposed area</b>
<b>5.0</b>	<b>List of mandatory spares</b>
<b>6.0</b>	<b>Indicative Single Line Diagram</b>
<b>7.0</b>	<b>Indicative PV array layout</b>
<b>8.0</b>	<b>Site photos</b>
<b>9.0</b>	<b>Data sheet of PV module</b>
<b>10.0</b>	<b>FQP for Civil Works</b>

# Exhibit 1



NOTE:-  
 \*AREA marked ⊙-AVAILABLE LAND AREA(PTS)= 36.0ACRES  
 \*AREA marked ⊗-AVAILABLE LAND AREA (Pathermunda)=9.20 ACRES  
 \*Actual Land Details for PTS & Pathermunda are enclosed as Annexure A & B.

- NOTES:
- 01. ALL DIMENSIONS AND SPACES TO BE IN METRES.
  - 02. ALL DIMENSIONS AND LEVELS ARE IN METRES.
  - 03. BOUNDARY
  - 04. FENCING
  - 05. BOUNDARY IN ALL EXISTING
  - 06. RAILWAY LINE
  - 07. FORMATION LEVEL
  - 08. ANTI-CORROSION PIPE
  - 09. RIVER
  - 10. BRIDGE
  - 11. MAINLINE OF WATER PIPE LINE
  - 12. FIRE HYDRANT SYSTEM
  - 13. FIRE HYDRANT LANDING VALVES
  - 14. EXTENSION IS SHOWN
  - 15. LEVEL CROSSING-GATE




		पद्म श्री श्री श्री कृष्णमूर्ति TÁLCHER SUPER THERMAL POWER PROJECT P.O. DEBPSHINHA, KANINA, DIST-ANGUL, ORISSA. PH-751047	
AVAILABLE LAND DETAILS FOR FOR SOLAR PLANT AT TSTPS			
DATE	SCALE	DESIGN	REVISED
NO.	1:5000	9500-FES-C-2011-139	

CABLE TRESTLE WITH SEPARATE CABLE TRAYS IN THE SCOPE OF BIDDER  
 CABLE TRESTLE WITH SEPARATE CABLE TRAYS



### Exhibit 2




LEGEND	
DOUBLE POLE STRUCTURE (EXISTING)	
FOUR POLE STRUCTURE (EXISTING)	
O/H AL DOG CONDUCTOR( EXISTING- NOT TO BE REPLACED)	
1C X 300 SQ.MM - 4 NOS CABLE TO BE LAID	
CABLE TO BE LAID BY 1C X 300 SQ.MM - 7 NOS CABLE	
UNDERGROUND CABLE 1C X 300 SQ.MM( EXISTING - NOT TO BE REPLACED)	
O/H AL DOG CONDUCTOR (TO BE LAID BY NTPC)	
BREAKER	

**SCHEMATIC DIAGRAM OF PROPOSED POWER EVACUATION SCHEME FOR SOLAR PV PROJECT AT NTPC TALCHER KANIHA**


This document is the property of NTPC Limited. No part of this document will be reproduced by any means without the written permission.

# Exhibit 3 (a)



SWITCHYARD AREA

EXHIBIT - 3 (b)



**TENTATIVE AREA AVAILABLE FOR SOLAR PLANT AT PATHARMUNDA**

# Exhibit-4

**Due to huge file size, contractor is advised to collect the soft copy of the Geo Technical Investigation report of both the sites (8 MW and 2 MW) from BHEL EDN Bangalore**

**EXHIBIT - 5**

**LIST OF MANDATORY SPARES FOR 10 MWP TALCHER SOLAR PV POWER PLANT**

<b>SI No:</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit Price</b>
1	2	3	4
<b>Mandatory Spares</b>			
1	Inverters/ Power Conditioning Unit (PCU)	10% of Total Population (Minimum one no.)	
2	Combiner Box with String Monitoring Unit	2% of Total Population for each type (Minimum one no.)	
3	Control Card for PCU	5% of Total Population for each type (Minimum one no.)	
4	Surge Protection Device/ MOV	5% of Total Population (Minimum one no.)	
5	Fuses of each type for ac and dc systems	10% of Total Population (Minimum one no.)	
6	LV Bushing with metal parts and gaskets	1 no.	
7	Set of valves for Transformer	1 no.	
8	Pressure Relief Device	1 no.	
9	HV Bushing with Metal parts and Gaskets	1 no.	
10	WTI with contacts of Transformer	1 no.	
11	OTI with contacts of Transformer	1 no.	
12	Buchholz relay complete of transformer	1 no.	
13	Set of gasket of each type of Transformer	1 no.	
14	Magnetic Oil Guage (MOG) of Transformer	1 no.	
15	HT Circuit Breaker	1 no.	
16	LT Circuit Breaker	5% of Total Population for each type (Minimum one no.)	
17	Earthing Trolley	1 no.	
18	Bus Potential Transformer	1 no.	
19	Current Transformer for HT & LT System	1 no. of each type	

COPYRIGHT AND CONFIDENTIAL  
THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LTD. IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY.

REF. DRG. No.


SIGN. & DATE

INVENTORY No.


# Exhibit - 6 (a)

This drawing is indicative and preliminary only

- Notes:**
1. Plant Layout Design:
    - a) 12X630 KWp and 1X630 KWp PV array
    - b) 13 Nos of 630 KWp PCUs (transformer less)
    - c) Six Nos of CSS with 1.6 MW Capacity and One No. of CSS with 0.63\*\* MW Capacity
    - d) SPV Plant HT Panel comprises of 8 Incoming feeders with LBS. Out of 8, seven are from seven Nos of CSS and one for Aux. Transformer. Two outgoing VCB panels will be fed to 11kV Switchgear cubicle. Additionally Bus PT is also there.
    - e) 11 kV Switchgear cubicle comprises of 9 panels: 2 Incomer panels from SPV Plant HT Panel, 2 Outgoing panels to Colony feeders, 4 panels for spare and one panel for coupler. Additionally Bus PT is also there.
  2. Metering & protection provided:
    - a) at CSS level
    - b) at SPV Plant HT Panel level
    - c) at 11kV Proposed new switchgear cubicle
  3. ACB can be part of PCU(inverter).
  4. This scheme depends on type of PCU
  5. SCADA output from each inverter room will be taken to SCADA room.
  6. Protection in CSS:
    - a) LT switchgear: over current, short circuit and earth fault
    - b) Transformer: Oil Temp., Winding Temp., and Pressure Relief Device
    - c) HT switchgear: Over current and Earth fault



\*\* Transformer capacity shall be of standard size and corresponding type test reports shall be available.



PROJECT NAME : 8.23 MWp Solar Project  
CUSTOMER NAME : NTPC Talcher

BHARAT HEAVY ELECTRICALS LIMITED.  
ELECTRONICS DIVISION, BANGALORE

REV.	DATE	ALTERED	REV.	DATE	ALTERED	NAME	SIGN	DATE
		CHECKED			CHECKED			
		APPROVED			APPROVED			
						DRAWN		
						CHECKED		
						APPROVED		

	DEPT. SC&PV	CODE 439	TITLE:  SINGLE LINE DIAGRAM OF 8.23 MWp SPV PLANT	No. OF SHEETS	01
				SHEET No.	01
WBS. No.		DRG. No.		REV	

1

2

3

4

WBS. No.

DRG. No.

REV

COPYRIGHT AND CONFIDENTIAL  
THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LTD. IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY.

REF. DRG. No.



SIGN. & DATE

INVENTORY No.

### Exhibit - 6 (b)

This drawing is indicative and preliminary only

- Notes:**
- Plant Layout Design:
    - 2X630 KWp and 1X630 KWp PV array
    - 3 Nos of 630 KWp PCUs (transformer less)
    - One CSS with 1.6 MW Capacity and other CSS with 0.63\*\* MW Capacity
    - HT Panel comprises of 9 panels: 2 Incomer panels from PV Plant, 2 Outgoing panels to Ash pond transformer, 2 Panels for misc. switchgear, 2 panels for spare and one panel for coupler. Addition to this Bus PT also is there.
  - Metering & protection provided:
    - at CSS level
    - at HT Panel (proposed new switchgear) level
  - ACB can be part of PCU(inverter).
  - This scheme depends on type of PCU
  - SCADA output from each inverter room will be taken to SCADA room.
  - Protection in CSS:
    - LT switchgear: over current, short circuit and earth fault
    - Transformer: Oil Temp., Winding Temp., and Pressure Relief Device
    - HT switchgear: Over current and Earth fault



PROJECT NAME : 1.90 MWp Solar Project  
CUSTOMER NAME : NTPC Talcher


REV.	DATE	ALTERED	REV.	DATE	ALTERED	NAME	SIGN	DATE
		CHECKED			CHECKED			
		APPROVED			APPROVED			
						DRAWN		
						CHECKED		
						APPROVED		

**BHARAT HEAVY ELECTRICALS LIMITED.**  
ELECTRONICS DIVISION, BANGALORE

TITLE: **SINGLE LINE DIAGRAM OF 1.90 MWp SPV PLANT**

DEPT. SC&PV	CODE 439	No. OF SHEETS	01
		SHEET No.	01
WBS. No.		DRG. No.	REV





THIS DRAWING IS  
PRELIMINARY AND  
TENTATIVE





### SWITCHYARD AREA


## EXHIBIT - 7 (b)

### ARRAY DETAILS

PV ARRAY CAPACITY	1.9 MWp
Total no.of PV Modules (240Wp)	7920 nos
PV Modules in series string	24 nos
Total No. of strings	330 nos
Series strings/630kWp	110 nos
No. of Inverters (630 kW)	3 nos
String Monitoring Units	12 nos (16 i/p-1 o/p)

### LEGEND

	2x12-240W STRUCTURE - 330 Nos.
	Centralised Main Control System 150 sq.mtrs (RCC Type)
	Compact Sub Station 3.83x 2.33 x2.41(h) mtrs -1 no
	Compact Sub Station 3.2 x 2 x2.41(h) mtrs - 1 no.





VILLAGE PATHARMUNDA

VILLAGE  
PATHARMUNDA

All dimensions are in metres

PROJECT: 1.9 MWp SPV POWER PLANT  
CUSTOMER: NTPC, TALCHER

	BHARAT HEAVY ELECTRICALS LIMITED		DRN	NAME	SIGN.	DATE	No. OF VAR
	ELECTRONICS DIVISION, BANGALORE		CKD	ASN		Mar'13	
			APPD	MS			
DEPT. SCPV	FOR UNSPECIFIED-TOLERANCES		SCALE	WEIGHT(Kg)	REF. TO ASSY. DRG.	ITEM NO.	No. OF ITEM
CODE 439	REFER ED 0230499		NTS				
TITLE						DRAWING NO.	
2MWp PV ARRAY LAYOUT FOR NTPC TALCHER						3-679-05-00xxx	
SHEET NO. 01				NO. OF SHEETS 01			

COPYRIGHT AND CONFIDENTIAL  
The information on this document is the property of Bharat Heavy Electricals Limited. It must not be used directly or indirectly in anyway detrimental to the interest of the Company

REF. DRG.NO.

SIGN & DATE

INVENTORY NO.

REV.	DATE	ALTERED	REV.	DATE	ALTERED	REV.	DATE	ALTERED	REV.	DATE	ALTERED	REV.	DATE	ALTERED
		CHECKED			CHECKED			CHECKED			CHECKED			CHECKED
		APPROVED			APPROVED			APPROVED			APPROVED			APPROVED



8 MW SITE



2 MW SITE





PRODUCT STANDARD  
ELECTRONICS DIVISION

CD-4-4001-116

REV. 00

A4-10

PAGE 01 OF 01

TECHNICAL SPECIFICATION FOR PV MODULE L20220 (240 WATTS)

- 1. PV MODULE TYPE NO. : L20220
- 2. CONFIGURATION : SINGLE GLASS LAMINATED TYPE WITH 60 NOS. OF 156-mm MONO CRYSTALLINE SILICON SOLAR CELLS (10\*6) IN SERIES CONFIGURATION.
- 3. OVERALL SIZE : 1656 (±3) \* 996 (±2) \* 50 (±1) mm
- 4. WEIGHT : 20 Kg. (Typ.)
- 5. PV MODULE FRAME MATERIAL : ANODISED ALUMINIUM
- 6. JUNCTION BOX : IP65 GRADE JUNCTION BOX WITH CABLES AND CONNECTORS
- 7. RFID Tag : RFID Tag containing Module data
- 8. TYPICAL ELECTRICAL CHARACTERISTICS:
  - 8.1 OPEN CIRCUIT VOLTAGE (Voc) : 36.0 V
  - 8.2 SHORT CIRCUIT CURRENT (Isc) : 8.5 A
  - 8.3 VOLTAGE AT PEAK POWER POINT (Vmp) : 29 V
  - 8.4 CURRENT AT PEAK POWER POINT (Imp) : 8.28 A
  - 8.5 PEAK POWER OUTPUT (Pmax.) : ≥ 240 Wp
  - 8.6 MODULE EFFICIENCY : 14.6 %
  - 8.7 CELL EFFICIENCY (@ Module level) : 16.7 %
  - 8.8 FILL FACTOR : ≥ 0.70

NOTE :

- 1. Electrical specifications mentioned above are at Standard Test Conditions of 1000 W/sq. m solar insolation (AM 1.5) and at 25 deg C temperature.
- 2. Measurement repeatability of peak power output: ± 3 %

REFER MODULE DRAWING NO. : 3-679-02-00366

Rev (00)

APPROVED BY :

SR

PREPARED

PJ

ISSUED

Engg.

DATE

25.04.2013

COPY RIGHT AND CONFIDENTIAL

The information on this document is the property of Bharat Heavy Electrical Limited. It must not be used directly or indirectly in any way detrimental to the interest of the company.

# **EXHIBIT - 10**

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN				ANNEXURE- I				
		ITEM : CIVIL WORK SUB-SYSTEM : GEOTECH INVI, FOUNDATIONS, EXCAVATION & FILL, SITE LEVELLING, CONCRETE, ROAD, BUILDING ETC.	QP NO. : REV. NO. : DATE : PAGE :	1 0	PROJECT: PACKAGE: CONTRACT NO. MAIN CONTRACTOR	Acceptance Norms		Format of Record		Remarks
SI. No	Activity and operation	Characteristics / instruments	Class of check	Type of Check	Quantum Of check	Reference Document	9	D*	10	
1	2	3	4	5	6	7	8			
<b>1 GENERAL REQUIREMENTS</b>										
A	All bought out items to be procured from the approved Contractor and on approval of Quality plans by NTPC as	-	B	Verification of TC and/or Testing	100%	NTPC Tech. Spec. /BOQ	SR/LB	√	The TC submitted should bear proper identification or correlation with the batch of material supplied and same shall be brought out in the challan/ consignment note .	
B	Submission of list of Bought out items and their Contractors for each of the bought out item identified for approval within the period agreed in LOA.	-	A	Physical	One time	NTPC Tech. Spec. /BOQ	SR/LB		To be submitted to CQA for approval with a copy to site .	
<b>2 EXCAVATION AND FILLING IN FOUNDATION WORKS</b>										
<b>Excavations-</b>										
2.1		Nature, type of soil/rock before and during excavations	As agreed / required	B	Visual	Random in eah shift	Tech Specs and Const. Drawings	SR		
2.2		Initial ground level before start of excavations	As agreed / required	B	Measurement	100%	Tech Specs and Const. Drawings	SR	√	
2.3		Final shape and Dimensions of excavations.	As agreed / required	B	Measurement	100%	Tech Specs and Const. Drawings	SR		
2.4		Final excavation lelvels	As agreed / required	B	Measument	100%	Tech Specs and Const. Drawings	SR	√	
2.5		Side slope of final excavation	As agreed / required	B	Measurement	Random in eah shift	Tech Specs and Const. Drawings	SR		
2.6		Excavation in Hard Rock- If required								
i		Receipt, Storage, accountability of Explosive	As agreed / required	B	Physical	Random in each week	Indian Explosive Act 1940/all statutory norms, Tech Specs and Const. Drawings	SR	√	NTPC approved specialist blasting agency such as CMRI, NIRM shall be deployed at site for trial blasts, design blasts, blast vibration monitoring etc. Seismographs shall be deployed at site for monitoring of blast operation vibrations.
ii		Execution of Blasting Operation	As agreed / required	B	Physical	Random in eah shift	IS:4081, Tech Specs and Const. Drawings	SR	√	
iii		Submission of Blasting report to EIC	As agreed / required	C	Physical	Each blast	Tech Specs and Const. Drawings		√	
2.7		Excavation in Hard Rock (Blasting Prohibited)	As agreed / required	B	Physical	100%	As per approved drawing/ scheme, Tech Specs and Const. Drawings	SR	√	
<b>Fill/ Backfill -</b>										
<b>2.8 A Suitability of borrow fill material - If earth is brought from area within the NTPC acquired area</b>										
		Suitability	As agreed / required	B	Visual	Randon in each shift	As per technical specifications			
<b>2.8 B Suitability of borrow fill material- Applicable in case the earth is brought from an area, out of the NTPC aquired land area</b>										
i		Grain size analysis	Set of Seives, Hydrometer etc.	B	Physical	Once per each type of source or change of source	IS:2720 (Pt.IV), Tech Specs and Const. Drawings	SR/TR	√	
ii		Liquid & plastic limit	Mechanical liquid limit device, grooving tools, Evaporating Disc, Spatula, Palette knives, Balance oven containers, etc.	B	Physical	Once per each type of source or change of source	IS:2720 (Pt.IV) , Tech Specs and Const. Drawings	SR/TR	√	
iii		Shrinkage limit	-do-	B	Physical	Once per each type of source or change of source	IS:2720 (Pt.IV), Tech Specs and Const. Drawings	SR/TR	√	
iv		Free Swell Index	Measuring cylinders, etc.	B	Physical	Once per each type of source or change of source	IS:2720 (Pt.XI), Tech Specs and Const. Drawings	SR/TR	√	
v		<b>Chemical Analysis</b>								

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN				ANNEXURE- I				
		ITEM : CIVIL WORK SUB-SYSTEM : GEOTECH INVI, FOUNDATIONS, EXCAVATION & FILL, SITE LEVELLING, CONCRETE, ROAD, BUILDING ETC.	QP NO. : REV. NO. : DATE : PAGE :	1 0	PROJECT: PACKAGE: CONTRACT NO. MAIN CONTRACTOR	Reference Document	Acceptance Norms	Format of Record	Remarks	
SI. No	Activity and operation	Characteristics / instruments	Class of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D* 10	
a		Organic Matter	Oven chemical balance, volumetric flasks, burettes, pipettes, conical flasks set of sieves, measuring cylinders etc.	B	Physical	Once per each type of source or change of source	IS:2720 Pt.XXII, Tech Specs and Const. Drawings	SR/TR	√	
b		Calcium carbonate	Reagents and indicators, Burette, flask s, funnels etc.	B	Physical	Once per each type of source or change of source	Part XXIII of IS-2720, Tech Specs and Const. Drawings	SR/TR	√	
c		pH value	As agreed / required	B	Physical	Once per each type of source or change of source	Part XXVI of IS-2720, Tech Specs and Const. Drawings	SR/TR	√	
d		Total soluble sulphate	As agreed / required	B	Physical	Once per each type of source or change of source	Part XXVII of IS-2720, Tech Specs and Const. Drawings	SR/TR	√	
2.9	Standard proctor Test	Optimum moisture content and max. dry density before fill	As per IS: 2720 Proctor needle apparatus etc.	A	Physical	Once per each type of source or change of source	IS 2720 (Pt.VII), Tech Specs and Const. Drawings	SR/TR	√	
2.10	Moisture content	Moisture content of fill before compaction	As per IS: 2720, balance, oven etc.	A	Physical	Once per each type of source or change of source	IS 2720 (Pt.II), Tech Specs and Const. Drawings	SR/TR	√	
2.11	Degree Of Compaction Of Fill / Backfill									
i		Dry density by core cutter method  ---- OR----  Dry density in place by sand displacement method	As per IS: 2720/compaction test (core cutter), balance etc.	A	Physical	i) For foundation fill/ backfill one for every 10 foundations for each compacted layer. ii) For area filling, one every 1000 SQM area for each compacted layer.	IS 2720 (Pt. XXIX), Tech Specs and Const. Drawings	SR/TR	√	
ii		Relative density (Density Index)	As per IS: 2720, balance oven etc.	A	Physical	----do---- (i) & (ii) above	IS 2720 (Pt. XIV), Tech Specs and Const. Drawings	SR/TR	√	
iii		Dry Density by proctor needle penetration	As per IS-2720, proctor needle apparatus etc.	B	Physical	Random checks to be carried out for each compacted layer	Tech Specs and Const. Drawings	SR/TR	√	
3.0	MATERIALS									
		Expert opinion regarding suitability of construction materials shall be taken from Specialist Institute (Identified during pre award)								
3.1	CEMENT									
		Retesting of cement	as per IS:4031	A	Testing	At Random	As per relevant IS Codes	Test Report	√	Each consignment of cement shall be duly correlated with manufactureres TC, in case the cement is supplied by the contractor one sample from each lot shall be tested for setting time and compressive strength . Acceptance norms shall be as per relevant IS. If cement is stored more than 60 days in godown of contractor same shall be retested for comp. Strength & setting time.
3.2	Coarse Aggregate	Moisture content	as per IS:2386	B	Physical	Once for each stack of 100 Cu.M. or part	IS : 456 : 383/Tech Spec	IS SR/LB	√	during monsoon when this has to be done every day before start of concreting
ii		Specific gravity, water absorption	IS:2386	A	Physical	Once for each source & for every change of source	IS: 2386 Part-III, IS:456, IS:383/Tech Spec	SR/LB/ Test Report	√	
iii		Sieve analysis, flakiness index, elongation index,	IS:2386	B	Physical	One per 100 cum., or part thereof	IS: 2386 Part-I, IS:383/Tech Spec	SR/LB	√	
iv		Deleterious materials (coal & lignite, clay lumps, material finer than 75 microm sieve, soft fragment, shale)	IS:2386	A	Physical	Once per source/ on every change of source	IS: 2386 Part-II, IS:383/Tech Spec	SR/LB/ Test Report	√	

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN					ANNEXURE- I			
		ITEM : CIVIL WORK SUB-SYSTEM : GEOTECH INVI, FOUNDATIONS, EXCAVATION & FILL, SITE LEVELLING, CONCRETE, ROAD, BUILDING ETC.	QP NO. : REV. NO. : DATE : PAGE :	1 0	PROJECT: PACKAGE: CONTRACT NO. MAIN CONTRACTOR	Reference Document	Acceptance Norms	Format of Record	Remarks	
Sl. No	Activity and operation	Characteristics / instruments	Class of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D* 10	
v		Soundness	IS:2386	A	Physical	-do-	IS: 2386 Part-V, IS:383	SR/LB/ Test Report	√	
vi		Crushing value abrasion value and impact value	IS:2386	A	Physical	-do-	IS:383, IS-2386 Part IV/Tech Spec	SR/LB/ Test Report	√	
<b>3.3 Fine Aggregate</b>										
i		Moisture content, water absorption	balance , oven etc	B	Physical	To be done every day before start of work	IS: 2386 Part-III IS:383	SR/LB/TR	√	
ii		Deleterious materials (coal & lignite, clay lumps, material finer than 75 micron sieve, soft fragment, shale)	IS:2386	B	Physical	Once per source& for on every change of source	IS: 2386 Part-II, IS:383	SR/LB/TR	√	
iii		All other tests similar to coarse aggregates as mentioned above.					IS-2386, IS-383	SR/LB/TR	√	except test for flakiness index,elongation index, abrasion value, impact value
<b>3.4 Water</b>										
i		Complete tests as per IS:456	Buret, conical flask, pipette etc	B	Testing	One per 3 month for each source.	IS:3025 part 22 and 23 (for test procedure), IS:456(for acceptance criteria )	SR/LB/TR	√	
<b>3.5 CONCRETE</b>										
i		4 Trial mixes to ascertain the workability and cube strength	After receiving the recommended mix design from specialist agency.	A	Physical	One for each mix proportion	NTPC tech specification	SR/LB	√	
ii		Crushing strength (works Tests cubes)	IS:516	A	Physical	IS 456-2000	IS:516, IS:456, NTPC Tech. Spec.	SR/LB/ Test Report	√	Min. of 6 cubes for each mix, 3 specimen shall be tested at 7 days remaining 3 shall be for 28 days comp. Strength.
iii		Workability - slump test	IS:1199	B	Physical	At the time of concrete pouring at site every two hrs	IS:456/NTPC Tech. Spec.	SR/LB/TR	√	
iv		Water content		B	Physical	Once per shift	As per approved design mix.	SR/LB	√	At batching plant
<b>3.5.1 Admixtures for Concrete</b>										
		Type of admixture	As per IS:9103	A	EIC Approved source and review of MTC/ test reports	For each lot received at site	Designed mix and IS:9103	Test Report	√	Admixture of appd. Brand and tested quality shall be used (each lot of admixture will included with brochure in which the type of admixture and its properties shall be clearly indicated)
		Suitability	As per IS:9103	B	Physical	For each lot received at site	Designed mix and IS:9103	SR/LB/TR	√	Relative density, pH and slump retention on each batch / lot of admixture and to compare these properties with MTC
<b>3.6 Concrete conveying, placing &amp; compaction</b>										
i		mixing of concrete shall be done in a approved mixer such as to produce a homogenous mix				To be calibrated at the time of starting and subsequently once in three months, and shall conform to IS:4925	Review of calibration chart/ Certificate, IS 4926		√	
ii		Arrangement for transportation & placement of concrete.	As required	C	Visual	100%	Before clearance for concreting	Inspection Report	√	
iii		Calibration of Batching Plant	batcher should comply with requirement of IS 4926/IS:4925	A	Physical	To be calibrated at the time of starting and subsequently once in three months, and shall conform to IS:4925	Review of calibration chart/ Certificate	Calibration Certificate	√	Provision of online printer is mandatory
iv		Handling and Transportation of concrete	As required	B	Physical	100%	As per construction/erection methodology (to be approved one week prior to start of work)	SR		

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN				ANNEXURE- I				
		ITEM : CIVIL WORK SUB-SYSTEM : GEOTECH INVI, FOUNDATIONS, EXCAVATION & FILL, SITE LEVELLING, CONCRETE, ROAD, BUILDING ETC.	QP NO. : REV. NO. : DATE : PAGE :	1 0	PROJECT: PACKAGE: CONTRACT NO. MAIN CONTRACTOR	Reference Document	Acceptance Norms	Format of Record	Remarks	
SI. No	Activity and operation	Characteristics / instruments	Class of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D* 10	
v		Placement of concrete	Visual	B	Physical	100%	As per construction/erection methodology and tech.specs / No segregation	SR	√	
vi		Placement	Visual	B	Physical	100%	As per approved construction methodology	SR	√	
vii		Compacting	As required	B	Physical	At Random	IS:456	SR	√	
viii		Curing	As required	B	Physical	At Random	Period of curing as per IS 456 (use gunny bags / curing compound)	SR	√	
<b>3.7 TEST/CHECK ON RCC STRUCTURE IN HARDENED CONDITIONS</b>										
i		Visual inspection of concrete surface of all dynamic foundations just after removal of shuttering	As required	A	Visual	100%	As per Technical Specification	SR	√	
ii		Embedment of inserts in concrete shall be checked for gap if any using hammer for all dynamic foundations	Hammer	A	Visual	100%	As per Technical Specification	SR	√	No hollow sound
iii		Dimensional check on finished structures & Dimensional tolerances	As required	B	Measurement	Approved Drawing	As per IS:456/ tech. Specification.	SR/LB	√	
iv		Water Tightness Test of liquid retaining structure/ tanks	As required	A	Test	100%	IS:3370/ Tech. Specification	SR/LB	√	
<b>3.8 REINFORCEMENT STEEL</b>										
i		Physical and Chemical Properties for each lot as per relevant IS codes	As required/ agreed	A	EIC Approved source and review of MTC/ test reports	Each batch of delivery	IS : 1786, IS:432, IS:1566, Tech Specs and Const. Drawings	MTC	√	Applicable if steel is procured by Contractor
ii		Freedom from cracks surface flaws, Lamination.	As agreed / required	B	Visual	Random in each shift	IS: 1852, IS:432, IS:1786, Tech Specs and Const. Drawings	SR		To be checked at site. Steel collected from source should be free from excessive rust. To be stored as per Technical Specs.
<b>3.9 PLACEMENT OF REINFORCEMENT STEEL</b>										
i		Bar bending schedule with necessary lap, Spacers & Chairs	As agreed / required	B	Visual & Measurement	Random in each shift	Approved Drawings, Tech Specs and Const. Drawings, IS:2502	SR	√	
ii		Bending of bars, cutting tolerance	As agreed / required	B	Visual & Measurement	Random in each shift	Approved Drawings, Tech Specs and Const. Drawings, IS:2502	SR	√	
iii		Acceptance - Cover, spacing of bars, spacers and chairs after the reinforcement cage is put inside the formwork	As agreed / required	B	Visual & Measurement	Random in each shift	Approved Drawings, Tech Specs and Const. Drawings	SR	√	
<b>3.10 STAGING AND FORMS</b>										
i		Materials and accessories	As agreed / required	B	Visual	Once before start of work	As per relevant IS, Tech Specs and Const. Drawings	SR		
ii		Soundness of staging, shuttering and scaffolding including application of mould oil / release agent	As agreed / required	B	Visual	Once before start of work	As per manufacturer's spec.and as per 3696,4014, 4990, Tech Specs and Const. Drawings	SR		
iii		Acceptance of formwork before start of concreting		B	Physical / visual	Before start of each concreting	As per provisions and tolerances, Tech Specs and Const. Drawings	SR	√	
<b>3.11 INSPECTION OF CONCRETE SURFACE JUST AFTER REMOVAL OF FORM WORK</b>										
i	Visual inspection jointly with NTPC	Concrete surface, position and alignment of embedded parts and inserts	--	B	Visual	Once for TG, BFP & MILL foundations	As per provisions and tolerances of equipment supplier, Tech Specs and Const. Drawings		√	Inspection protocol shall be signed Jointly by Contractor and NTPC CCD & Erection
ii	Submission of grouting / repair methodology if concrete surface / position and alignment of embedded parts / inserts are found defective		--	B	Review and approval	once for each type of defect	As per provisions and tolerances, Tech Specs and Const. Drawings		√	

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN				ANNEXURE- I				
		ITEM : CIVIL WORK SUB-SYSTEM : GEOTECH INVI, FOUNDATIONS, EXCAVATION & FILL, SITE LEVELLING, CONCRETE, ROAD, BUILDING ETC.	QP NO. : REV. NO. : DATE : PAGE :	1 0	PROJECT: PACKAGE: CONTRACT NO. MAIN CONTRACTOR	Reference Document	Acceptance Norms	Format of Record	Remarks	
Sl. No	Activity and operation	Characteristics / instruments	Class of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D* 10	
3.12	<b>EMBEDDED PART(INCLUDING LAYING OF RAILS &amp; ANCHOR FASTENERS)</b>									
i		Position / alignment / levels of embedded parts / bolt hole / pipe sleeves / rails / PVC pipes / etc	As agreed / required	B	Physical/ measurement	100%	As per drawing, Tech Specs and Const. Drawings	SR/ Protocol	√	Exposed surface of the embedded parts other than holding down bolts are to be painted with as per technical specifications
ii		Welding / tying of embedment to reinforcement	As agreed / required	B	Physical/ measurement	Random in each shift	As per drawing, Tech Specs and Const. Drawings	SR		
3.13	<b>PRE-CAST CONCRETE</b>									
i		Crushing strength	compression strength testing machine	A	Physical	one sample of six cubes per 50m m3 or part thereof	IS:516 & IS: 456	SR/LB	√	A minimum of three specimen shall be tested for 7 and 28 days compressive strength
ii		Workmanship and dimensions	Visual	B	Physical	100%	As per IS:456/NTPC Tech. specification.	Register		
iii		Load Test	As required	B	Physical	1% up to 1000 nos. and 0.5% for more than 1000 nos. for each type	IS:456/ As decided by NTPC Site Engr. Incharge.	Inspection Report	√	
3.14	<b>JOINTS IN CONCRETE</b>									
i		Joint material - bitumen impregnated fibre board, PVC water stops, Sealing compound, Expanded polystyrene board, Hydrophillic strip, Acrylic polymer etc.	As per manufacturer Standards	A	EIC Approved source and review of MTC/ test reports	Each batch of delivery	Tech Specs and Const. Drawings, IS 1838, IS 1834, IS12200	MTC	√	
ii		Acceptance of installation	As agreed / required	B	Acceptance	Each installation randomly	Tech Specs and Const. Drawings			
3.15	<b>DAMP PROOF COURSE</b>									
i		Material - Hot bitumen and water proofing materials etc	As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each batch of delivery at site	Tech Specs and Const. Drawings, IS 702	SR	√	
ii		Acceptance of damp proof course	As agreed / required	B	Acceptance	100%	Tech Specs and Const. Drawings	SR		
3.16	<b>GROUTING</b>									
i		Material	As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each batch of delivery	Tech Specs and Const. Drawings	SR	√	
		Type of mix - fluid mix, plastic mix, stiff mix etc.	As agreed / required	B	Physical	Prior to start of work	Tech Specs and Const. Drawings	SR	√	
ii		Mixing, placement, application and grout pressure	As agreed / required	B	Physical	Random in each shift	Tech Specs and Const. Drawings	SR		
iii		Compressive strength	As agreed / required	A	Physical	Random in each shift	Tech Specs and Const. Drawings	SR	√	
iv		Acceptance of the grouts	As agreed / required	B	Physical	Each grout section	Tech Specs and Const. Drawings	SR		
4.00	<b>BRICK MASONARY</b>									
4.1	<b>Test on Bricks</b>									
		Dimensions , shape, compressive strength, water absorption, warpage, efflorescence.	As agreed / required	A	Measurement/ Physical Test	As per relevant IS Code/ One Sample for 30,000 nos. or part thereof	IS: 1077, IS:13757, IS: 12894 / Tech Specs and const. Drawings	Inspection Report	√	Efflorescence shall be checked at each source.
4.2	<b>Test on Mortar</b>									
i		Compressive strength	As agreed / required	B	Test	At random	IS 2250-1981, Tech Specs and Const. Drawings	LB		
ii	<b>Sand</b>	Grading	As agreed / required	B	Test		IS:2116	SR/LB		
4.3	<b>Masonry construction</b>									
		Workmanship, verticality and alignment	As agreed / required	B	Visual/ Physical	100%	IS 2212, IS 1905 , Tech Specs and Const. Drawings	SR/LB		
5.00	<b>FINISHING AND ALLIED WORKS</b>									
5.1	<b>PLASTERING- MATERIAL</b>									

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN					ANNEXURE- I			
		ITEM : CIVIL WORK SUB-SYSTEM : GEOTECH INVI, FOUNDATIONS, EXCAVATION & FILL, SITE LEVELLING, CONCRETE, ROAD, BUILDING ETC.	QP NO. : REV. NO. : DATE : PAGE :	1 0	PROJECT: PACKAGE: CONTRACT NO. MAIN CONTRACTOR	Reference Document	Acceptance Norms	Format of Record	Remarks	
Sl. No	Activity and operation	Characteristics / instruments	Class of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D* 10	
i	Sand	Deleterious Material As agreed / required	B	Physical	Once per source	IS : 2386 (Part-I &II) & IS :2116, Tech Specs and Const. Drawings	SR			
ii		Grading As agreed / required	B	Physical	50 Cum./or part thereof	Tech Specs and Const. Drawings	SR			
iii	Galvanised wire mesh	Galvanized hexagonal wire netting for lath plastering As agreed / required	B	EIC Approved source and review of MTC/ test reports	Each batch of delivery	Tech Specs and Const. Drawings	SR			
<b>5.2 PLASTERING - WORKMANSHIP</b>										
i		Curing As agreed / required	C	Physical	100%	Tech specifications, construction drawings and agreed methodology	SR			
ii		Thickness and finishing of plaster, grooves etc As agreed / required	B	Visual/ Measurement	Random in each shift	Tech Specs and Const. Drawings	SR/LB			
iii		Truiness of plastering system As agreed / required	B	Visual/ Physical	Random in each shift	Tech Specs and Const. Drawings	SR			
<b>5.3 STONE GRIT PLASTER/ GRANULAR TEXTURED COAT FINISH</b>										
i		Material As agreed / required	B	Approved source and review of MTC	For each lot received at site	Tech Specs and Const. Drawings	SR	√		
ii		Thickness, finishing and grooves etc As agreed / required	B	Visual/ Measurement	Random in each shift	Tech Specs and Const. Drawings	SR	√		
<b>6.0 SHEETING AND OTHER WORKS</b>										
<b>6.1 PAINTING SYSTEM - CONCRETE WORKS AND PLASTERED MASONARY SURFACES</b>										
i	Materials and accessories- Oil Bound, Acrylic Emulsion, Chemical Resistant, Oil Resistant Paint etc.	Shade, type from brand and manufacturer as approved by NTPC EIC As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each batch of delivery	Tech Specs and Const. Drawings	SR/MTC	√		
ii	Surface prepration	As required As agreed / required	C	Physical /visual	Random in each shift	Tech Specs and Const. Drawings	SR			
iii	Acceptance of painted surfaces	As required As agreed / required	B	Physical	Each surface at random	Tech Specs and Const. Drawings	SR			
<b>6.1.1 PAINTING SYSTEM - STEEL WORKS (OTHER THAN STRUCTURAL STEEL WORKS)</b>										
i		Painting Materials and accessories -	A	EIC Approved source and review of MTC/ test reports	Each batch of delivery	Tech Specs and Const. Drawings	SR/MTC	√	Mfr.'s T.C. shall be correlated with the consignment received.	
ii		Submission of painting methodology -	B	For Review of painting system	Before start of painting work	Tech Specs and Const. Drawings				
iii		Surface prepration As agreed / required	B	Physical /visual	Each Erection Mark	Tech Specs and Const. Drawings, Relevant code/ standards	SR	√		
iv		Primer Thickness Elcometer	B	Measurement	Each Erection Mark	Tech Specs and Const. Drawings	SR	√		
v		DFT of paint Elcometer	B	Measurement	Each Erection Mark	Tech Specs and Const. Drawings	SR	√		
vi		Acceptance of painted surfaces Elcometer	B	Visual and measurement	Each Erection Mark	Tech Specs and Const. Drawings	SR			
<b>7.00 DOORS , WINDOWS VENTILATORS &amp; GRILL</b>										
<b>7.1 Steel doors</b>										
i		Materials (MS sheet, fasteners, hinges, jamps, lock strike plate etc As agreed / required	A	Visual/ Physical / test report	For each lot received at site	Tech Specs and Const. Drawings	SR / LB	√	Review of test report	
ii		Flush Door shutters, teak beading As agreed / required	A	EIC Approved source and review of MTC/ test reports	For each lot received at site	IS 2202, Tech Specs and Const. Drawings	SR	√	Review of test report	
iii		Hollow metal doors (material and dimensions) As agreed / required	A	Visual/ Physical/Test report	For each lot received at site	Tech Specs and Const. Drawings		√	Review of test report	
iv		Acceptance As agreed / required	B	Visual/ Physical	Random	Tech Specs and Const. Drawings	SR/LB			
<b>7.2 Anodised aluminium works</b>										


LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN					ANNEXURE- I			
		ITEM : CIVIL WORK SUB-SYSTEM : GEOTECH INVI, FOUNDATIONS, EXCAVATION & FILL, SITE LEVELLING, CONCRETE, ROAD, BUILDING ETC.		QP NO. : REV. NO. : DATE : PAGE :	1 0	PROJECT: PACKAGE: CONTRACT NO. MAIN CONTRACTOR				
SI. No	Activity and operation	Characteristics / instruments		Class of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks
1	2	3		4	5	6	7	8	9	D* 10
i		Materials- Aluminium sections, alkali resistant paint	As agreed / required	A	Visual/ Physical / test report	For each lot received at site	IS: 1948, IS: 1949, IS:733, IS1285, IS:1868, IS:11857/ Tech Specs and Const. Drawings	SR / LB	√	Review of test report For aluminium door/windows, check for anodisation as per Tech. Spec
ii		Particle Door	As agreed / required	A	EIC Approved source and review of MTC/ test reports	For each lot received at site	IS:12823 (phenol formaldehyde sythetic resin, BWP type), Tech Specs and Const. Drawings	SR	√	Review of test report
iii		Acceptance	As agreed / required	B	Visual/ Physical	Random	Tech Specs and Const. Drawings	SR		
<b>7.3 Fire proof doors</b>										
i		Source of supply	As agreed / required	A	Review of purchase order (unpriced copy) / drawings of suppliers / certificate of CBRl	For each source	Tech Specs and Const. Drawings	SR	√	Procured from Approved parties as per relevant IS/Tech, The door drawing proposed for supply should have been tested and approved by CBRl Roorkee for the similar dimensions for minimum 2 hours fire rating.
ii		Receipt inspection	As agreed / required	A	Visual/ Physical/ Review of MTC	For each lot received at site	Tech Specs and Const. Drawings	SR	√	
iii		Finishing and acceptance	As agreed / required	B	Visual / physical	Random	Tech Specs and Const. Drawings	SR		
<b>7.4 Rolling shutters</b>										
i		Surface finish and thickness of plate of approved make and DFT	As agreed / required	A	Physical / visual / review of MTC	Random for each lot of delivery	Tech Specs and Const. Drawings	SR	√	
ii		Finishing and acceptance	As agreed / required	B	Physical and acceptance	Random	Tech Specs and Const. Drawings	SR		
<b>7.5 Steel windows / Grills/ Louvre</b>										
i		Material fabrication and fixtures	As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each lot of delivery	IS: 1038 / IS:1361, IS: 7452 and Tech Specs and Const. Drawings	SR	√	
ii		Finishing and acceptance	As agreed / required	B	Visual / physical	Random	IS: 1038 / IS:1361, IS: 7452 and Tech Specs and Const. Drawings	SR	√	
<b>7.6 Glass and glazing</b>										
i		Clear float glass, wired glass, tinted glass, curtain glass, hermetically sealed	As agreed / required	B	EIC Approved source and review of MTC/ test reports	For each lot received at site	IS: 14900, IS:1081, IS: 3548, IS:5437 Tech Specs and Const. Drawings	SR	√	
ii		Installation finishing and acceptance	As agreed / required	B	Visual/ Physical	Random	Tech Specs and Const. Drawings	SR		Leak proof installation with neoprene gasket
<b>7.7 Curved dome on roof/ Poly Carbonate Sheet</b>										
i		Source of supply	As agreed / required	A	EIC Approved source and review of MTC/ test reports	For each lot received at site	Tech Specs and Const. Drawings	SR	√	
ii		Installation finishing and acceptance	As agreed / required	B	Visual / physical	Random	Tech Specs and Const. Drawings	SR		
<b>7.8 Reflective toughened glass</b>										
i		Material	As agreed / required	A	EIC Approved source and review of MTC/ test reports	For each lot received at site	Tech Specs and Const. Drawings	SR	√	
ii		Installation finishing and acceptance	As agreed / required	B	Visual / physical	Random	Tech Specs and Const. Drawings	SR		
<b>7.9 False Ceiling</b>										
i		Materials ( gypsum glass, glass fibre membrane, fibre board acoustical tiles etc)	As agreed / required	A	EIC Approved source and review of MTC/ test reports	For each lot received at site	Tech Specs and Const. Drawings	SR	√	Compare MTC with technical specification and requirement
ii		Installation finishing and acceptance	As agreed / required	B	Visual / physical	Random	Tech Specs and Const. Drawings	SR		

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN				ANNEXURE- I				
		ITEM : CIVIL WORK SUB-SYSTEM : GEOTECH INVI, FOUNDATIONS, EXCAVATION & FILL, SITE LEVELLING, CONCRETE, ROAD, BUILDING ETC.	QP NO. : REV. NO. : DATE : PAGE :	1 0	PROJECT: PACKAGE: CONTRACT NO. MAIN CONTRACTOR	Reference Document	Acceptance Norms	Format of Record	Remarks	
Sl. No	Activity and operation	Characteristics / instruments	Class of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D* 10	
7.10	<b>WATER PROOFING</b>									
		Methodology for the application of water proofing system	As required	B	Review	for each type of treatment	Tech Specs and Const. Drawings	SR	√	
7.10.1	<b>General Requirement- Water Proofing</b>									
	i Polyurethane based coating, polyester scrim cloth, extruded HD dimpled polyurethane	Material	As agreed / required	A	EIC Approved source and review of MTC/ test reports	For each lot received at site	Tech Specs /Const. Drawings	SR	√	MTC shall contain all the parameters specified in the technical specifications
	ii	Acceptance of water proofing work	As agreed / required	B	Physical	100%	Tech Specs and Const. Drawings			
7.10.2	<b>Roof / Basement Treatment</b>									
	i Graded under bed	Levels / slopes	As required	C	Physical	100%	Tech Specs and Const. Drawings			
	ii Elastomeric coatings	Material- Primer coat, finishing coat	As required	B	EIC Approved source and review of MTC/ test reports	Each lot of delivery	Tech Specs and Const. Drawings	SR	√	
	iii Wearing course	Materials - PCC, chicken wire mesh, elastomeric sealant	As required	B	Review of MTC	Each lot of delivery	Tech Specs and Const. Drawings	SR	√	
	iv	Acceptance of water proofing work	As agreed / required	B	Physical	100%	Tech Specs and Const. Drawings			
7.11	<b>Fencing and Gates</b>									
	i PVC coated chain link fencing (IS 2720), Welded wire mesh (IS 1566), Reinforced barbed tape galvanised (IS 2629) etc.	Materials	As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each batch of delivery	Tech Specs and Const. Drawings	SR/MTC	√	MTC shall contain all the parameters specified in the technical specifications
	ii Structural steel, painting system, caster wheel, ball and bearing, fixtures and fasteners	Materials	As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each batch of delivery	Tech Specs and Const. Drawings	SR/MTC	√	MTC shall contain all the parameters specified in the technical specifications
	iii	Alignments, erection painting, DFT etc.	As agreed / required	B	Physical / measurements	Each installation	Tech Specs and Const. Drawings	SR		
	iv	Acceptance of the installation and working	As agreed / required	B	Physical / measurements	Each installation	Tech Specs and Const. Drawings	SR		
7.12	<b>FLOOR FINISHES AND ALIED WORKS</b>									
7.12.1	<b>Cement Concrete Flooring</b>									
	i	Glass/ PVC strips in joints	As agreed / required	B	Physical	Random in each shift	Tech Specs and Const. Drawings	SR		
	ii	Finishing and acceptance	As agreed / required	B	Physical	100%	Tech Specs and Const. Drawings	SR		
7.12.2	<b>Tiles</b>									
	i Ceramic, vitrified, glass mosaic, acid alkali resistant, heavy duty cement concrete tiles	Materials	As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each lot of delivery	Tech Specs and Const. Drawings	SR	√	MTC shall contain all the parameters specified in the technical specifications
	ii	Finishing and acceptance	As agreed / required	B	Physical	100%	Tech Specs and Const. Drawings	SR		
7.12.3	<b>Interlocking Blocks</b>									
	i	Materials	As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each lot of delivery	Tech Specs and Const. Drawings	SR	√	MTC shall contain all the parameters specified in the technical specifications
	ii	Finishing and acceptance	As agreed / required	B	Physical	100%	Tech Specs and Const. Drawings	SR		
7.12.4	<b>Kota Stone, Granite and Marble</b>									
	i	Quality, texture, thickness, colour for each lot of delivery from approved source	As agreed / required	B	Physical	Each batch of delivery	Tech Specs and Const. Drawings	SR	√	
	ii	Finishing and acceptance	As agreed / required	B	Physical	100%	Tech Specs and Const. Drawings	SR		
7.12.5	<b>Metallic / non-metallic hardener</b>									
	i	Material	As agreed / required	B	Physical	Each batch of delivery	Tech Specs and Const. Drawings	SR	√	

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN					ANNEXURE- I			
		ITEM : CIVIL WORK SUB-SYSTEM : GEOTECH INVI, FOUNDATIONS, EXCAVATION & FILL, SITE LEVELLING, CONCRETE, ROAD, BUILDING ETC.	QP NO. : REV. NO. : DATE : PAGE :	1 0	PROJECT: PACKAGE: CONTRACT NO. MAIN CONTRACTOR	Reference Document	Acceptance Norms	Format of Record	Remarks	
SI. No	Activity and operation	Characteristics / instruments	Class of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D* 10	
ii		Finishing and acceptance	As agreed / required	B	Physical	100%	Tech Specs and Const. Drawings	SR		
7.12.6	<b>Acid / alkali and oil resistant high built seamless epoxy based resin and treatment</b>									
i	Material	Bricks, vitreous tiles, mortar, sealing, paints, coatings, sheets, fillers etc	As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each batch of delivery	Tech Specs and Const. Drawings	SR	√	Experienced workers under supervisors recommended/ appointed by manufacturer to be deployed
iii		Surface preparation	As agreed / required	B	Physical	Random in each shift	Tech Specs and Const. Drawings, IS			
iii		Finishing and acceptance	As agreed / required	B	Physical	100%	Tech Specs and Const. Drawings	SR		
7.13	<b>Doors/Windows Sections</b>									
i	Material - Rolled Steel, Z Sections, T-iron frames sections, Plates etc.	Review of MTC/ make / Physical checks, tests (if MTC is not available)	As agreed / required	A	EIC Approved source and review of MTC/ test reports	For each batch of delivery	Tech Specs and Const. Drawings	SR	√	
ii		Acceptance of Steel Glazed doors and T-iron frames sections after fixing	As agreed / required	B	Physical and acceptance	Random for each installation	Tech Specs and Const. Drawings	SR		
8.0	<b>WATER SUPPLY / SANITARY INSTALLATIONS</b>									
8.1	<b>Water supply fittings and fixtures</b>									
i	Materials	GI/ MS pipes and fittings	As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each lot of delivery as per Specifications	Tech Specs and Const. Drawings	SR	√	
ii	Disinfection	Before use	As agreed / required	B	Physical	Each installation	Tech Specs and Const. Drawings	SR		
iii	Hydraulic test	Before use / leakage	As agreed / required	A	Physical	Each installation	Tech specs and const drawings	SR	√	
iv		Acceptance and working	As agreed / required	B	Acceptance	Random	Tech Specs and Const. Drawings	SR		
8.2	<b>Sand cast iron / cast iron pipes</b>									
i	Material	SCI / CI pipes and fittings / joints	As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each lot of delivery as per Specifications	Tech Specs and Const. Drawings	SR	√	
ii		Acceptance and leakage	As agreed / required	B	Physical	Random	Tech Specs and Const. Drawings	SR		
8.3	<b>Sanitary fittings and fixtures</b>									
i	Material	Sanitary items and fixtures i.e. water closets, urinals, wash basins, sinks, mirrors, shelves, towel rail, soap containers, geyser, water cooler, etc, water supply / sanitation pipes, manhole cover and frames etc	As agreed / required	B	EIC Approved source and review of MTC/ test reports	Each lot of delivery as per Specifications	Tech Specs and Const. Drawings	SR	√	
ii		Acceptance of installations of all sanitary items and fixtures	As agreed / required	B	Acceptance	100%	Tech Specs and Const. Drawings	SR		
8.4	<b>RCC Pipes</b>									
i	Material	RCC pipes	As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each lot of delivery as per Specifications	Tech Specs and Const. Drawings /IS 458	SR	√	
ii		Acceptance and leakage	As agreed / required	B	Physical	Random	Tech Specs and Const. Drawings	SR		
8.5	<b>Water Storage Tanks</b>									
i	Material	Over head / loft type	As agreed / required	A	EIC Approved source and review of MTC/ test reports	Each lot of delivery as per Specifications	Tech Specs and Const. Drawings	SR	√	
ii		Acceptance and leakage	As agreed / required	B	Acceptance	Random	Tech Specs and Const. Drawings	SR		
9.0	<b>ROAD WORKS</b>									

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN				ANNEXURE- I				
		ITEM : CIVIL WORK SUB-SYSTEM : GEOTECH INVI, FOUNDATIONS, EXCAVATION & FILL, SITE LEVELLING, CONCRETE, ROAD, BUILDING ETC.	QP NO. : REV. NO. : DATE : PAGE :	1 0	PROJECT: PACKAGE: CONTRACT NO. MAIN CONTRACTOR	Reference Document	Acceptance Norms	Format of Record	Remarks	
Sl. No	Activity and operation	Characteristics / instruments	Class of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D* 10	
9.1	<b>Construction of Sub-Grade and earthen/hard soulders</b>									
i		Standard proctor Test As per IS: 2720	A	Physical	One in every 2000 cum for each type and source of fill materials	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification, IS 2720 (Pt.VII)	SR/TR	√	In cutting or existing levelled ground - quantum of check shall be one per 1000 SQM	
ii		Moisture content of fill before compaction As per IS: 2720	B	Physical	One in every 2000 cum for each type and source of fill materials	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification, IS 2720 (Pt.II)	SR/TR		In cutting or existing levelled ground - quantum of check shall be one per 1000 SQM	
iii		Dry density by core cutter method ---- OR ---- Dry density in place by sand displacement method As per IS: 2720	A	Physical	One in every 500 SQM area for each compacted layer.	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification, IS 2720 (Pt. V.VII) IS 2720 (Pt. V.VIII)	SR/TR	√	Both for embankment and cut formation quantum of check - One in every 1000 SQM area for each compacted layer.	
iv		Lines, grade and cross section As required / agreed	B	Physical	One in every 500 SQM area	As per Tech Specs and Const. Drawings	SR		Template, straight edge	
9.2	<b>Water Bound Macadam (Non-Bituminous) for base course and sub-base course</b>									
i		Aggregate Impact value Aggregate Impact value Test Apparatus	A	Physical	One test per 200 cum of aggregate	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification,	SR	√		
ii		Grading Set of IS Sieves	B	Physical	One test per 100 cum of aggregate	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification,	SR			
iii		Flakiness index and elongation index Flakiness test gauge	B	Physical	One test per 200cum of aggregate	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification,	SR			
iv		Atterberg Limits of binding material Atterberg limits determination	A	Physical	One test per 25 cum of binding material	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification,	SR	√		
v		Atterberg Limits of portion of aggregate passing 425 micron sieve Atterberg limits determination	A	Physical	One test per 100cum of aggregate	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification,	SR	√		
vi		Camber, surface, slope As required / agreed	B	Physical	One in every 500 SQM area	As per Tech Specs and Const. Drawings	SR		Template, straight edge	
9.3	<b>Bituminous Macadam for base and binder course</b>									
i		Quality of binder Penetrometre with St. needle	A	Physical	No. of samples per Lot & tests as per IS:73, IS:217, IS:8887 as applicable	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification, IS	SR	√		
ii		Aggregate Impact Value / Los angeles abrasion value Aggregate Impact Value Test apparatus	A	Physical	Once per source	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√		
iii		Flakiness Index and elongation index of aggregates Flakiness test gauge	B	Physical	One test per 50 cum of aggregate	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR			
iv		Stripping value of aggregate (Immersion tray test) As required / agreed	B	Physical	Initially one set of 3 representative specimen per source, and on every change of source.	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR			
v		Water sensitivity of mix As required / agreed	A	Physical	Initially one set of 3 representative specimen per source, and on every change of source.	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√		
vi		Grading of aggregates Set of Sieves	B	Physical	Two test per day per plant both on individual constituents and mixed aggregate from dryer	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR			
vii		Water absorption of aggregate As required / agreed			Initially one set of 3 representative specimen per source, and on every change of source.	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR			
viii		Soundness ( Magnesium and Sodium Sulphate) As required as per IS:2386	A	Physical	Once per source by each method and on every change of source	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√		
ix		Percentage of fractured faces As required / agreed	B	Physical	When gravel is used one test per 50cum of aggregates	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR			

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN				ANNEXURE- I				
		ITEM : CIVIL WORK SUB-SYSTEM : GEOTECH INVI, FOUNDATIONS, EXCAVATION & FILL, SITE LEVELLING, CONCRETE, ROAD, BUILDING ETC.	QP NO. : REV. NO. : DATE : PAGE :	1 0	PROJECT: PACKAGE: CONTRACT NO. MAIN CONTRACTOR	Reference Document	Acceptance Norms	Format of Record	Remarks	
SI. No	Activity and operation	Characteristics / instruments	Class of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D* 10	
x		Binder content and aggregate grading	Bitumen extractor	A	Physical	Periodic, subject to a min of two tests per day per plant	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√	
xi		Control of Temperature of binder and aggregate for mixing and of the mix at the time of laying and rolling	Thermometer	B	Physical	At regular close intervals	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR		
xii		Rate of spread of mixed materials	As required / agreed	B	Physical	Regular control through checks of layer thickness	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR		
xiii		Density of compacted Layer	As required / agreed	A	Physical	One test per 250 sqm of area	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√	
<b>9.4 Bituminous Surfacing - Open graded premix carpet and Seal coat</b>										
i		Quality of binder	Penetrometre with St. needle	A	Physical	No. of samples per Lot & tests as per IS:73, IS:217, IS:8887 as	IS 73, Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√	
ii		Aggregate Impact Value / Los angeles abrasion value	Aggregate Impact Value Test apparatus	A	Physical	One test per 50 cum of aggregate	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√	
iii		Flakiness Index and elongation index of aggregates	Flakiness test gauge	B	Physical	One test per 50 cum of aggregate	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR		
iv		Stripping value of aggregate (Immersion tray test)	As required / agreed	B	Physical	Initially one set of 3 representative specimen per source, and on every change of source.	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR		
v		Water absorption test		A	Physical	Initially one set of 3 representative specimen per source, and on every change of source.	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√	
vi		Water sensitivity of mix	As required / agreed	A	Physical	Initially one set of 3 representative specimen per source, and on every change of source.	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√	
vii		Grading of aggregates	Set of Sieves	B	Physical	One test per 25 cum of aggregates	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR		
viii		Soundness ( Magnesium and Sodium Sulphate)	As required as per IS:2386	A	Physical	Once per source by each method and on every change of source	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√	
ix		Polished stone value	As required as per BS:812(Part 114)	B	Physical	As required	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR		
x		Temperature of binder at application	Thermometer	B	Physical	At regular close intervals	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR		
xi		Binder content	Bitumen extractor	A	Physical	One test per 500 cum & not less than two tests per day	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√	
xii		Rate of spread of materials	As required / agreed	B	Physical	One test per 500 cum and not less than 2 tests per day	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR		
xiii		Percentage of fractured faces	Bitumen extractor	A	Physical	When gravel is used one test per 50cum of aggregates	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√	
<b>9.5 Tack Coat/ Prime coat/ fog coat</b>										
i		Quality of binder	Penetrometre with Standard needle	A	Physical	No. of samples per Lot & tests as per IS:73, IS:217, IS:8887 as	IS 73, Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√	
ii		Temperature of binder at application	Thermometer	B	Physical	At regular close intervals	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR		

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN				ANNEXURE- I				
		ITEM : CIVIL WORK SUB-SYSTEM : GEOTECH INVI, FOUNDATIONS, EXCAVATION & FILL, SITE LEVELLING, CONCRETE, ROAD, BUILDING ETC.	QP NO. : REV. NO. : DATE : PAGE :	1 0	Page 12 of 12	PROJECT: PACKAGE: CONTRACT NO. MAIN CONTRACTOR	Reference Document	Acceptance Norms	Format of Record	Remarks
Sl. No	Activity and operation	Characteristics / instruments	Class of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D*	10
iii		Rate of spread of binder	As required / agreed	B	Physical	One test per 500 cum and not less than 2 tests per day	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR		
9.6	RCC Pavements	Concrete - Material, Mix design, Trial Mixes, Production, Transportation, Placement, Compaction, Curing, Test on green concrete, Test on hardened concrete etc.	As required / agreed	-	-	Refer FQP for concrete Works	Refer FQP for concrete Works, , Tech Specs and Const. Drawings, IRC & MOST	-	-	FQP for Concrete Works shall be application for all concrete works
9.7	Alignment, Level, Surface regularity and rectification									
i		Horizontal alignment, Surface levels and Surface regularity	As required / agreed	B	Physical	As per section 900 of MOSRTH specification	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR		
ii		Rectification	As required / agreed	B	Physical	Each rectification	As per Tech Specs and Const. Drawings, Section 900 of MOSRTH specification	SR	√	
<b>Legend to be used: Class # : A = Critical, B=Major, C=Minor; SR, TR, MTC, LB</b> <b>Categorization Witnessing &amp; Accepting (As per NTPC QA&amp;I System)</b> <b>Category 'A' FQA Engineer in association with Executing Engineer, Category 'B' Executing Engineer, Category 'C' Executing Engineer ;SR = Site Register , TR= Test Report, MfTC = Manufacturer's Test Certificate</b>										
Manufacturer/ Sub-supplier	Main-supplier					For NTPC USE 				
Signature		This document shall be read in conjunction with NTPC Tech. Specifications, BOQ, Drawings					REVIEWED BY	APPROVED BY	APPROVAL SEAL	

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN					ANNEXURE II			
		ITEM : STRUCTURAL STEEL WORK		QP NO. :			PROJECT:			
		SUB-SYSTEM : FABRICATION & ERECTION		REV. NO. :	0		PACKAGE:			
				DATE :	1 of 4		CONTRACT NO.			
Sl. No	Activity and operation	Characteristics / instruments	Class# of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D* 10	
<b>1.00</b>	<b>STRUCTURAL STEEL MATERIAL</b>									
i	Issed by NTPC	Material- Visual Examination, Identification and marking for grade/ type of steel	B	Visual	Each plate/ Section	Tech Specs and Const. Drawings			MS steel conforming to IS 2062 and IS 8500 to be clearly demarcated by application of distinct coloured pain strips on each piece/ off-cuts of respective grades/ type of steel	
ii	Procured by contractor	Structural steel procured from NTPC approved sources- Mechanical (YS, UTS, Elg, UT if specified),and Chemical properties (CE as per IS)	A	Review	For each batch of each section delivered at site	Technical Specification and Construction Drawings, IS 2062, 8500	SR	√	Correlated MTC shall be verified. In the event of non submission of MTC , sample shall be selected by FQA for testing	
<b>1.01</b>	<b>PRE-WELDING REQUIREMENTS</b>									
i		Welding Procedure Specification * (WPS*)	-	A	Review	Each Welding Process	Technical Specification and Construction Drawings, ASME-IX/ AWS D 1.1	WPS	√ *To be approved by CQA	
ii		PQR and Welder's Qualification	-	A	Physical	Each welder	PQR/ WQR, AWS-D1.1/ASME-IX, Technical	Test Report	√	
iii		Welding consumables	-	B	Physical	Random in each shift	Approved WPS, Latest NTPC	SR	√	
<b>1.02</b>	<b>FIT-UP</b>									
i		Marking and Cutting	Tape, ruler etc	B	Visual & Measurement	Each plate/ Section	Technical Specification and Construction Drawings/ Approved cutting plan	SR		
ii		Match markings for trial assembled components	-	B	Physical	Each fit-up	Technical Specification and Construction Drawings	SR		
iii		Weld Fit Up- Edge Preparation/ Gap/ Alignment	Tape, ruler etc	B	Physical	Each fit-up	Technical Specification and Construction Drawings, IS 7215	SR	√ If required suitable stiffners shall be provided to prevent deflection.	
<b>1.03</b>	<b>PRE HEATING (wherever applicable)</b>									
i		Pre-Heating Temperature	Thermal chalk	B	Measurement	Each pre-heating	Technical Specification and Construction Drawings, Approved WPS	SR	√	
ii		Post Weld Heat Treatment (PWHT), if required	Thermo couple with time temperature recorder	A	Time & Temperature	Each PWHT	Technical Specification and Construction Drawings, Approved WPS	SR	√	
<b>1.04</b>	<b>WELDING REQUIREMENTS</b>									
i		Sequence of welding	-	B	Physical	Random in each shift	Technical Specification and Construction Drawings, Agreed scheme	SR		
ii		Removal/ grinding of temporary attachments	-	B	Measurement	All cleats/ attachments	Technical Specification and Construction Drawings, Approved Drg.	SR		
iii		Completeness after welding- Dimensions/ distortion	Weld gauge	B	Visual	Each structure component	Technical Specification and Construction Drawings, IS 822	SR	√	
iv		Completeness of welding (each butt & fillet weld)		B	Visual	Each structure component	Technical Specification and Construction Drawings, Approved Drg.	SR	√	

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN					ANNEXURE II			
		ITEM : STRUCTURAL STEEL WORK		QP NO. :			PROJECT:			
		SUB-SYSTEM : FABRICATION & ERECTION		REV. NO. :	0		PACKAGE:			
				DATE :			CONTRACT NO.			
Sl. No	Activity and operation	Characteristics / instruments	Class# of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D*	10
<b>2.00</b>	<b>NON DESTRUCTIVE AND DESTRUCTIVE TESTING</b>									
<b>2.1</b>	<b>FILLET WELDS</b>									
i		size and visual examination As required/ agreed	B	Visual/ Measurement	100%	As per technical specifications and construction drawings, IS 822, AWS D 1.1		SR		As per requirement of NTPC Engineer
ii		Dye Penetration Test As required/ agreed	B	Physical	25% weld length of tension member of crane girder and 5% of Weld length with min. 300mm at each loaction except crane girder to all other fillet welds	As per technical specifications and construction drawings, IS 822, AWS D 1.1		SR		
<b>2.2</b>	<b>BUTT WELDS</b>									
i		Visual examination As required/ agreed	B	Visual	Random in each shift	As per technical specifications and construction drawings, IS 822, AWS D 1.1		SR		As per requirement of NTPC Engineer
ii		DPT As required/ agreed	B	Physical	100% on all butt welds after back gouging on root run and 10% on final weld.	As per technical specifications and construction drawings, IS 822, AWS D 1.1		IR		All butt welds to be back gouged before DPT
iii		Mechanical testing on production test coupons As required/ agreed	B	Physical	Min. one joint per built up beams, coloums and crane girder.	As per technical specifications and construction drawings, IS 822, AWS D 1.1		IR	√	Test on production test coupons
iv		Radiography Test As required/ agreed	A	Physical	100% radiography test on butt welds of tension flange (bottom flange) of crane girder. All other butt welds shall be subjected to 10% weld length of each welder.	As per technical specifications and construction drawings, IS 822, AWS D 1.1		IR	√	Wherever RT is not feasible UT to be carried out. In case of failure of any welds in SPOT/RT or UT the % of retesting shall be doubled at that particular loaction. Acceptance criteria of NDT on welds shall be as per AWS D1.1.
<b>2.4</b>	<b>FULL PENETRATION WELDS (OTHER THAN BUTT WELDS)</b>									
		Ultrasonic Testing As required/ agreed	A	Physical	i) 100% UT on the web to flange joint of crane girder ii) 10% UT on other full penetration joints	As per technical specifications and construction drawings, IS 822, AWS D 1.1		IR	√	In case of failure of any welds in SPOT/RT or UT the % of retesting shall be doubled at that particular loaction. Acceptance criteria of NDT on welds shall be as per AWS D1.1.
<b>3.00</b>	<b>FOUNDATION CHECKS</b>									
i		Dimensions and levels- Shape, lines (including diagonal checks) Theodolite, Tape etc	B	Physical/ Measurement	Each Foundation	Tech Specs and Const. Drawings		SR	√	
ii		Foundation Bolts and Embedments- Verticality, Levels, pitch distance Theodolite, Tape, Piano wires etc	B	Physical/ Measurement	Each Foundation	Tech Specs and Const. Drawings		SR	√	
<b>4.00</b>	<b>PAINTING SYSTEM</b>									
i		Painting Materials and accessories -	A	Review of MTC	Each batch of delivery	Tech Specs and Const. Drawings		SR/MTC	√	Mfr.'s T.C. shall be correlated with the consignment received.

LOGO	SUPPLIERS NAME AND ADDRESS:	INDICATIVE FIELD QUALITY PLAN					ANNEXURE II			
		ITEM : STRUCTURAL STEEL WORK		QP NO. :		PROJECT:				
		SUB-SYSTEM : FABRICATION & ERECTION		REV. NO. :	0	PACKAGE:				
				DATE :		CONTRACT NO.				
Sl. No	Activity and operation	Characteristics / instruments	Class# of check	Type of Check	Quantum Of check	Reference Document	Acceptance Norms	Format of Record	Remarks	
1	2	3	4	5	6	7	8	9	D*	10
ii		Submission of painting methodology	-	B	For Review of painting system	Before start of painting work	Tech Specs and Const. Drawings			
iii		Surface preparation	As agreed / required	B	Physical /visual	Each Erection Mark	Tech Specs and Const. Drawings, Relevant code/ standards	SR	√	
iv		Primer Thickness	Elcometer	B	Measurement	Each Erection Mark	Tech Specs and Const. Drawings	SR	√	
v		DFT of paint	Elcometer	B	Measurement	Each Erection Mark	Tech Specs and Const. Drawings	SR	√	
vi		Acceptance of painted surfaces	Elcometer	B	Visual and measurement	Each Erection Mark	Tech Specs and Const. Drawings	SR		
<b>5.00</b>	<b>PRE-ASSEMBLY CHECKS</b>									
i		Punch Erection marks and match marks on members	-	B	Visual/ Physical	Each structural member	Tech Specs and Const. Drawings			Markings for - Assembly designation, Part number, Weight, Any other important identifications.
ii		Pre-assembly as per match mark	-	B	Visual/ Physical	Each structural member	Tech Specs and Const. Drawings			
iii		Camber, sweep and total length after trial assembly of structure.	Theodolite, Tape, plumb, piano wires etc	B	Visual/ Physical	Each structural member	Tech Specs and Const. Drawings	SR	√	
iv		Control assembly check at shop	Theodolite, Tape, plumb, piano wires etc	B	Visual/ Physical	Every first and tenth set of identical structure	Tech Specs and Const. Drawings			
v		Completion of primer & intermediate coat of paint		B	Visual / Physical	Random	Tech Specs and Const. Drawings	SR		
<b>6.00</b>	<b>ERECTION CHECKS</b>									
i		Alignment, slopes, level, tolerances of erected member	Theodolite, Tape, plumb, piano wires etc	B	Measurement	Each structural member	Tech Specs and Const. Drawings	SR	√	
ii		Tightening of bolts/ Torque including foundation bolts with lock nuts	Wrench/ Torque wrench if specified	B	Visual/ Physical	Each structural member	Tech Specs and Const. Drawings	SR	√	
iii		Completion of all erection fillet & butt welds		B	Visual	Each structural member	Tech Specs and Const. Drawings	SR	√	
iv		Acceptance of erected structure	Theodolite, Tape, plumb, piano wires etc	B	Visual/ Physical	Each erected structure	Tech Specs and Const. Drawings, IS 7215 and IS 12843	SR	√	
<b>7.00</b>	<b>PERMANENT BOLTS AND NUTS AND WASHERS</b>									
i		Material- Permanent mild steel Bolts, mild steel Nuts, High strength structural Bolts, Washers- Dimensions, properties, Class, storage along with MTC	Screw gauge, Vernier, Tape etc.	A	Physical and MTC Review	Once for each lot of delivery	Tech Specs and Const. Drawings	SR/MTC	√	
ii		Contact surfaces before bolting	-	B	Physical	Random before assembly for	Tech Specs and Const. Drawings, IS 4000	SR		
iii		Inspection of the assembled bolts	-	B	Physical	Randomly in each shift for assembled bolts	Tech Specs and Const. Drawings, IS 4000	SR		
iv		Tensioning	As agreed / required	B	Physical	Randomly during snug tight test and after full tensioning	Tech Specs and Const. Drawings, IS 4000	SR	√	
v		Acceptance of installed bolts	-	B	Physical	Each bolt	Tech Specs and Const. Drawings	SR		
<b>8.00</b>	<b>ELECTROFORGED GRATINGS</b>									
i		Material from approved source	As agreed / required	A	Physical and MTC Review	Once for each lot of delivery	Tech Specs and Const. Drawings	SR/MTC	√	Also refer the approved MQP

