

#### ADDENDUM-4

DATE: 29-01-2014

#### Civil & structural works for CHP & AHP packages for Suratgarh Super Critical Thermal Power Station Stage-5, Units 7 & 8, CHP & AHP

Tender Ref: 88/13/6039/MVG dated 13.12.2013

1. **Document Ref:** Special Conditions of Contract, Volume-1, Section-B-4.1, Sh. B4-1/2, Rev:R1, Dt. 02.01.2014

Equipment list of Civil Works in the referred document **earlier as**

SL. NO	DESCRIPTION	UNIT	PACKAGE-1	PACKAGE-2
51	Portable insulated metal site office (cabin) of minimum size 35m length, 5m width, 3m height with required computers with printers, A1 size drawing plotters and latest version of necessary software like Auto Cad, PDF reader and communication facilities like Fax, Email and Telephone with STD facility, furniture, lighting, ventilation and Air conditioned space and with required doors and windows Aluminium fittings etc.	NO	4	1
52	Portable insulated metal/plastic (Sintex or approved equivalent) toilet of size 5m length, 3m width, 3m height with required sanitary fittings	NO	3	2
53	PVC (Sintex or approved equivalent) water tank of 3000 litres capacity	NOS	5	3

**Shall be read as below:**

SL. NO	DESCRIPTION	UNIT	PACKAGE-1	PACKAGE-2
51	Contractors Site Office of area minimum 100sqm with required computers with printers, A1 size drawing plotters and latest version of necessary software like Auto Cad, PDF reader and communication facilities like Fax, Email and Telephone with STD facility, furniture, lighting, ventilation / Air conditioned	NO	2	1
52	Toilet for Contractors site office with required sanitary fittings complete	NO	4	2
53	PVC (Sintex or approved equivalent) water tank of 2000 litres capacity for Contractors office	NOS	2	1

2. **Document Ref:** SCHEDULE OF QUANTITIES FOR CHP, AHP & ENABLING WORKS (Civil, Structural, Architectural Works for 2X660MW RRVUNL – Suratgarh Thermal Power Station, Rev01 Dt: 28.12.2014 Page 24 of 58

Schedule of quantity in the referred document **earlier as**

SL. NO	DESCRIPTION
14.1	Providing & laying 50mm thick heavy duty cement concrete flooring with metallic hardener pigmented topping of 12mm thick uniform graded treated iron particles over under bed of 1 part of cement, 1 part of sand and 2 parts chips (10mm down. Well graded) by volume (only sufficient water added to give workable consistency) in the flooring complete as per specification.
14.2	Providing and laying 50mm thk granolithic flooring without hardener topping with finishing, curing etc. complete as per specification, approved drawings and direction of engineer-in charge

**Shall be read as below:**

SL. NO	DESCRIPTION
14.1	Providing & laying 50mm thick heavy duty Ironite flooring with metallic hardener topping of 12mm thick uniform graded treated iron particles over underbed of 1 part of cement, 1 part of sand and 2 parts stone chips (10mm down well graded coarse aggregate) by volume (only sufficient water added to give workable consistency) in the flooring complete including finishing, curing etc. complete as per specification, approved drawings and direction of engineer-in charge. Metallic hardener topping shall consist of one part of a cement-ironite mixture to two parts by bulk of well-graded approved crushed granite of maximum 6/10 mm size. The cement ironite mixture shall consist of well mixed dry mixture containing one part ironite to four parts cement by weight.
14.2	Providing and laying 50mm thk granolithic flooring (without metallic hardener) in cement concrete 1:1:2 (1 part of cement, 1 part of sand and 2 parts stone chips (10mm down well graded coarse aggregate) by volume (only sufficient water added to give workable consistency) in the flooring complete including finishing, curing etc. complete as per specification, approved drawings and direction of engineer-in charge.

3. Any further addendum such issued carry part of the bidding documents and this will be available at the web site from where the original documents have been received / downloaded by the bidder. Hence bidders are requested to visit the web site on regular basis.

**For Further Queries if any, Contact:**

**Sh. M.V.Gautam**

Sr. DGM / BG-1A (MM)

BHEL-ISG,

Prof.C.N.R.RAO CIRCLE, MALLESWARAM,

BANGALORE-560 012

Off: 080 2218 4087; E.MAIL: [mvg@bhelisg.com](mailto:mvg@bhelisg.com)