



JHANSI

BHARAT HEAVY ELECTRICALS LIMITED , JHANSI
FACTORY CIVIL DEPARTMENT

Name of work: - Fabrication Shop – Facility for storage & administration.

Tender Enquiry No. FCX / TE / 3 / 14 / R

DT 23/11/2013

CORRIGENDUM SLIP -1

This corrigendum is issued on 23/11/2013 and henceforth forms a part of tender document for tender no FCX/TE/3/14/R. The following clauses of tender are hereby clarified / amended and all tenderers must submit their offers in light of the same. The tenderer must submit this corrigendum slip (duly signed and stamped) along with tender documents.

1. Refer page 69, Item no 63 of Price Bid (Extra - 3) mentioned as “**P/fixing false ceiling** “. This must be read as follows

Providing and fixing at all height false ceiling with 12 mm thick semi perforated gyp board tiles of approved quality including providing and fixing of frame work made of special sections power pressed from M.S. sheet and galvanised in accordance with zinc coating of grade 350 as per IS : 277 and consisting of angle cleats of size 25mm wide x 1.6mm thick with flanges of 22mm and 37mm at 1200mm centre to centre one flange fixed to the ceiling with dash fastener 12.5mm diax40mm long with 6mm dia bolts to the angle hangers of 25x25x0.55mm of required length, and other end of angle hanger being fixed with nut and bolts to G.I. channels 45x15x0.9mm running at the rate of 1200mm centre to centre to which the ceiling section 0.5mm thick button wedge of 80mm with tapered flanges of 26mm each having clips of 10.5mm at 450mm centre to centre shall be fixed in a direction perpendicular to G.I. channel with connecting clips made out of 2.64mm diax230mm long G.I. wire at every junction including fixing the gypsum board with ceiling section and perimeter channels 0.5mm thick 27mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450mm centre to centre with 25mm long drive-all screws @ 230mm interval including jointing and fixing to a flush finish of tapered and square edges of the board with recommended filler, jointing tapes, finisher and painting with Decoplast or any other approved paint for Gypboard and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed all complete as per drawing and specification and direction of the Engineer in Charge.

2. Refer page 69, Item no 64 of Price Bid (Extra – 4) mentioned as “**P/fixing PVC floor** “. This must be read as follows

Providing and fixing PVC floor 1.5mm thick as per approved quality, brand and colour by Engineer in charge

Signature & seal issuing authority

Sign, seal & date of contractor