

BHARAT HEAVY ELECTRICALS LIMITED
Centralized Stamping Unit, Jagdishpur
Distt- Amethi (U.P)

SECTION-IV: BOQ & PRICE SCHEDULE (AFTER INCORPORATION OF CORRIGENDUM-I) FOR REFURBISHMENT OF DAMAGES IN PLANT BOUNDARY WALL & ASSOCIATED WORKS AT JAGDISHPUR AT BHEL, JAGDISHPUR

TE No: BHE/CSU/CVL/105

S.No.	DESCRIPTION OF WORK	UNIT	QTY.	Quoted Rate (Rs.)		Quoted Amount (Rs.)
				In Figures	In Words	
1	Earthwork in excavation in foundation trenches or drains (not exceeding 1.5 m in width or 10 Sqm on plain) including dressing of sides and ramming of bottom, lift up to 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m. All kinds of soil	Cum	20.00			
2	Supplinying and filling in plinth with jamuna sand including watering, raming consolidating,dressing complete	Cum	56.50			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work up to plinth level 1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size).	Cum	3.20			
4	Brick work with F.P.S Brick of class designation 75 in foundation, plinth and super structure in cement mortar 1:6 (1 cement : 6 coarse sand).	Cum	25.81			
5	Providing and fixing Reinforcement for R.C.C. work includig , straighting, cutting, bending, placing, cleaning of rust in position and binding,all complete. Cold twisted bars.	Kg	627.00			
6	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns,pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :size).1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	Cum	7.84			
7	Centring and shuttering including strutting, propping etc. and removal of form work for Lintels, beams, plinth beams, girders, bressumers and cantilevers.	Sqm	55.00			
8	12 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand).	Sqm	100.40			
9	White washing with lime to give an even shade New work (three or more coats)	Sqm	100.40			
10	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade New work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	Sqm	100.40			
11	Dismantling and Demolishing all types of brick work including stacking of serviceable material and disposal of unserviceable material within 1 Km lead from the dismantled structure.	Cu.M.	21.90			

BHARAT HEAVY ELECTRICALS LIMITED
Centralized Stamping Unit, Jagdishpur
Distt- Amethi (U.P)

SECTION-IV: BOQ & PRICE SCHEDULE (AFTER INCORPORATION OF CORRIGENDUM-I) FOR REFURBISHMENT OF DAMAGES IN PLANT BOUNDARY WALL & ASSOCIATED WORKS AT JAGDISHPUR AT BHEL, JAGDISHPUR

TE No: BHE/CSU/CVL/105

S.No.	DESCRIPTION OF WORK	UNIT	QTY.	Quoted Rate (Rs.)		Quoted Amount (Rs.)
12	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m including disposal of surplus excavated earth within lead of 500 meter from the site.	Cum	50.00			
13	Providing non-asbestos high impact Polypropylene reinforced cement 6 mm thick corrugated sheets (as per IS: 14871) roofing up to any pitch and fixing with polymer coated J, or L hooks, bolts and nuts 8 mm dia. G.I. plain and bitumen washers or with self drilling fastener and EPDM washers etc. complete (excluding the cost of purlins, rafters and trusses), including cutting sheets to size and shape wherever required.	Sqm	24.00			
14	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Cum	45.00			
Note: Service tax shall be payable extra as applicable.					Total=	