



**AIR CONDITIONING SYSTEM  
2X500 MW NNTPP  
SG PACKAGE**

**SPECIFICATION NO. PE-TS-400-553-A001**

**ADDENDUM No. 1**

**DATE: 04.02.2016**

**SHEET 1 OF 2**

**2X500 MW NNTPP  
SG PACKAGE**

**ADDENDUM No. 1**

(TECH SPEC No. PE-TS-400-553-A001)

**AIR CONDITIONING SYSTEM**



**AIR CONDITIONING SYSTEM  
2X500 MW NNTPP  
SG PACKAGE**

**SPECIFICATION NO. PE-TS-400-553-A001**

**ADDENDUM No. 1**

**DATE: 04.02.2016**

**SHEET 2 OF 2**

**AMENDMENT TO EXISTING CLAUSES OF TECHNICAL SPECIFICATION**

| Sl. No. | Clause                      | Existing description  | To be read as (Amendment)  |
|---------|-----------------------------|---|--|
| 1       | Suggestive price format 3.2 | Sheet metal cabinet type air handling units (double skin as per specification) consisting of chilled water cooling coil, centrifugal blower, TEFC sq cage induction motor, drive set, filters (pre, fine and HEPA filters), 3 way motorised mixing valve with thermostatic controls and other accessories to meet AC load of control room areas at ESP-1 and ESP-2 building. HEPA Filters shall be provided in Common discharge plenum. | Sheet metal cabinet type air handling units (double skin as per specification) consisting of chilled water cooling coil, centrifugal blower, TEFC sq cage induction motor, drive set, filters (pre, fine and HEPA filters), 3 way motorised mixing valve with thermostatic controls and other accessories to meet AC load of control room areas at ESP-1 and ESP-2 building. Fine and HEPA Filters shall be provided at the discharge of each individual AHUs. |