

**BHEL PSSR SCT DEPT  
CORRIGENDUM-1 TO TENDER NOTICE BHEL PSSR SCT 1490,dated:1/2/2012**

**Some of the bidders sought clarifications vide letters or in Pre Bid discussion held on 30.01.2012 at BHEL PSSR Regarding Bellary 1x700MW Civil and Structural Works Tender Specification BHEL PSSR SCT 1490 and clarifications are furnished below for your information**

S.No	Ref No	Bidder's Query	BHEL Reply
1		Subhead 100 : We request you to consider any coffer dams, sheet piling if required, the same shall be measured and paid seperately. We presume that shortcreting/Gunniting shall be measured and paid seperately under relevant items. Also mode of measurement for rock excavation states that 50% voids will be considered for payment and this shall be considered as 30% like other contracts.	Will be dealt as per CL 2.15 in GCC
2		BOQ 109: Please confirm that carriage of material directly from excavation area. We presume that land required for disposal will be with in the plant premises (owners land)	Material disposal area will be within the project site with a lead of 4-5 kms
3		BOQ 303: We presume that TG column, beams. TG deck bottom, TG side wall shall be measured under Formwork for TG superstructure.	Only TG deck formwork will be measured in Item no. 303, for columns, beams it will be measured in Item No 302
4		BOQ 305A: Shuttering for mill.bunker tripler floor: Please confirm the maximum weight of MS support/sheets per sqm	<b>Item description revised as below:</b> Providing permanent steel shuttering for Mill Bunker tripper floor and roof at an altitude ranging from 62m to 74m from FFL for RCC slab casting using materials like 3.15/3.2mm thick M.S sheet, angles/channels, etc., cutting to required size, lifting, placing in position of supporting members and steel sheets by tack / stitch welding at site. Rate to include cost of all materials, consumables, tools and tackles, fabrication and erection charges, complete.
5		BOQ 305B: Temperory staging: Please confirm the duration for staging	Duration is 60days
6		BOQ 920: Skylight with polycarbonate sheet: Presume that necessary supporting arrangement shall be measured and paid seperately	Yes .Will be measured and paid as per the applicable item
7		BOQ 1606A: Gypsum board false celing: Please confirm whther the grid with Aluminium or GI	As per BOQ Items it is clearly mentioned as Aluminium , bidder to quote accordingly.
8		BOQ 1809: Pressure Grouting: Please confirm the unit of measurement	BOQ Items is clear, bidder to quote accordingly

All other conditions and tender submission date remain same

AGM/Contracts