

Bharat Heavy Electricals Ltd
Component Fabrication Plant, Rudrapur
Materials Management Dept

CORRIGENDUM FOR TENDER ENQUIRY NIT_21232

Following amendments in Enq 14E0306 dated 22.01.2015 (NIT_21232) has been incorporated. Tender due date has also been extended upto 03rd March 2015, 14.00 hrs. In view of this, bidders may submit their offer on or before 03rd March 2015, 14.00 hrs.

Summary of amendments in Techno-commercial terms & conditions.		
Clause No.	Original Description in Tender	Revised Description in Tender
Price bid/ Sl. No. 1	Design, Manufacturing, Supply, Installation, Testing and Commissioning of silent DG Set - 300 KVA set as per specification in section I, II, III & IV of Part-A (Techno-commercial Specifications).	Design, Manufacturing and supply of silent DG Set - 300 KVA set or higher rating set (However no price benefits will be given in-lieu of higher rating) as per specification in section I, II, III & IV of Part-A (Techno-commercial Specifications).
Price bid/ Sl. No. 1	Erection & Commissioning charges	Installation, Testing & Commissioning charges
Section-I Sl. No. 1.1	Only those vendors, who have supplied and commissioned at least ONE equipment of Rated capacity as specified in Section IV and such equipment is presently working satisfactorily after commissioning (on the date of opening of Tender), should quote.	Only those vendors, who have supplied and commissioned at least ONE equipment of Rated capacity or higher capacity as specified in Section IV and such equipment is presently working satisfactorily after commissioning (on the date of opening of Tender), should quote.
Section-III Sl. No. 3	The bidder / vendor shall assure a continuous support for the supply of spares and service for seven years, from the date of commissioning of equipment at BHEL works.	The bidder / vendor shall assure a continuous support for the supply of spares and service for Seven Years, from the date of commissioning of equipment at BHEL works on chargeable basis.
Section-III Sl. No.13	Offer validity: 120 days	Offer validity: 120 days from the date of techno-commercial bids (Part-A) opening.

Sanjay Bhardwaj
 स्कन्दसिंह भारद्वाज / Sanjay Bhardwaj
 अभियन्ता (सामग्री प्रबंधन) Engineer (Mat. Mang.)
 भारत भारद्वाज BHEL - Rudrapur

Section-III Sl. No. 14	Delivery Period: Within 08-10 weeks from the date of placement of P.O.	Delivery Period: Supply within 12 weeks from the date of placement of P.O. Installation, Testing & Commissioning within 03 weeks from the date of supply.
Section-IV Sl. No. 2.1.8	Governor/Class(Electronic backed by mechanical/ A1 or higher)	Governor / Class: (Electronic / Electronic backed by mechanical) / A1 or higher.
Section-IV Sl. No. 2.1.15	MS Black Pipe complete with Bends & Flanges- 12 meters.	MS Black Pipe (after wards of silencer output), complete with Bends & Flanges- 12 meters.
Section-IV Sl. No. 2.1.17	Lube oil by-pass filter	Not required.
Section-IV Sl. No. 2.4.1	The control panel body will be fabricated out of 14-18 SWG MS Sheet. Panel will be suitable for floor mounting, indoor installation for placement outside the Acoustic Enclosure. Panel enclosure shall be in dust and vermin proof enclosure. Cabling/Wiring/control cabling of Panel with DG shall be done with copper conductor of appropriate size. Cables are ferruled for proper maintenance/checking/wiring of panel. Detachable cable gland plates are provided. AMF panel shall have all the necessary contactors, indicating lights, push buttons.	The control panel body will be fabricated out of 14-18 SWG MS Sheet. Panel will be suitable for floor mounting, indoor installation for placement outside the Acoustic Enclosure (Distance within 03 meters from acoustic enclosure) . Panel enclosure shall be in dust and vermin proof enclosure. Cabling/Wiring/control cabling of Panel with DG shall be done with copper conductor of appropriate size. Cables are ferruled for proper maintenance/checking/wiring of panel. Detachable cable gland plates are provided. AMF panel shall have all the necessary contactors, indicating lights, push buttons.
Section-IV Sl. No.2.4.2.3	Diesel level controller	Diesel level indicator
Section-IV Sl. No.2.4.2.4	Temperature Sensor	Water / Coolant Temperature indicator
Section-IV Sl. No. 2.5.1	The enclosure shall be in modular construction with the provision to assemble and dismantle easily at site. The enclosure shall be dispatched in dismantled condition.	The enclosure shall be in modular construction with the provision to assemble and dismantle easily at site. The enclosure may be dispatched in dismantled condition.
Section-IV Sl. No. 2.8.2	Routine Inspection test for following to be carried out by supplier as per applicable IS to be witnessed by BHEL before dispatch.	Routine Inspection test for following to be carried out by supplier as per applicable IS to be witnessed by BHEL before dispatch (all testing charges to be borne by Suppliers) .
Section-IV Sl. No.2.8.2.4	Load Test	Load Test (at 100% load for one hour and at 10% overload for one hour.)

SkandShiv Bhatnagar
 स्कन्दशिव भारद्वाज/SkandShiv Bhatnagar
 अभियन्ता (सामग्री प्रबन्धन) Engineer (Mat. Mang.)
 बी.एच.ई.एल. रुद्रपुर B.H.E.L. - Rudrapur
 263153

Section-IV Sl. No.3.0	Installation, Testing and commissioning of DG at BHEL works.	Installation, Testing and commissioning of DG at BHEL works.(Civil Foundation work by BHEL)
Section-IV Sl. No.3.1	The installation includes installation of DG set including fixing of radiator, cooling fans, first filling of Lubricating oil & coolant fixing of exhaust system, vibration dampeners(AVM pads), connection of cables, connection of earthing system, installation of acoustic chamber and any other job required to be carried out for installation of the DG SET at BHEL works.	The installation includes installation of DG set including fixing of radiator, cooling fans, first filling of Lubricating oil & coolant fixing of exhaust system, vibration dampeners (AVM pads), connection of cables, connection of earthing system (earthing pits and earthing strips shall be provided by BHEL), installation of acoustic chamber and any other job required to be carried out for installation of the DG SET at BHEL works. Un-loading & shifting by BHEL in presence of supplier.

Corrigendum as above-mentioned shall be updated on BHEL website www.bhel.com.

SkandShiv Bhardwaj
 स्कन्दशिव भारद्वाज/SkandShiv Bhardwaj
 अभियन्ता (सामग्री प्रबन्धन) Engineer(Mat.Mng.)
 बी.एच.ई.एल. रुद्रपुर B.H.E.L. -Rudrapur
 उत्तराखण्ड- 263153 Uttarakhand 263153-