

TCN-04**REF. TENDER NO. PSER:SCT:HLD-B674:06**

In connection with above mentioned tender, following changes may be noted for compliance by all bidders :-

- 1) Erection of IBR terminal points in existing unit-I are excluded from the scope of contractor. However inter-connection between Unit-I & Unit-II upto battery limit is included in the scope of contractor.
- 2) Variation of +/- 20 % mentioned anywhere in the tender is modified as +/- 30 %. Accordingly variation shall be revised as +/- 30 %, appearing at page 34 of 40, anx-I, point no. 3.
- 3) In clause no. 14.01, page 24 of 40 , anx-IV shall be read as anx-III.
- 4) BOQ cum rate schedule Vol-III is revised and is enclosed vide Rev-01, Vol-III.
- 5) In vol-II of tender, clause 16.03, terms of payment, lines "applicable for all PGS except 32,33 & 37" & "applicable for 32 & 33(insulation)" stands deleted.

These clarifications (TCN-04) will form a part of the tender document and should be submitted (duly signed) along with bid as specified. Quoted price of bidders will be presumed on the basis of original tender (including TCN-01, TCN-02 & TCN-03) & these clarifications (TCN-04). These clarifications (TCN-04) including all enclosures mentioned below will form a part of the tender document and should be submitted (duly signed) along with bid as specified. **Price shall be quoted in revised BOQ (vol-III), Revision-01 only. Revision-01 of Vol-III (BOQ cum rate schedule) is enclosed.** This BOQ supersedes earlier BOQ issued along with original tender.

- Based on clarifications furnished above, all the bidders are requested to submit their offer without any deviation, within stipulated time i.e. by **06-07-2006 (Receipt date)**. Technical bid shall be opened on next working day.
- **All the clauses of original tender document (including TCN-01, TCN-02 & TCN-03), which are not mentioned/covered in above clarifications (TCN-04), will remain unchanged. All other queries raised by bidders shall not be taken into consideration.**

ENCLOSURE : 1. [Revision-01 of BOQ cum rate schedule](#) (Vol-III) alongwith preamble.

TENDER DOCUMENT NO: PSER:SCT:HLD-B674:06

VOLUME – III

Rev-01

RATE SCHEDULE

FOR

**ERECTION , TESTING & COMMISSIONING OF SUPPLEMENTAY FIRED
1X130TPH WHRSG**

AT

**IOC HALDIA PROJECT
DIST.– MIDNAPORE, WEST BENGAL**

TENDER DOCUMENT NO: PSER:SCT:HLD-B674:06

VOLUME – III (Rev-01)

PREAMBLE

01. This preamble forms part of tender document and schedule of items. The tenderer should read this preamble carefully in rates for various items. Clauses under this preamble shall be read in conjunction with Volume-IB and Volume – II as applicable.
02. The work shall be carried out as per specifications, description of the items in this schedule and / or engineer's instructions.
03. Items of work provided in this schedule but not covered in this specification shall be executed strictly as per instruction of the engineer.
04. Unless specifically mentioned otherwise in the tender document, the tenderer shall quote for the finished items and shall provide for the complete cost towards power, fuel, tools, tackles, equipment, constructional plants, temporary works labour, dismantling of all temporary piping, structures, valves, pumps, tanks & other misc. equipment, strengthening of roads/culverts/bridges etc including arranging all clearances etc required for carrying out different activities & tests, material, levies, taxes (except service tax), transport, layout, repairs, rectification, maintenance till handing over, supervisions, colonies, shops, establishments, overheads, profits and all incidental items not specifically mentioned but reasonably implied and necessary to complete the work according to the tender document and this schedule.
05. The quantities of the various items mentioned in this schedule of items are approximate, based on very preliminary information and may vary to any extent or be deleted altogether. The quoted rates of each item will remain firm throughout the period of execution including extension, for reasons whatsoever, as long as variation in the total value of work executed under any part of this contract including extra items, if any but excluding any price variation remains, within thirty percent ($\pm 30\%$) of the total awarded price as per LOI .
06. Rates shall be quoted in figures and in words in clear legible writing. No overwriting is allowed. All scoring and cancellations should be countersigned and in case of illegibility the interpretation of engineer shall be final. All entries shall be in English language.

All works item wise shall be measured upon completion and paid for at the rates quoted and accepted as per BHEL approved payment schedule/billing break-up & tender conditions.

07. The tenderer shall be deemed to have studied the specifications and details of work to be done within the time schedule attached and to have acquainted him of the conditions prevailing at site.

08. Engineer's decision shall be final and binding on the contractor regarding clarification of items in the schedule with respect to the other sections/volumes of the contract.
09. Only authorised persons of bidder having power should sign in the price bid. All the pages must be signed.
10. For bid evaluation purpose (deciding L1), grand total price for material handling & erection, commg. portion shall be considered.
11. Quoted rates shall be inclusive of all taxes, duties etc., except service tax as per tender terms. Service tax(as applicable) shall be payable/reimbursable extra as per tender terms.

TENDER DOCUMENT NO: PSER:SCT:HLD-B674:06
VOLUME-III (Rev-01)
RATE SCHEDULE FOR THE WORK (TO BE QUOTED BY THE BIDDER)

DESCRIPTION OF WORK	QUANTITY (Metric tons)	UNIT Rate per MT, in RS. (In figures)	UNIT Rate per MT, in RS. (In words)	Amount in RS.
a) Material Handling: Receipt / Taking delivery Of materials, unloading from Trucks / Trailers, shifting, verifying, stacking storing, handing over etc. at Haldia site stores/store Yard / premises, shifting and stacking, Including verification, at Site stores / storage yard / described by other clauses of contracts etc as directed by BHEL engineer and as per detailed scope given in tender specification.	900 MT			
b) Erection, Commg. of HRSG: Providing required manpower including supervision, T&Ps and consumables for receipt of materials from stores and arranging their issue, transportation to site, temporary storage prior to erection, if required preservation including touch up painting, stacking, watch and ward, checking, chipping and leveling of foundation if necessary, pre-assembly, erection, alignment, grouting, welding, radiography, LPI / MPI Testing, wherever required, heat treatment, application of thermal insulation, finish painting, including supply of paints etc. as described in other clause etc., other commissioning activities including post commissioning trial operation and full load operation of erection testing & commissioning of 1x130 ton per hour WHRSG (phase – 2) with auxiliaries and pipings at IOCL - Haldia, West Bengal, as per detailed scope given in tender specification.	900 MT			
GRAND TOTAL AMOUNT IN RUPEES				