

INSTALLATION OF CABLE RACKS, LAYING & TERMINATION OF POWER CABLES IN NEW FACTORY UNDER CAS Phase-II.

Enquiry No. 9250800129.

NIT:5316

Dated 27.09.2008.

S.NO:	DESCRIPTION	UOM	QTY	UNIT RATE in Rs.	VALUE in Rs.
30	Excavation of earth (ordinary soil) to a depth of 0.8m and 0.3m width and laying single run of Medium voltage 3.5 core 185sqmm PVC AA cable in the trench and supply and laying of quality brick and river sand over the cables and closing the trench with the excavated earth to make good. The Medium voltage 3.5-core 95sqmm PVC AA cable will be supplied by BHEL free of cost at site. Required quantity of Brick and sand will be supplied by the contractor.	MTRS	3000		

Kindly read as 3.5-core 185sqmm instead of 3.5-core 95sqmm in item no:30 of the Enquiry No. 9250800129.

INSTALLATION OF CABLE RACKS, LAYING & TERMINATION OF POWER CABLES IN NEW FACTORY UNDER CAS Phase-II.

Enquiry No. 9250800129.

NIT:5316

Dated 27.09.2008.

S.NO:	DESCRIPTION	UOM	QTY	UNIT RATE in Rs.	VALUE in Rs.
30	Excavation of earth (ordinary soil) to a depth of 0.8m and 0.3m width and laying single run of Medium voltage 3.5 core 185sqmm PVC AA cable in the trench and supply and laying of quality brick and river sand over the cables and closing the trench with the excavated earth to make good. The Medium voltage 3.5-core 185sqmm PVC AA cable will be supplied by BHEL free of cost at site. Required quantity of Brick and sand will be supplied by the contractor.	MTRS	3000		