

**NAME OF THE WORK: ERECTION AND COMMISSIONING  
OF 750KVA &1000KVA COMPACT SUBSTATIONS UNDER CAS-PHASE-II  
Enquiry No. 9250800131 Dated 27.09.2008.  
NIT5318**

| Sl.no. | Description  | UOM | Qty | UNIT RATE IN Rs. | VALUE IN Rs. |
|--------|--|-----|-----|------------------|--------------|
| 100    | Erection , Testing and commissioning of floor mounting cubicle type MV Switch gear panel approx size 9000M long x1200mm depth x 2 500mm ht weight 2500 Kgs consisting of 19 nos ACB breakers on the floor with required supply of foundation bolts ,grouting ,earthing , cementing etc . During erection all the panel inner wirings should be checkedup for its proper tightning , coupling the panel compartments bus bars , minor touching up of painting , writing of the cables sizes etc should be carriedout as per Engineer instructions at the time of commissioning .(The MV switch gear panels in compartments will be issued by BHEL free of cost at site) | NOS | 6   |                  |              |

Kindly read as 9000mm instead of 9000M in item no:100 of the Enquiry No. 9250800131.

**NAME OF THE WORK: ERECTION AND COMMISSIONING  
OF 750KVA &1000KVA COMPACT SUBSTATIONS UNDER CAS-PHASE-II  
Enquiry No. 9250800131 Dated 27.09.2008.  
NIT:5318**

| Sl.no. | Description   | UOM | Qty | UNIT RATE IN Rs. | VALUE IN Rs. |
|--------|---|-----|-----|------------------|--------------|
| 100    | Erection , Testing and commissioning of floor mounting cubicle type MV Switch gear panel approx size 9000mm long x1200mm depth x 2 500mm ht weight 2500 Kgs consisting of 19 nos ACB breakers on the floor with required supply of foundation bolts ,grouting ,earthing , cementing etc . During erection all the panel inner wirings should be checkedup for its proper tightning , coupling the panel compartments bus bars , minor touching up of painting , writing of the cables sizes etc should be carriedout as per Engineer instructions at the time of commissioning .(The MV switch gear panels in compartments will be issued by BHEL free of cost at site) | NOS | 6   |                  |              |