

Sl. No.	Quantity	Description of work	Rate (both in figures and in words)	Unit	Amount
a	100	Door With Frame		SQM	

An additional 5 mm thick PVC strip of 20mm wide width is to be stuck on the interior side of the C-Channel using solvent cement etc., complete all as per manufacturer's specification and direction of Engineer-in-charge. The door frame shall be of size 50 x 47mm made out of 5 mm thick extruded rigid PVC foam sheet mitre at corners, joined perfectly and inserted with 2 Nos. of 150 mm long L shape brackets made of 15 mm MS square tube. The vertical door profile is to be reinforced with 19 Gauge 19 mm MS square tube, all weather sealed throughout the frame. The shutter shall be provided with powder coated 6" tower bolt - 3 Nos, 4" handle - 2 Nos and 3 Nos. of 4" SS hinge. Frame shall have to be rigidly fixed with wall by means of 100 mm SS screws driven at least not less than 10 places

Total -- -- --

(RUPEES ONLY)

NOTE:-

1. Service Tax will be extra if applicable for this contract. Service Tax paid by the contractor with respect to this work will be reimbursed by BHEL on production of documentary evidence for having paid the service tax.
2. The period of contract is Fifteen months. However the contractor is required to maintain stage wise schedule of completion as indicated in the preamble.

CONTRACTOR

60

ACCEPTING OFFICER