

on of Press shop Extension towards South Side including Machine
 Foundation


MACHINE FOUNDATION

Schedule 'A'

Annexure-II

SL. NO.	DESCRIPTION OF WORKS	Unit	Quantity	Rate to be quoted by the contractor		Amount	
				Rs.	P.	Rs.	P.
1	Providing & fixing wooden pockets for casting of foundation to get different shape.	Each	515.00				
2	Providing & fixing in position 25mm thick bitumen impregnated fibre board conforming to IS 1838 including cost of primer, sealing compound in expansion joints.	Sqm	180.00				
3	Grouting below bed plate/machine foundation including pockets & machine bed with conbextra GP2, sika grout 214 or equivalent i/c cleaning & vibrating etc. complete mortar is to be machine mixed.	Cum	17.00				
4	Fabrication & Erection of temporary barricade with structural steel members in single/built up sections, fixing them with A.C./G.S. sheets along with all necessary fittings / fixtures for construction of machine foundation so as to prevent fouling of adjoining/ nearby areas with dirt/dust/earth e.t.c., followed by dismantling the above complete including dismantling & stacking with a lead of 50m.	Sqm	857.00				
5	Providing & laying of coarse sand conforming to IS 383-1970 after screening and removed of foreign material in foundation plinth and around the foundation.	Cum	121.00				
6	Steel work for fabrication & placing in position embedment and inserts in RCC including cutting welding the anchor bar as per drawing and site requirement. The inserts made from the MS plate, angle or channel	MT	1.50				
	Total Cost of Annexure-II						

Sr. Engineer(MOD/Civil)



PDF

Complete

*Your complimentary
use period has ended.
Thank you for using
PDF Complete.*

**Click Here to upgrade to
Unlimited Pages and Expanded Features**