

Internal/External repairing of structural cracks and Painting work in EMRP					
			NIT NO. BHEL/EMRP/HR/13-14/T-05		
PRICE SCHEDULE					
Sr. No.	Item Brief	Qty	Unit	Unit Rate (In Rs.)	Amount (In Rs.)
1	2	3	4	5	6=(4x5)
1	Providing all materials and labours for painting with Anti corrosive Paint over Roof Trusses, Purlins, ISMB Coloumns, Crane Shaft and other Steel Structures in workshop building including thoroughly cleaning the existing surface by scrapping, applying one coat of Steel Primer of approved brand and two or more coats of Anti Corrosive Paint of approved brand and shade complete including making necessary arrangement of scaffolding and other safety precautions to the satisfaction of Engineer In-charge.				
1.1	With Epoxy Paint	16500	Sqft		
2	Providing all materials and labours for painting internal surface of the office building with Luster paint of approved brand and shade including surface preparation by scrapping and applying a coat of White Cement based Putty of average thickness 1mm of approved brand to be followed with 2 coats of chalk putty to make surface smooth and a coat of appropriate primer and 2 or more coats of paint complete including cost of scaffolding, cleaning of the entire area to the satisfaction of Engineer In-charge.	30000	Sqft		
3	Providing and applying white cement based putty of average thickness 1mm of approved brand and manufacturer to prepare the surface even and smooth complete.	5000	Sqft		
4	Providing and applying Rusticide SS Rust Passivator or equivalent as approved to the existing reinforcement bars including wire brushing, cleaning etc. complete as directed. Note: The item shall be paid on actual consumption of Rusticide SS or Equivalent.	10	Ltr		
5	Providing and applying two coats of rust preventor slurry made out of "Polyalk Fixoprime" or equivalent as approved and Cement in proportion 1:1 to existing reinforcement bars as directed complete. Note: The item shall be paid on actual consumption of Polyalk Fixoprime or equivalent.	15	Kg		
6	Providing and applying "Polyalk EP Polymer Modified Cement Mortar" or equivalent as approved in required proportions to RCC members including hand packing, curing and making the surface rough for palstering etc. complete as directed. Note: The item shall be paid on actual consumption of Polymer latex "polyalk EP" or equivalent.				
6.1	In proportion 1:5:15	100	Kg		
7	Repair with cement plaster with cement mortar of 1:4 ratio complete including cost of all materials, labours and other incidentals etc. as directed by Engineer In-charge.	500	Sqft		
Sub Total					
Add Taxes @					
Total					

Amount in Words: Rs.