

Earthing BOQ (below ground) for 400kV FSC wardha Project

Sl. No.	Item Description	Unit	Qty	Rate	Amount
1	Aux Earth Mat (1.5mX1.5m) with spacing between conductor 300mm	Nos.	30		
2	No. of Pig tail risers	Nos.	200		
3	Laying of subsidiary conductor between pig tail riser and main earth mat	Meter	1500		
4	Test pit for Rod Electrode	Nos.	9		
5	Test pit for electronic earthing	Nos.	4		
	Total Amount				

Note:

The indicated Qty is tentative and may vary upto any extent. Earthing conductor/conductor means 40mm dia MS Rod.