

BILL OF QUANTITY- CUM -PRICE SCHEDULE

Name of Project : 400/220kV Substation Extension at Bellary .
Name of Work : Gravelling Works in Switchyard .

S.No.	Description of Item	Quantity	Unit	Unit Rate (Rs)	Amount (Rs)
1	Providing and laying stone aggregate in switch yard areas in two layers of 75 mm each using 40 mm aggregates size in top layer and 20mm size aggregate in bottom layer .Before laying the stone aggregates , the yard surface shall be treated with antiweed treatment all complete as per Customer's specification. (The rate shall be inclusive of all materials ,labour,loading,unloading and surface preparation etc. required for aggregate laying and antiweed treatment)	30000	sqm	100.00	3000000.00