

BHEL replies for queries raised by bidders in pre-bid meeting held on 17.06.2016

Tender enquiry no. T7H1P99301 (NIT 27846)

Description: Supply of Column Posts (required for MMS) for NTPC 1x50 MWp Solar PV project, Mandasaur

Sl no	Query	BHEL reply
1	Does scope include E&C also?	No. E&C not applicable.
2	a) Galvanizing to be by NTPC approved sources	a) Shall be as per NIT. List of sub vendors for Galvanization of MMS are not specified by NTPC.
	b) Galvanizing done at in-house acceptable?	b) Shall be as per Pre-Qualifying Criteria i.e., Bidder should have experience in supply of Galvanized members. Requirement of in-house/outsourcing is not mentioned in NIT
3	Billing to be done at base weight or actual weight	Billing to be done on final actual weight. However, bidder to clearly mention both the weights on the package
4	a) The size of members, dimensions and model arrangement are liable to change?	a) Vendors may pl. note that the size of members, their dimensions and model arrangement are liable to change. The GA drawing shown in MMS is for tender purpose only as indicated in NIT.
	b) Fabrication drawings shall be in BHEL's or Bidder's scope?	b) All fabrication drawings indicating slotted holes, welding details, radius of sections, etc., shall be given to successful bidder.
5	Does we need to submit filled in C-form format given in NIT along with part-I bid	BHEL will issue C-form based on request from vendor in the prescribed format for a supply with invoice details. Hence it is applicable after receipt of order. Therefore, while submission of part-I bids, bidder to accept the format given.
6	Does we need to submit BG, CPBG along with part-I bid	BG, CPBG are to be submitted on receipt of purchase order from BHEL. Therefore, while submission of part-I bids, bidder to accept the format given.
7	Above 3000 mm we will provide splice plate joint. ----- Allowed or Not	Splice plate joints are not allowed.
8	Cold roll forming machine is not available at our facility. We have cold forming machine upto 3000 mm. ----- Acceptable or Not	Not Acceptable.
9	As per the tender the billing quantity is supposed to be on actual Weighment basis, since the material is hot dipped galvanized, the weight of material will increase by 4-5% approximately, hence kindly reconfirm if we will be able to do the billing on actual Weighment basis as we will calculate our costing based on your feedback.	Vendor to note that the measurement of weight shall be on the finished product only as per NIT.
	EG. CL1 weight as per technical specification is 43.12 but actual Weighment after Galvanizing may be around 45.27	
10	Weighment to be done at vendor works (or near to vendor works) prior to dispatch is taken for final payment?	Weighment to be done at vendor works (or near to vendor works) prior to dispatch, and also at site (or near to site). Payment will be done as per site certification based on weighment done at site (or near to site). How ever, vendor shall submit certified Weigh Bridge documents for empty truck & loaded truck in both of the above cases. Vendor to submit site certification also. BHEL reserves the right to inspect/witness any of the weighment.