

BHEL replies for queries raised by bidders in pre-bid meeting held on 17.06.2016

Tender enquiry no. T7H1P99303 (NIT 27848)

Description: Supply of Fasteners (required for MMS) for NTPC 1x50 MWp Solar PV project, Mandasaur

SI NO	Bidder's Query	Reply given by BHEL
1	How should be the packing of fasteners?	Packing shall be as per clause "J" of Specification PY60052 (reproduced-below):- <i>Hardware shall be supplied in plastic wrapped hessian cartons/ plastic wrapped thick cardboard cartons to avoid bursting and spillage of contents during transport and storage at site. Each carton shall be clearly identified with the type of hardware packed in it and its quantity. Cartons shall be in weight not exceeding 30 kg for easy handling and storage at site.</i>
2	As fasteners will be packed in boxes, the weight of boxes will be included in the weightment for dispatches	<ul style="list-style-type: none"> • The weight of packing material like boxes, etc to be deducted for arriving the weight of fasteners dispatched. • The weight of empty boxes to be measured before putting the fasteners inside the boxes. • Bidder to clearly label weight of material inside box and total weight incl. box clearly on the carton.
3	Please provide drawings of fasteners	Fasteners are to be provided as per IS codes and no separate drawing shall be issued by BHEL.
4	Please confirm whether full thread of half thread bolt	Both Full and Half thread bolts may be required. However, the requirement shall be communicated to vendor before price bid opening as stated in NIT.
5	Please confirm numbers of Nut/ plain washer/ spring washer to be given along with bolt	Each Fastener comprises of Bolt-1 No., Nut-1 No., Spring Washer-1 No. and Plain Washer-2 Nos. The total number of fasteners required for each MMS and the total number of MMS required are already communicated in the Tender document.
4	Please recheck the length of M10x15 mm as it is insufficient to fasten with washers and nut	M10x25mm fasteners are to be provided, in place of M10x15mm
5	Weighment to be done at vendor works (or near to vendor works) prior to dispatch is taken for final payment?	Weighment to be done at vendor works (or near to vendor works) prior to dispatch, and also at site (or near to site). Payment will be done as per site certification based on weightment done at site (or near to site). However, vendor shall submit certified Weigh Bridge documents for empty truck & loaded truck in both of the above cases. Vendor to submit site certification also. BHEL reserves the right to inspect/witness any of the weighment.