

Issued to agency:



BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM, HYDERABAD-32
FACTORY CIVIL ENGINEERING DEPARTMENT

SCHEDULE- A

Tender Notice No:

PRICE BID

HY/FCD/OT-16/2009-10 , Dt:- 10.11.2009

Item no : 01

Name of work : - Civil Works For Shifting of Gas turbine assembly activities to New FR-9FA assembly Bay.

S. No	Description	Approx Qty	Unit	Rate in Rs	Amount (Rs)
1	Dismantling reinforced cement concrete / plain cement concrete and disposing of debries upto to a lead of 2 KM including loading, unloading and spreading as directed by Engineer-in-charge etc., complete.	35.00	Cu.m	582.68	20393.80
2	Earth work in excavation in all soils by mechanical means (Hydraulic Excavtors) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50M.	80.00	Cu.m	103.40	8272.00
3	Earth work in excavation by mechanical means (Hydraulic Excavators) / manual measn over areas (exceeding 30 cm in depth , 1.5 m in width as well as 10 Sq.m on plan) including disposal of excavated earth , lead upto 50 m and lift upto 1.5 m, disposing earth to be levelled and neatly dressed for Hard Rock (Blasting prohibited).	7.00	Cu.M	325.25	2276.75
4	Providing and laying in position cement concrete of specified garde excluding the cost of centering and shuttering including consolidation by vibrations for all works up to plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size).	12.00	Cu.M	2449.00	29388.00
5	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering ,shuttering, finishing and reinforcement ,including consolidation by vibrations for all works up to plinth level with 1:1½ :3 (1 cement : 1½ coarse sand : 3 graded stone aggregate of 20 mm nominal size).	108.00	Cu.M	3732.00	403056.00

S. No	Description	Approx Qty	Unit	Rate in Rs	Amount (Rs)
6	Centering and shuttering including strutting, propping etc; and removal of form work, for columns, pillars,peirs,abutments,machine foundations, posts and struts.	70.00	Sq.M	180.40	12628.00
7	Reinforcement for R.C.C. work including straightening , cutting , bending , placing in position and binding grills with binding wire all complete by cold twisted bars.	8.64	M.T	42700.00	368928.00
8	Conveyance of excavated spoil up to a lead of 2 Kms, including loading , unloading and spreading etc. complete as directed by Engineer- in- charge.	80.00	Cu.M	56.41	4512.80
9	Grouting with cement mortar 1:1 including cost of all materials, labour, curing, for all leads and lifts etc; complete.For pockets	4.00	Cu.m	6016.56	24066.24
Total Rs.					873,521.59
Total : Rs. Eight Lakhs Seventy Three thousand five hundred twenty two only.					

Service Tax:- The Service tax as applicable is extra which will be paid by BHEL to the agency after submission of necessary valid documents by the agency.

Note : The Tenders are required to quote the tender value on percentage (%) basis at excess or less or on as per estimate value

Tender %	In figure	In words
Excess		
Less		
Estimated Rate only		

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer