



**BHARAT HEAVY ELECTRICALS LIMITED  
RAMACHANDRAPURAM::HYDERABAD::32  
FACTORY CIVIL DEPARTMENT**

SCHEDULE- A

Tender Notice No:

HY/FCD/OT- 06 /2010-11 , Dt:- 28.06.2010

**PRICE BID**

Item no : 01

**Name of work : Internal Roads at New Blade Shop (Providing WBM BT road work).**

S.No	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
	<b>Phase - I (WBM work)</b>				
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidation with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth lead upto 50 metres.	7047.00	Sq.m	33.90	238893.30
2	Supply and Stacking at site of 63 mm to 45 mm size stone aggregate.	1409.40	Cu.m	768.45	1083053.43
3	Supply and Stacking at site of morrum.	493.29	Cu.m	421.85	208094.39
4	Laying spreading and compacting stone aggregate of specified sizes to WBM specification including spreading in uniform thickness, hand picking, rolling with 3 wheeled road / vibratory roller 8 - 10 tonne in stages to proper grade and camber , applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate watering and compaction to the required density.	1902.69	Cu.m	192.55	366362.96

S.No	Description	Qty	Unit	Rate (Rs)	Amount (Rs)
<b>Phase - II (B.T. work)</b>					
1	Providing and applying tack coat using hot straight run bitumen of grade 80/100 including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications on WBM surface @ 0.75 Kg/Sq. m .	7047.00	sq.m	32.72	230577.84
2	Providing and Laying <b>premix bituminous macadam base course</b> with stone aggregate of quality size and grading as specified in CPWD specification and straight run bitumen of grade 80/100 @ 4 % by weight of total mix including hot mixing of stone aggregate and bitumen in hot mix plant, transporting mixed material and laying mixed material with paver finisher to the required level and grade , rolling with road roller of 8 to 10 tonne capacity to achieve the required compaction and density of <b>50 mm compacted thickness</b> .	7047.00	Sq.m	279.60	1970341.20
				<b>Total</b>	<b>40,97,323.12</b>
<b>Total : Rs. Forty lakhs ninty seven thousand three hundred twenty three only.</b>					

**Note:** The B.T. work has to be commenced by the agency after 2 Months of laying of WBM road and to ensure proper consolidation.

**Service Tax:-** The Service tax as applicable is extra which will be paid by BHEL to the ager after submission of necessary valid documents by the agency.

**Note :** The Tenders are required to quote the tender value on percentage (%) basis at excess or less or on as per estimate value

Tender %	In figure	In words
Excess		
Less		
Estimated value		

**Name of the Contractor :**

**Signature of the Contractor**

**Accounts Representative**

**Opening officer**