



**BHARAT HEAVY ELECTRICALS LIMITED**  
 RAMACHANDRAPURAM, HYDERABAD-32  
 FACTORY CIVIL ENGINEERING DEPARTMENT

Issued to agency:

## SCHEDULE- A

Tender Notice No:

**PRICE BID**

HY/FCD/OT-6/2009-10 , Dt:23.07.09

Item no: 04

**Name of work : - Demolishing of Coal ash bunker at Boiler house  
 in Factory area**

Sl. No	Description of the item	Qty	Unit	Rate in Rs	Amount Rs.
	<b>Demolishing of Coal Ash Bunker - Part - I</b>				
1	Dismantling of Coal Ash bunker (Hopper) consisting RCC frame work, brick work and MS of height approximately 18.50M and disposing the material upto a lead of 2 KM , site clearance as directed by the Enginner -incharge.	180.00	Cu.m	7345.00	1322100.00
	<b>Total of part - I</b>				<b>1322100.00</b>
	<b>Dismantling of 5 Storied (23m height) Stair case and adjoining cabins. - Part -II</b>				
1	Dismantling <b>brick masonry</b> walls for all heights, removing and clearing the debries and carting away upto to lead of 2 KM including loading, unloading and spreading segregating useful materials as directed by Engineer-in-charge including the cost of all labour scaffolding etc., complete.(conventional method).				
a)	Upto 1st floor	145.00	Cum	1620.00	234900.00
b)	Upto 2nd floor	145.00	Cum	1940.00	281300.00
c)	Upto 3rd floor	145.00	Cum	2480.00	359600.00
d)	Up to 4th floor	50.00	Cum	3025.00	151250.00
e)	Up to 5th floor	50.00	Cum	3455.00	172750.00
2	Dismantling <b>reinforced cement concrete / plain cement concrete</b> and disposing of debries upto to a lead of 2 KM including loading, unloading and spreading as directed by Engineer-in-charge etc., complete.				
a)	Upto 1st floor	40.00	Cum	3780.00	151200.00
b)	Upto 2nd floor	40.00	Cum	4420.00	176800.00
c)	Upto 3rd floor	40.00	Cum	5290.00	211600.00
d)	Up to 4th floor	35.00	Cum	6260.00	219100.00

Sl. No	Description of the item	Qty	Unit	Rate in Rs	Amount Rs.	
e)	Up to 5th floor	35.00	Cum	7450.00	260750.00	
3	Dismantling doors ,windows,and clerestory windows(steel or wood) shutter including chowkhats,architrave,holdfasts etc complete and stacking within 50 m lead of area 3.00 sq meters and below (conventional method).	68.00	Nos	54.60	3712.80	
<b>Total of part - II</b>					<b>2222962.80</b>	
<b>Dismantling of Acid tanks - 4 No.s -Part -III</b>						
1	Dismantling of Acid tanks .	4.00	No.s	15000.00	60000.00	
2	RCC Foundations	38.00	Cu.m	3500.00	133000.00	
3	Partion wall Dismantaling	10.00	Cu.m	1500.00	15000.00	
4	Disamantaling M.S. Stair Case plat forms and handing over the material to BHEL.	2.00	MT	7200.00	14400.00	
<b>Note: All dismantled material/scrap is the property of BHEL</b>					<b>Total of part - III</b>	<b>222400.00</b>
<b>Total Of Part I + Part - II + Part -III in Rs.</b>					<b>3,767,462.80</b>	

Rupees : Thirty Seven lakhs sixty seven thousand four hundred sixty three only.

**Service Tax:-** The Service tax as applicable is extra which will be paid by BHEL to the agency after submission of necessary valid documents by the agency.

**Note :** The Tenders are required to quote the tender value on percentage (%) basis at

Tender %	In figure	In words
Excess		
Less		
Estimated Rate only		

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer