



**BHARAT HEAVY ELECTRICALS LIMITED  
RAMACHANDRAPURAM::HYDERABAD::32  
FACTORY CIVIL DEPARTMENT**

**SCHEDULE- A**

Tender Notice No:

**PRICE BID**

HY/FCD/OT- 10 /2010-11, Dt:- 29.07.2010

Item no : 02

**Name of work : Misc. Masonry works in Factory and Admn. Building area.**

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Demolishing brick work manually / by mechanically means including stacking of serviceable material and disposing off unserviceable materials within 50 meters lead as per directions off Engineer-in-charge. - in cement mortar	100.00	Cu.M	310.75	31075.00
2	Demolishing stone rubble masonry manually / by means including stacking of serviceable material and disposing of unserviceable materials within 50 meters lead as per directions of Engineer-in-charge. - in cement mortar	5.00	Cu.M	370.75	1853.75
3	Dismantling doors, windows and clerestory windows (steel & wood) shutters including chowkhats , architrave , holdfasts etc. complete and stacking within 50 meters lead.	25.00	Sq.M	75.35	1883.75
4a	Earth work in excavation by mechanical means (Hydraulic Excavtors) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan ) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m.	150.00	Cu.m	103.40	15510.00
4b	----do---- up to First additional depth of 1.50 M to 3.00 M.	8.00	Cu.M	122.30	978.40
5	Earth work in excavation by mechanical means (Hydraulic Excavtors) / manual means over areas (exceeding 30 cm in depth , 1.5 m in width as well as 10 Sq.m on plan) including disposal of excavated earth , lead upto 50 m and lift upto 1.5 m, disposing earth to be levelled and neatly dressed for <b>Hard Rock</b> ( Blasting prohibited).	5.00	Cu.M	325.25	1626.25

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
6	<b>Filling</b> available eacavated earth (excluding rock) intrenches , plinth , sides of foundations etc. in layers not exceeding 20 cm in depth , consolidation each deposited layer by ramming and watering , lead upto 50 m lift upto 1.5 m .	40.00	Cu.M	45.70	1828.00
7	Conveyance of excavated spoil up to a lead of 2 Kms, including loading , unloading and spreading etc. complete as directed by Engineer- in- charge.	150.00	Cu.M	56.41	8461.50
8	Providing and laying in position plain cement concrete of specified garde, consolidation excluding the cost of centering and shuttering - all work up to plinth level with <b>1:4:8</b> (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size ).	175.00	One Cu.M	2449.00	428575.00
9 a	Providing and laying in position plain cement concrete of specified garde, consolidation by <b>vibration</b> excluding the cost of centering and shuttering - all work up to plinth level with <b>1:2:4</b> (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size ).	70.00	One Cu.M	3257.45	228021.50
9 b	<b>Plain cement concrete work in walls</b> (any thickness) including attached pilasters , buttersses , plinth and string courses , fillets , columns , lintels , beams,pillars, piers,abutments. Posts and struts etc. up to <b>floor five level</b> excluding cost of centering , shuttering , finishing and reinforcement : <b>with 1:2:4</b> (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	15.00	One Cu.M	3579.10	53686.50
10	<b>Reinforced cement concrete work in walls</b> (any thickness) including attached pilasters , buttersses , plinth and string courses , fillets , columns , lintels , beams,pillars, piers,abutments. Posts and struts etc. up to <b>floor five level</b> excluding cost of centering , shuttering , finishing and reinforcement : <b>with 1:2:4</b> (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).				
a	<b>for slab</b>	1.00	One Cu.M	3673.85	3673.85
b	<b>columns and column footings</b>	1.00	One Cu.M	3720.00	3720.00
c	<b>Lintels and beams</b>	1.00	One Cu.M	3720.00	3720.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
d	walls	1.00	One Cu.M	3720.00	3720.00
e	Providing and laying in position <b>reinforced cement concrete</b> excluding cost of centering , shuttering , finishing and reinforcement all works <b>upto plinth level : with 1:2:4</b> (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	1.50	One Cu.M	3359.60	5039.40
11	Coursed rubble masonry (second sort) with hard stone in foundations & plinth with cement mortar 1:6 ( 1 Cement : 6 Coarse sand).	20.00	One Cu.M	1913.10	38262.00
12	Brick work with FPS bricks of class designation 75 in superstructure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6	90.00	One Cu.M	2463.60	221724.00
13 a	Half brick masnory with FPS bricks of glass designation 75 in superstructure above plinth level upto floor V level in cement mortar 1:4 (1cement : 4 Coarse sand) including plastering with cement mortar 1:6 20 mm ( 1 cement : 6 coarse sand) on both sides.	20.00	One Cu.M	405.70	8114.00
b	...do.. With reinforcement of 6 mm dia MS rounds at every 4th layer, but excluding cost of steel and its fabrication.	5.00	One Cu.M	453.50	2267.50
14	Plastering in <b>CM 1:6 , 12 mm</b> thick to internal and external surfaces of walls including the cost of all materials , labour , curing etc, complete.	90.00	One Sq.m	82.55	7429.50
15a	Plastering in <b>CM 1:6 , 20 mm</b> thick to internal and external surfaces of walls including the cost of all materials , labour , curing etc, complete - Upto 10.00 m height	500.00	One Sq.m	102.90	51450.00
15b	-----do-----for height 10.01 m to 14.40 m height.	20.00	One Sq.m	176.00	3520.00
15c	-----do-----for height 14.41 m to 20.00 m height.	20.00	One Sq.m	249.00	4980.00
16	Plastering to the ceiling in CM 1:3 , 6mm ( 1 cement : fine sand ) .	15.00	One Sq.m	62.15	932.25
17	Finishing the top of the concrete flooring in CM 1:3, 15mm thick including neat finishing, curing etc;complete.	120.00	One Sq.m	122.50	14700.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
18	Flooring in 25 mm thick using 1:3 (1cement : 3 parts of granite stone chips of 3 to 10 mm guage ( no sand ) ellies pattern first sort including neat finishing, curing, cost of materials etc; complete.	500.00	One Sq.m	196.00	98000.00
19	Flooring in 25 mm thick using 1:1 granolithic flooring in 25 mm thick (1 cement : 1 parts of granite stone chips of 3 to 10 mm guage ( no sand ) ellies pattern first sort including neat finishing, curing, cost of materials etc; complete.	300.00	One Sq.m	206.45	61935.00
20	Fixing Chowkhat in existing opening in brick / RCC wall with dash fastners of appropriate size / chemical fastener (3No.s on each vertical member of door chowkhat and 2 No.s on each verticle member of window 1.20m height as per CPWD specifications including cost of dash fasteners / chemical fastners .	10.00	Each	81.05	810.50
21	Providing and fixing 16mm MS Fan Clamps of standard shape and size in exisiting RCC slab including cutting chase and making good and painting exposed portion of the calmps complete .	7.00	Each	113.85	796.95
22	Reinforcment for R.C.C. work including straightening , cutting , bending , placing in position and binding all complete by cold twisted bars.	1.00	M.T	42700.00	42700.00
23	Dismantling the broken RCC covers and casting and fixing with new cable trench covers with reinforced cement concrete 1:1.5:3 using 20 mm and down graded metal including the cost of cutting, welding of angle iron frame, sprinkling of ironite at 2 Kgs/sq.m. and neat finishing excluding the cost of angle iron and M.S. reinforcement (Angle iron will be supplied by BHEL at their stores and M.S. rounds on cost recovery basis under separate item by BHEL at their stores). Thickness of covers will be varying from 75 mm to 100 mm.	40.00	One Sq.m	400.70	16028.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
24	Granolithic topping of 25 mm thick using 1 cement 1 granite chips of 10mm down graded laid over base concrete when it is green conditions and ironite finishing 12mm thick using a mix of 50Kg of ironite , 200 Kg of cement and 0.30 Cu.m of granite metal 6mm down graded including cost of from work , curing etc. complete.	7.50	One Sq.m	485.00	3637.50
25	Plastering over <b>roof slab in CM 1:4, 20mm</b> thick mixed with water proofing compound, Make: "Sika" @ 3% by weight of cement as per manufacturer's specification, curing as directed. Rate quoted shall include finishing, cost of all materials and labour etc., complete. (Cement =7.69 kgs/sq.m x3% WP@ Rs 20.00 per kg=Rs 4.61) upto 10 m height.	500.00	One Sq.m	115.05	57525.00
26 a	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacture) of approved make in all colours, shades except burgundy, bottle green , black of any size as approved by engineer-in-charge in skirting , risers of steps and dados over 12mm thick bed of cement mortar 1:3 (1cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 Kg per Sq.m including pointing in white cement mixed with pigment of matching shade complete.	150.00	One Sq.m	556.80	83520.00
26 b	Providing and Laying ceramic glazed floor tiles 300 X 300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS:15622 of approved make in colours such as white , Ivory , grey , fume red brown , laid on 20mm thick cement mortar 1:4 (1cement : 4 Coarse sand) including pointing the joints with white cement and matching pigments etc; complete.	100.00	One Sq.m	598.65	59865.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
27	Supplying and laying of <b>vitrified tiles</b> of brighter shades and marble design of Premium Quality (1st quality ) in required texture, design and colour, for flooring /skirting /cladding using vitrified tiles of size <b>600 x 600mmx8 mm</b> thick of approved make. It includes cost of cutting, chamfering of tiles to required size, with base of Conmax C - 500 tile adhesive for fixing tiles on existing mosaic/cement flooring, jointing the tiles with colour tint etc. complete as directed by Engineer-in-charge. The rate quoted shall include cost of all materials, labour, adhesives, colour tint material, leads and lifts etc. complete. Amount will be paid on the basis of measurement of the area of finished work only. It also includes surface preparation of existing ceramic floor giving necessary slopes, cleaning joints and grouting joints with pigmented additives to match shade of the tile, making pockets for electrical, communication, network cables etc. complete as directed by Engineer-in-charge. Amount will be paid on the basis of measurement for finished work only.	100.00	One Sq.m	950.00	95000.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
28	Providing and fixing 10mm thick <b>acid and alkali resitant tiles</b> of approved make and colour using acid and or aikali reising mortar bedding anf joints filled with acid and or alkali resisting cement as per Is:4457 complete as per the directions of Engineer-in-charge in flooring on a bed of 10 mm thick mortar 1:4 (1acid proof cement : 4 coarse sand) with acid and alkali resistant tile.	200.00	One Sq.m	873.00	174600.00
				<b>Total</b>	<b>18,41,170.10</b>
<b>Total : Rs. Eighteen lakhs forty one thousand one hundred seventy only.</b>					

**Service Tax:-** The Service tax as applicable is extra which will be paid by BHEL to the agency after submission of necessary valid documents by the agency.

**Note :** The Tenders are required to quote the tender value on percentage (%) basis at excess or less or on as per estimate value

Tender %	In figure	In words
Excess		
Less		
Estimated value		

**Name of the Contractor :**

**Signature of the Contractor**

**Accounts Representative**

**Opening officer**