



BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRA PURAM:: HYDERABAD:: 32
FACTORY CIVIL ENGINEERING DEPARTMENT

SCHEDULE- A

Tender Notice No:

HY/FCD/OT-10/2008-09 , Dt:23.09.08

PRICE BID

Item no: 1

Name of work:- Cement concrete flooring in 04 block near columns between C3 & D3 and C11 & D11.

S.No	Description of the item	Qty	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic Excavtors) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50m	75.00	Cu.m	103.40	7755.00
2	Providing and laying in position cement concrete of specified garde excluding the cost of centering and shuttering including consolidation by vibrations for all works up to plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size).	60.00	Cu.M	2449.00	146940.00
3	Providing and laying in position cement concrete of specified garde excluding the cost of centering and shuttering including consolidation by vibrations for all works up to plinth level with 1:2:4 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size).	10.00	Cu.M	3257.45	32574.50
4	Flooring in 25mm thick using 1 cement and 3 parts of granite stone chips of 3 to 10mm gauge (no sand) ellis pattern first sort including neat finishing , curing, cost of materials etc; complete.	240.00	Sq.m	196.00	47040.00
5	Dismantling brick masonry walls for all heights, removing and clearing the debries and carting away upto to a lead of 2KM including loading, unloading and spreading segregating useful materials as directed by Engineer-in-charge including the cost of all labour scaffolding etc; complete.	7.00	Cu.M	355.88	2491.16
6	Demolishing R.C.C. work manually / by mechanically means including stacking of steel bars and disposal of unserviceable materials within 2.00 Km lead as per direction of Engineer - in - charge .	72.00	Cu.M	582.68	41952.96
7	Brick work with FPS bricks of class designation 75 in superstructure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6.	7.50	Cu.M	2357.40	17680.50
8	Plastering in CM 1:6 , 20 mm thick to internal and external surfaces of walls including the cost of all materials , labour , curing etc, complete - Upto 10.00 m height	40.00	Sq.m	102.90	4116.00

S.No	Description of the item	Qty	Unit	Rate	Amount
9	Plastering in CM 1:4 , 15 mm thick to internal and external surfaces of walls including the cost of all materials , labour , curing etc, complete - Upto 10.00 m height	45.00	Sq.m	110.70	4981.50
10	Centering and shuttering including strutting, propping etc; and removal of walls (any thickness) including attached pilasters, buttersses, plinth and string courses etc;	80.00	Sq.M	180.40	14432.00
11	Reinforcement for R.C.C. work including straightening , cutting , bending , placing in position and binding grills with binding wire all complete by cold twisted deformed bars.	0.50	M.T	42700.00	21350.00

Total: Rs **341,313.62**

Total: Rupees Three lakh forty one thousand three hundred and fourteen only.

I / We have quoted% above [] / below [] (tick the relevant) for the rates given above.

% in words:

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer