

Issued to agency:



BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM, HYDERABAD-32
FACTORY CIVIL ENGINEERING DEPARTMENT

SCHEDULE- A

PRICE BID

Tender Notice No:

HY/FCD/OT-02/2009-10 , Dt: 17.04.09

Item no: 2

Name of the work :- Modification to O2 Product stores.

S.No.	Nature of work	Qty	Unit	Rate in Rs	Amount
1	Dismantling of weldmesh / expanded metal from ceiling including gas cutting etc., complete as directed by Engineer-in-charge. The dismantled materials should be handed over to BHEL stores for reuse wherever required.	144.00	One Sq.m	54.60	7862.40
2	Dismantling M.S. partitions (Weldmesh, glazed or panelled) of standard size 1.20 M x 2.40 M or 1.20 x 3.30 M including M.S. Posts and transporting and stacking the materials for reuse etc., complete as directed by the Engineer-in-charge (The rate shall include for removing glass panes before dismantling glazed partitions and stacking glass panes)	25.00	Each	462.00	11550.00
3	Dismantling and re-erection of steel door of size (1.2x2.90M) for M.S. steel partition for cabins (weldmesh, glazed or panelled) with required M.S. posts and all accessories such as hinges, aldrops etc., including gas cutting, welding etc., complete as directed by Engineer-in-charge. (The rate shall include for fixing glass panes after erection of door in case of glazed doors).	1.00	Each	763.60	763.60
4	Demolishing brick work in cement mortar manually / by mechanically means including stacking of serviceble material and disposing off unserviceble materials upto a lead of 2 KM as directed by Engineer-in-charge.	25.00	One Cu.m	355.90	8897.50
5	Brick work with FPS bricks of class designation 75 in superstructure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6 including curing cost of all materials and labour complete.	58.00	One Cu.m	2357.40	136729.20
6	Plastering in CM 1:6 , 20 mm thick to internal and external surfaces of walls including the cost of all materials , labour , curing etc, complete - Upto 10.00 m height	311.00	Sq.m	95.10	29576.10

S.No.	Nature of work	Qty	Unit	Rate in Rs	Amount
7	Applying two coats of oil bound distemper of given shade over a coat of primer including through cleaning of the surfaces, cost of all labour and other incidentals. (Only OBD, OBD Primer Paint will be supplied by BHEL)	600.00	One Sq.m	41.55	24930.00
8	Providing and laying in position specified grade of reinforced cement concrete including consolidation by vibrations excluding the cost of centering ,shuttering and reinforcement for all works up to plinth level with 1:1½ :3 (1 cement : 1½ coarse sand : 3 graded stone aggregate of 20 mm nominal size).-- for lintels and beams.	21.00	Cu.M	3732.00	78372.00
9	Reinforcement for R.C.C. work including straightening , cutting , bending , placing in position and binding all complete by cold twisted bars.	0.70	M.T	42700.00	29890.00
10	Centering /shuttering including strutting, propping etc; and removal of form for columns, pillars,peirs, abutments, machine foundations, posts and struts.	90.00	Sq.M	119.25	10732.50
11	Demolishing R.C.C. work manually / by mechanically means including stacking of steel bars and disposal of unserviceable materials within 2.00 Km lead as per direction of Engineer - in - charge .	5.50	One Cu.m	582.68	3204.74
12 a	Earth work excavation by mechanical means (Hydraulic Excavtors) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m.	14.00	One Cu.m	103.40	1447.60
12 b	----do---- up to First additional depth of 1.50 M to 3.00 M.	18.00	One Cu.m	125.70	2262.60
13	Providing and laying in position plain cement concrete of specified garde, consolidation excluding the cost of centering and shuttering - all work up to plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size).	2.50	One Cu.M	2449.00	6122.50
14	Filling with excavated earth (excluding rock) in trenches , plinth , sides of foundations etc. in layers not exceeding 20 cm in depth , consolidation each deposited layer by ramming and watering , lead upto 50 m lift upto 1.5 m .	15.50	Cu.M	45.70	708.35

S.No.	Nature of work	Qty	Unit	Rate in Rs	Amount
15	Flooring in 25mm thick using 1 cement and 3 parts of granite stone chips of 3 to 10mm gauge (no sand) ellis pattern first sort including neat finishing , curing,cost of materials etc; complete.	20.00	Sq.m	196.00	3920.00
16	Conveyance of excavated spoil up to a lead of 2 Kms, including loading , unloading and spreading etc. complete as directed by Engineer- in- charge.	17.00	Cu.M	56.41	958.97
17	Applying two coats of synthetic enamel paint of given shade to old steel work including scraping old surfacess, cost of all labour, tools and other incidentals etc.complete.(Only Synthetic enamel Paint will be supplied by BHEL free of cost).	21.00	One Sq.m	33.25	698.25
18	Dismantling the existing structural steel work Carefully by loosening nuts, gas cutting as per the site conditions and reerecting the same, suitably modifying by gas cutting, welding, drilling new holes, jointing the new members by welding or bolting etc., complete.	0.25	One MT	890.11	222.53
Total				Rs	358,848.84
Total : Rupees Three lakhs fifty eight thousand eight hundred forty eight and paise eighty four only.					

I/ We have quoted% above [] / below [] (tick the relevant) for the rates given above.
% in words:

Name of the contractor :

Signature of the contractor

Accounts Representative

Opening Officer