



BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM::HYDERABAD::32
FACTORY CIVIL ENGINEERING DEPARTMENT

SCHEDULE- A

Tender Notice No:

PRICE BID

HY/FCD/OT-7/2008-09 , Dt: 08.08.08

Item no: 1

Name of work:- Civil works- Renovation of Spinner Pit No. 1 & 2 in 04 block

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Removing Existing Railway Track over the existing pit covering along with with all fixtures & structural steel and handling over to stores.	4.00	MT	890.11	3560.44
2	Demolishing R.C.C. work manually / by mechanically means including stacking of steel bars and disposal of unserviceable materials within a lead of 2 KM as per direction of Engineer - in - charge .	58.00	Cu.M	582.70	33796.60
3	Earth work in excavation by mechanical means (Hydraulic Excavtors) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m.	40.00	Cu.m	103.40	4136.00
4	Filling with available excavated earth (excluding rock) in trenches , plinth , sides of foundations etc. in layers not exceeding 20 cm in depth , consolidation each deposited layer by ramming and watering , lead upto 50 m .	2.00	Cu.M	45.70	91.40
5	Conveyance of excavated spoil up to a lead of 2 Kms, including loading , unloading and spreading etc. complete as directed by Engineer- in- charge.	38.00	Cu.M	56.41	2143.58
6	Providing and laying in position plain cement concrete of specified grade, consolidation excluding the cost of centering and shuttering - all work up to plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size).	6.00	Cu.m	2449.00	14694.00
7	Providing and Laying in position specified grade of reinforced cement excluding the cost of centering, shuttering, finishing and reinforcement - all work up to plinth level - with 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	70.00	Cu.m	3732.00	261240
CONTRACTOR(S)			ISSUING OFFICER		

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
8	Centering and shuttering including strutting, propping etc; and removal of form for RCC walls , rafts etc...,	120.00	Sq.M	180.40	21648.00
9	Reinforcmnt for R.C.C. work including straightening , cutting , bending , placing in position and binding all complete by cold twisted bars.	4.80	MT	42700.00	204960.00
10	Fixing of MS bolts of 40mm dia and 1000mm long in position in concrete foundations including cost of labour etc; complete MS bolts will be issued on free of cost by BHEL at their stores.	0.51	MT	9910.00	5064.01
11	Fixing 52 Kg rails for various gauges at floor level including fixing side guide angle etc., complete with necessary clamps required for fixing rails in position and alignment, leveling as per B.I.S 7215-1974. (M.S rails, M.S. Angles, Strl. steel will be issued free of cost by BHEL at their stores).	1.04	MT	6000.00	6240.00
12	Fabrication and fixing inserts / angles in concrete wall with lugs of required dia welded to the insert plates. (Strl. Steel,elctrodes and gases required for work will be issued on free of cost by BHEL at their stores).	4.40	MT	4000.00	17600.00
13	Painting at site of all structural steel work with 2 coats of aluminium paint / synthetic enamel paint of approved shade to trusses, columns, girders, bracings etc., with aluminium paint or synthetic enamel paint as required etc., complete. The required paint only will be issued free of cost by B.H.E.L at their stores.	4.40	MT	596.50	2624.60
Total Rs					577798.63

Total Rupees Five lakhs seventy seven thousands seven hundred and

I / We have quoted% above [] / below [] (tick the relevant) for the rates given above.

% in words:

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer

ISSUING OFFICER