

**SCHEDULE –A**

*Name of work: Provision of aluminium partition/cabins .*

(For Membrane technology lab, MW Sintering (2 Nos.) RK— 1 & 2 UPS & DGM/Finance office etc.)

<b>S.N.</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amt.</b>
1	<b><u>Al. Partition</u></b> Providing/fabricating/assembling and fixing Anodized aluminum Fixed partition using Jindal make medium Weight aluminium section as follows:- Horizontal members Size - 63.50 x 38.10 mm at 0.75 kg/m.c/c spacing shall not exceed 90 cm vertical members size - 63.50 x 38.10mm at 0.75 kg/m.c/c spacing shall not be more Than 90 cm/bottom portion - 3' height portion - Novopan pre laminated board 12mm thick Including necessary clips, Rubber beading Aluminium Beading and fixing to the Adjoining/existing wall/partition etc. Top portion 5mm thick plain glass/grounded glass with all necessary fittings/fixtures etc., complete as per sample shown	Smt	219.14		
2	<b><u>Aluminium door</u></b> Providing/fabricating/assembling and fixing anodised aluminium door type – plain door/sliding door to the existing aluminium partition using jindal make medium weight aluminium sections medium weight as follows:- Vertical, top and centre member shall be size 47.62 mm x 44.45 mm and bottom members shall be 114.3 x 44.45 mm top portion – with plain glass 5 mm thick/grounded glass, bottom portion 3' height Novopan pre laminated board 12mm thick c/c spacing of members shall not exceed 90 cm c/c. The work including necessary clips, rubber beading aluminium triangular beading, locks, hinges, door stoppers handles on both the sides etc., complete and fixing to the adjoining members wall/frame work with all necessary fittings/ fixture etc., complete as per sample shown	Smt	23.52		
3	<b><u>Removing Aluminium Partition;-</u></b> Labour charges for dismembering and removing the existing aluminium partition along with door and all fittings, having top Portion glass panels and bottom wood panels and transporting to the store etc complete	Smt	10.00		

4	<p><b><u>Re fixing Al Partition:</u></b></p> <p>Labour charges for fabricating assembling and fixing aluminium partition along with door using available materials and fittings which are to be collected from existing aluminium partition, doors having top portion glass panels and bottom portion wood panels as per the samples shown etc., complete. All the materials required shall be supplied by department.</p>	Smt	10.00		
5	<p><b><u>False ceiling</u></b></p> <p>Providing and fixing gypsum board false ceiling using plain gypsum board 6 to 8 mm thick using GI and powder coated Tee and L angles of size 25 x 25mm to have Grid work of 60 x 60cm with necessary GI wire 5mm dia Hanger with adjustable J Bolt &amp; nut for height adjustment from gypsum board roof including levelling etc., complete inclusive of cost of materials &amp; labour etc complete including making provisions for fixing light fittings, fans etc., as per the sample shown</p>	Smt	45.90		
6	<p><b><u>Door closure</u></b></p> <p>Supply and fix hydraulic door closure - of everite make to aluminium door with necessary fixtures etc as per sample shown</p>	NO	9.00		
7	<p><b><u>C.C. 1:2:4</u></b></p> <p>Providing and laying cement concrete 1:2:4 using clean granite jelly of 20mm and downsize for cills, coping, bond slab, flooring etc., excluding cost of centring, shuttering, bar bending charges and Plastering</p>	Cmt	1.00		
8	<p><b><u>Brickwork</u></b></p> <p>Providing and constructing brick masonry for main walls /partition walls/chambers etc with approved quality of table moulded bricks of standard size in CM 1:4 with necessary scaffolding and curing etc complete</p>	Cmt	1.00		

9	<p><b><u>Plastering</u></b></p> <p>Providing plastering in CM 1:4, 20 mm thick for new surface/patches in repair works ,including providing and removing scaffolding rounding of all corners with finishing of lime rendering / Sand finish/water proof addition as required including curing etc complete to burnt brick masonry/Concrete surface etc</p>	Smt	10.00		
10	<p><b><u>WALL-BORES</u></b></p> <p>Making wall bores up to 45x45x45 cm thick in brick work, size stone masonry/concrete and packing with cement concrete 1:2:4 and finishing with cement mortar 1:4 ect., complete</p>	Each	30Nos		
<b>Total(Rs)</b>					

(Total Rs.....)

Signature of contractor

Name:-

Address:-