

A. The following are added as Clause Nos. 1.13.1.7 and 1.13.1.8 respectively in VOLUME-IA PART-I CHAPTER – XIII – MATERIAL HANDLING, TRANSPORTATION AND SITE STORAGE:

1.13.1.7 All Transformers including Generator Transformers are stored in the storage area near BHEL site office. The distance between this storage area and the final erection site is between 1 to 1.5 kms. Loading of the Transformers at the storage area, transportation to erection site, unloading at erection site are in the scope of the Contractor along with the required T&P. Also refer Clause 1.14.1.2.2 in **VOLUME-IA PART-I CHAPTER XIV- SCOPE OF WORKS- DETAILED.**

1.13.1.8 Due to lack of closed storage space at 1x600 MW Rayalaseema TPP, Stage IV Unit 6 stores area, more than 90% of the electrical and C&I panels are stored in the storage sheds at Rayalaseema Stage 2 & 3, which are located about 6 kms from the erection area. Further, these old stage sheds are of very low in head room, and to bring out the panels from these sheds, no crane can be used and panels can pulled out only on pipe rollers manually or any other suitable method.

B. Notice Inviting Tender (NIT) Annexure 3 is Applicable for this Tender.

All other conditions of the Tender Specification remain unchanged.

Bidders are requested to consider this Corrigendum as part of the Tender Specification and quote accordingly


AGM/ SCT