

SCHEDULE

NAME OF WORK: PROVIDING WATERPROOF TREATMENT OVER THE SHEEL- ROOF TOP SURFACE AT BLDG NO. 7 & CANTEEN BLDG INSIDE OUR FACTORY PREMISES.

SL.NO	DESCRIPTION	UNIT	QTY	RATE IN FIGS & WORDS		AMOUNT	
				Rs.	Ps	Rs.	Ps
1	Removal of Existing Tarfelt sheet from the Shell Roof Top surface & Scraping of the surface & disposal of removed sheet/waste debris as directed by Engineer-In-Charge. Cost inclusive of scaffolding, Transportation etc at all heights & levels	Sqm	635.00				

CONTRACTOR

EMPLOYER

SL.NO	DESCRIPTION	UNIT	QTY	RATE IN FIGS & WORDS		AMOUNT	
				Rs.	Ps	Rs.	Ps
2	Providing & Laying of Super Thermolay APP modified Water proofing Membrane with non-woven polyster mat reinforcement 4mm thick of STP or equivalent after applying one coat of industrial Bitumen of 90/15.Second coat of Hot Bitumen is to be applied on the surface of Water proofing Membrane of M/s STP or equivalent, over the Shalikote T-30Primer of M/s STP or equivalent & top surface is to be finished with one coat of Super shield Silver Paint of M/s STP or equivalent for Shell Roof top Surface at Building No.7 & Canteen ,as directed by the Engineer-In-Charge. Cost inclusive of Tools,Tackles ,Scaffolding ,Lead, lift inclusive of LPG Gas.etc complete at all heights & levels.	Sqm	2231.00				

CONTRACTOR

EMPLOYER

SL.NO	DESCRIPTION	UNIT	QTY	RATE IN FIGS & WORDS		AMOUNT	
				Rs.	Ps	Rs.	Ps
3	Providing & painting with Super Silver Shield Paint of M/s STP or equivalent over the Water proofing Membrane one coat as directed by the Engineer-In-Charge. Cost inclusive of Tools,Tackles, Scaffolding, Lead, lift etc. complete at all heights & levels.	Sqm	10430.00				
GRAND TOTAL							

Rupees in Words.....

CONTRACTOR

EMPLOYER