

**Asphalting of roads in plant and townships**

**SCOPE OF WORK**

1. Cleaning of the existing WBM road surface of approximate 900 sq. meter
2. Cleaning the existing bituminous road surface approximate 4400 sq. meter
3. Providing primer coat for bituminous surface approximate 4400 sq. meter
4. Providing primer coat for macadam surface approximate 4400 sq. meter
5. Providing bituminous concrete of 40 mm thick approximate 210 cu. meter
6. Providing bituminous seal coat approximate 5300 sq. meter

Note :

1. The work is to be carried out in the plant and town ship premises as per the directions of Engineer-in-charge.
2. Bidders to visit the premises and inspect the area of work for ascertaining the nature and extent of work involved before submitted their bids.
3. The details of the area and work to be carried out are provided in the annexed Schedule-A which is also to be used for submitting the price bid.