

**BHARAT HEAVY ELECTRICALS LIMITED**

BOILER AUXILIARIES PLANT

RANIPET - 632406

**ESTIMATE**

ESTIMATE REF NO : CTS/RB/14/09

NAME OF WORK : PROVIDING GRANITE TOP FOR COOKING PLATFORM, SINK AND CERAMIC WALL TILING WORK IN TOWNSHIP QTRS

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE RS P	AMOUNT RS P
15.23.1	01A	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead For thickness of tiles 10 mm to 25 mm	500.000	SQM	10.90	5450.00
14.17	02	Raking out joints in lime or cement mortar and preparing the surface for re-pointing or replastering including disposal of rubbish to the dumping ground within 50 metres lead.	500.000	CUM	10.85	5425.00
8.2.2.2	03A	Providing and fixing 18 mm thick gang saw cut mirror polished (premoulded and prepolished) machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size of approved shade, color and texture laid over 20 mm thick base cement mortar 1:4 (1 Cement : 4 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touchups, including rubbing, curing, moulding and polishing to edge to give high gloss finish etc. complete at all levels. Area of slab over 0.50 sqm	400.000	SQM	2514.12	1005649.60
8.3.2	04A	Extra for providing edge moulding to 18 mm thick marble stone counters, vanities etc. including machine polishing to edge to give high gloss finish etc. complete as per design approved by engineer-in-charge. Granite work	650.000	METR	97.60	63440.00
11.36	05	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS-15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by engineer-in-charge in skirting, risers of steps and dados over 12 mm thick bed of cement mortar 1:3 (1 Cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm including pointing in white cement	480.000	SQM	492.26	236286.91

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

**BHARAT HEAVY ELECTRICALS LIMITED**

BOILER AUXILIARIES PLANT

RANIPET - 632406

**ESTIMATE**

ESTIMATE REF NO : CTS/RB/14/09

NAME OF WORK : PROVIDING GRANITE TOP FOR COOKING PLATFORM, SINK AND CERAMIC WALL  
TILING WORK IN TOWNSHIP QTRS

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE RS P	AMOUNT RS P
		mixed with matching pigment of matching shade complete.				
DATA	06	Supplying at site of work, carrying and fixing in position of granite (black colour) kitchen sink of size 0.60X0.45X.30M (2'X1.5'x1'). The front face of the sink to be semipolished and top edges to be mouled, providing one no of 32 mm waste coupling with waste pipe etc., complete. Rate to include cost of all materials, labour charges and making good all damages, to the wall, floor etc. to match the existing work etc., complete all as per standard specifications and instructions of engineer-in-charge.	245.000	EACH	2062.14	505223.66

1821475.17

ESCALATION @ %

0.00

TOTAL ESTIMATED VALUE

1821475.17

CONTRACTOR TENDER PERCENTAGE @ ABOVE / BELOW / AT PAR \_\_\_\_\_%

(Percentage in words )

SERVICE TAX @ %

TOTAL VALUE OF WORK

=====

=====

CONTRACTOR/ TENDERER

ACCEPTING OFFICER