



भारत हेवी इलेक्ट्रिकल्स लिमिटेड

( भारत सरकार का उपक्रम )

**BHARAT HEAVY ELECTRICALS LIMITED**

(A Govt. of India Undertaking)

**TCN - 02**

Ref: PSER:SCT:KLN-E1754:TCN-02

Date: 21-07-2016

Sub	Tender change notice (TCN) - 02	
Job	Design/ Engineering and construction of 33 KV sub-station along with supply, erection, testing and commissioning of equipment and system for construction power distribution system (11 KV overhead lines, package sub-station etc.), high mast lighting / temporary illumination system including obtaining clearances from various authorities, operation & maintenance (O&M), etc of construction power network for 2x660 MW Maitree Super Thermal power project at Moidara village, Rampalupazila, Bagerhat district, Bangladesh	
Ref	1.0	Tender No. <b>PSER:SCT:KLN-E1754:16.</b>
	2.0	BHEL's NIT, vide reference no PSER:SCT:KLN-E1754:5101, Dated 01-07-2016.
	3.0	BHEL's TCN-01, vide reference no PSER:SCT:KLN-E1754:TCN-01, dated 12-07-2016.
	4.0	All other pertinent issues till date.

With reference to above, following points/ documents, relevant to tender, may please be noted and complied with while submitting offer.

- 1.0 Pre-bid Clarification is attached vide **Annexure-A to TCN-02.**
- 2.0 Soil Investigation Report (Draft copy) for 2x660 MW Maitree STPP is attached herewith for tender purpose only.
- 3.0 Revised 'No deviation certificate' as per enclosed Annexure-2. Bidder shall submit no deviation certificate as per enclosed format only.
- 4.0 All other terms & conditions shall remain unchanged.

Thanking you,

Yours faithfully,  
for BHARAT HEAVY ELECTRICALS LTD

ENGR (SCT)

Encl : As above.

पावर सेक्टर पूर्वी क्षेत्र ( मुख्यालय )

POWER SECTOR EASTERN REGION, DJ-9/1, SECTOR-II, SALT LAKE CITY, KOLKATA - 700 091

फैक्स/Fax : (033) 23211960

फोन/Phone : बोर्ड/EPABX : 23211691, 23211798, 23211796

## ANNEXURE-A TO TCN-02

JOB: DESIGN/ ENGINEERING AND CONSTRUCTION OF 33 KV SUB-STATION ALONG WITH SUPPLY, ERECTION, TESTING AND COMMISSIONING OF EQUIPMENT AND SYSTEM FOR CONSTRUCTION POWER DISTRIBUTION SYSTEM (11 KV OVERHEAD LINES, PACKAGE SUB-STATION ETC.), HIGH MAST LIGHTING / TEMPORARY ILLUMINATION SYSTEM INCLUDING OBTAINING CLEARANCES FROM VARIOUS AUTHORITIES, OPERATION & MAINTENANCE (O&M), ETC OF CONSTRUCTION POWER NETWORK FOR 2X660 MW MAITREE SUPER THERMAL POWER PROJECT AT MOIDARA VILLAGE, RAMPALUPAZILA, BAGERHAT DISTRICT, BANGLADESH

TENDER NO: PSER:SCT:KLN-E1754:16

SI No	SLD/ Technical Specs/ General		Specification requirement / Tender Condition	Deviation / Clarification	BIDDER'S QUERY	BHEL'S CLARIFICATION	
1	Page No.3	clause No.4	Enclosure	C/D	Protection degree for Transformer compartment should be IP23 Offerd CSS : Ventilation apertures should be sufficient for natural ventilation (Class K15) i.e Rated class of Trafo compartment is K15	Protection degree for Transformer compartment of Packaged Sub-Station shall be as per IP 24	
2	Page No.4	ClauseNo.5	RMU	C	Offered RMU is non-extensible, Motorized operated, 3 way, 1 no.VCB + 2 nos. LBS with bottom explosion (for internal arc fault 21KA/ 1 sec) and Bus Metering Panel, but without Auxiliary trafo and without Fault passage	This arrangement is in line to our Technical Specification of PSS/CSS	
3	Page No.4	ClauseNo.5	Internal arc and Short time current	D	Offered CSS, IAC is 21KA/1sec and 21KA/3sec STC	This is in line to our Technical Specification of PSS/CSS with the indicated IAC 18.4KA/1S	
4	Page No.7	Annexure-A	Numerical relay / SLD	C	We confirm to offer Self Powered Numerical Relay (Type:C&S make) in VCBs. Being it self powered relay following	Protection arrangement as per SLD of PSS/CSS shall require to be provided.	
					series trip mechanism, shunt trip coil and other relays like SF6 Gas pressure Lock out, trip circuit supervision etc. not been considered.	For VCB arrangement it is not required to provide SF6 gas pr. lock out relay but other protection arrangement as per SLD of PSS/CSS shall require to be provided.	
					but we have considered Tafu card instead of Auxiliary Relay (for OTI, WTI, Buchloz & PRV), for TR Protection with 12 Window annunciation.	Tafu Card is not acceptable.	
					No other Relays are considered.	Protection arrangement as per SLD of PSS/CSS shall require to be provided.	
5	General	NA	Type tests	C	We shall submit relevant type tests for your review and acceptance.No further type testing is considered in scope of supply	Tender condition and Tech. Spec. shall be followed	
6	General	NA	CSS	C	C Rated class of Tr compartment is K15.	CSS shall have degree of protection IP54 for HV,LV compartments and IP23 for transformer compartment.	Protection degree for Transformer compartment of Packaged Sub-Station shall be as per IP 24
					CSS is with 30 X 3 Sqmm Earth bus bar.	Earth Bus inside CSS shall be provided by using 50x6 mm GI Flat	
7	General	NA	CSS	C	2.2 Weather proof enclosure(IP as stated against reply to clause 1.1) of sub-station of sheet steel of thickness min. 2	Acceptable.	
					mm. Base frame however shall be 4 mm thickness	This is in line to our Technical Specification of PSS/CSS	
8	General	NA	CSS	C	CSS is not skid mounted	Arrangement shall be provided for fixing the CSS on concrete foundation rigidly.	
9	General	NA	Capacitor bank	C	We have considered 125KVAR APFC panel in 4 steps with 1no. 630Amp MCCB with Adjustable O/L and S/C as I/C and	It is mandatorily to be provided in the CSS "415V, 300 KVAR Capacitor Banks with minimum 4 steps APFC Relay"	
					MCCBs as O/G	MCCBs shall be used as O/G for LV	
10	General	NA	Bus Bar	C	We have considered Aluminium Bus Bar for LV and RMU	The RMU to be equipped with 2 Isolators and 1 Circuit Breaker.	

## ANNEXURE-A TO TCN-02

JOB: DESIGN/ ENGINEERING AND CONSTRUCTION OF 33 KV SUB-STATION ALONG WITH SUPPLY, ERECTION, TESTING AND COMMISSIONING OF EQUIPMENT AND SYSTEM FOR CONSTRUCTION POWER DISTRIBUTION SYSTEM (11 KV OVERHEAD LINES, PACKAGE SUB-STATION ETC.), HIGH MAST LIGHTING / TEMPORARY ILLUMINATION SYSTEM INCLUDING OBTAINING CLEARANCES FROM VARIOUS AUTHORITIES, OPERATION & MAINTENANCE (O&M), ETC OF CONSTRUCTION POWER NETWORK FOR 2X660 MW MAITREE SUPER THERMAL POWER PROJECT AT MOIDARA VILLAGE, RAMPALUPAZILA, BAGERHAT DISTRICT, BANGLADESH

TENDER NO: PSER:SCT:KLN-E1754:16

11	General	NA	LV Switch Gears	C	As I/C: with O/L, S/C and E/F with Ammeter, Voltmeter, Metering CT and Aux. Contacts. 1no. 800AMP,4P,MP based, ACB As O/G: With Adjustable O/L and S/C with Rotary switch, Phase Barrier and Spreadrs links but without any Measuring meters, Metering CT and Aux. contacts. (1)2nos. TM based,63Amp, 4P, MCCB (2)4nos. TM based, 100Amp, 4P, MCCB (3)2nos. MP based, 400Amp, 4P, MCCB (4)2nos. MP based, 630Amp, 4P, MCCB	Basic requirement and circuitry arrangement of CSS/PSS has been clearly specified in the Tech. Specification and SLD and it is necessarily be followed in making of CSS/PSS.
12	General	NA	Transformer	C	(1)As per IS1180, EE class-1, 500 KVA , 11/0.433 KV Oil type Air natural transformer with Off Load Tap Changer with tapping range +5% to -10% in 6 steps of 2.5% with @50% loading = 1.6KW (Subject to IS tolerance) @10% Loading = 4.75W (Subject to IS tolerance) %Z = 4.5% (Subject to IS tolerance)	Transformer of CSS shall be provided with Off Load Tap Changer with tapping range +5% to -5% in 04 steps of 2.5%
13	General	NA	Battery and Battery charger and Auxiliary Trafo	D	We have considered Battery and Battery Charger for 24V DC but Auxiliary trafo for 230V AC supply shall be in Scope	Tender condition and Tech. Spec. shall be followed
14	General	NA	Enclosure C	C	We have Considered GI Enclosure	Enclosure for the entire package substation shall be preferably of 2 mm Galvanized Iron Sheet( except base of the enclosure, base should be made of 4mm hot dip galvanized steel )
15	General	NA			As per the specification RMU type mentioned is Ringmaster, however as per in RMU detail speciifcation the requirement is for both SF6/ Vacuum type CB. Hence, we are going ahead with VCB with RMU type FBX. Kindly confirm.	VCB with RMU is acceptable
16	General	NA			We shall provide Battery and Battery charger in the RMU instead of Power Pack. Kindly clarify.	In case the RMU is provided with 24V DC back-up for min. 10 Minute duration through battery and charger arrangement then no separate power pack arrangement is required.
17	General	NA			The Outdoor Enclosure of the PSS shall be of GI material with single powder coating of 80-100 microns. Hence, the offered PSS shall be suitable for the normal atmosphere conditions instead of salty weather conditions.	Enclosure for the entire package substation shall be preferably of 2 mm Galvanized Iron Sheet( except base of the enclosure, base should be made of 4mm hot dip galvanized steel ) painted with the colour epoxy high solid finish paint with minimum 80 micron(μm) total dry film thickness (DFT) of approved make and shade to achieve an even shade over steel sections with minimum 80 micron(μm) primer coats and keeping overall DFT with primer not less than 160 microns(μm) including touchup painting as per specification, manufacturer's recommendations, relevant BS or equivalent international standards and as approved by BHEL. Painting shall be of High Durability complying ISO 12944 Part 1.
18	General	NA			As per the Type tested design PSS is suitable for Temperature class of -5Deg C to + 40 Deg C. However, necessary de-rating to be considered above the same.	As per Tech. Spec. of CSS temperature range has been specified as -25° C to + 45° C

## ANNEXURE-A TO TCN-02

JOB: DESIGN/ ENGINEERING AND CONSTRUCTION OF 33 KV SUB-STATION ALONG WITH SUPPLY, ERECTION, TESTING AND COMMISSIONING OF EQUIPMENT AND SYSTEM FOR CONSTRUCTION POWER DISTRIBUTION SYSTEM (11 KV OVERHEAD LINES, PACKAGE SUB-STATION ETC.), HIGH MAST LIGHTING / TEMPORARY ILLUMINATION SYSTEM INCLUDING OBTAINING CLEARANCES FROM VARIOUS AUTHORITIES, OPERATION & MAINTENANCE (O&M), ETC OF CONSTRUCTION POWER NETWORK FOR 2X660 MW MAITREE SUPER THERMAL POWER PROJECT AT MOIDARA VILLAGE, RAMPALUPAZILA, BAGERHAT DISTRICT, BANGLADESH

## TENDER NO: PSER:SCT:KLN-E1754:16

19	General	NA			For MV - Trafo connection we can offer cable connection suitable upto 95sq.mm.	Cable connection shall be suitable for 3X 1C-150 Sq. mm cable
20	General	NA			Trafo-LV connection - The LT current rating required is Max. 666.67A. Hence, kindly confirm if 800A AL busbar is acceptable for the same or not instead 2000A.	800A AL Busbar is not acceptable, it is to be suitable for 2000A current carrying capacity.
21	General	NA			We shall provide Tafu Card with 7 LED display for the Trafo fault indication in the RMU. Kindly confirm the acceptance of the same.	Use of Tafu Card is not acceptable.
22	General	NA			Supply of Lighting Mast etc mentioned in the Technical specification shall not be in our scope. Our scope shall be limited only upto supply of PSS.	This query has been withdrawn by the concerned bidder.
23	General	NA			Soil Report of the site	Soil investigation work are in progress at site.Majority of the investigation work has been completed. Draft copy of the soil report of the completed work is attached for tender purpose only.
24			TYPICAL PEAK REQUIREMENT IS EXPECTED TO BE IN THE RANGE OF 5 TO 6 MVA	---	---	PEAK REQUIREMENT OF 5 TO 6 MVA POWER SHALL BE CATERED THROUGH 02 NOS 5 MVA 33/11 KV POWER TRANSFORMERS.
25	TCC, VOL-1F-TS-1, R-0, CL. NO. 2.3 26 (PAGE- 7 OF 27)		33 / 11 KV TRANSFORMERS..... WITH INBUILT AUTOMATIC STEP VOLTAGE REGULATOR ARRANGEMENT	---	---	BOTH THE 5 MVA (33/11 KV) TRANSFORMERS SHALL BE HAVING INBUILT AUTOMATIC STEP VOLTAGE REGULATORS WITH MIN. VOLTAGE CONTROL FACILITY IN 04 STEPS EQUALLY DISTRIBUTED FOR LOW AND HIGH VOLTAGE CONDITIONS.
26	TCC, VOL-1F-TS-1, R-0, CL. NO. 2.3 26 (PAGE- 6 OF 27)		PROVISION SHALL BE KEPT FOR INSTALLATION AND WIRING CONNECTIONS OF ENERGY METER IN 33 KV CONTROL / RELAY PANEL	---	---	SUPPLY OF ENERGY METER IS NOT IN THE SCOPE OF VENDOR.
27	GCC, VOL-1B- CL. NO. 1.3.1 (PAGE 4 OF 30)		RATES SHALL BE ENTERED IN FIGURE AS WELL AS IN WORDS.	---	---	IT IS MANDATORY TO WRITE THE "TOTAL" VALUE OF THE QUOTED PRICE IN PRICE SCHEDULE BOTH IN WORDS AND FIGURE.
28	GENERAL		WHICH SPECIFICATION SHALL BE FOLLOWED FOR DESIGN AND MANUFACTURING THE 5 MVA, 33/11 KV POWER TRANSFORMER.	---	---	DESIGN SPECIFICATION OF CBIP. INDIA (CENTRAL BOARD OF IRRIGATION AND POWER) SHALL BE FOLLOWED.
29	TCC, VOL-1F-TS-1, R-0, CL. NO. 3.1 (PAGE- 8 OF 27)		PACKAGED SUBSTATION SHALL BE EQUIPPED WITH INBUILT 125 KVAR APFC PANEL.....	---	---	AS PER STATUTORY NORMS OF BANGALADESH GOVT., FOR 500 KVA TRANFORMER IT IS REQUIRE TO USE 300 KVAR APFC PANEL. HENCE, THE RELEVANT TENDER CL. MAY BE READ AS 300 KVAR INSTEAD OF 125 KVAR.
30	GENERAL		WHETHER STEEL OR CONCRETE POLES SHALL BE USED IN 33 KV SUBSTATION.	---	---	SUITABLE SPC POLE AS PER REC/BSI/IEC SPECIFICATION MAY BE USED IN 33 KV SUBSTATION.

## ANNEXURE-A TO TCN-02

JOB: DESIGN/ ENGINEERING AND CONSTRUCTION OF 33 KV SUB-STATION ALONG WITH SUPPLY, ERECTION, TESTING AND COMMISSIONING OF EQUIPMENT AND SYSTEM FOR CONSTRUCTION POWER DISTRIBUTION SYSTEM (11 KV OVERHEAD LINES, PACKAGE SUB-STATION ETC.), HIGH MAST LIGHTING / TEMPORARY ILLUMINATION SYSTEM INCLUDING OBTAINING CLEARANCES FROM VARIOUS AUTHORITIES, OPERATION & MAINTENANCE (O&M), ETC OF CONSTRUCTION POWER NETWORK FOR 2X660 MW MAITREE SUPER THERMAL POWER PROJECT AT MOIDARA VILLAGE, RAMPALUPAZILA, BAGERTHAT DISTRICT, BANGLADESH

TENDER NO: PSER:SCT:KLN-E1754:16

31	GENERAL	BASE STRUCTURE OF PACKAGED SUBSTATION	—	—	BASE OF PACKAGED SUBSTATION SHALL SUITABLE FOR REMOVING AND REERECTING THE UNIT.
32	GENERAL	CURRENCY OF QUOTING THE TENDER RATE SCHEDULE.	—	—	Bidder shall quote their prices in INR only as per Volume-III, Price Schedule.
33	GENERAL	WHAT WILL BE EXCHANGE RATE OTHER THAN "INR"	—	—	EXCHANGE RATE SHALL BE AS PER SBI TT SELLING RATE PREVAILING ON THE LATEST DUE DATE OF OFFER SUBMISSION AS PER TENDER/TCN.
34	GENERAL	TAXES AND DUTIES	—	—	RELEVANT TENDER CLAUSE SHALL BE FOLLOWED
35	VOL-III, SCH-3: SUPPLY PRICE, ITEM SRL. NO. 17.0	AB CABLE, 3X1C, 150 SQMM WITH 180 SQMM MESSENGER WIRE WITH REQUIRED ACCESSORY	—	—	ITEM DESCRIPTION MAY BE READ AS: AB CABLE, 3X1C, 150 SQMM ALUMINIUM WITH 180 SQMM MESSENGER WIRE WITH REQUIRED ACCESSORIES
36	Cl. no. 6.2 of VOL-IF-TS-3, R-0, Technical Specification	—	—	—	The cl. No. 27.0 of Vol-1F-TCC-CML on Guarantee shall prevail & this supercedes Cl. no. 6.2 of VOL-IF-TS-3, R-0, Technical Specification.

## FACTUAL REPORT ON:

## GEOTECHNICAL INVESTIGATION FOR 2x660MW MAITREE SUPER THERMAL POWER PROJECT

CLIENT: BHEL

LOCATION: RAMPAL BAGERHAT

## FACTUAL REPORT

JUNE, 2016



## DEVELOPMENT CONSTRUCTIONS LTD.

HOUSE 11, ROAD 19A, SECTOR 4, UTTARA MODEL TOWN, DHAKA-1230, BANGLADESH  
GPO BOX NO. 609, CABLE: DRILLCO, DHAKA. PHONE: 880-2-58957231, 58950378  
FAX:880-2-58957283, EMAIL: fcl@dcl-fcl.com, WEB: <http://www.dcl-fcl.com>

## TABLE OF CONTENTS

SECTION		PAGE
<b>1</b>	<b>INTRODUCTION</b>	
1.1	DESCRIPTION	1
1.2	SCOPE OF WORKS	1
1.2.1	FIELD INVESTIGATION WORK	1
1.2.2	LABORATORY WORK	1
1.3	STRUCTURE OF REPORT	2
<b>2</b>	<b>TOPOGRAPHIC AND GEOLOGICAL SETTINGS</b>	
2.1	TOPOGRAPHY AND LANDSCAPE	3
2.2	REGIONAL GEOLOGY	3
2.3	SEISMICITY	4
<b>3</b>	<b>INVESTIGATION METHODOLOGY</b>	
3.1	DRILLING OF BOREHOLES	4
3.2	SPT TEST AND DISTURBED SAMPLE COLLECTION	5
3.3	UNDISTURBED SAMPLE COLLECTION	5
3.4	MEASUREMENT OF GROUND WATER	5
3.5	ELECTRONIC STATIC CONE PENETRATION TEST WITH PORE PRESSURE (CPT-U)	6
3.6	FIELD VANE SHEAR TEST	6
3.7	Electrical Resistivity Test	7
<b>4</b>	<b>INVESTIGATION RESULTS</b>	
4.1	CLASSIFICATION OF SOIL	8
4.2	SUMMARY OF BOREHOLES	8
4.3	LABORATORY TEST	11
<b>5</b>	<b>GEOTECHNICAL PROPERTIES</b>	
5.1	SOIL GRADATION	12
5.2	SOIL PLASTICITY	12

5.3	GEOTECHNICAL PROPERTIES	13
<b>6</b>	<b>RECOMMENDATION</b>	
6.1	ANALYSIS FOR SHALLOW FOUNDATION	17
6.1.1	BEARING CAPACITY	17
6.1.2	CONSOLIDATION	26
6.2	DEEP FOUNDATION	
6.2.1	ANALYSIS BORED CAST-IN-SITU PILES	26
6.2.2	SIDE RESISTANCE FOR CAST-IN-SITU PILES	26
6.2.3	TIP RESISTANCE FOR CAST-IN-SITU PILES	27
6.2.4	ESTIMATED PILE CAPACITY FOR CAST-IN-SITU PILES	32
6.2.5	ANALYSIS PRE CAST DRIVEN PILES	36
6.2.5.1	SIDE RESISTANCE FOR DRIVEN PILES	36
6.2.5.2	TIP RESISTANCE FOR DRIVEN PILES	36
6.2.6	ESTIMATED PILE CAPACITY FOR PRECAST DRIVEN PILES	38
6.2.7	TESTING OF PILES	40
<b>7.</b>	<b>EXCAVATION, COMPACTION, AND GROUND IMPROVEMENT CRITERIA</b>	
7.1	SUITABILITY OF ON SITE SOIL AS STRUCTURAL FILL	<b>40</b>
7.2	BACKFILL MATERIAL	40
7.3	MATERIAL BELOW PAVEMENTS	40
7.4	SLOPES FOR EXCAVATION	40
7.5	GROUND IMPROVEMENT OF SOFT COHESIVE LAYER	40
<b>8.</b>	<b>ANALYSIS FOR LIQUEFACTION POTENTIAL</b>	
8.1	GENERAL	41
8.2	METHOD	41
8.2.1	CALCULATION OF CYCLIC STRESS RATIO	41
8.2.2	CALCULATION OF CYCLIC RESISTANCE RATIO	41
8.2.3	FACTOR OF SAFETY	41

8.2.4	CALCULATION OF LIQUEFACTION POTENTIAL INDEX	41
8.3	ANALYSIS OF RESULT	42
9.	REFERENCES	42
<b>FIGURES</b>		
FIGURE 1:	ARIAL PHOTOGRAPH	
FIGURE 2:	SEISMIC MAP	
FIGURE 3:	ELECTRICAL RESISTIVITY TEST SETUP	
FIGURE 4:	SOIL GRADATION ENVELOP	
FIGURE 5:	SOIL PLASTICITY	
<b>APPENDICES</b>		
APPENDIX A:	LAYOUT FOR TEST LOCATION	
APPENDIX B:	FIELD TEST RESULTS	
APPENDIX C:	LABORATORY TEST RESULTS	
APPENDIX D:	ANALYSIS OF RESULT	

## 1. INTRODUCTION

### 1.1 DESCRIPTION

This report presents the data obtained from geotechnical investigation and laboratory test for proposed 2X660 MW MAITREE STPP, Rampal, Bagerhat. The project location map is shown in Figure-1.

### 1.2 SCOPE OF WORK

The Scope of work for this project is illustrated as follow:

- Performing geotechnical investigation including field and laboratory testing.
- Preparing a Geotechnical Report based on engineering analysis to present the data obtained through investigation.

#### 1.2.1 FIELD INVESTIGATION WORK

Field work included drilling and in-situ testing at various locations. Field investigation work has been performing from March, 2016.

Following is a list of field work undertaken for this geotechnical investigation:

- Setting out test locations using and establishing their elevation from nearest survey benchmark as provided by BHEL using total station.
- Drilling using rotary drilling rig only.
- Performing Standard Penetration Test (SPT) using automatic trip hammer according to ASTM D1586 standard.
- Recovering undisturbed soil samples from borehole according to ASTM D1587 standard.
- Electronic Static Cone Penetration Test as per ASTM D5778.
- Conducting in-situ Vane Shear Test as per ASTM D2573
- Conducting Electrical Resistivity Test as per ASTM G57 – 95(a)

#### 1.2.2 LABORATORY WORK

All soil samples were subjected to visual-manual soil classification procedures in accordance with ASTM D-2488. In order to evaluate the engineering properties of the existing sub-surface material for this project, laboratory testing was performed on selected soil samples obtained from test borings.

Following laboratory tests were performed by DCL at its geotechnical testing laboratory in Uttara, Dhaka during April, 2016:

i.	Bulk Density/Unit Weight	ASTM D7263
ii.	Moisture Content Test	ASTM D2216
iii.	Particle Size Distribution	ASTM D0422
iv.	Atterberg Limits	ASTM D4318
v.	Specific Gravity Test	ASTM D0854

- |      |                    |            |
|------|--------------------|------------|
| vi.  | Consolidation Test | ASTM D2435 |
| vii. | Direct Shear Test  | ASTM D3080 |

### 1.3 STRUCTURE OF REPORT

The Report has been divided in following segments:

Appendix A contains the layout for test location.

Appendix B contains field test results

Appendix C contains the laboratory test report.

Appendix D contains the analysis of results.

## 2. TOPOGRAPHIC AND GEOLOGICAL SETTING

### 2.1 TOPOGRAPHY AND LANDSCAPE

The site is located at Rampal upazilla under Bagerhat district. The site is proposed to be used as 2x660MW Maitree Super Thermal Power Project on the north-east bank of river Pussur. The plot is fairly flat with dredge filling, of which a part is bounded by masonry boundary wall. The site is accessible through a feeder road.



Figure 1: Aerial Photo of the Proposed Site

### 2.2 REGIONAL GEOLOGY

Geological map of Bangladesh published by Geological Survey of Bangladesh (GSB) depicts as Marsh clay and peat-Grey or bluish-grey clay, black herbaceous peat and yellowish-grey silt. Alternating beds of peat and peaty clay common in bills and large structurally controlled depressions; peat is thickest in deeper parts. Thin beds of peat and clay are interbedded with alluvial silt in the north-central Sylhet depression. Chains of linear lakes north of the Ganges River and south of the Shillong Plateau in the Sylhet depression suggest these areas are subsiding.

### 2.3 SEISMICITY

The project area falls under the Seismic Zone 1 of Bangladesh Seismic Zoning map where the basic co-efficient may be considered around 0.12 (Bangladesh National Building Code, BNBC 2006).




Figure 2: Seismic Map of Bangladesh (BNBC 2006)

### 3. INVESTIGATION METHODOLOGY

Following describes in brief each of the field works undertaken.

#### 3.1 DRILLING OF BOREHOLES

Boreholes were drilled by rotary boring methods using a bladed bit to produce a nominal diameter for 150mm. Flushing of the hole was achieved by the addition of bentonite to form a mud of sufficient density to lift soil cutting satisfactorily. Careful attention was given to drilling rates with slow rotation speeds and a slow bit advance to ensure that soil particles cut by the bit was able to rise in bentonite mud column and thus ensure a 'clean' base to the bore hole. Casing of 150 mm diameter was used in the uppermost few meters of each boring.

### 3.2 SPT TEST AND DISTURBED SAMPLE COLLECTION

Standard Penetration Test (SPT) according to ASTM D 1586 was executed using automatic trip hammer at 1.0m intervals for first 5m and 1.5m interval for greater depths to determine relative density/consistency and classification of soil at different elevation inclusive collection of disturbed soil samples from each interval in accordance to the requirements of the specification of the Engineer. An exploratory boring with a diameter 150mm is bored to the depth of the first test. A SPT sampler, connected with required length of BW size rod to a 63.5 kg hammer, is inserted in to the boring. SPT sampler is split-spoon sampler with a ball valve to permit exit of air or water from the top during driving and to assist in retaining sample during withdrawal; in addition, the sampler has a tapered shoe for allowing penetration in to the ground. The number of blows required to progress the sampler 450 mm is recorded in three 150 mm intervals. The SPT N-value is calculated by summing the hammer blows required to advance the sampler during the last two intervals of the test. The blow count for the first 150 mm is recorded; however, this number is ignored during the N-value since the soil immediately below the drilling rod is disturbed.

After test is complete, the SPT sampler is withdrawn and opened. The amount of soil recovered in the sampler is recorded including its description; next, sample is transferred to an airtight container. The uncorrected SPT results are shown in the borehole records. Disturbed samples from split spoon at all SPT location labeled and preserved in airtight container before transferring them to DCL's laboratory in Dhaka.

Boring logs with SPT records are enclosed is Appendix B-1.

### 3.3 UNDISTURBED SAMPLE COLLECTION

Undisturbed Shelby tube sampling was under taken in drill holes as per ASTM D1587 of the contract document. An exploratory boring with a diameter ranging from 100mm to 125mm is bored to the depth of the first test. A sampler, connected with a connector rod to a 63.5 kg (140 lb) hammer, is inserted in to the boring. The Shelby sampler of 72mm diameter is open drive sampler with holes on top to permit exit of air or water from the top during driving.

After driving is complete, the sampler rotated through two complete revolutions to shear the superficial deposits horizontally at the bottom; afterwards, the sampler is withdrawn. Next, the sample tube is sealed on the both ends using three alternating layers of 20mm wax and aluminum foil and rubber capped. Sample tubes were properly labeled and a marking "TOP" was attached on the tube. All tubes were stored and transported vertically.

### 3.4 MEASUREMENT OF GROUND WATER

Water level inside the casing was measured for all boreholes 24 hour after completion of drilling. Measurement of water level was recorded by using a measuring tape and data was recorded. But it should be noted that this recorded data may not reflect long term ground water level due to the presence of perched water table, monsoon, and drilling operation. Therefore, recorded ground water data may not accurately reflect actual or long term ground water elevation.

### 3.5 ELECTRONIC STATIC CONE PENETRATION TEST WITH PORE PRESSURE (CPT-U)

Electronic Cone Penetration Testing was carried out using a 15cm<sup>2</sup> projected area electronic cones with 60° apex angle and 225cm<sup>2</sup> friction sleeve area advance using a 20Ton hydraulic penetrometer. A total of eight (8) out of fifteen (15) soundings (designated SCPT-1 through SCPT-15) were performed at selected locations. CPT tests were terminated 60m (maximum) below existing grade and tests were conducted in accordance to ASTM D 5778. Throughout the test the cone was advanced by applying thrust on 1m long 36mm diameter rod at a rate of 2.0cm/sec. After advancement of each 1m segment subsequent rod was attached and operation was repeated.

The cone manufactured by GeoMil is a subtraction type cone equipped with instruments to measure (a) Cone Pressure, (b) Sleeve Friction, and (c) Dynamic Pore Pressure; furthermore, the cone is also equipped with two inclinometers to monitor its verticality at all times. Depth of the cone was recorded using an opto-electric encoder. All data was recorded for every centimeter automatically in a computer running proprietary software.

Prior to commencement of each test, the pressure transducer of the cone was saturated using silicon oil. The cone was calibrated prior to commencement and at the end of each test conforming to the specification using CPTest software (from GeoMil), this software also automatically recorded all data from the cone.

After completion of the test all collected data was plotted using CPTask software, which was also used to estimate engineering parameters from the in situ test data. This software was used to estimate following engineering parameters: Friction Angle, Undrained Shear Strength, Relative Density, and Classification.

CPT logs are enclosed is Appendix B-2.

### 3.6 FIELD VANE SHEAR TEST

Field Vane Shear Test is used for measuring undrained shear strength parameter of cohesive soil by means of rotating a vane in boreholes.

Procedure:

- i. Locate the advancement equipment over the test location. The test can be performed in a pre-drilled hole, pushing from the surface, or with drilling through vane housing.
- ii. Set a reaction casing to transfer forces to the torque head without twist or slippage.
- iii. When drilling, stop the drill hole at a depth such that the vane tip may penetrate undisturbed soil for a depth of at least five times the outside diameter of the hole. In the case where vane housing is used, advance the housing to a depth which that is at least five vane housing diameters less than the desired depth of the vane tip.
- iv. Advance the vane from the bottom of the hole or the vane housing in a single thrust to the depth at which the test is to be conducted. The vane shall be pushed down without any use of blows, vibration, or rotation. No torque should be applied to the rods during the thrust.

- v. The vane is retracted in the casing, when the test zone is reached the vane is pushed out of the shoe 35 to 50 cm. Vane rod friction in this case should be negligible.
- vi. The time from the end of vane penetration to beginning rotation shall be no more than 5 minutes. With the vane in position, apply the torque to the vane at a rate of 0.1 deg/s until failure.

The test results are presented in APPENDIX B-3

### 3.7 Electrical Resistivity Test

Thirty two (32) out of forty three (43) electrical resistivity tests was carried using a Chauvin-Arnoux (Model: CA6460) Soil Resistivity Meter at ground surface with electrode spacing of 0.5m, 1.0m, 2.0m, 3.0 m, 4.0m, 6m, 8m, and 10m utilizing the Wenner - 4 Pin method. Steel electrode pegs of 2m length were hammered into the ground at the required spacing and were connected to the resistance meter as detailed in the diagram below (ASTM G57 – 95(a)).




Figure 3: Electrical Resistivity Test Setup

A low voltage 97 Hz square wave current was passed between the two (outer) current electrodes E, H. The detector measures the voltage drop between the two (inner) potential electrodes ES, S, and compares this with internal standard resistors and indicates the resistance reading in ohms on a LCD display. Soil resistivity is then calculated using the following formula for the Wenner electrode configuration:

$$\rho_w = 2\pi d R_{S-ES}$$

The test results are presented in APPENDIX B-4

**4. INVESTIGATION RESULTS**

**4.1 CLASSIFICATION OF SOIL**

The Unified Soil Classification System (ASTM D2487) was used to classify the soil encountered in boring.

**4.2 SUMMARY OF FIELD INVESTIGATION**

Following list presents borehole number, location coordinates and chainage and ground surface elevation. Borehole location plans are included in Appendix A. Borehole logs are included in Appendix B.

BH No	UTM Coordinate		Ground Elevation*
	Easting	Northing	
BH-5	454556	499277	+4.861m
BH-6	454996	498577	+5.530m
BH-11	454711	499306	+4.732m
BH-13	454936	498888	+5.279m
BH-15	454839	499204	+5.369m
BH-19	454786	499146	+5.262m
BH-20	454799	499117	+5.193m
BH-22	454719	499146	+5.415m
BH-23	454598	499145	+5.620m
BH-24	454547	499137	+5.821m
BH-25	454467	498740	+5.532m
BH-26	454603	499118	+5.584m
BH-27	454655	499128	+5.397m
BH-29	454759	499075	+5.750m
BH-30	454799	499075	+5.450m
BH-32	454799	499033	+5.508m
BH-39	454599	499054	+5.718m
BH-40	454639	499033	+5.560m
BH-42	454374	498993	+5.532m
BH-45	454559	499012	+5.391m

BH-46	454599	499012	+5.263m
BH-47	454579	498990	+5.183m
BH-48	454559	498972	+5.623m
BH-50	454559	498932	+5.428m
BH-51	454679	499012	+5.325m
BH-52	454719	499012	++5.490m
BH-53	454759	499012	+5.908m
BH-54	454741	498989	+5.742m
BH-55	454808	498999	+5.573m
BH-57	454679	498972	+5.627m
BH-60	454604	498898	+5.563m
BH-61	454575	498882	+5.508m
BH-63	454692	498858	+5.530m
BH-69	454559	498852	+5.351m
BH-71	454579	498772	+5.544m
BH-72	454627	498772	+5.645m
BH-73	454674	498772	+5.276m
BH-74	454719	498772	+5.489m
BH-90	455215	498519	+5.651m

\*Elevation reference provided by BHEL

Table 1: Test locations for BH

ERT No.	UTM Coordinate	
	Easting	Northing
ERT-1	454183	499389
ERT-2	454660	499304
ERT-3	454759	499304
ERT-4	454946	499286
ERT-5	454799	499254
ERT-6	454405	499247
ERT-7	454739	499204

ERT-8	454639	499204
ERT-9	454757	499168
ERT-10	454171	499184
ERT-11	455250	498563
ERT-12	454521	499120
ERT-13	454631	499126
ERT-14	454686	499135
ERT-15	454732	499113
ERT-16	454773	498998
ERT-17	454651	498977
ERT-18	454541	498959
ERT-19	454424	498915
ERT-20	454173	498918
ERT-21	454635	498859
ERT-22	454780	498858
ERT-23	454325	498807
ERT-24	454111	498682
ERT-25	454221	498668
ERT-26	454422	498594
ERT-27	454462	498690
ERT-28	454547	498700
ERT-29	454728	498692
ERT-30	454657	498634
ERT-31	454850	498577
ERT-32	453977	497753

Table 2: Test locations for ERT

SCPT	UTM Coordinate	
	Easting	Northing
SCPT-1	454755	499146
SCPT-2	454599	499075
SCPT-3	454759	498972
SCPT-4	454599	498822
SCPT-5	454154	499208
SCPT-6	454154	498948
SCPT-7	454223	498651
SCPT-9	454079	497722

Table 3: Test locations for SCPT

#### 4.3 LABORATORY TEST

Following table lists the schedule of laboratory test undertaken. All tests were under taken at DCL's own laboratory in Dhaka. A table summarizing all tests result is enclosed in Appendix-D, and all laboratory test reports are enclosed in Appendix-C.

Laboratory Test	Quantity
Bulk Density/Unit Weight	101
Moisture Content Test	120
Particle Size Distribution	187
Atterberg Limits	114
Specific Gravity Test	59
Consolidation Test	1
Direct Shear Test	13

Table 4: Quantity of Laboratory Tests.

## 5. GEOTECHNICAL PROPERTIES

### 5.1 SOIL GRADATION

Figure 4 shows the soil gradation envelope of all tests performed under the current investigation program.




Figure 4: Soil Gradation Envelope

### 5.2 SOIL PLASTICITY

Figure 5 shows the plasticity chart of all soil samples tested under the current investigation program.




Figure 5: Soil Plasticity

### 5.3 GEOTECHNICAL PROPERTIES

Following tables are provided as a summary of test results done at various locations:

Layer No	USCS/Visual Classification	Depth (m)	SPT N	Moisture Content (%)	Index Properties	Strength Properties <sup>1</sup> C (kPa) Φ(deg.)
1	SM	0-6.0	2 - 8	-	-	-
2	MH	6.0-13.0	0 - 4	46.61- 52.58	LL=54 - 66 PI=18 - 30	-
3	ML	8.0 -28.0	3 - 41	39.78	LL=38 - 46 PI=9 - 18	-
4	SP-SM	13.0 -23.0	9 -24	-	-	-
5	SM	28.0-40.0	12 - 57	-	-	-
6	ML	26.0 -43.0	12 - 43	-	LL=36 - 40 PI=11	-
7	SM	29.0- 70.0	22 - 73	-	-	-

Table 5-1: Summary of test results for Chimney Area (BH-71, 72, 73, 74)

Layer No	USCS/Visual Classification	Depth (m)	SPT N	Moisture Content (%)	Index Properties	Strength Properties <sup>1</sup> C (kPa) Φ(deg.)
1	SM	0 - 6.5	3 - 5	-	-	-
2	ML	6.5 - 26.0	2 - 22	42.03	LL=48 PI=19	Φ=30.3 C=22.6
3	SP-SM	26.0- 30.0	24 - 44	-	-	-
4	SM	26.0 -40.0	20 - 38	-	-	-

Table 5-2: Summary of test results for Clarified Pump House (BH-25)

Layer No	USCS/Visual Classification	Depth (m)	SPT N	Moisture Content (%)	Index Properties	Strength Properties <sup>1</sup> C (kPa) Φ(deg.)
1	SP-SM	0- 7.5	2 - 6	-	-	-
2	ML	6.0 - 14.0	1 - 4	49.86	LL=47 PI=15-18	-
3	CH	5.0-14.0	3-5	47.82	LL=51 PI=23	-
4	CL	12.0-14.0	4 - 5	-	LL=35 PI=11	-
5	SM	14.0-26.0	20-45	-	-	-
6	ML	15.0-30.0	4-32	-	LL=34 PI=8	-

Table 5-3: Summary of test results for Switch Yard Area (BH-5, 11, 15)

Layer No	USCS/Visual Classification	Depth (m)	SPT N	Moisture Content (%)	Index Properties	Strength Properties <sup>1</sup> C (kPa) Φ(deg.)
1	SM	0-6.5	2-7	-	-	-
2	SP-SM	0-7.5	2-9	-	-	-
3	MH	7.0-15.0	1-6	51.74-63.42	LL=59-73 PI=17-31	-
4	CH	6.0-12.0	2-3	45.79-69.93	LL=73 PI=40	-
5	OH	6.0-12.0	1-4	110.8	LL=60-78 PI=24-32	-
6	ML	12.0-40.0	6-62	34.52	LL=35-38 PI=10-11	-
7	SP-SM	22.0-28.0	24-32	-	-	Φ=30.2 C=28.1
8	SM	32.0-40.0	23-58	-	-	-

Table 5-4: Summary of test results for Transformer Yard (BH-19, 20, 22, 23, 24, 26, and 27)

Layer No	USCS/Visual Classification	Depth (m)	SPT N	Moisture Content (%)	Index Properties	Strength Properties <sup>1</sup> C (kPa) Φ(deg.)
1	SP-SM	0-6.5	2-10	-	-	-
2	SM	0-6.0	4-7	-	-	-
3	OH	6.0-9.0	2-5	52.41	LL=82-91 PI=39-47	-
4	MH	5.0-19.0	0-15	37.89-59.17	LL=53-90 PI=21-40	-
5	ML	12.0-30.0	9-23	-	LL=33 PI=8	-
6	SM	19.0-27.0	22-55	-	-	-
7	ML	27.0-40.0	5-43	28.44-31.95	LL=30-34 PI=6-8	-
8	SP-SM	40.0-70.0	38-78	-	-	-
9	SP	51.0-70.0	43-75	-	-	-

Table 5-5: Summary of test results for Boiler Area (BH-45 to 48, 51 to 57)

Layer No	USCS/Visual Classification	Depth (m)	SPT N	Moisture Content (%)	Index Properties	Strength Properties <sup>1</sup> C (kPa) Φ(deg.)
1	SM	0.0-6.0	2-6	-	-	-
2	OH	5.5-9.5	2-7	114.0	LL=131 PI=62	-
3	MH	5.0-16.5	0-5	23.74- 44.66	LL=53-69 PI=20-32	-
4	ML	6.0-40.0	2-55	31.62- 62.86	LL=36-48 PI=10-18	-
5	SM	13.0-40.0	8-40	-	-	Φ=29.8-30.6 C=25.8-28.1

Table 5-6: Summary of test results for ESP Area (BH-50, 60, 61, 63, 69)

Layer No	USCS/Visual Classification	Depth (m)	SPT N	Moisture Content (%)	Index Properties	Strength Properties <sup>1</sup> C (kPa) Φ(deg.)
1	SM	0.0-6.0	2-6	-	-	-
2	ML	6.0-12.0	2-6	39.79	LL=40 PI=10	-
3	SM	12.0-24.0	10-33	-	-	-
4	ML	24.0-28.5	13-15	-	LL=38 PI=10	-
5	SM	28.5-37.5	23-40	-	-	-
6	ML	37.5-40.0	26-28	-	LL=44 PI=13	-

Table 5-7: Summary of test results for Gas Cylinder Room (BH-13)

Layer No	USCS/Visual Classification	Depth (m)	SPT N	Moisture Content (%)	Index Properties	Strength Properties <sup>1</sup> C (kPa) Φ(deg.)
1	SP-SM	0-5.5	3-4	-	-	-
2	MH	5.0-11.0	2-4	40.76	LL=63 PI=29	-
3	Clayey Silt	11.0-15.5	4-5	-	-	-
4	Silty Sand	15.5-30.0	12-35	-	-	-

Table 5-8: Summary of test results for Helipad Area (BH-90)

Layer No	USCS/Visual Classification	Depth (m)	SPT N	Moisture Content (%)	Index Properties	Strength Properties <sup>1</sup> C (kPa) Φ(deg.)
1	SP-SM	0.0-7.5	3-7	-	-	-
2	MH	7.5-13.5	0-3	46.28	LL=68 PI=24	-
3	ML	13.5-30.0	8-60	-	LL=31 PI=7	Φ=30.8 C=-19.9
4	Fine Sand	30.0-40.0	30-58	-	-	-

Table 5-9: Summary of test results for IDCT (BH-42)

Layer No	USCS/Visual Classification	Depth (m)	SPT N	Moisture Content (%)	Index Properties	Strength Properties <sup>1</sup> C (kPa) Φ(deg.)
1	SP-SM	0-6.5	6-24	24.82	-	-
2	OH	6.5-10.0	2	44.74	LL=108 PI=44	-
3	Silty Clay	10.0-15.5	3-5	-	-	-
4	Clayey Silt	15.5-20.0	11-18	-	-	-
5	Silty Sand	20.0-23.0	18-19	-	-	-
6	ML	23.0-25.0	11	29.20	LL=34 PI=9	-
7	Silty Sand	25.0-27.0	30	-	-	-
8	Silty Clay	27.0-29.5	20	-	-	-
9	SM	29.5-40.0	26-72	27.58	-	-

Table 5-10: Summary of test results for Sub Station Temperature (BH-6)

Layer No	USCS/Visual Classification	Depth (m)	SPT N	Moisture Content (%)	Index Properties	Strength Properties <sup>1</sup> C (kPa) Φ(deg.)
1	SP-SM	0.0-6.5	3-6	-	-	-
2	SM	0.0-6.0	3-6	-	-	-
3	OH	11.0-22.0	7-11	-	-	-
4	MH	6.0-13.0	0-4	43.17	LL=51 PI=17	-
5	ML	11.0-40.0	5-80	-	LL=30-36 PI=6-10	-
6	SP-SM	14.0-28.5	12-20	-	-	Φ=30.6 C=-19.8
7	SM	32.0-70.0	18-70	-	-	-

Table 5-11: Summary of test results for TG Building (BH-29, 30, 32, 39, 40)

## 6.0 RECOMMENDATION

Due to insignificant number of boreholes, distance between boreholes, and varying terrain, proper soil profile could not be developed. A soil anticipated profile diagram is enclosed in Appendix B. As such, recommendation and calculations for foundation are given per-location basis.

### 6.1 ANALYSIS FOR SHALLOW FOUNDATION

#### 6.1.1 BEARING CAPACITY

Due to the presence of soft to very soft material below the near surface, it is not recommended to implement shallow foundation in the proposed site for heavy or major structure as it is likely to consolidate under induced pressure of shallow foundation resulting in excessive settlement. Minor structures may be rested on isolated shallow foundation;

Following equation (Terzaghi) was used to determine bearing capacity of square foundation:

$$q_u = 1.3 \times c \times N_c + \sigma_{zD} N_q + 0.5 \gamma B N_y s_y$$

For un-drained condition ( $\Phi=0^\circ$ ) analysis:

$$N_c=5.7 \quad N_q=1; \quad N_y=0; \quad s_y=0.8;$$

$$q_a = \frac{q_u}{FS}$$

Location with SPT value is use to evaluate bearing capacity

Location/ Station	Footing Depth below EGL (m)	Footing Size (m x m)	Ultimate Bearing Capacity, $q_u$ (kPa)	Allowable Bearing capacity, $q_a$ (kPa), FS=3
Chimney Area (BH-71,72,73,74)	1.0	1.0 x 1.0	220	73
	2.0		330	110
	3.0		375	125
Clarified Pump House (BH-25)	1.0	1.0 x 1.0	210	70
	2.0		330	110
	3.0		390	130
Switch Yard (BH-5,11,15)	1.0	1.0 x 1.0	210	70
	2.0		315	105
	3.0		360	120
Transformer Yard (BH- 19,20,21,22,23,24,26,27)	1.0	1.0 x 1.0	220	73
	2.0		315	105
	3.0		360	120
Boilar Area (BH-45 to 48, 51 to 57)	1.0	1.0 x 1.0	220	73
	2.0		330	110
	3.0		390	130
ESP Area (BH-50,60,61,63,69)	1.0	1.0 x 1.0	210	70
	2.0		315	105
	3.0		375	125
Gas Cylinder Room (BH-13)	1.0	1.0 x 1.0	220	73
	2.0		330	110
	3.0		390	130
Helipad Area (BH-90)	1.0	1.0 x 1.0	210	70
	2.0		255	85
	3.0		315	105
IDCT Area (BH-42)	1.0	1.0 x 1.0	220	73
	2.0		330	110
	3.0		375	125
Sub-Station Temperature (BH-6)	1.0	1.0 x 1.0	220	73
	2.0		330	110
	3.0		390	130
T.G Building (BH-29,30,32,39,40)	1.0	1.0 x 1.0	220	73
	2.0		330	110
	3.0		375	125

Table 6: Bearing capacity Estimation for shallow foundation considering 25mm settlement  
(Footing Size: 1m X 1m)

Location/ Station	Footing Depth below EGL (m)	Footing Size (m x m)	Ultimate Bearing Capacity, $q_u$ (kPa)	Allowable Bearing capacity, $q_a$ (kPa), FS=3
Chimney Area (BH-71,72,73,74)	1.0	2.0 x 2.0	120	40
	2.0		150	50
	3.0		195	65
	4.0		270	90
	5.0		420	140
Clarified Pump House (BH-25)	1.0	2.0 x 2.0	135	45
	2.0		165	55
	3.0		225	75
	4.0		300	100
	5.0		435	145
Switch Yard (BH-5,11,15)	1.0	2.0 x 2.0	105	35
	2.0		150	50
	3.0		195	65
	4.0		270	90
	5.0		420	140
Transformer Yard (BH- 19,20,21,22,23,24,26,27)	1.0	2.0 x 2.0	120	40
	2.0		150	50
	3.0		195	65
	4.0		270	90
	5.0		420	140
Boilar Area (BH-45 to 48, 51 to 57)	1.0	2.0 x 2.0	135	45
	2.0		135	55
	3.0		210	70
	4.0		285	95
	5.0		405	135
ESP Area (BH-50,60,61,63,69)	1.0	2.0 x 2.0	105	35
	2.0		150	50
	3.0		195	65
	4.0		270	90
	5.0		435	145
Gas Cylinder Room (BH-13)	1.0	2.0 x 2.0	135	45
	2.0		165	55
	3.0		225	75
	4.0		285	95
	5.0		450	150
Helipad Area (BH-90)	1.0	2.0 x 2.0	105	35
	2.0		150	50

	3.0		210	70
	4.0		285	95
	5.0		435	145
IDCT Area (BH-42)	1.0	2.0 x 2.0	150	50
	2.0		180	60
	3.0		240	80
	4.0		315	105
	5.0		435	145
Sub-Station Temperature (BH-6)	1.0	2.0 x 2.0	150	50
	2.0		195	65
	3.0		255	85
	4.0		285	95
	5.0		315	105
T.G Building (BH-29,30,32,39,40)	1.0	2.0 x 2.0	105	35
	2.0		150	50
	3.0		195	65
	4.0		270	90
	5.0		420	140

Table 7: Bearing capacity Estimation for shallow foundation considering 25mm settlement  
(Footing Size: 2m X 2m)

Location/ Station	Footing Depth below EGL (m)	Footing Size (m x m)	Ultimate Bearing Capacity, $q_u$ (kPa)	Allowable Bearing capacity, $q_a$ (kPa), FS=3
Chimney Area (BH-71,72,73,74)	1.0	3.0 x 3.0	75	25
	2.0		120	40
	3.0		180	60
	4.0		240	80
	5.0		270	90
Clarified Pump House (BH-25)	1.0	3.0 x 3.0	90	30
	2.0		135	45
	3.0		195	65
	4.0		285	95
	5.0		330	110
Switch Yard (BH-5,11,15)	1.0	3.0 x 3.0	75	25
	2.0		120	40
	3.0		180	60
	4.0		255	85
	5.0		285	95
Transformer Yard (BH-	1.0	3.0 x 3.0	75	25
	2.0		120	40

19,20,21,22,23,24,26,27)	3.0	3.0 x 3.0	180	60
	4.0		225	75
	5.0		255	85
Boilar Area (BH-45 to 48, 51 to 57)	1.0	3.0 x 3.0	75	25
	2.0		135	45
	3.0		180	60
	4.0		240	80
	5.0		270	90
ESP Area (BH-50,60,61,63,69)	1.0	3.0 x 3.0	75	25
	2.0		120	40
	3.0		180	60
	4.0		225	75
	5.0		270	90
Gas Cylinder Room (BH-13)	1.0	3.0 x 3.0	90	30
	2.0		135	45
	3.0		165	55
	4.0		225	75
	5.0		270	90
Helipad Area (BH-90)	1.0	3.0 x 3.0	75	25
	2.0		120	40
	3.0		180	60
	4.0		225	75
	5.0		270	90
IDCT Area (BH-42)	1.0	3.0 x 3.0	90	30
	2.0		150	50
	3.0		210	70
	4.0		255	85
	5.0		285	95
Sub-Station Temperature (BH-6)	1.0	3.0 x 3.0	105	35
	2.0		135	45
	3.0		165	55
	4.0		225	75
	5.0		270	90
T.G Building (BH-29,30,32,39,40)	1.0	3.0 x 3.0	75	25
	2.0		120	40
	3.0		180	60
	4.0		255	85
	5.0		285	95

Table 8: Bearing capacity Estimation for shallow foundation considering 25mm settlement  
(Footing Size: 3m X 3m)

Location/ Station	Footing Depth below EGL (m)	Footing Size (m x m)	Ultimate Bearing Capacity, $q_u$ (kPa)	Allowable Bearing capacity, $q_a$ (kPa), FS=3
Chimney Area (BH-71,72,73,74)	1.0	4.0 x 4.0	60	20
	2.0		105	35
	3.0		150	50
	4.0		195	65
	5.0		225	75
Clarified Pump House (BH-25)	1.0	4.0 x 4.0	75	25
	2.0		120	40
	3.0		195	65
	4.0		225	75
	5.0		255	85
Switch Yard (BH-5,11,15)	1.0	4.0 x 4.0	60	20
	2.0		105	35
	3.0		150	50
	4.0		195	65
	5.0		225	75
Transformer Yard (BH- 19,20,21,22,23,24,26,27)	1.0	4.0 x 4.0	60	20
	2.0		90	30
	3.0		150	50
	4.0		180	60
	5.0		225	75
Boilar Area (BH-45 to 48, 51 to 57)	1.0	4.0 x 4.0	60	20
	2.0		105	35
	3.0		150	50
	4.0		210	70
	5.0		255	85
ESP Area (BH-50,60,61,63,69)	1.0	4.0 x 4.0	60	20
	2.0		105	35
	3.0		150	50
	4.0		195	65
	5.0		225	75
Gas Cylinder Room (BH-13)	1.0	4.0 x 4.0	60	20
	2.0		105	35
	3.0		150	50
	4.0		195	65
	5.0		240	80
Helipad Area (BH-90)	1.0	4.0 x 4.0	75	25
	2.0		120	40

	3.0		195	65
	4.0		225	75
	5.0		255	85
IDCT Area (BH-42)	1.0	4.0 x 4.0	75	25
	2.0		120	40
	3.0		165	55
	4.0		195	65
	5.0		225	75
Sub-Station Temperature (BH-6)	1.0	4.0 x 4.0	75	25
	2.0		105	35
	3.0		165	55
	4.0		210	70
	5.0		240	80
T.G Building (BH-29,30,32,39,40)	1.0	4.0 x 4.0	60	20
	2.0		105	35
	3.0		150	50
	4.0		195	65
	5.0		225	75

Table 9: Bearing capacity Estimation for shallow foundation considering 25mm settlement  
(Footing Size: 4m X 4m)

Location/ Station	Footing Depth below EGL (m)	Footing Size (m x m)	Ultimate Bearing Capacity, $q_u$ (kPa)	Allowable Bearing capacity, $q_a$ (kPa), FS=3
Chimney Area (BH-71,72,73,74)	1.0	5.0 x 5.0	45	15
	2.0		90	30
	3.0		135	45
	4.0		180	60
	5.0		225	75
Clarified Pump House (BH-25)	1.0	5.0 x 5.0	60	20
	2.0		105	35
	3.0		150	50
	4.0		195	65
	5.0		225	75
Switch Yard (BH-5,11,15)	1.0	5.0 x 5.0	45	15
	2.0		90	30
	3.0		135	45
	4.0		180	60
	5.0		210	70
Transformer Yard (BH- 19,20,21,22,23,24,26,27)	1.0	5.0 x 5.0	45	15
	2.0		90	30
	3.0		135	45
	4.0		170	57

	5.0		210	70
Boilar Area (BH-45 to 48, 51 to 57)	1.0	5.0 x 5.0	45	15
	2.0		90	30
	3.0		150	50
	4.0		195	65
	5.0		225	75
ESP Area (BH-50,60,61,63,69)	1.0	5.0 x 5.0	45	15
	2.0		90	30
	3.0		135	45
	4.0		180	60
	5.0		225	75
Gas Cylinder Room (BH-13)	1.0	5.0 x 5.0	45	15
	2.0		90	30
	3.0		135	45
	4.0		180	60
	5.0		225	75
Helipad Area (BH-90)	1.0	5.0 x 5.0	60	20
	2.0		105	35
	3.0		150	50
	4.0		195	65
	5.0		225	75
IDCT Area (BH-42)	1.0	5.0 x 5.0	45	15
	2.0		90	30
	3.0		135	45
	4.0		180	60
	5.0		210	70
Sub-Station Temperature (BH-6)	1.0	5.0 x 5.0	60	20
	2.0		105	35
	3.0		150	50
	4.0		180	60
	5.0		210	70
T.G Building (BH-29,30,32,39,40)	1.0	5.0 x 5.0	45	15
	2.0		90	30
	3.0		135	45
	4.0		180	60
	5.0		225	75

Table 10: Bearing capacity Estimation for shallow foundation considering 25mm settlement  
(Footing Size: 5m X 5m)

Location with CPT value is use to evaluate bearing capacity

Bearing Capacity Base on CPT result					
25mm settlement					
Size(m) Depth (m)	1x1	2x2	3x3	4x4	5x5
1	88	49	29	-	-
2	108	64	34	24	-
3	125	65	41	35	33
4	136	62	50	47	45
5	93	66	61	59	58
40mm settlement					
Size(m) Depth (m)	1x1	2x2	3x3	4x4	5x5
1	132	75	45	-	-
2	155	90	46	30	25
3	175	85	49	40	36
4	186	73	56	51	48
5	114	73	66	63	61
75mm settlement					
Size(m) Depth (m)	1x1	2x2	3x3	4x4	5x5
1	224	130	80	40	24
2	257	149	72	44	33
3	283	129	67	50	43
4	294	98	69	59	55
5	161	89	75	70	68

Table 11: Bearing capacity Estimation for shallow foundation based on CPT results

## 6.1.2 CONSOLIDATION

One Consolidation test data was available at the time of writing this report.

## 6.2 DEEP FOUNDATION

### 6.2.1 ANALYSIS BORED CAST-IN-SITU PILES

Ultimate Pile capacities have been calculated based on methods outlined in "Nominal Axial Compression Resistance of Single Drilled Shaft" in AASTHO LRFD 2007 Section 10. The ultimate unit is given by the relationship following relationship for drilled shaft:

$$\varphi R_u = \varphi q_p R_p + \varphi q_s R_s$$

In which:

$$R_p = q_p A_p$$

$$R_s = q_s A_s$$

Where:

$R_p$  = Nominal Shaft Tip Resistance

$R_s$  = Nominal Shaft Side Resistance

$q_p$  = Unit Tip Resistance

$q_s$  = Unit Side Resistance

$\varphi q_p$  = Resistance factor for tip resistance

$\varphi q_s$  = Resistance factor for side resistance

### 6.2.2 SIDE RESISTANCE FOR CAST-IN-SITU PILES

Nominal side resistance in cohesive soil is determined by following equation:

$$q_s = \alpha S_u$$

In which:

$$\alpha = 0.55 \text{ for } \frac{S_u}{p_a} \leq 1.5$$

$$\alpha = 0.55 - \left( \frac{S_u}{p_a} - 1.5 \right) \text{ for } 1.5 \leq \frac{S_u}{p_a} \leq 2.5$$

Where:

$S_u$  = Undrained Shear Strength (MPa)

$\alpha$  = Adhesion Factor (dimensionless)

$p_a$  = Atmospheric pressure (=0.101MPa)

Side Resistance in cohesionless sandy soil:

Nominal side resistance in cohesionless soil is determined by following equation ( $\beta$  - method):

$$f_s = \beta \sigma'_v \text{ for } 0.25 \leq \beta \leq 1.2$$

$$\text{For } N_{60} \geq 15 : \beta = 1.5 - (7.7 \times 10^{-3} \sqrt{z})$$

$$\text{For } N_{60} < 15 : \beta = \frac{N_{60}}{15} (1.5 - (7.7 \times 10^{-3} \sqrt{z}))$$

Where:

$\sigma'_v$  = Vertical effective stress at soil layer mid-depth

$\beta$  = Load Transfer coefficient (dimensionless)

z = Depth below ground, at soil layer mid-depth

$N_{60}$  = Average SPT blow count (corrected only for hammer efficiency) = (ER/60%)N and ER=80% for automatic trip hammer (Equation 10.4.6.2.4-2 of AASHTO LRFD 2007)

### 6.2.3 TIP RESISTANCE FOR CAST-IN-SITU PILES

Tip Resistance in cohesionless soil may be estimated using following equation:

$$q_p = 1.2 N_{60} \text{ for } 0.57 N_{60} \leq 50$$

$$q_p = 0.59 \left[ N_{60} \left( \frac{p_u}{\sigma'_v} \right) \right]^{0.8} \sigma'_v \text{ for } N_{60} > 50$$

Where:

$p_u$  = Atmospheric pressure (=0.101MPa)

$\sigma'_v$  = vertical effective stress at the tip elevation of the shaft (MPa)

$N_{60}$  = Average SPT blow count (corrected only for hammer efficiency) in the design zone under consideration (blows/300mm)

Based on the above design SPT N-values and undrained shear strength data obtained from field and laboratory tests, following units resistance has been estimated:

#### 6.2.4 ESTIMATED PILE CAPACITY FOR CAST-IN-SITU PILES

Using above *ultimate* unit resistance following *working* load capacities of different boreholes were calculated based on SPT Value:

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Chimney Area (BH-71,72,73,74)	550	25.0	666	291	80
	600	25.0	745	317	95
	750	25.0	999	396	150
	1000	25.0	1483	528	220
	550	30.0	739	367	80
	600	30.0	819	400	95
	750	30.0	1071	500	150
	1000	30.0	1534	667	220
	550	40.0	1060	530	80
	600	40.0	1173	578	95
	750	40.0	1532	723	150
	1000	40.0	2188	964	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Clarified Pump House (BH-25)	550	25.0	578	278	80
	600	25.0	642	303	95
	750	25.0	846	379	150
	1000	25.0	1223	505	220
	550	30.0	726	355	80
	600	30.0	805	387	95
	750	30.0	1056	484	150
	1000	30.0	1518	646	220
	550	40.0	1001	521	80
	600	40.0	1106	568	95
	750	40.0	1432	710	150
	1000	40.0	2019	947	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Switch Yard Area (BH-5,11,15)	550	25.0	565	262	80
	600	25.0	629	286	95
	750	25.0	834	358	150
	1000	25.0	1217	477	220
	550	30.0	693	340	80
	600	30.0	769	370	95
	750	30.0	1009	463	150
	1000	30.0	1451	617	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Transformer Yard (BH19,20,21,22, 23,24,26,27,28)	550	25.0	627	282	80
	600	25.0	700	307	95
	750	25.0	934	384	150
	1000	25.0	1376	512	220
	550	30.0	721	360	80
	600	30.0	799	393	95
	750	30.0	1044	491	150
	1000	30.0	1492	654	220
	550	40.0	1105	525	80
	600	40.0	1228	573	95
	750	40.0	1621	716	150
	1000	40.0	2351	955	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Boilar Area (BH- 45 to 48, 51 to 57)	550	25.0	692	313	80
	600	25.0	772	342	95
	750	25.0	1029	427	150
	1000	25.0	1512	570	220
	550	30.0	777	390	80
	600	30.0	861	425	95
	750	30.0	1123	532	150
	1000	30.0	1603	709	220
	550	40.0	1122	553	80
	600	40.0	1244	603	95

	750	40.0	1629	754	150
	1000	40.0	2338	1005	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
ESP Area (BH-50,60,61,63,69)	550	25.0	586	264	80
	600	25.0	654	288	95
	750	25.0	872	360	150
	1000	25.0	1283	481	220
	550	30.0	653	341	80
	600	30.0	720	372	95
	750	30.0	932	465	150
	1000	30.0	1313	619	220
	550	40.0	1028	500	80
	600	40.0	1140	546	95
	750	40.0	1498	682	150
	1000	40.0	2158	909	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Gas Cylinder Area (BH-13)	550	25.0	507	304	80
	600	25.0	553	332	95
	750	25.0	691	415	150
	1000	25.0	921	553	220
	550	30.0	774	392	80
	600	30.0	857	427	95
	750	30.0	1116	534	150
	1000	30.0	1588	712	220
	550	40.0	1026	557	80
	600	40.0	1129	608	95
	750	40.0	1447	760	150
	1000	40.0	2010	1013	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Helipad Area (BH-90)	550	25.0	585	249	80
	600	25.0	655	271	95
	750	25.0	882	339	150
	1000	25.0	1316	452	220
	550	30.0	719	329	80

	600	30.0	801	359	95
	750	30.0	1065	449	150
	1000	30.0	1560	599	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
IDCT Area (BH-42)	550	25.0	643	248	80
	600	25.0	724	271	95
	750	25.0	991	338	150
	1000	25.0	1511	451	220
	550	30.0	753	324	80
	600	30.0	842	354	95
	750	30.0	1132	442	150
	1000	30.0	1684	589	220
	550	40.0	1047	490	80
	600	40.0	1164	535	95
	750	40.0	1541	668	150
	1000	40.0	2244	891	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Sub-Station Temperature (BH-6)	550	25.0	582	240	80
	600	25.0	653	262	95
	750	25.0	884	327	150
	1000	25.0	1329	436	220
	550	30.0	624	375	80
	600	30.0	681	409	95
	750	30.0	851	511	150
	1000	30.0	1135	681	220
	550	40.0	1113	530	80
	600	40.0	1237	578	95
	750	40.0	1632	723	150
	1000	40.0	2366	964	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
TG Building (BH-)	550	25.0	644	277	80
	600	25.0	720	302	95
	750	25.0	968	378	150
	1000	25.0	1441	503	220

29,30,32,39,40)	550	30.0	704	353	80
	600	30.0	780	385	95
	750	30.0	1017	482	150
	1000	30.0	1452	642	220
	550	40.0	1030	519	80
	600	40.0	1139	567	95
	750	40.0	1485	708	150
	1000	40.0	2116	944	220
	1000	50.0	2761	1331	220

Table12: Estimated Drilled Shaft Capacity for different diameter based on SPT

Note:

1. Usually 550mm diameter pile is not recommended due to construction constrain i.e. lowering of tremie using 75mm CC block.
2. Pile capacity could be enhanced around 25% by base grouting which shall be confirmed by load test.
3. Negative skin friction is not considered in calculating drilled shaft capacity.

#### 6.2.4 ESTIMATED PILE CAPACITY FOR CAST-IN-SITU PILES

Using above *ultimate* unit resistance following *working* load capacities of different boreholes were calculated based on CPT Test:

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-1 (Transformer Yard)	550	25.0	765	291	80
	600	25.0	840	318	95
	750	25.0	1072	397	150
	1000	25.0	1456	530	220
	550	30.0	1054	347	80
	600	30.0	1161	378	95
	750	30.0	1511	473	150
	1000	30.0	2158	630	220
	550	40.0	1532	555	80
	600	40.0	1685	605	95
	750	40.0	2175	757	150
	1000	40.0	3031	1009	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-2 (TG Building)	550	25.0	1003	310	80
	600	25.0	1093	339	95
	750	25.0	1385	424	150
	1000	25.0	1869	565	220
	550	30.0	1061	370	80
	600	30.0	1171	403	95
	750	30.0	1500	504	150
	1000	30.0	2113	672	220
	550	40.0	1855	611	80
	600	40.0	2057	667	95
	750	40.0	2701	833	150
	1000	40.0	3836	1111	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-3 (Boiler Area)	550	25.0	919	225	80
	600	25.0	1038	245	95
	750	25.0	1336	307	150
	1000	25.0	1835	409	220
	550	30.0	838	319	80
	600	30.0	918	349	95
	750	30.0	1155	436	150
	1000	30.0	1555	581	220
	550	40.0	1083	418	80
	600	40.0	1186	456	95
	750	40.0	1484	570	150
	1000	40.0	1990	760	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-4 (ESP Area)	550	25.0	761	285	80
	600	25.0	838	311	95
	750	25.0	1085	389	150
	1000	25.0	1572	519	220
	550	30.0	1173	358	80
	600	30.0	1310	390	95
	750	30.0	1710	488	150
	1000	30.0	2385	651	220
	550	40.0	1745	605	80
	600	40.0	1930	660	95
	750	40.0	2502	825	150
	1000	40.0	3482	1101	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-5 (IDCT)	550	25.0	1039	294	80
	600	25.0	1165	321	95
	750	25.0	1577	402	150
	1000	25.0	2457	536	220
	550	30.0	1315	439	80
	600	30.0	1455	479	95
	750	30.0	1894	599	150
	1000	30.0	2726	799	220
	550	40.0	1737	659	80
	600	40.0	1915	719	95
	750	40.0	2465	899	150
	1000	40.0	3617	1199	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-6 (IDCT)	550	25.0	899	263	80
	600	25.0	1005	287	95
	750	25.0	1346	359	150
	1000	25.0	1818	479	220
	550	30.0	1152	352	80
	600	30.0	1284	385	95
	750	30.0	1674	481	150
	1000	30.0	2413	641	220
	550	40.0	1328	461	80
	600	40.0	1466	503	95
	750	40.0	1899	629	150
	1000	40.0	2665	839	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-7 (PT Plant Area)	550	25.0	958	260	80
	600	25.0	1076	284	95
	750	25.0	1430	355	150
	1000	25.0	2126	474	220
	550	30.0	1204	380	80
	600	30.0	1324	415	95
	750	30.0	1712	518	150
	1000	30.0	2417	691	220
	550	40.0	1819	619	80
	600	40.0	2010	675	95
	750	40.0	2618	844	150
	1000	40.0	3725	1126	220

Borehole	Pile diameter (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-9 (Intake Area)	550	25.0	825	270	80
	600	25.0	920	295	95
	750	25.0	1230	369	150
	1000	25.0	1843	492	220
	550	30.0	1129	374	80
	600	30.0	1244	408	95

	750	30.0	1603	511	150
	1000	30.0	2215	681	220

Table13: Estimated Drilled Shaft Capacity for different diameter based on CPT

## 6.2.5 ANALYSIS OF PRECAST DRIVEN PILES

### 6.2.5.1 SIDE RESISTANCE FOR DRIVEN PILES

For cohesionless soil:

Nominal side resistance in cohesionless soil for driven displacement pile is determined by following equation:

$$f = K\bar{p}_o \tan\delta$$

Where:

f=unit skin friction for driven piles (kPa)

p<sub>o</sub>=effective overburden pressure at the point

δ = friction angle between soil and pile wall

Nominal side resistance in cohesive soil is determined by following equation:

$$f_s = c_x \alpha_x$$

In which:

α<sub>x</sub> = coefficient that is a function of c<sub>x</sub>, and

c<sub>x</sub>= undrained shear strength at depth x.

α<sub>x</sub> is taken equal to 1 for c less than 24 kPa. For c in excess of 24kPa but less than or equal to 72 kPa α<sub>x</sub> decrease linearly from unity at c equal to 24kPa 0.5 at c equal to 72 kPa. For c in excess of 72 kPa α<sub>x</sub> is taken as 0.5.

### 6.2.5.2 TIP RESISTANCE FOR DRIVEN PILES

Tip Resistance (Cohesionless):

Tip Resistance in cohesionless soil may be estimated using following equation:

$$q = \bar{p}_o N_q$$

Where:

q=unit tip resistance for driven piles (kPa)

p<sub>o</sub>= effective overburden pressure at pile tip

N<sub>q</sub>=bearing capacity factor

## 6.2.6 ESTIMATED PILE CAPACITY FOR PRECAST DRIVEN PILES

Using above *ultimate* unit resistance following *working* load capacities of different boreholes was calculated based on SPT Test Results:

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Chimney Area (BH-71,72,73,74)	350	24.0	537	244	60
	400	24.0	634	279	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Clarified Pump House (BH-25)	350	24.0	534	252	60
	400	24.0	629	288	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Switch Yard (BH-5,11,15)	350	24.0	514	231	60
	400	24.0	608	264	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Transformer Yard (BH19,20,21,22,23,24,26,27)	350	24.0	509	230	60
	400	24.0	603	262	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Boilar Area (BH-45 to 48, 51 to 57)	350	24.0	574	267	60
	400	24.0	677	305	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
ESP Area (BH-50,60,61,63,69)	350	24.0	516	230	60
	400	24.0	612	263	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Gas Cylinder Room (BH-13)	350	24.0	712	275	60
	400	24.0	855	315	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Helipad Area (BH-90)	350	24.0	348	134	60
	400	24.0	418	153	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
IDCT Area (BH-42)	350	24.0	425	206	60
	400	24.0	499	236	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
Sub-Station Temperature (BH-6)	350	24.0	344	207	60
	400	24.0	394	236	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
T.G Building (BH-29,30,32,39,40)	350	24.0	532	240	60
	400	24.0	629	274	70

Table 13: Estimated Capacity of Precast R.C.C. Driven pile for different size based on SPT

### 6.2.6 ESTIMATED PILE CAPACITY FOR PRECAST DRIVEN PILES

Using above *ultimate* unit resistance following *working* load capacities of different boreholes was calculated based on CPT Test Results:

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-1 (Transformer Yard)	350	24.0	589	214	60
	400	24.0	672	245	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-2 (TG Building)	350	24.0	633	217	60
	400	24.0	741	248	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-3 (Boiler Area)	350	24.0	440	157	60
	400	24.0	510	179	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-4 (ESP Area)	350	24.0	692	218	60
	400	24.0	812	249	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-5 (IDCT)	350	24.0	658	210	60
	400	24.0	768	240	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-6 (IDCT)	350	24.0	532	200	60
	400	24.0	613	228	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-7 (PT Plant Area)	350	24.0	597	176	60
	400	24.0	719	201	70

Borehole	Pile size (mm)	Length(m)	Pile capacity(kN)		
			Compression(kN)	Tension(kN)	Lateral(kN)
SCPT-9 (Intake Area)	350	24.0	579	201	60
	400	24.0	673	230	70

Table 13: Estimated Capacity of Precast R.C.C. Driven pile for different size based on SCPT

### 6.2.7 TESTING OF PILES

Individual piles or groups may be subjected to compression, tension, and/or lateral loads. Following are methods for confirming design capacity of piles under each type of loading condition.

Test Type	Test Method
Axial Compression	ASTM D1143
Axial Tension	ASTM D3689
Lateral	ASTM D3966

Table 11: Pile load Test Methods

## 7. Excavation, Compaction, and Ground Improvement Criteria:

### 7.1 Suitability of On Site Soil as Structural Fill

The materials covering the site near the surface consist of mostly dredged fill comprises of silty sand material, which are suitable for general backfilling purpose. However, the final decision should be taken during construction and after suitable testing program.

### 7.2 Backfill Material

Any back-fill material used for foundation should be well-graded, free draining backfill material with no more than five (5) percent passing a 0.075 millimeter sieve. All back fill material should be free from presence of organic or other harmful subsistence. All back fill material should be placed in layers of 150mm and should achieve 95% maximum dry density as defined by Modified Proctor Compaction Test. Field density test as defined by ASTM D1556 should be performed at regular intervals to ensure quality of compaction.

### 7.3 Material below Pavements:

Material selected for use in the top 500mm for cut or fill areas in the roadway shall be in addition to meeting the requirements; the materials passing the #200 (0.076mm) sieve shall not exceed 35%, the liquid limit & plasticity index for these material shall not be more than 35% & 10% respectively and soaked CBR value shall not be less than 15& and the swell not exceed 2%.

### 7.4 Slopes for excavation:

The materials covering the site near the surface consist of mostly silty sand. Open excavation at 1H:1V slope may be permitted for up to 1m depth. Appropriate shoring should be used for greater excavation particularly during rainy seasons or where it is required.

### 7.5 Ground Improvement of soft cohesive layer:

The subsurface encountered during soil exploration comprises of very soft to soft cohesive organic soil from 6m to 18m below ground level which is susceptible to consolidation settlement. This very

soft compressible soil requires be replacing or improving prior to use as a foundation layer. However, soil replacement at such depth shall not be viable and economic. Thus soil improvement is recommended. There are several methods of ground improvement. Among which "Perforated Vertical drain/ Wick drain" or "sand column" with preloading of 1.25times the design pressure could be used considering of its applicability, economy and characteristic of soil for this particular project.

## **8 Analysis for Liquefaction Potential**

### **8.1 General:**

The shear stress induced/developed at different depth during an earthquake depends upon the overburden pressure while the shear resistance can be calculated based on the SPT values.

The shear stress induces/developed and the shear resistances offered by the soil are evaluated in terms of Cyclic Stress Ratio (CSR) and the Cyclic Resistance Ratio (CRR) respectively. The CSR is the ratio of the shear stress developed to the effective over burden pressure at various depths while the CRR is the ratio of the shear resistance of the soil to the effective overburden pressure at various depths.

### **8.2 Method:**

#### **8.2.1 Calculation of Cyclic Stress Ratio:**

For the determination of the CSR values at various depths, a peak horizontal ground acceleration coefficient of 0.12 as stated in Bangladesh National Building Code (BNBC 2006) has been taken in to consideration.

CSR values have been determined using the well-established and widely accepted methods given by Seed & Idriss (1971) which also included the stress reduction coefficient which varies with depth.

#### **8.2.2 Calculation of Cyclic Resistance Ratio:**

The CRR values have been determined using the method given by Robertson (2010) for an earthquake magnitude of 7.5 giving due consideration to the fact that earthquake of magnitude greater than 7 have been recorded in the Northern Bangladesh. The procedure is an update on procedure originally published in NCEER-97-0022 (Proceedings of the Workshop on Evaluation of Liquefaction Resistance of Soils).

#### **8.2.3 Factor of Safety:**

Factor of safety has been calculated based on ratio between CRR and CSR. A factor of safety of less than 1.20 indicates liquefiable soil.

#### **8.2.4 Calculation of Liquefaction Potential Index:**

Liquefaction Potential calculation based on SPT is enclosed in appendix.

### **8.3 Analysis of Result:**

The variations of the CSR and the CRR with depth based on the results of each of the SPT have been presented in Appendix-B. Factor of safety (F.S.) are also included in the calculation sheet.

Soil is liquefiable below upto 6m from ground level as indicated by low factor of safety for all the boring location. Furthermore, the degree of susceptibility of liquefaction, as indicated is also high.


In view of the above, this depth of soil susceptible to liquefaction, ground improvement method may be used to improve the soil. Hence the proposed structures have to be supported on pile foundation exceeding the liquefiable depths.

### **9.0 REFERENCES**

1. Geological Map of Bangladesh (1990). Md. Md. Khurshid Alam, AKM Shahidul Hasan, and Mujibur Rahman Khan, Geological Survey of Bangladesh and John W. Whitney, United States Geological Survey of Bangladesh. Published by Geological Survey of Bangladesh.
2. Bangladesh National Building Code (2006). Director, Housing and Building Research Institute, Ministry of Housing and Public Works.
3. American society for testing and materials (ASTM).
4. American Association of State Highway and Transportation Organization (AASHTO).

## **APPENDIX-A**

### **MAP**



TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT

Sub Consultant

Drg. No.

DCU/BHEL/  
Layout

Date: 21-06-16

Engineer

Emran Uddin  
Engr. Rafiqul Islam  
Engr. Rokmuzz zaman

Location

Rampal, Bagerhat.

Client & Owner

Client: BHEL  
Owner: BIFPCL

Drawing Title:

Layout Plan

Development Constructions Ltd.  
House 11, Road 19A, Uttara, Dhaka 1230  
Phone +880-2-5895231, Fax +880-2-5895283  
Email: dc@dccltd.com, Web: http://www.dccltd.com

Project

2x660MW Maitree STPP.

# Appendix-B

## **FIELD TEST RESULT**

# Appendix-B1

## BOREHOLE LOGS





**DEVELOPMENT CONSTRUCTIONS LIMITED.**

Geotechnical Engineering Laboratory, Dhaka.

House 11, Road 19A, Sector 4, Uttara, Dhaka 1230, Bangladesh.

Phone: +880-2-58957231. Fax: (880) 2-58957283. Email: fcl@dcl-fcl.com. Web: http://www.dcl-fcl.com

Project: 2x660MW BIFPCL STPP Maitree Thermal Power Plant.

Client: BHEL; Owner: BIFPCL

Location: Rampal, Bagerhat.

Grain Size		Atterberg Limits		Moisture Content		Unit Weight		Specific Gravity	Consolidation			Shear Strength			Standard Penetration Test					Sample No.	Sample Rec. (mm)	Depth (m)	Elev (m)	Layer Symbol	Borehole: BH-06 WD(m) 2.60m	E: 454996m N: 498577m Elev: 5.530m Start: 26.03.16 End: 28.03.16				
Gravel (%)	Sand (%)	Fines (%)	L.L.	P.I.	w (%)	$\gamma_t$	$\gamma_d$	$G_s$	$e_o$	$C_c$	$C_r$	Type	$C_u/S_u$ (kN/m <sup>2</sup> )	$\Phi^\circ$ (Deg)	150mm	150mm	150mm	A-Value	0								10	20	30	40
00	88	12	N	P	24.82														02	02	04	06				D1	400	1.0	5.0	SP-SM - Poorly graded Sand With Silt. Loose to Medium.Grey.
																			02	03	03	06				D2	380	2.0	4.0	
																			02	03	03	06				D3	390	3.0	3.0	OH- Organic Silt. Soft. Grey.
																			08	11	13	24				D4	360	4.0	2.0	
																			01	01	01	02				D5	390	5.0	0.0	Silty Clay. Soft to Medium.Grey.
00	13	87	108	44	44.74	19.14	13.22	2.68											00	00	02	02				UDS-1	340	6.0	-1.0	
																			01	02	02	04				D6	370	7.0	-2.0	Silty Sand. Medium.Grey.
																			01	02	02	04				D7	380	8.0	-3.0	
																			01	02	03	05				D8	370	9.0	-4.0	Clayey Silt. Stiff. Grey.
																			01	02	02	04				UDS-2	360	10.0	-5.0	
																			01	02	02	04				D9	400	11.0	-6.0	Silty Sand. Medium. Grey.
																			01	01	02	03				D10	390	12.0	-7.0	
																			05	08	10	18				D11	320	13.0	-8.0	ML- Silt with Sand. Stiff to Hard.Grey.
																			02	05	08	13				D12	360	14.0	-9.0	
																			03	04	07	11				D13	400	15.0	-10.0	Silty Sand. Dense. Grey.
																			07	08	10	18				D14	390	16.0	-11.0	
																			04	08	11	19				D15	360	17.0	-12.0	Silty Clay. Very Stiff. Grey.
00	22	78	34	09	29.20														04	05	06	11				D16	450	18.0	-13.0	
																			11	13	17	30				D17	310	19.0	-14.0	
																			10	14	19	33				D18	330	20.0	-15.0	
																			07	09	11	20				D19	450	21.0	-16.0	
																			09	11	15	26				UDS-3	360	22.0	-17.0	
																										D20	350	23.0	-18.0	

Legend

L.L. = Liquid Limit  
P.I. = Plasticity Index  
w = Moisture Content  
 $G_s$  = Specific Gravity

$\gamma_t$  = Bulk Unit Weight  
 $\gamma_d$  = Dry Unit Weight  
 $C_c$  = Compression Index  
 $C_r$  = Re-compression Index

$e_o$  = Initial Void Ratio  
 $C_u$  = Undrained Cohesion  
 $S_u$  = Undrained Shear Strength  
WD = Depth of Water Measured 24h after Completion of Drilling

$\Phi$  = Angle of Internal Friction  
D = Disturbed Sample  
UD = Undisturbed Sample  
DST = Direct Shear Test

Clay  
Silt  
Sand  
Gravel

Drawn BY: Md. Emran Uddin  
Checked BY: Md. Rafiqul Islam  
Approved BY: Engr. Mehedy Amin  
Date : 25.06.16









# DEVELOPMENT CONSTRUCTIONS LIMITED.

Geotechnical Engineering Laboratory, Dhaka.

House 11, Road 19A, Sector 4, Uttara, Dhaka 1230, Bangladesh.

Phone: +880-2-58957231. Fax: (880) 2-58957283. Email: fcl@dcl-fcl.com. Web: http://www.dcl-fcl.com

**Project:** 2x660MW BIFPCL STPP Maitree Thermal Power Plant.

**Client:** BHEL; Owner: BIFPCL

**Location:** Rampal, Bagerhat.

Grain Size			Atterberg Limits		Moisture Content (%)	Unit Weight (kN/m <sup>3</sup> )		Specific Gravity (G <sub>s</sub> )	Consolidation			Shear Strength			Standard Penetration Test				Sample No.	Sample Rec. (mm)	Depth (m)	Elev (m)	Layer Symbol	Borehole: <b>BH-13</b>	E: 454936m N: 498888m Elev: 5.279m	WD(m) 2.43m	Start: 03.05.16 End: 04.05.16
Gravel (%)	Sand (%)	Fines (%)	L.L.	P.I.		Y <sub>t</sub>	Y <sub>d</sub>		e <sub>0</sub>	C <sub>c</sub>	C <sub>r</sub>	Type	C <sub>u</sub> /S <sub>u</sub> (kN/m <sup>2</sup> )	Φ° (Deg)	150mm	150mm	150mm	N-Value									
00	85	15	N	P														D22	310	31.0	-26.0	SM- Silty Sand. Medium to Dense. Grey.					
																		D23	260	32.0	-27.0						
																		D24	320	33.0	-28.0						
																		D25	360	34.0	-29.0						
																		D26	340	35.0	-30.0						
																		D27	490	36.0	-31.0						
																				37.0	-32.0						
																				38.0	-33.0	ML- Silt. Very Stiff. Grey.					
																				39.0	-34.0						
00	13	87	44	13																40.0	-35.0						
END OF BORING																											

**Legend**

L.L. = Liquid Limit  
P.I. = Plasticity Index  
w = Moisture Content  
G<sub>s</sub> = Specific Gravity

Y<sub>t</sub> = Bulk Unit Weight  
Y<sub>d</sub> = Dry Unit Weight  
C<sub>c</sub> = Compression Index  
C<sub>r</sub> = Re-compression Index

e<sub>0</sub> = Initial Void Ratio  
C<sub>u</sub> = Undrained Cohesion  
S<sub>u</sub> = Undrained Shear Strength  
WD = Depth of Water Measured 24h after Completion of Drilling

Φ = Angle of Internal Friction  
D = Disturbed Sample  
UD = Undisturbed Sample  
DST = Direct Shear Test

Clay  
Silt  
Sand  
Gravel

Drawn BY: Md. Emran Uddin  
Checked BY: Md. Rafiqul Islam  
Approved BY: Engr. Mehedy Amin  
Date : 25.06.16





## DEVELOPMENT CONSTRUCTIONS LIMITED.

Geotechnical Engineering Laboratory, Dhaka.

House 11, Road 19A, Sector 4, Uttara, Dhaka 1230, Bangladesh.

Phone: +880-2-58957231. Fax: (880) 2-58957283. Email: fcl@dcl-fcl.com. Web: http://www.dcl-fcl.com

Project: 2x660MW BIFPCL STPP Maitree Thermal Power Plant.

Client: BHEL; Owner: BIFPCL

Location: Rampal, Bagerhat.

Grain Size		Atterberg Limits		Moisture Content		Unit Weight (kN/m <sup>3</sup> )		Specific Gravity (G <sub>s</sub> )	Consolidation			Shear Strength			Standard Penetration Test					Sample No.	Sample Rec. (mm)	Depth (m)	Elev (m)	Layer Symbol	Borehole: <b>BH-19</b>	E: 454786m N: 499146m Elev: 5.262m	Start: 08.04.16 End: 09.04.16			
Gravel (%)	Sand (%)	Fines (%)	L.L.	P.I.	w (%)	Y <sub>t</sub>	Y <sub>d</sub>		e <sub>0</sub>	C <sub>c</sub>	C <sub>r</sub>	Type	C <sub>u</sub> /S <sub>u</sub> (kN/m <sup>2</sup> )	Φ° (Deg)	150mm	150mm	A-Value	0	10									20	30	40
00	87	13	N	P													01	01	01	02				D1	370	5.0				
																	01	01	02	03				D2	340	4.0	SM- Silty Sand. Very Loose. Grey.			
																	01	01	01	02				D3	365	3.0				
																	01	01	01	02				D4	350	2.0				
																	01	01	02	03				D5	340	1.0				
																	01	01	02	03				D6	480	0.0				
																	00	01	01	02				D7	450	-1.0	CH- Fat Clay. Very Soft to Soft. Grey.			
																	01	01	01	02				D8	475	-2.0				
00	09	91	73	40	77.93	15.44	8.67	2.68									01	01	01	02				D9	480	-3.0				
																	01	01	01	02				D10	370	-4.0				
																	00	00	01	01				UDS-1	310	-5.0				
																	01	01	01	02				D11	475	-6.0				
																	01	01	01	02				D12	480	-7.0				
																	01	02	04	06				D13	370	-8.0	ML- Silty Sand. Medium to Very stiff. Grey.			
																	02	03	05	08				D14	365	-9.0				
																	03	03	04	07				D15	340	-10.0				
																	03	04	04	08				D16	350	-11.0				
																	04	05	07	12				D17	340	-12.0				
00	41	59	N	P													04	05	07	12				D18	355	-13.0				
																	06	07	11	18				D19	365	-14.0				
																	06	08	12	20				D20	370	-15.0				
																	08	10	15	25				D21	365	-16.0				
																	11	12	16	28				D22	370	-17.0				
																	10	12	15	27				D23	350	-18.0				
																	10	12	15	27				D24	365	-19.0				
																	02	02	03	05				UDS-2	420	-20.0				
																	02	02	03	05				D25	350	-21.0				
																	03	03	03	06				D26	480	-22.0				
																	03	03	03	06				D27	350	-23.0	ML- Silt with Sand. Medium. Grey.			
																	03	03	03	06				D28	420	-24.0				
																								D29	350	-25.0				

Legend	L.L. = Liquid Limit	Y <sub>t</sub> = Bulk Unit Weight	e <sub>0</sub> = Initial Void Ratio	Φ = Angle of Internal Friction	Clay	Drawn BY: Md. Emran Uddin		
	P.I. = Plasticity Index	Y <sub>d</sub> = Dry Unit Weight	C <sub>u</sub> = Undrained Cohesion	D = Disturbed Sample			Checked BY: Md. Rafiqul Islam	
	w = Moisture Content	C <sub>c</sub> = Compression Index	S <sub>u</sub> = Undrained Shear Strength	UD = Undisturbed Sample				Approved BY: Engr. Mehedy Amin
	G <sub>s</sub> = Specific Gravity	C <sub>r</sub> = Re-compression Index	WD = Depth of Water Measured 24h after Completion of Drilling	DST = Direct Shear Test				















# DEVELOPMENT CONSTRUCTIONS LIMITED.

Geotechnical Engineering Laboratory, Dhaka.

House 11, Road 19A, Sector 4, Uttara, Dhaka 1230, Bangladesh.

Phone: +880-2-58957231. Fax: (880) 2-58957283. Email: fcl@dcl-fcl.com. Web: http://www.dcl-fcl.com

**Project:** 2x660MW BIFPCL STPP Maitree Thermal Power Plant.

**Client:** BHEL; Owner: BIFPCL

**Location:** Rampal, Bagerhat.

Grain Size			Atterberg Limits		Moisture Content (%)	Unit Weight (kN/m <sup>3</sup> )		Specific Gravity (G <sub>s</sub> )	Consolidation			Shear Strength			Standard Penetration Test				Sample No.	Sample Rec. (mm)	Depth (m)	Elev (m)	Layer Symbol	Borehole: <b>BH-23</b>	E: 454608m N: 499144m Elev: 5.620m	Start: 24.04.16 End: 26.04.16	
Gravel (%)	Sand (%)	Fines (%)	L.L.	P.I.		Y <sub>t</sub>	Y <sub>d</sub>		e <sub>0</sub>	C <sub>c</sub>	C <sub>r</sub>	Type	C <sub>u</sub> /S <sub>u</sub> (kN/m <sup>2</sup> )	Φ° (Deg)	150mm	150mm	150mm	N-Value									
00	45	55	N	P															D22	420	31.0	25.0	ML- Sandy Silt. Stiff to Hard. Grey.	WD(m) 2.60m			
													10	12	18	30			D23	450	32.0	26.0					
													09	13	20	33			D24	430	33.0	27.0					
													17	19	23	42	(430mm/ Frist 50 blows)			D25	400	34.0				28.0	
													10	16	20	36			D26	340	35.0	29.0					
													15	18	22	40	(440mm/ Frist 50 blows)			D27	420	36.0				30.0	
00	44	56	N	P															D28	330	37.0	31.0	END OF BORING				
													13	15	21	36					38.0	32.0					
																						39.0	33.0				
																						40.0	34.0				
													20	27	35	62	(380mm/ Frist 50 blows)					35.0	35.0				

<b>Legend</b>	L.L. = Liquid Limit	Y <sub>t</sub> = Bulk Unit Weight	e <sub>0</sub> = Initial Void Ratio	Φ = Angle of Internal Friction		Clay Silt Sand Gravel	Drawn BY: Md. Emran Uddin Checked BY: Md. Rafiqul Islam Approved BY: Engr. Mehedy Amin Date : 25.06.16
	P.I. = Plasticity Index	Y <sub>d</sub> = Dry Unit Weight	C <sub>u</sub> = Undrained Cohesion	D = Disturbed Sample			
	w = Moisture Content	C <sub>c</sub> = Compression Index	S <sub>u</sub> = Undrained Shear Strength	UD = Undisturbed Sample			
	G <sub>s</sub> = Specific Gravity	C <sub>r</sub> = Re-compression Index	WD = Depth of Water Measured 24h after Completion of Drilling	DST = Direct Shear Test			

































# DEVELOPMENT CONSTRUCTIONS LIMITED.

Geotechnical Engineering Laboratory, Dhaka.

House 11, Road 19A, Sector 4, Uttara, Dhaka 1230, Bangladesh.

Phone: +880-2-58957231. Fax: (880) 2-58957283. Email: fcl@dcl-fcl.com. Web: http://www.dcl-fcl.com

Project: 2x660MW BIFPCL STPP Maitree Thermal Power Plant.

Client: BHEL; Owner: BIFPCL

Location: Rampal, Khulna.

Grain Size		Atterberg Limits		Moisture Content (%)	Unit Weight (kN/m <sup>3</sup> )		Specific Gravity (G <sub>s</sub> )	Consolidation			Shear Strength			Standard Penetration Test				Sample No.	Sample Rec. (mm)	Depth (m)	Elev (m)	Layer Symbol	Borehole: BH-39	E: 454599m N: 499054m Elev: 2.718m	Start: 06.04.16 End: 12.04.16
Gravel (%)	Sand (%)	Fines (%)	L.L.		P.I.	Y <sub>t</sub>		Y <sub>d</sub>	e <sub>0</sub>	C <sub>c</sub>	C <sub>r</sub>	Type	C <sub>u</sub> /S <sub>u</sub> (kN/m <sup>2</sup> )	Φ° (Deg)	150mm	150mm	150mm								
00	10	90	35	09													D22	350	31.0	-25.0					
																	D23	360	32.0	-26.0					
																	D24	370	33.0	-27.0					
																	D25	380	34.0	-28.0					
																	D26	340	35.0	-29.0					
																	D27	350	36.0	-30.0					
																	D28	380	37.0	-31.0					
																	D29	370	38.0	-32.0					
																	D30	360	39.0	-33.0					
																	D31	330	40.0	-34.0					
																	D32	340	41.0	-35.0					
																	D33	350	42.0	-36.0					
00	81	19	N	P													D34	360	43.0	-37.0					
																	D35	370	44.0	-38.0					
																	D36	360	45.0	-39.0					
																	D37	310	46.0	-40.0					
																	D38	320	47.0	-41.0					
																	D39	310	48.0	-42.0					
																	D40	320	49.0	-43.0					
																	D41	330	50.0	-44.0					
																	D42	320	51.0	-45.0					
																			52.0	-46.0					
																			53.0	-47.0					
																			54.0	-48.0					
																			55.0	-49.0					
																			56.0	-50.0					
																			57.0	-51.0					
																			58.0	-52.0					
																			59.0	-53.0					
																			60.0	-54.0					
																			61.0	-55.0					



























































# DEVELOPMENT CONSTRUCTIONS LIMITED.

Geotechnical Engineering Laboratory, Dhaka.

House 11, Road 19A, Sector 4, Uttara, Dhaka 1230, Bangladesh.

Phone: +880-2-58957231. Fax: (880) 2-58957283. Email: fcl@dcl-fcl.com. Web: http://www.dcl-fcl.com

**Project:** 2x660MW BIFPCL STPP Maitree Thermal Power Plant.

**Client:** BHEL; Owner: BIFPCL

**Location:** Rampal, Bagerhat.

Grain Size		Atterberg Limits		Moisture Content		Unit Weight (kN/m <sup>3</sup> )		Specific Gravity		Consolidation			Shear Strength			Standard Penetration Test					Sample No.	Sample Rec. (mm)	Depth (m)	Elev (m)	Layer Symbol	Borehole: <b>BH-60</b>	E: 454604m N: 498898m Elev: 5.563m	Start: 10.04.16 End: 12.04.16		
Gravel (%)	Sand (%)	Fines (%)	L.L.	P.I.	w (%)	Y <sub>t</sub>	Y <sub>d</sub>	G <sub>s</sub>	e <sub>0</sub>	C <sub>c</sub>	C <sub>r</sub>	Type	C <sub>u</sub> /S <sub>u</sub> (kN/m <sup>2</sup> )	Φ° (Deg)	150mm	150mm	A-Value	0	10	20									30	40
00	86	14	N	P														01 02 02 04	(blows/310mm)	D1	340	1.0	5.0							
																		02 02 02 04	(blows/305mm)	D2	320	2.0	4.0							
																		01 02 03 05	(blows/305mm)	D3	340	3.0	3.0							
																		02 02 03 05	(blows/305mm)	D4	380	4.0	2.0							
																		01 02 03 05	(blows/310mm)	D5	260	5.0	1.0							
																		00 00 00 00	(blows/310mm)	D6	490	6.0	0.0							
																		01 01 01 02	(blows/305mm)	D7	440	7.0	-1.0							
00	09	91	69	32	44.66	16.11	11.14	2.69										01 02 02 04		UDS-1	260	8.0	-2.0				MH- Elastic Silt. Very soft to Soft. Grey.			
																		01 02 02 04		D8	420	9.0	-3.0							
																		01 01 01 02	(blows/305mm)	D9	440	10.0	-4.0				SM- Silty Sand. Loose to Dense. Grey.			
																		01 02 02 04	(blows/305mm)	D10	360	11.0	-5.0							
																		03 03 05 08		D11	340	12.0	-6.0				SM- Silty Sand. Loose to Dense. Grey.			
																		03 04 06 10		D12	360	13.0	-7.0							
																		06 10 12 22		D13	340	14.0	-8.0				SM- Silty Sand. Loose to Dense. Grey.			
																		08 12 13 25		D14	320	15.0	-9.0							
00	85	15	N	P														07 11 18 29		D15	320	16.0	-10.0				SM- Silty Sand. Loose to Dense. Grey.			
																		DST 28.1 29.8 11 12 14 26		D16	280	17.0	-11.0							
																		15 20 21 41		D17	340	18.0	-12.0				SM- Silty Sand. Loose to Dense. Grey.			
																		14 18 22 40		D18	320	19.0	-13.0							
																		05 05 08 13		D19	440	20.0	-14.0				SM- Silty Sand. Loose to Dense. Grey.			
																		06 08 10 18		D20	370	21.0	-15.0							
																		06 08 10 18		D21	375	22.0	-16.0	SM- Silty Sand. Loose to Dense. Grey.						
																						23.0	-17.0							
																							24.0	-18.0	SM- Silty Sand. Loose to Dense. Grey.					
																							25.0	-19.0						
																								26.0	-20.0	SM- Silty Sand. Loose to Dense. Grey.				
																								27.0	-21.0					
																									28.0	-22.0	SM- Silty Sand. Loose to Dense. Grey.			
																									29.0	-23.0				
																										30.0	-24.0	SM- Silty Sand. Loose to Dense. Grey.		

**Legend**  
 L.L. = Liquid Limit  
 P.I. = Plasticity Index  
 w = Moisture Content  
 G<sub>s</sub> = Specific Gravity  
 Y<sub>t</sub> = Bulk Unit Weight  
 Y<sub>d</sub> = Dry Unit Weight  
 C<sub>c</sub> = Compression Index  
 C<sub>r</sub> = Re-compression Index  
 e<sub>0</sub> = Initial Void Ratio  
 C<sub>u</sub> = Undrained Cohesion  
 S<sub>u</sub> = Undrained Shear Strength  
 WD = Depth of Water Measured 24h after Completion of Drilling  
 Φ = Angle of Internal Friction  
 D = Disturbed Sample  
 UD = Undisturbed Sample  
 DST = Direct Shear Test  
 Clay  
 Silt  
 Sand  
 Gravel  
 Drawn BY: Md. Emran Uddin  
 Checked BY: Md. Rafiqul Islam  
 Approved BY: Engr. Mehedy Amin  
 Date : 25.06.16



























# DEVELOPMENT CONSTRUCTIONS LIMITED.

Geotechnical Engineering Laboratory, Dhaka.

House 11, Road 19A, Sector 4, Uttara, Dhaka 1230, Bangladesh.

Phone: +880-2-58957231. Fax: (880) 2-58957283. Email: fcl@dcl-fcl.com. Web: http://www.dcl-fcl.com

**Project:** 2x660MW BIFPCL STPP Maitree Thermal Power Plant.

**Client:** BHEL; Owner: BIFPCL

**Location:** Rampal, Khulna.

Grain Size		Atterberg Limits		Moisture Content (w %)	Unit Weight (kN/m <sup>3</sup> )		Specific Gravity (G <sub>s</sub> )	Consolidation			Shear Strength			Standard Penetration Test				Sample No.	Sample Rec. (mm)	Depth (m)	Elev (m)	Layer Symbol	Borehole: <b>BH-73</b>	E: 454674m N: 498772m Elev: 5.276m	Start: 16.04.16 End: 19.04.16							
Gravel (%)	Sand (%)	Fines (%)	L.L.		P.I.	Y <sub>t</sub>		Y <sub>d</sub>	e <sub>0</sub>	C <sub>c</sub>	C <sub>r</sub>	Type	C <sub>u</sub> /S <sub>u</sub> (kN/m <sup>2</sup> )	Φ° (Deg)	150mm	150mm	A-Value									0	10	20	30	40	50	
00	86	14	N	P												11	16	16	32				D22	340	31.0	-26.0	SM- Silty Sand. Medium to Dense. Grey.					
																10	16	18	34				D23	320	32.0	-27.0						
																10	14	15	29				D24	360	33.0	-28.0						
																09	10	12	22				D25	300	34.0	-29.0						
																07	07	07	14				D26	440	35.0	-30.0						
00	11	89	36	11												08	08	09	17				D27	440	36.0	-31.0	ML- Silt. Stiff to Hard. Grey.					
																09	10	10	20				D28	390	37.0	-32.0						
																06	06	06	12				D29	490	38.0	-33.0						
																11	18	22	40	(445mm/ Frist 50 blows)				D30	390	39.0		-34.0				
																30	37	33	70	(230mm/ Frist 50 blows)				D31	220	40.0		-35.0				
																13	14	23	37	(450mm/ Frist 50 blows)				D32	340	41.0	-36.0	SM- Silty Sand. Dense to Very dense. Grey.				
																17	20	22	42	(380mm/ Frist 50 blows)				D33	290	42.0	-37.0					
																17	20	23	43	(380mm/ Frist 50 blows)				D34	300	43.0	-38.0					
																15	28	40	68	(320mm/ Frist 50 blows)				D35	240	44.0	-39.0					
																13	24	27	51	(360mm/ Frist 50 blows)				D36	300	45.0	-40.0					
																15	22	32	54	(360mm/ Frist 50 blows)				D37	250	46.0	-41.0					
00	84	16	N	P												24	33	40	73	(260mm/ Frist 50 blows)				D38	220	47.0	-42.0	SM- Silty Sand. Dense to Very dense. Grey.				
																20	27	31	58	(390mm/ Frist 50 blows)				D39	240	48.0	-43.0					
																25	50	-	(220mm/ Frist 50 blows)				D40	200	49.0	-44.0						
																23	35	25	60	(260mm/ Frist 50 blows)				D41	240	50.0	-45.0					
																20	29	34	63	(305mm/ Frist 50 blows)				D42	250	51.0	-46.0					

Legend	L.L. = Liquid Limit	Y <sub>t</sub> = Bulk Unit Weight	e <sub>0</sub> = Initial Void Ratio	Φ = Angle of Internal Friction	
	P.I. = Plasticity Index	Y <sub>d</sub> = Dry Unit Weight	C <sub>u</sub> = Undrained Cohesion	D = Disturbed Sample	
	w = Moisture Content	C <sub>c</sub> = Compression Index	S <sub>u</sub> = Undrained Shear Strength	UD = Undisturbed Sample	
	G <sub>s</sub> = Specific Gravity	C <sub>r</sub> = Re-compression Index	WD = Depth of Water Measured 24h after Completion of Drilling	DST = Direct Shear Test	

Drawn BY: Md. Emran Uddin  
 Checked BY: Md. Rafiqul Islam  
 Approved BY: Engr. Mehedy Amin  
 Date : 25.06.16










## **Appendix-B2**


# **CONE PENETRATION TEST LOGS**






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com



	Test according NEN 5140 class 1	
	G.L. 5.212 NAP	W.L.: 0
Project: <b>Maitree Thermal Power Project</b>		
Location: <b>Rampal</b>		
Position: <b>454755, 499146 RD</b>		


Predrill :	<b>0 m Predrilled</b>
Date:	<b>4/11/2016</b>
Cone no.:	<b>S15CFIP.S09131</b>
Project no.:	<b>Maitree Thermal</b>
CPT no.:	<b>01</b>
	<b>1/12</b>






 <b>DEVELOPMENT CONSTRUCTIONS LTD.</b> House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8957236, Fax: +880-2-8957243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.212 NAP	W.L.: <b>0</b>	Project: <b>Maitree Thermal Power Project</b>	Date: <b>4/11/2016</b>
	Location: <b>Rampal</b>		Cone no.: <b>S15CFIP.S09131</b>	Project no.: <b>Maitree Thermal</b>
	Position: <b>454755, 499146 RD</b>		CPT no.: <b>01</b>	2/12
	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT			






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.212 NAP	W.L.: <b>0</b>	Project: <b>Maitree Thermal Power Project</b>	Date: <b>4/11/2016</b>
	Location: <b>Rampal</b>	Position: <b>454755, 499146 RD</b>	Cone no.: <b>S15CFIP.S09131</b>	Project no.: <b>Maitree Thermal</b>
	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	CPT no.: <b>01</b>	3/12	






 <b>DEVELOPMENT CONSTRUCTIONS LTD.</b> House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8957236, Fax: +880-2-8957243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.212 NAP	W.L.: <b>0</b>	Date: <b>4/11/2016</b>	
	Project: <b>Maitree Thermal Power Project</b>		Cone no.: <b>S15CFIP.S09131</b>	
	Location: <b>Rampal</b>		Project no.: <b>Maitree Thermal</b>	
	Position: <b>454755, 499146 RD</b>		CPT no.: <b>01</b>	<b>4/12</b>



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8997236, Fax: +880-2-8997243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according to NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.212 NAP	W.L.: <b>0</b>	Date: <b>4/11/2016</b>	
	Project: <b>Maitree Thermal Power Project</b>		Cone no.: <b>S15CFIP.S09131</b>	
	Location: <b>Rampal</b>		Project no.: <b>Maitree Thermal</b>	
	Position: <b>454755, 499146 RD</b>		CPT no.: <b>01</b>	<b>5/12</b>



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according to NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.212 NAP	W.L.: <b>0</b>	Date: <b>4/11/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>Maitree Thermal Power Project</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>		CPT no.: <b>01</b>	<b>6/12</b>
	Position: <b>454755, 499146 RD</b>			






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com


Test according to NEN 5140 class 1  
 G.L. 5.212 NAP      W.L.: 0



Project: **Maitree Thermal Power Project**  
 Location: **Rampal**  
 Position: **454755, 499146 RD**


Predrill : **0 m Predrilled**  
 Date: **4/11/2016**  
 Cone no.: **S15CFIP.S09131**  
 Project no.: **Maitree Thermal**  
 CPT no.: **01**      **7/12**






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according to NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.212 NAP	W.L.: <b>0</b>	Project: <b>Maitree Thermal Power Project</b>	Date: <b>4/11/2016</b>
	Location: <b>Rampal</b>	Position: <b>454755, 499146 RD</b>	Cone no.: <b>S15CFIP.S09131</b>	Project no.: <b>Maitree Thermal</b>
	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	CPT no.: <b>01</b>	8/12	






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8997236, Fax: +880-2-8997243                  Web: http://www.dcl.com Email: dcl@dcl.com</p>	 <p>225 cm<sup>2</sup> 15 cm<sup>2</sup></p>	Test according to NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.212 NAP	W.L.: <b>0</b>	Project: <b>Maitree Thermal Power Project</b>	Date: <b>4/11/2016</b>
	Location: <b>Rampal</b>	Position: <b>454755, 499146 RD</b>	Cone no.: <b>S15CFIP.S09131</b>	Project no.: <b>Maitree Thermal</b>
	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	CPT no.: <b>01</b>	9/12	






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8997236, Fax: +880-2-8997243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.212 NAP	W.L.: <b>0</b>	Date: <b>4/11/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>Maitree Thermal Power Project</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>		CPT no.: <b>01</b>	<b>10/12</b>
	Position: <b>454755, 499146 RD</b>		TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8997236, Fax: +880-2-8997243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>		
	G.L. 5.212 NAP	W.L.: <b>0</b>	Date: <b>4/11/2016</b>		Cone no.: <b>S15CFIP.S09131</b>	
	Project: <b>Maitree Thermal Power Project</b>				Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>				CPT no.: <b>01</b>	
	Position: <b>454755, 499146 RD</b>				11/12	




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>		
	G.L. 5.212 NAP	W.L.: <b>0</b>	Date: <b>4/11/2016</b>		Cone no.: <b>S15CFIP.S09131</b>	
	Project: <b>Maitree Thermal Power Project</b>				Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>				CPT no.: <b>01</b>	
	Position: <b>454755, 499146 RD</b>				12/12	






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com



	Test according NEN 5140 class 1	
	G.L. 5.78 NAP	W.L.: 0
Project: <b>Maitree Thermal Power Project</b> Location: <b>RampalT</b> Position: <b>454599, 499075 RD</b>		


Predrill :	<b>0 m Predrilled</b>
Date:	<b>4/13/2016</b>
Cone no.:	<b>S15CFIP.S09131</b>
Project no.:	<b>Maitree Thareemal</b>
CPT no.:	<b>02</b>
	<b>1/12</b>



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according to NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.78 NAP	W.L.: <b>0</b>	Date: <b>4/13/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>Maitree Thermal Power Project</b>	Location: <b>RampalT</b>	Project no.: <b>Maitree Thareemal</b>	CPT no.: <b>02</b>
	Position: <b>454599, 499075 RD</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	2/12	




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8997236, Fax: +880-2-8997243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.78 NAP	W.L.: <b>0</b>	Date: <b>4/13/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>Maitree Thermal Power Project</b>		Project no.: <b>Maitree Thareemal</b>	
	Location: <b>RampalT</b>		CPT no.: <b>02</b>	3/12
Position: <b>454599, 499075 RD</b>		TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT		






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com



Test according NEN 5140 class 1  
 G.L. 5.78 NAP      W.L.: 0  
 Project: **Maitree Thermal Power Project**  
 Location: **RampalT**  
 Position: **454599, 499075 RD**


Predrill : **0 m Predrilled**  
 Date: **4/13/2016**  
 Cone no.: **S15CFIP.S09131**  
 Project no.: **Maitree Thareemal**  
 CPT no.: **02**      **4/12**






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	 <p>Test according to NEN 5140 class 1</p>	Predrill : <b>0 m Predrilled</b> Date: <b>4/13/2016</b>
	G.L. 5.78 NAP      W.L.: <b>0</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>Maitree Thermal Power Project</b> Location: <b>Rampal IT</b>	Project no.: <b>Maitree Thareemal</b>
	Position: <b>454599, 499075 RD</b>	CPT no.: <b>02</b> <b>5/12</b>
	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8997236, Fax: +880-2-8997243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.78 NAP	W.L.: <b>0</b>	Date: <b>4/13/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>Maitree Thermal Power Project</b>	Location: <b>RampalT</b>	Project no.: <b>Maitree Thareemal</b>	CPT no.: <b>02</b>
	Position: <b>454599, 499075 RD</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	6/12	




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b> House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8957236, Fax: +880-2-8957243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	225 cm <sup>2</sup> 15 cm <sup>2</sup>	G.L. 5.78 NAP	W.L.: <b>0</b>	Date: <b>4/13/2016</b>
	Project: <b>Maitree Thermal Power Project</b>			Cone no.: <b>S15CFIP.S09131</b>
	Location: <b>RampalT</b>			Project no.: <b>Maitree Thareemal</b>
	Position: <b>454599, 499075 RD</b>			CPT no.: <b>02</b>
TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT				7/12



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according to NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.78 NAP	W.L.: <b>0</b>	Date: <b>4/13/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>Maitree Thermal Power Project</b>		Project no.: <b>Maitree Thareemal</b>	
	Location: <b>RampalT</b>		CPT no.: <b>02</b>	<b>8/12</b>
	Position: <b>454599, 499075 RD</b>			




**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com






Test according NEN 5140 class 1  
 G.L. 5.78 NAP      W.L.: 0



Predrill :	<b>0 m Predrilled</b>
Date:	<b>4/13/2016</b>
Cone no.:	<b>S15CFIP.S09131</b>
Project no.:	<b>Maitree Thareemal</b>
CPT no.:	<b>02</b>
	<b>9/12</b>


Project: **Maitree Thermal Power Project**  
 Location: **RampalIT**  
 Position: **454599, 499075 RD**






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.78 NAP	W.L.: <b>0</b>	Date: <b>4/13/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>Maitree Thermal Power Project</b>		Project no.: <b>Maitree Thareemal</b>	
	Location: <b>RampalIT</b>		CPT no.: <b>02</b>	
	Position: <b>454599, 499075 RD</b>		10/12	






 <b>DEVELOPMENT CONSTRUCTIONS LTD.</b> House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8997236, Fax: +880-2-8997243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com		Test according to NEN 5140 class 1		Pre-drill : <b>0 m Pre-drilled</b>
	G.L. 5.78 NAP	W.L.: <b>0</b>	Date: <b>4/13/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>Maitree Thermal Power Project</b>		Project no.: <b>Maitree Thareemal</b>	
	Location: <b>RampalIT</b>		CPT no.: <b>02</b>	11/12
	Position: <b>454599, 499075 RD</b>		TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8997236, Fax: +880-2-8997243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.78 NAP	W.L.: <b>0</b>	Date: <b>4/13/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>Maitree Thermal Power Project</b>		Project no.: <b>Maitree Thareemal</b>	
	Location: <b>RampalIT</b>		CPT no.: <b>02</b>	<b>12/12</b>
	Position: <b>454599, 499075 RD</b>		TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	





 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	 <p>Test according NEN 5140 class 1</p>	Predrill : <b>0 m Predrilled</b> Date: <b>4/9/2016</b>
	G.L. 5.3 NAP      W.L.: <b>0</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2X660MW Maitree STPP</b>	Project no.: <b>Maitree Thermal</b>
	Location: <b>Rampal</b>	CPT no.: <b>03</b> 1/12
	Position: <b>454759, 498972 RD</b>	






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	 <p>r u2          225 cm<sup>2</sup>          15 cm<sup>2</sup></p>	Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>	
	G.L. 5.3 NAP		W.L.: <b>0</b>	Date: <b>4/9/2016</b>	
	Project: <b>2X660MW Maitree STPP</b>				Cone no.: <b>S15CFIP.S09132</b>
	Location: <b>Rampal</b>				Project no.: <b>Maitree Thermal</b>
	Position: <b>454759, 498972 RD</b>				CPT no.: <b>03</b>
TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT				2/12	



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	<p>Test according NEN 5140 class 1</p>	<p>Predrill : <b>0 m Predrilled</b></p>	
	<p>G.L. 5.3 NAP</p>	<p>W.L.: <b>0</b></p>	<p>Date: <b>4/9/2016</b></p>
	<p>Project: <b>2X660MW Maitree STPP</b></p>	<p>Cone no.: <b>S15CFIP.S09132</b></p>	
	<p>Location: <b>Rampal</b></p>	<p>Project no.: <b>Maitree Thermal</b></p>	
	<p>Position: <b>454759, 498972 RD</b></p>	<p>CPT no.: <b>03</b></p>	<p>3/12</p>




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.3 NAP	W.L.: <b>0</b>	Date: <b>4/9/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2X660MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>		CPT no.: <b>03</b>	4/12
	Position: <b>454759, 498972 RD</b>		TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com



Test according NEN 5140 class 1  
 G.L. 5.3 NAP W.L.: 0  
 Project: **2X660MW Maitree STPP**  
 Location: **Rampal**  
 Position: **454759, 498972 RD**


Predrill : **0 m Predrilled**  
 Date: **4/9/2016**  
 Cone no.: **S15CFIP.S09132**  
 Project no.: **Maitree Thermal**  
 CPT no.: **03** 5/12






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	 <p>Test according NEN 5140 class 1</p>	Predrill : <b>0 m Predrilled</b> Date: <b>4/9/2016</b>
	G.L. 5.3 NAP      W.L.: <b>0</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2X660MW Maitree STPP</b> Location: <b>Rampal</b>	Project no.: <b>Maitree Thermal</b>
	Position: <b>454759, 498972 RD</b>	CPT no.: <b>03</b> <b>6/12</b>
	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.3 NAP	W.L.: <b>0</b>	Date: <b>4/9/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2X660MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>		CPT no.: <b>03</b>	7/12
	Position: <b>454759, 498972 RD</b>		TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.3 NAP	W.L.: <b>0</b>	Date: <b>4/9/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2X660MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>		CPT no.: <b>03</b>	8/12
	Position: <b>454759, 498972 RD</b>		TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com


Test according NEN 5140 class 1  
 G.L. 5.3 NAP      W.L.: 0

Project: **2X660MW Maitree STPP**  
 Location: **Rampal**  
 Position: **454759, 498972 RD**


Predrill :	<b>0 m Predrilled</b>	
Date:	<b>4/9/2016</b>	
Cone no.:	<b>S15CFIP.S09132</b>	
Project no.:	<b>Maitree Thermal</b>	
CPT no.:	<b>03</b>	<b>9/12</b>




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8997236, Fax: +880-2-8997243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.3 NAP	W.L.: <b>0</b>	Date: <b>4/9/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2X660MW Maitree STPP</b>	Location: <b>Rampal</b>	Project no.: <b>Maitree Thermal</b>	CPT no.: <b>03</b>
	Position: <b>454759, 498972 RD</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	10/12	



<p>DEVELOPMENT CONSTRUCTIONS LTD. House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8957236, Fax: +880-2-8957243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>	
		G.L. 5.3 NAP	W.L.: 0	Date: <b>4/9/2016</b>	
	Project: <b>2X660MW Maitree STPP</b>			Cone no.: <b>S15CFIP.S09132</b>	
	Location: <b>Rampal</b>			Project no.: <b>Maitree Thermal</b>	
	Position: <b>454759, 498972 RD</b>			CPT no.: <b>03</b>	<b>11/12</b>




<p>DEVELOPMENT CONSTRUCTIONS LTD.                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>	
	G.L. 5.3 NAP	W.L.: <b>0</b>	Date: <b>4/9/2016</b>		
	Project: <b>2X660MW Maitree STPP</b>		Cone no.: <b>S15CFIP.S09132</b>		
	Location: <b>Rampal</b>		Project no.: <b>Maitree Thermal</b>		
	Position: <b>454759, 498972 RD</b>		CPT no.: <b>03</b>	<b>12/12</b>	






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com



	Test according NEN 5140 class 1	
	G.L. 5.264 NAP	W.L.: 0
Project: <b>2x660MW Maitree STPP</b>		Predrill : <b>0 m Predrilled</b> Date: <b>4/16/2016</b> Cone no.: <b>S15CFIP.S09131</b> Project no.: <b>Maitree Thermal</b> CPT no.: <b>04</b>
Location: <b>RampalIT</b>		
Position: <b>454599, 498822 GCS</b>		


TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT		1/12
--	--	------






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according to NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.264 NAP	W.L.: <b>0</b>	Date: <b>4/16/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>2x660MW Maitree STPP</b>	Location: <b>RampalIT</b>	Project no.: <b>Maitree Thermal</b>	CPT no.: <b>04</b>
	Position: <b>454599, 498822 GCS</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	2/12	






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.264 NAP	W.L.: <b>0</b>	Date: <b>4/16/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>2x660MW Maitree STPP</b>	Location: <b>RampalIT</b>	Project no.: <b>Maitree Thermal</b>	CPT no.: <b>04</b>
	Position: <b>454599, 498822 GCS</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	3/12	





 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	 <p>Test according NEN 5140 class 1</p>	Predrill : <b>0 m Predrilled</b>		
	G.L. 5.264 NAP	W.L.: <b>0</b>	Date: <b>4/16/2016</b>	
	Project: <b>2x660MW Maitree STPP</b>		Cone no.: <b>S15CFIP.S09131</b>	
	Location: <b>RampalIT</b>		Project no.: <b>Maitree Thermal</b>	
	Position: <b>454599, 498822 GCS</b>		CPT no.: <b>04</b>	<b>4/12</b>




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	225 cm <sup>2</sup> 15 cm <sup>2</sup>	G.L. 5.264 NAP	W.L.: <b>0</b>	Date: <b>4/16/2016</b>
	Project: <b>2x660MW Maitree STPP</b>	Cone no.: <b>S15CFIP.S09131</b>		
	Location: <b>RampalIT</b>	Project no.: <b>Maitree Thermal</b>		
	Position: <b>454599, 498822 GCS</b>	CPT no.: <b>04</b>	<b>5/12</b>	




 <b>DEVELOPMENT CONSTRUCTIONS LTD.</b> House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8957236, Fax: +880-2-8957243 Web: http://www.dcl.com Email: dcl@dcl.com	Test according NEN 5140 class 1 G.L. 5.264 NAP W.L.: 0	Predrill : <b>0 m Predrilled</b> Date: <b>4/16/2016</b> Cone no.: <b>S15CFIP.S09131</b> Project no.: <b>Maitree Thermal</b> CPT no.: <b>04</b>
	Project: <b>2x660MW Maitree STPP</b> Location: <b>RampalIT</b> Position: <b>454599, 498822 GCS</b>	6/12
	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	
	1.40	
	15	






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com



 225 cm <sup>2</sup> 15 cm <sup>2</sup>	Test according NEN 5140 class 1	
	G.L. 5.264 NAP	W.L.: 0
Project: <b>2x660MW Maitree STPP</b>		
Location: <b>RampalIT</b>		
Position: <b>454599, 498822 GCS</b>		


Predrill :	<b>0 m Predrilled</b>
Date:	<b>4/16/2016</b>
Cone no.:	<b>S15CFIP.S09131</b>
Project no.:	<b>Maitree Thermal</b>
CPT no.:	<b>04</b>
	<b>7/12</b>






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according to NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.264 NAP	W.L.: <b>0</b>	Date: <b>4/16/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>2x660MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>RampalIT</b>		CPT no.: <b>04</b>	<b>8/12</b>
	Position: <b>454599, 498822 GCS</b>			




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>		
	G.L. 5.264 NAP		W.L.: <b>0</b>		Date: <b>4/16/2016</b>	
	Project: <b>2x660MW Maitree STPP</b>				Cone no.: <b>S15CFIP.S09131</b>	
	Location: <b>RampalIT</b>				Project no.: <b>Maitree Thermal</b>	
	Position: <b>454599, 498822 GCS</b>				CPT no.: <b>04</b>	
9/12						






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8997236, Fax: +880-2-8997243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.264 NAP	W.L.: <b>0</b>	Date: <b>4/16/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>2x660MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>RampalIT</b>		CPT no.: <b>04</b>	
	Position: <b>454599, 498822 GCS</b>		10/12	



<p>DEVELOPMENT CONSTRUCTIONS LTD. House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8997236, Fax: +880-2-8997243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>		
	$\frac{r}{u2}$ $\frac{L}{15}$ $\frac{cm^2}{cm^2}$	G.L. 5.264 NAP	W.L.: <b>0</b>		Date: <b>4/16/2016</b>	
	Project: <b>2x660MW Maitree STPP</b>				Cone no.: <b>S15CFIP.S09131</b>	
	Location: <b>RampaIT</b>				Project no.: <b>Maitree Thermal</b>	
	Position: <b>454599, 498822 GCS</b>				CPT no.: <b>04</b>	<b>11/12</b>




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8997236, Fax: +880-2-8997243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.264 NAP	W.L.: <b>0</b>	Date: <b>4/16/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>2x660MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>RampalIT</b>		CPT no.: <b>04</b>	12/12
	Position: <b>454599, 498822 GCS</b>		TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com



	Test according NEN 5140 class 1	
	G.L. 5.3 NAP	W.L.: 0
Project:	<b>2x660 MW Maitree STPP</b>	
Location:	<b>RampalT</b>	
Position:	<b>454154, 499208 GCS</b>	


Predrill :	<b>0 m Predrilled</b>
Date:	<b>4/17/2016</b>
Cone no.:	<b>S15CFIP.S09132</b>
Project no.:	<b>Maitree Thermal</b>
CPT no.:	<b>05</b>
	<b>1/12</b>






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	 <p>Test according to NEN 5140 class 1</p>	Predrill : <b>0 m Predrilled</b>
	G.L. 5.3 NAP      W.L.: <b>0</b>	Date: <b>4/17/2016</b>
	Project: <b>2x660 MW Maitree STPP</b>	Cone no.: <b>S15CFIP.S09132</b>
	Location: <b>RampalT</b>	Project no.: <b>Maitree Thermal</b>
	Position: <b>454154, 499208 GCS</b>	CPT no.: <b>05</b> 2/12






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>		
	G.L. 5.3 NAP	W.L.: <b>0</b>	Date: <b>4/17/2016</b>		Cone no.: <b>S15CFIP.S09132</b>	
	Project: <b>2x660 MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>			
	Location: <b>RampalT</b>		CPT no.: <b>05</b>			
	Position: <b>454154, 499208 GCS</b>				3/12	






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	225 cm <sup>2</sup> 15 cm <sup>2</sup>	G.L. 5.3 NAP	W.L.: <b>0</b>	Date: <b>4/17/2016</b>
	Project: <b>2x660 MW Maitree STPP</b>			Cone no.: <b>S15CFIP.S09132</b>
	Location: <b>RampalIT</b>			Project no.: <b>Maitree Thermal</b>
	Position: <b>454154, 499208 GCS</b>			CPT no.: <b>05</b>
TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT				4/12



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.3 NAP	W.L.: <b>0</b>	Date: <b>4/17/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2x660 MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>RampalT</b>		CPT no.: <b>05</b>	<b>5/12</b>
	Position: <b>454154, 499208 GCS</b>			



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.3 NAP	W.L.: <b>0</b>	Date: <b>4/17/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2x660 MW Maitree STPP</b>	Project no.: <b>Maitree Thermal</b>		
	Location: <b>RampalIT</b>	CPT no.: <b>05</b>	6/12	
	Position: <b>454154, 499208 GCS</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT		






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com


Test according to NEN 5140 class 1  
 G.L. 5.3 NAP      W.L.: 0



Project: **2x660 MW Maitree STPP**  
 Location: **Rampal**  
 Position: **454154, 499208 GCS**

Predrill : **0 m Predrilled**  
 Date: **4/17/2016**  
 Cone no.: **S15CFIP.S09132**  
 Project no.: **Maitree Thermal**  
 CPT no.: **05**      7/12




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	 <p>Test according to NEN 5140 class 1</p>	Predrill : <b>0 m Predrilled</b>		
	G.L. 5.3 NAP	W.L.: <b>0</b>	Date: <b>4/17/2016</b>	
	Project: <b>2x660 MW Maitree STPP</b>		Cone no.: <b>S15CFIP.S09132</b>	
	Location: <b>RampalIT</b>		Project no.: <b>Maitree Thermal</b>	
	Position: <b>454154, 499208 GCS</b>		CPT no.: <b>05</b>	<b>8/12</b>




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8997236, Fax: +880-2-8997243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.3 NAP	W.L.: <b>0</b>	Date: <b>4/17/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2x660 MW Maitree STPP</b>	Location: <b>RampalIT</b>	Project no.: <b>Maitree Thermal</b>	CPT no.: <b>05</b>
	Position: <b>454154, 499208 GCS</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	9/12	






<p>DEVELOPMENT CONSTRUCTIONS LTD.                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8997236, Fax: +880-2-8997243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	<p>Test according to NEN 5140 class 1</p>	Predrill : <b>0 m Predrilled</b>	
	G.L. 5.3 NAP      W.L.: <b>0</b>	Date: <b>4/17/2016</b>	
	Project: <b>2x660 MW Maitree STPP</b>	Cone no.: <b>S15CFIP.S09132</b>	
	Location: <b>RampalIT</b>	Project no.: <b>Maitree Thermal</b>	
	Position: <b>454154, 499208 GCS</b>	CPT no.: <b>05</b>	<b>11/12</b>




<p>DEVELOPMENT CONSTRUCTIONS LTD. House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8957236, Fax: +880-2-8957243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	<p>Test according NEN 5140 class 1</p>	Predrill : <b>0 m Predrilled</b>	
	G.L. 5.3 NAP      W.L.: <b>0</b>	Date: <b>4/17/2016</b>	
	Project: <b>2x660 MW Maitree STPP</b>	Cone no.: <b>S15CFIP.S09132</b>	
	Location: <b>RampalIT</b>	Project no.: <b>Maitree Thermal</b>	
	Position: <b>454154, 499208 GCS</b>	CPT no.: <b>05</b>	<b>12/12</b>






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com


	Test according NEN 5140 class 1	
	G.L. 5.618 NAP	W.L.: 0
Project: <b>2X660MW Maitree STPP</b>		
Location: <b>Rampal</b>		
Position: <b>454154, 498948 GCS</b>		


Predrill :	<b>0 m Predrilled</b>
Date:	<b>4/19/2016</b>
Cone no.:	<b>S15CFIP.S09131</b>
Project no.:	<b>Maitree Thermal</b>
CPT no.:	<b>06</b>
	<b>1/12</b>






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according to NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.618 NAP	W.L.: <b>0</b>	Date: <b>4/19/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>2X660MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>		CPT no.: <b>06</b>	2/12
	Position: <b>454154, 498948 GCS</b>			






 <b>DEVELOPMENT CONSTRUCTIONS LTD.</b> House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8997236, Fax: +880-2-8997243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com	Test according NEN 5140 class 1 G.L. 5.618 NAP W.L.: 0	Predrill : <b>0 m Predrilled</b> Date: <b>4/19/2016</b> Cone no.: <b>S15CFIP.S09131</b> Project no.: <b>Maitree Thermal</b> CPT no.: <b>06</b>
	Project: <b>2X660MW Maitree STPP</b> Location: <b>Rampal</b> Position: <b>454154, 498948 GCS</b>	3/12
	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	
	1.40	
	225 cm <sup>2</sup> 15 cm <sup>2</sup>	



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	225 cm <sup>2</sup> 15 cm <sup>2</sup>	G.L. 5.618 NAP	W.L.: 0	Date: <b>4/19/2016</b>
	Project: <b>2X660MW Maitree STPP</b>	Cone no.: <b>S15CFIP.S09131</b>		
	Location: <b>Rampal</b>	Project no.: <b>Maitree Thermal</b>		
	Position: <b>454154, 498948 GCS</b>	CPT no.: <b>06</b>	4/12	




 <b>DEVELOPMENT CONSTRUCTIONS LTD.</b> House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8957236, Fax: +880-2-8957243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com	 Test according to NEN 5140 class 1 G.L. 5.618 NAP      W.L.: 0	Predrill : <b>0 m Predrilled</b> Date: <b>4/19/2016</b>
	Project: <b>2X660MW Maitree STPP</b> Location: <b>Rampal</b>	Cone no.: <b>S15CFIP.S09131</b>
	Position: <b>454154, 498948 GCS</b>	Project no.: <b>Maitree Thermal</b>
		CPT no.: <b>06</b>
		5/12



**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com

	Test according NEN 5140 class 1	
	G.L. 5.618 NAP	W.L.: 0
Project: <b>2X660MW Maitree STPP</b>		
Location: <b>Rampal</b>		
Position: <b>454154, 498948 GCS</b>		


Predrill :	<b>0 m Predrilled</b>
Date:	<b>4/19/2016</b>
Cone no.:	<b>S15CFIP.S09131</b>
Project no.:	<b>Maitree Thermal</b>
CPT no.:	<b>06</b>
	<b>6/12</b>






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com



	Test according NEN 5140 class 1	
	G.L. 5.618 NAP	W.L.: 0
Project: <b>2X660MW Maitree STPP</b>		Predrill : <b>0 m Predrilled</b> Date: <b>4/19/2016</b> Cone no.: <b>S15CFIP.S09131</b> Project no.: <b>Maitree Thermal</b> CPT no.: <b>06</b>
Location: <b>Rampal</b>		
Position: <b>454154, 498948 GCS</b>		

Predrill :	<b>0 m Predrilled</b>
Date:	<b>4/19/2016</b>
Cone no.:	<b>S15CFIP.S09131</b>
Project no.:	<b>Maitree Thermal</b>
CPT no.:	<b>06</b>
	<b>7/12</b>




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b> House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8957236, Fax: +880-2-8957243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.618 NAP	W.L.: <b>0</b>	Date: <b>4/19/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>2X660MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>		CPT no.: <b>06</b>	<b>8/12</b>
	Position: <b>454154, 498948 GCS</b>			




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.618 NAP	W.L.: <b>0</b>	Date: <b>4/19/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>2X660MW Maitree STPP</b>	Location: <b>Rampal</b>	Project no.: <b>Maitree Thermal</b>	CPT no.: <b>06</b>
	Position: <b>454154, 498948 GCS</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	9/12	









<p>DEVELOPMENT CONSTRUCTIONS LTD.          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according to NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	225 cm <sup>2</sup> 15 cm <sup>2</sup>	G.L. 5.618 NAP	W.L.: 0	Date: <b>4/19/2016</b>
	Project: <b>2X660MW Maitree STPP</b>			Cone no.: <b>S15CFIP.S09131</b>
	Location: <b>Rampal</b>			Project no.: <b>Maitree Thermal</b>
	Position: <b>454154, 498948 GCS</b>			CPT no.: <b>06</b>



<p>DEVELOPMENT CONSTRUCTIONS LTD.                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8997236, Fax: +880-2-8997243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.618 NAP	W.L.: <b>0</b>	Date: <b>4/19/2016</b>	Cone no.: <b>S15CFIP.S09131</b>
	Project: <b>2X660MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>		CPT no.: <b>06</b>	
	Position: <b>454154, 498948 GCS</b>		12/12	




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	 <p>r u2                  225 cm<sup>2</sup>                  15 cm<sup>2</sup></p>	Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.917 NAP		W.L.: <b>0</b>	Date: <b>4/20/2016</b>
	Project: <b>2x660MW Maitree STPP</b>			Cone no.: <b>S15CFIP.S09132</b>
	Location: <b>Rampal</b>			Project no.: <b>Maitree Thermal</b>
	Position: <b>454223, 498651 GCS</b>			CPT no.: <b>07</b>






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com



Test according NEN 5140 class 1  
 G.L. 5.917 NAP      W.L.: 0  
 Project: **2x660MW Maitree STPP**  
 Location: **Rampal**  
 Position: **454223, 498651 GCS**


Predrill : **0 m Predrilled**  
 Date: **4/20/2016**  
 Cone no.: **S15CFIP.S09132**  
 Project no.: **Maitree Thermal**  
 CPT no.: **07**      2/12






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	 <p>Test according NEN 5140 class 1</p>	Predrill : <b>0 m Predrilled</b>		
	G.L. 5.917 NAP	W.L.: <b>0</b>	Date: <b>4/20/2016</b>	
	Project: <b>2x660MW Maitree STPP</b>		Cone no.: <b>S15CFIP.S09132</b>	
	Location: <b>Rampal</b>		Project no.: <b>Maitree Thermal</b>	
	Position: <b>454223, 498651 GCS</b>		CPT no.: <b>07</b>	3/12



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.917 NAP	W.L.: <b>0</b>	Date: <b>4/20/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2x660MW Maitree STPP</b>	Location: <b>Rampal</b>	Project no.: <b>Maitree Thermal</b>	CPT no.: <b>07</b>
	Position: <b>454223, 498651 GCS</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	4/12	




 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.917 NAP	W.L.: <b>0</b>	Date: <b>4/20/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2x660MW Maitree STPP</b>	Location: <b>Rampal</b>	Project no.: <b>Maitree Thermal</b>	CPT no.: <b>07</b>
	Position: <b>454223, 498651 GCS</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	5/12	






**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com


	Test according NEN 5140 class 1	
	G.L. 5.917 NAP	W.L.: 0
Project: <b>2x660MW Maitree STPP</b>		
Location: <b>Rampal</b>		
Position: <b>454223, 498651 GCS</b>		


Predrill :	<b>0 m Predrilled</b>
Date:	<b>4/20/2016</b>
Cone no.:	<b>S15CFIP.S09132</b>
Project no.:	<b>Maitree Thermal</b>
CPT no.:	<b>07</b>
	<b>6/12</b>



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.917 NAP	W.L.: <b>0</b>	Date: <b>4/20/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2x660MW Maitree STPP</b>	Location: <b>Rampal</b>	Project no.: <b>Maitree Thermal</b>	CPT no.: <b>07</b>
	Position: <b>454223, 498651 GCS</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	7/12	



 <b>DEVELOPMENT CONSTRUCTIONS LTD.</b> House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8957236, Fax: +880-2-8957243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com	Test according NEN 5140 class 1 G.L. 5.917 NAP W.L.: 0	Predrill : <b>0 m Predrilled</b> Date: <b>4/20/2016</b> Cone no.: <b>S15CFIP.S09132</b> Project no.: <b>Maitree Thermal</b> CPT no.: <b>07</b>
	Project: <b>2x660MW Maitree STPP</b> Location: <b>Rampal</b> Position: <b>454223, 498651 GCS</b>	8/12
	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	
	f u2 225 cm <sup>2</sup> 15 cm <sup>2</sup>	
	1.40	




**DEVELOPMENT CONSTRUCTIONS LTD.**  
 House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.  
 Phone: +880-2-8957236, Fax: +880-2-8957243  
 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com

Test according NEN 5140 class 1


G.L. 5.917 NAP      W.L.: 0

Project: **2x660MW Maitree STPP**  
 Location: **Rampal**  
 Position: **454223, 498651 GCS**


Predrill : **0 m Predrilled**  
 Date: **4/20/2016**  
 Cone no.: **S15CFIP.S09132**  
 Project no.: **Maitree Thermal**  
 CPT no.: **07**      **9/12**




<p>DEVELOPMENT CONSTRUCTIONS LTD.          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.917 NAP	W.L.: <b>0</b>	Date: <b>4/20/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2x660MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>		CPT no.: <b>07</b>	<b>10/12</b>
	Position: <b>454223, 498651 GCS</b>		TENDER NO - PSER: SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	






<p>DEVELOPMENT CONSTRUCTIONS LTD.                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8997236, Fax: +880-2-8997243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according to NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>		
	G.L. 5.917 NAP	W.L.: <b>0</b>	Date: <b>4/20/2016</b>		Cone no.: <b>S15CFIP.S09132</b>	
	Project: <b>2x660MW Maitree STPP</b>				Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>				CPT no.: <b>07</b>	
	Position: <b>454223, 498651 GCS</b>				11/12	






<p>DEVELOPMENT CONSTRUCTIONS LTD.                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 5.917 NAP	W.L.: <b>0</b>	Date: <b>4/20/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2x660MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>		CPT no.: <b>07</b>	<b>12/12</b>
	Position: <b>454223, 498651 GCS</b>		TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	 <p>r u2                  225 cm<sup>2</sup>                  15 cm<sup>2</sup></p>	Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>	
	G.L. 2.468 NAP		W.L.: <b>0</b>	Date: <b>4/23/2016</b>	
	Project: <b>2x660MW Maitree STPP</b>				Cone no.: <b>S15CFIP.S09132</b>
	Location: <b>Rampal</b>				Project no.: <b>Maitree Thermal</b>
	Position: <b>454079, 497722 GCS</b>				CPT no.: <b>09</b>






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	 <p>Test according NEN 5140 class 1</p>	Predrill : <b>0 m Predrilled</b>
	G.L. 2.468 NAP      W.L.: <b>0</b>	Date: <b>4/23/2016</b>
	Project: <b>2x660MW Maitree STPP</b>	Cone no.: <b>S15CFIP.S09132</b>
	Location: <b>Rampal</b>	Project no.: <b>Maitree Thermal</b>
	Position: <b>454079, 497722 GCS</b>	CPT no.: <b>09</b> <b>2/8</b>






 <b>DEVELOPMENT CONSTRUCTIONS LTD.</b> House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8957236, Fax: +880-2-8957243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 2.468 NAP	W.L.: <b>0</b>	Project: <b>2x660MW Maitree STPP</b>	Date: <b>4/23/2016</b>
	Location: <b>Rampal</b>	Position: <b>454079, 497722 GCS</b>	Cone no.: <b>S15CFIP.S09132</b>	Project no.: <b>Maitree Thermal</b>
	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	CPT no.: <b>09</b>	3/8	






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 2.468 NAP	W.L.: <b>0</b>	Date: <b>4/23/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2x660MW Maitree STPP</b>		Project no.: <b>Maitree Thermal</b>	
	Location: <b>Rampal</b>		CPT no.: <b>09</b>	4/8
	Position: <b>454079, 497722 GCS</b>			






 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>                  House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.                  Phone: +880-2-8957236, Fax: +880-2-8957243                  Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 2.468 NAP	W.L.: <b>0</b>	Date: <b>4/23/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2x660MW Maitree STPP</b>	Location: <b>Rampal</b>	Project no.: <b>Maitree Thermal</b>	CPT no.: <b>09</b>
	Position: <b>454079, 497722 GCS</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	5/8	



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8957236, Fax: +880-2-8957243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according to NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	G.L. 2.468 NAP	W.L.: <b>0</b>	Date: <b>4/23/2016</b>	Cone no.: <b>S15CFIP.S09132</b>
	Project: <b>2x660MW Maitree STPP</b>	Location: <b>Rampal</b>	Project no.: <b>Maitree Thermal</b>	CPT no.: <b>09</b>
	Position: <b>454079, 497722 GCS</b>	TENDER NO - PSER:SCT:KLN-E1754:16 (TCN-02) - DRAFT SI REPORT	6/8	



 <p><b>DEVELOPMENT CONSTRUCTIONS LTD.</b>          House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh.          Phone: +880-2-8997236, Fax: +880-2-8997243          Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>		Test according NEN 5140 class 1		Predrill : <b>0 m Predrilled</b>
	225 cm <sup>2</sup> 15 cm <sup>2</sup>	G.L. 2.468 NAP	W.L.: <b>0</b>	Date: <b>4/23/2016</b>
	Project: <b>2x660MW Maitree STPP</b>	Cone no.: <b>S15CFIP.S09132</b>		
	Location: <b>Rampal</b>	Project no.: <b>Maitree Thermal</b>		
	Position: <b>454079, 497722 GCS</b>	CPT no.: <b>09</b>	<b>7/8</b>	



<p>DEVELOPMENT CONSTRUCTIONS LTD. House 11, Road 18/A, Sector 4, Uttara, Dhaka 1230, Bangladesh. Phone: +880-2-8997236, Fax: +880-2-8997243 Web: http://www.dcl-fcl.com Email: dcl@dcl-fcl.com</p>	<p>Test according to NEN 5140 class 1</p>	Predrill : <b>0 m Predrilled</b>	
	G.L. 2.468 NAP      W.L.: <b>0</b>	Date: <b>4/23/2016</b>	
	Project: <b>2x660MW Maitree STPP</b>	Cone no.: <b>S15CFIP.S09132</b>	
	Location: <b>Rampal</b>	Project no.: <b>Maitree Thermal</b>	
	Position: <b>454079, 497722 GCS</b>	CPT no.: <b>09</b>	<b>8/8</b>

# **Appendix-B4**

## **ELECTRICAL RESISTIVITY TEST**

**DEVELOPMENT CONSTRUCTIONS LTD.**  
SOIL RESISTIVITY TEST

Project: 2x660 MW Maitree STPP	Method: Four Point (Wenner)
Client: BHEL	Equipment: Chauvin-Arnoux (CA6460)
Location: Rampal, Bagerhat.	Test Date: 19-Apr-16 to 24-Apr-16

ERT-1	Position	E=454183, N=499389		ERT-1	Position	E=454183, N=499389	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	120.70	379		0.5	121.10	380
	1.0	88.60	557		1.0	89.20	560
	2.0	60.00	754		2.0	61.30	770
	3.0	28.80	543		3.0	30.10	567
	4.0	14.50	364		4.0	15.30	385
	6.0	4.70	177		6.0	5.10	192
	8.0	0.20	10		8.0	0.18	9
	10.0	0.10	6		10.0	0.09	6
ERT-2	Position	E=454660, N=499304		ERT-2	Position	E=454660, N=499304	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	122.40	385		0.5	122.30	384
	1.0	90.20	567		1.0	90.10	566
	2.0	67.50	848		2.0	67.60	849
	3.0	35.40	667		3.0	35.10	662
	4.0	17.20	432		4.0	17.30	435
	6.0	8.20	309		6.0	8.10	305
	8.0	1.30	65		8.0	1.30	65
	10.0	0.33	21		10.0	0.34	21
ERT-3	Position	E=454759, N=499304		ERT-3	Position	E=454759, N=499304	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	121.30	381		0.5	121.10	380
	1.0	89.40	562		1.0	89.30	561
	2.0	66.50	836		2.0	66.70	838
	3.0	34.40	648		3.0	34.30	647
	4.0	16.60	417		4.0	16.70	420
	6.0	7.70	290		6.0	7.60	287
	8.0	1.10	55		8.0	1.00	50
	10.0	0.33	21		10.0	0.32	20
Tested By:	Akbar Ali			Prepared By:	Md.Rafiqul Islam		

**DEVELOPMENT CONSTRUCTIONS LTD.**  
SOIL RESISTIVITY TEST

Project: 2x660 MW Maitree STPP	Method: Four Point (Wenner)
Client: BHEL	Equipment: Chauvin-Arnoux (CA6460)
Location: Rampal, Bagerhat.	Test Date: 18-Apr-16

ERT-4	Position	E=454946,N=499286		ERT-4	Position	E=454946,N=499286	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	117.50	369		0.5	117.60	369
	1.0	85.30	536		1.0	85.10	535
	2.0	61.70	775		2.0	62.70	788
	3.0	30.90	582		3.0	31.60	596
	4.0	13.40	337		4.0	13.70	344
	6.0	5.30	200		6.0	5.10	192
	8.0	0.80	40		8.0	0.79	40
10.0	0.25	16	10.0	0.24	15		
ERT-5	Position	E=454799, N=499254		ERT-5	Position	E=454799, N=499254	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	119.30	375		0.5	119.50	375
	1.0	88.20	554		1.0	88.10	554
	2.0	64.70	813		2.0	65.30	821
	3.0	32.80	618		3.0	33.20	626
	4.0	14.10	354		4.0	14.00	352
	6.0	6.30	238		6.0	6.10	230
	8.0	0.83	42		8.0	0.85	43
10.0	0.27	17	10.0	0.28	18		
ERT-6	Position	E=454405,N=499247		ERT-6	Position	E=454405,N=499247	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	118.70	373		0.5	118.50	372
	1.0	86.40	543		1.0	86.30	542
	2.0	64.70	813		2.0	65.10	818
	3.0	32.80	618		3.0	33.60	633
	4.0	13.00	327		4.0	12.70	319
	6.0	5.60	211		6.0	6.40	241
	8.0	0.81	41		8.0	0.83	42
10.0	0.27	17	10.0	0.28	18		
Tested By:	Akbar Ali		Prepared By:	Md.Rafiqul Islam			

**DEVELOPMENT CONSTRUCTIONS LTD.**  
SOIL RESISTIVITY TEST

Project: 2x660 MW Maitree STPP	Method: Four Point (Wenner)
Client: BHEL	Equipment: Chauvin-Arnoux (CA6460)
Location: Rampal, Bagerhat.	Test Date: 16-Apr-16 to 17-Apr-16

ERT-7	Position	E=454739,N=499204		ERT-7	Position	E=454739,N=499204	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	113.40	356		0.5	113.20	356
	1.0	86.30	542		1.0	86.50	543
	2.0	66.50	836		2.0	66.30	833
	3.0	37.40	705		3.0	37.70	711
	4.0	14.10	354		4.0	14.20	357
	6.0	5.30	200		6.0	5.00	188
	8.0	0.83	42		8.0	0.82	41
10.0	0.28	18	10.0	0.27	17		
ERT-8	Position	E=454639, N=499204		ERT-8	Position	E=454639, N=499204	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	110.10	346		0.5	109.40	344
	1.0	80.00	503		1.0	79.70	501
	2.0	69.60	875		2.0	19.40	244
	3.0	38.20	720		3.0	8.10	153
	4.0	15.20	382		4.0	5.30	133
	6.0	5.10	192		6.0	2.00	75
	8.0	0.85	43		8.0	0.84	42
10.0	0.26	16	10.0	0.27	17		
ERT-9	Position	E=454757,N=499168		ERT-9	Position	E=454757,N=499168	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	117.20	368		0.5	116.40	366
	1.0	87.80	552		1.0	87.60	550
	2.0	68.00	855		2.0	67.70	851
	3.0	37.10	699		3.0	36.42	687
	4.0	14.92	375		4.0	14.80	372
	6.0	30.82	1162		6.0	4.83	182
	8.0	0.76	38		8.0	0.77	39
10.0	0.26	16	10.0	0.25	16		
Tested By:	Akbar Ali		Prepared By:	Md.Rafiqul Islam			

**DEVELOPMENT CONSTRUCTIONS LTD.**  
SOIL RESISTIVITY TEST

Project: 2x660 MW Maitree STPP	Method: Four Point (Wenner)
Client: BHEL	Equipment: Chauvin-Arnoux (CA6460)
Location: Rampal, Bagerhat.	Test Date: 15-Apr-16 to 21-Apr-16

ERT-10	Position	E=454171,N=499184		ERT-10	Position	E=454171,N=499184	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	116.80	367		0.5	117.30	369
	1.0	88.50	556		1.0	89.10	560
	2.0	68.10	856		2.0	68.30	858
	3.0	37.40	705		3.0	37.60	709
	4.0	14.20	357		4.0	14.10	354
	6.0	4.73	178		6.0	4.77	180
	8.0	0.80	40		8.0	0.81	41
10.0	0.27	17	10.0	0.28	18		
ERT-11	Position	E=455250, N=498563		ERT-11	Position	E=455250, N=498563	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	113.30	356		0.5	113.10	355
	1.0	91.20	573		1.0	91.30	574
	2.0	70.70	888		2.0	70.80	890
	3.0	36.80	694		3.0	37.10	699
	4.0	19.10	480		4.0	19.10	480
	6.0	10.20	385		6.0	10.30	388
	8.0	2.30	116		8.0	2.10	106
10.0	0.28	18	10.0	0.39	25		
ERT-12	Position	E=454521,N=499120		ERT-12	Position	E=454521,N=499120	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	116.00	364		0.5	115.00	361
	1.0	85.70	538		1.0	85.00	534
	2.0	63.30	795		2.0	63.00	792
	3.0	33.20	626		3.0	32.70	616
	4.0	10.00	251		4.0	9.10	229
	6.0	2.50	94		6.0	2.40	90
	8.0	0.76	38		8.0	0.75	38
10.0	0.26	16	10.0	0.27	17		
Tested By:	Akbar Ali		Prepared By:	Md.Rafiqul Islam			

**DEVELOPMENT CONSTRUCTIONS LTD.**  
SOIL RESISTIVITY TEST

Project: 2x660 MW Maitree STPP	Method: Four Point (Wenner)
Client: BHEL	Equipment: Chauvin-Arnoux (CA6460)
Location: Rampal, Bagerhat.	Test Date: 10-Apr-16

ERT-13	Position	E=454631,N=499126		ERT-13	Position	E=454631,N=499126	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	97.50	306		0.5	98.00	308
	1.0	69.50	437		1.0	70.00	440
	2.0	16.10	202		2.0	15.70	197
	3.0	8.00	151		3.0	7.50	141
	4.0	6.10	153		4.0	5.20	131
	6.0	1.90	72		6.0	2.00	75
	8.0	0.97	49		8.0	1.00	50
10.0	0.65	41	10.0	0.55	35		
ERT-14	Position	E=454686, N=499135		ERT-14	Position	E=454686, N=499135	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	91.50	287		0.5	92.00	289
	1.0	60.50	380		1.0	61.00	383
	2.0	15.10	190		2.0	14.50	182
	3.0	7.10	134		3.0	6.40	121
	4.0	4.60	116		4.0	4.10	103
	6.0	1.78	67		6.0	1.70	64
	8.0	0.85	43		8.0	0.80	40
10.0	0.47	30	10.0	0.45	28		
ERT-15	Position	E=454732,N=499113		ERT-15	Position	E=454732,N=499113	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	95.00	298		0.5	93.00	292
	1.0	62.00	390		1.0	60.00	377
	2.0	14.41	181		2.0	13.50	170
	3.0	6.00	113		3.0	5.71	108
	4.0	3.70	93		4.0	3.31	83
	6.0	1.50	57		6.0	1.46	55
	8.0	0.75	38		8.0	0.72	36
10.0	0.41	26	10.0	0.42	26		
Tested By:	Akbar Ali		Prepared By:	Md.Rafiqul Islam			

**DEVELOPMENT CONSTRUCTIONS LTD.**  
SOIL RESISTIVITY TEST

Project: 2x660 MW Maitree STPP	Method: Four Point (Wenner)
Client: BHEL	Equipment: Chauvin-Arnoux (CA6460)
Location: Rampal, Bagerhat.	Test Date: 12-Apr-16

ERT-16	Position	E=454773,N=498998		ERT-16	Position	E=454773,N=498998	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	115.70	363		0.5	110.50	347
	1.0	82.00	515		1.0	63.00	396
	2.0	62.00	779		2.0	57.00	716
	3.0	32.00	603		3.0	29.60	558
	4.0	9.00	226		4.0	8.24	207
	6.0	2.70	102		6.0	2.35	89
	8.0	0.75	38		8.0	0.74	37
10.0	0.28	18	10.0	0.26	16		
ERT-17	Position	E=454651, N=498977		ERT-17	Position	E=454651, N=498977	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	111.50	350		0.5	112.00	352
	1.0	82.50	518		1.0	83.00	522
	2.0	61.00	767		2.0	63.00	792
	3.0	32.70	616		3.0	33.50	631
	4.0	9.50	239		4.0	10.00	251
	6.0	2.65	100		6.0	2.75	104
	8.0	0.72	36		8.0	0.77	39
10.0	0.26	16	10.0	0.27	17		
ERT-18	Position	E=454541,N=498949		ERT-18	Position	E=454541,N=498949	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	114.60	360		0.5	115.00	361
	1.0	84.60	532		1.0	85.20	535
	2.0	64.30	808		2.0	63.10	793
	3.0	33.70	635		3.0	33.80	637
	4.0	9.70	244		4.0	10.20	256
	6.0	2.80	106		6.0	2.50	94
	8.0	0.77	39		8.0	0.73	37
10.0	0.29	18	10.0	0.27	17		
Tested By:	Akbar Ali		Prepared By:	Md.Rafiqul Islam			

**DEVELOPMENT CONSTRUCTIONS LTD.**  
SOIL RESISTIVITY TEST

Project: 2x660 MW Maitree STPP	Method: Four Point (Wenner)
Client: BHEL	Equipment: Chauvin-Arnoux (CA6460)
Location: Rampal, Bagerhat.	Test Date: 15-Apr-16 to 17-Apr-16

ERT-19	Position	E=454424,N=498915		ERT-19	Position	E=454424,N=498915	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	116.70	367		0.5	117.00	368
	1.0	87.50	550		1.0	87.00	547
	2.0	65.60	824		2.0	65.00	817
	3.0	33.70	635		3.0	33.50	631
	4.0	10.30	259		4.0	10.20	256
	6.0	3.60	136		6.0	3.50	132
	8.0	0.80	40		8.0	0.77	39
10.0	0.27	17	10.0	0.28	18		
ERT-20	Position	E=454173, N=498918		ERT-20	Position	E=454173, N=498918	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	118.30	372		0.5	118.60	373
	1.0	88.70	557		1.0	88.50	556
	2.0	65.80	827		2.0	66.70	838
	3.0	34.50	650		3.0	34.60	652
	4.0	10.60	266		4.0	10.70	269
	6.0	4.30	162		6.0	4.30	162
	8.0	0.83	42		8.0	0.82	41
10.0	0.27	17	10.0	0.26	16		
ERT-21	Position	E=454635,N=498859		ERT-21	Position	E=454635,N=498859	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	111.80	351		0.5	112.00	352
	1.0	79.80	501		1.0	79.00	496
	2.0	62.10	780		2.0	61.70	775
	3.0	32.00	603		3.0	31.50	594
	4.0	9.50	239		4.0	9.20	231
	6.0	2.75	104		6.0	2.80	106
	8.0	0.76	38		8.0	0.75	38
10.0	0.26	16	10.0	0.27	17		
Tested By:	Akbar Ali		Prepared By:	Md.Rafiqul Islam			

**DEVELOPMENT CONSTRUCTIONS LTD.**  
SOIL RESISTIVITY TEST

Project: 2x660 MW Maitree STPP	Method: Four Point (Wenner)
Client: BHEL	Equipment: Chauvin-Arnoux (CA6460)
Location: Rampal, Bagerhat.	Test Date: 15-Apr-16 to 21-Apr-16

ERT-22	Position	E=454780,N=498858		ERT-22	Position	E=454780,N=498858	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	119.50	375		0.5	119.20	374
	1.0	88.20	554		1.0	88.10	554
	2.0	68.50	861		2.0	67.20	844
	3.0	37.60	709		3.0	37.00	697
	4.0	11.00	276		4.0	10.70	269
	6.0	3.89	147		6.0	3.70	139
	8.0	0.83	42		8.0	0.81	41
10.0	0.33	21	10.0	0.31	19		
ERT-23	Position	E=454325, N=498807		ERT-23	Position	E=454325, N=498807	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	119.30	375		0.5	119.10	374
	1.0	89.70	564		1.0	89.60	563
	2.0	67.10	843		2.0	67.20	844
	3.0	34.20	645		3.0	34.30	647
	4.0	11.70	294		4.0	11.40	287
	6.0	4.30	162		6.0	4.00	151
	8.0	0.81	41		8.0	0.83	42
10.0	0.26	16	10.0	0.27	17		
ERT-24	Position	E=454111,N=498682		ERT-24	Position	E=454111,N=498682	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	118.90	374		0.5	119.70	376
	1.0	89.50	562		1.0	89.30	561
	2.0	68.50	861		2.0	67.10	843
	3.0	36.60	690		3.0	36.30	684
	4.0	15.20	382		4.0	15.10	380
	6.0	7.00	264		6.0	6.20	234
	8.0	0.98	49		8.0	1.00	50
10.0	0.26	16	10.0	0.27	17		
Tested By:	Akbar Ali		Prepared By:	Md.Rafiqul Islam			

**DEVELOPMENT CONSTRUCTIONS LTD.**  
SOIL RESISTIVITY TEST

Project: 2x660 MW Maitree STPP	Method: Four Point (Wenner)
Client: BHEL	Equipment: Chauvin-Arnoux (CA6460)
Location: Rampal, Bagerhat.	Test Date: 21-Apr-16

ERT-25	Position	E=454221,N=498668		ERT-25	Position	E=454221,N=498668	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	123.30	387		0.5	123.10	387
	1.0	92.10	579		1.0	92.40	581
	2.0	69.70	876		2.0	70.10	881
	3.0	38.30	722		3.0	38.20	720
	4.0	16.40	412		4.0	16.10	405
	6.0	7.20	271		6.0	7.00	264
	8.0	1.30	65		8.0	1.20	60
10.0	0.36	23	10.0	0.35	22		
ERT-26	Position	E=454422, N=498594		ERT-26	Position	E=454422, N=498594	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	122.40	385		0.5	122.10	384
	1.0	91.60	576		1.0	91.30	574
	2.0	70.30	883		2.0	70.10	881
	3.0	39.40	743		3.0	39.30	741
	4.0	17.30	435		4.0	17.20	432
	6.0	7.80	294		6.0	8.10	305
	8.0	1.70	85		8.0	2.00	101
10.0	0.28	18	10.0	0.29	18		
ERT-27	Position	E=454462,N=498690		ERT-27	Position	E=454462,N=498690	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	124.20	390		0.5	124.00	390
	1.0	93.30	586		1.0	93.10	585
	2.0	70.65	888		2.0	70.70	888
	3.0	39.30	741		3.0	39.10	737
	4.0	18.10	455		4.0	18.20	457
	6.0	9.00	339		6.0	9.10	343
	8.0	2.10	106		8.0	2.05	103
10.0	0.37	23	10.0	0.38	24		
Tested By:	Akbar Ali		Prepared By:	Md.Rafiqul Islam			

**DEVELOPMENT CONSTRUCTIONS LTD.**  
SOIL RESISTIVITY TEST

Project: 2x660 MW Maitree STPP	Method: Four Point (Wenner)
Client: BHEL	Equipment: Chauvin-Arnoux (CA6460)
Location: Rampal, Bagerhat.	Test Date: 21-Apr-16 to 24-Apr-16

ERT-28	Position	E=454547,N=498700		ERT-28	Position	E=454547,N=498700	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	122.70	385		0.5	122.80	386
	1.0	88.80	558		1.0	89.60	563
	2.0	66.40	834		2.0	66.10	831
	3.0	35.60	671		3.0	35.70	673
	4.0	15.10	380		4.0	15.20	382
	6.0	7.30	275		6.0	7.40	279
	8.0	1.50	75		8.0	1.60	80
10.0	0.29	18	10.0	0.29	18		
ERT-29	Position	E=454728, N=498692		ERT-29	Position	E=454728, N=498692	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	116.70	367		0.5	117.10	368
	1.0	84.10	528		1.0	85.10	535
	2.0	60.70	763		2.0	61.50	773
	3.0	31.00	584		3.0	33.10	624
	4.0	18.50	465		4.0	19.10	480
	6.0	9.00	339		6.0	9.50	358
	8.0	0.20	10		8.0	0.21	11
10.0	0.11	7	10.0	0.10	6		
ERT-30	Position	E=454657,N=498577		ERT-30	Position	E=454657,N=498577	
	Direction	E-W			Direction	N-S	
	Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )		Electrode Spacing (d) (m)	$R_{S-ES}$ ( $\Omega$ )	$\rho_w$ ( $\Omega.m$ )
	0.5	119.70	376		0.5	124.40	391
	1.0	94.40	593		1.0	95.70	601
	2.0	67.60	849		2.0	68.20	857
	3.0	19.50	368		3.0	19.70	371
	4.0	9.10	229		4.0	10.23	257
	6.0	0.41	15		6.0	0.37	14
	8.0	0.13	7		8.0	0.15	8
10.0	0.09	6	10.0	0.08	5		
Tested By:	Akbar Ali		Prepared By:	Md.Rafiqul Islam			



**FORMAT FOR NO DEVIATION CERTIFICATE**  
**(To be submitted in the bidder's letter head)**

BHARAT HEAVY ELECTRICALS LIMITED,  
Power Sector - Eastern Region,  
Plot no 9/1, DJ Block, Sector – II, Salt Lake City,  
Kolkata – 700 091

Sub	No Deviation Certificate.	
Job	Design/ Engineering and construction of 33 KV sub-station along with supply, erection, testing and commissioning of equipment and system for construction power distribution system (11 KV overhead lines, package sub-station etc.), high mast lighting / temporary illumination system including obtaining clearances from various authorities, operation & maintenance (O&M), etc of construction power network for 2x660 MW Maitree Super Thermal power project at Moidara village, Rampalupazila, Bagerhat district, Bangladesh	
Ref	1.0	Tender No. PSER:SCT:KLN-E1754:16
	2.0	BHEL's NIT, vide reference no PSER:SCT:KLN-E1754:5101, Dated 01-07-2016.
	3.0	BHEL's TCN-01, vide reference no PSER:SCT:KLN-E1754:TCN-01, dated 12-07-2016.
	4.0	BHEL's TCN-02, vide reference no PSER:SCT:KLN-E1754:TCN-02, dated 21-07-2016.
	5.0	All other pertinent issues till date.

Dear Sirs,

With reference to above, this is to confirm that as per tender conditions, we have visited site before submission of our offer and noted the job content & site conditions etc. We also confirm that we have not changed/ modified the tender documents as appeared in the website/ issued by you and in case of such observance at any stage, it shall be treated as null and void.

We hereby confirm that we have not taken any deviation from tender clauses together with other references as enumerated in the above referred NIT. We hereby confirm our unqualified acceptance to all terms & conditions, unqualified compliance to technical specification, integrity pact (if applicable) and acceptance to reverse auctioning process.

In the event of observance of any deviation in any part of our offer at a later date whether implicit or explicit, the deviations shall stand null & void.

We confirm to have submitted offer in accordance with tender instructions and as per aforesaid references.

Thanking you,

Yours faithfully,

(Signature, date & seal of authorized  
representative of the bidder)

पावर सेक्टर पूर्वी क्षेत्र (मुख्यालय)

POWER SECTOR EASTERN REGION DJ-9/1, SECTOR-II, SALT LAKE CITY, KOLKATA - 700 091

फैक्स/Fax : (033) 23211960

फोन/Phone : बोर्ड/EPABX : 23211691, 23211798, 23211796