



भारत हेवी इलेक्ट्रिकल्स लिमिटेड

(भारत सरकार का उपक्रम)

BHARAT HEAVY ELECTRICALS LIMITED

(A Govt. of India Undertaking)

TCN - 05

Ref: PSER:SCT:BRM-C1273:TCN-05

Date: 28-11-2011

Sub	Tender change notice (TCN) 05	
Job	(i)PKG-A: Civil,structural and architectural works including piling and ground improvement etc of 1x250 MW unit # 8 for 2x 250MW units at Barauni TPP,Begusarai, Bihar. (ii)PKG-B: Civil,structural and architectural works including piling and ground improvement etc of 1x250 MW unit # 9 for 2x 250MW units at Barauni TPP,Begusarai, Bihar.	
Ref	1.0	Tender no PSER:SCT:BRM-C1273:11
	2.0	BHEL's NIT, vide reference no PSER:SCT:BRM-C1273:2584, dated 05-11-2011.
	3.0	BHEL's TCN-01 issued vide reference no PSER:SCT:BRM-C1273:TCN-01, dated 15-11-2011.
	4.0	BHEL's TCN-02 issued vide reference no PSER:SCT:BRM-C1273:TCN-02, dated 22-11-2011.
	5.0	BHEL's TCN-03 issued vide reference no PSER:SCT:BRM-C1273:TCN-03, dated 23-11-2011.
	6.0	BHEL's TCN-04 issued vide reference no PSER:SCT:BRM-C1273:TCN-04, dated 25-11-2011.
	7.0	All other pertinent issues till date.

With reference to above, following points/ documents, relevant to tender, may please be noted and complied with while submitting offer.

- 1.0 Revised Volume-III A, Price Schedule, Rev-3 for PKG-A, superseding earlier version.
- 2.0 Bidder shall submit offer for PKG-A and PKG-B, as applicable, in separate sealed envelopes, as per revised price schedule, as applicable.

Bidders are also requested to submit a declaration in techno-commercial offer that they have submitted their price bid in sealed envelope as per Revised Volume-III A, Price Schedule, Rev-3 format for PKG-A and Revised Volume-III A, Price Schedule, Rev-2 for PKG-B .

- 3.0 Revised 'No deviation certificate' as per enclosed Annexure-2. Bidder to submit 'No deviation certificate' as per attached format only.
- 4.0 All other terms & conditions shall remain unchanged.

Thanking you,

Yours faithfully,
for BHARAT HEAVY ELECTRICALS LTD

Engineer (SCT)

Encl

As above.

पावर सेक्टर पूर्वी क्षेत्र (मुख्यालय)

POWER SECTOR EASTERN REGION, DJ-9/1, SECTOR-II, SALT LAKE CITY, KOLKATA - 700 091

फैक्स/Fax : (033) 23211960

फोन/Phone : बोर्ड/EPABX : 23211691/ 23211798/ 23211795

FORMAT FOR NO DEVIATION CERTIFICATE
(To be submitted in the bidder's letter head)

BHARAT HEAVY ELECTRICALS LIMITED,
Power Sector - Eastern Region,
Plot no 9/1, DJ Block, Sector – II, Salt Lake City,
Kolkata – 700 091

Sub	No Deviation Certificate.	
Job	(i)PKG-A: Civil,structural and architectural works including piling and ground improvement etc of 1x250 MW unit # 8 for 2x 250MW units at Barauni TPP, Begusarai, Bihar. (ii)PKG-B: Civil,structural and architectural works including piling and ground improvement etc of 1x250 MW unit # 9 for 2x 250MW units at Barauni TPP, Begusarai, Bihar.	
Ref	1.0	Tender no PSER:SCT:BRM-C1273:11
	2.0	BHEL's NIT, vide reference no PSER:SCT:BRM-C1273:2584, dated 05-11-2011.
	3.0	BHEL's TCN-01 issued vide reference no PSER:SCT:BRM-C1273:TCN-01, dated 15-11-2011.
	4.0	BHEL's TCN-02 issued vide reference no PSER:SCT:BRM-C1273:TCN-02, dated 22-11-2011.
	5.0	BHEL's TCN-03 issued vide reference no PSER:SCT:BRM-C1273:TCN-03, dated 23-11-2011.
	6.0	BHEL's TCN-04 issued vide reference no PSER:SCT:BRM-C1273:TCN-04, dated 25-11-2011.
	7.0	BHEL's TCN-05 issued vide reference no PSER:SCT:BRM-C1273:TCN-05, dated 28-11-2011.
	8.0	All other pertinent issues till date.

Dear Sirs,

With reference to above, this is to confirm that as per tender conditions, we have visited site before submission of our offer and noted the job content & site conditions etc. We also confirm that we have not changed/ modified the tender documents as appeared in the website/ issued by you and in case of such observance at any stage, it shall be treated as null and void.

We hereby confirm that we have not taken any deviation from tender clauses together with other references as enumerated in the above referred NIT. We hereby confirm our unqualified acceptance to all terms & conditions, unqualified compliance to technical specification, integrity pact (if applicable) and acceptance to reverse auctioning process.

In the event of observance of any deviation in any part of our offer at a later date whether implicit or explicit, the deviations shall stand null & void.

We confirm to have submitted offer in accordance with tender instructions and as per aforesaid references.

Thanking you,

Yours faithfully,

(Signature, date & seal of authorized representative of the bidder)

<p>पावर सेक्टर पूर्वी क्षेत्र (मुख्यालय) POWER SECTOR EASTERN REGION DJ-9/1, SECTOR-II, SALT LAKE CITY, KOLKATA - 700 091 फैक्स/Fax : (033) 23211960 फोन/Phone : बोर्ड/EPABX : 23211691/ 23211798/ 23211796</p>

**VOLUME-III A
PRICE SCHEDULE, REV-3
(PACKAGE-A)**

PKG-A: CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS INCLUDING PILING AND GROUND IMPROVEMENT FOR MAIN POWER HOUSE, TG FOUNDATION, TRANSFORMER YARD, MILL AND BUNKER BAY FOUNDATION AND SUPER STRUCTURE , BOILER FOUNDATIONS, ESP FOUNDATIONS, BFP DECK, PA FAN FD FAN SA FAN & ID FAN FOUNDATIONS, TRANSFORMER YARD, ALL CABLE/PIPE RACKS-TRENCHES-CW PIPE CORRIDOR- ROAD & DRAINS WITHIN POWER BLOCK-1, ESP CONTROL ROOM, AIR COMPRESSOR HOUSE, BOILER AREA PAVING, ACW PUMP HOUSE, LUBE OIL ROOM, DG BUILDING, SERVICE BUILDING, COMPRESSOR HOUSE, CST TANK FOUNDATIONS, ALL MISCELLANEOUS STRUCTURE AND FOUNDATIONS WITHIN POWER BLOCK 1X250 MW UNIT # 8 FOR 2X250 MW UNITS AT BARAUNI TPP,BEGUSARAI, BIHAR.

TENDER NO - PSER:SCT:BRM-C1273:11

PREAMBLE

1.0	This preamble forms part of tender document and schedule of items. The tenderer should read this preamble carefully in rates for various items. Clauses under this preamble shall be read in conjunction with various volumes of tender as per NIT together with subsequent changes/ modifications etc thereto as applicable as on date of submission of price offer.
2.0	The work shall be carried out strictly as per specifications, description of the items in these schedule and / or engineer's instructions.
3.0	Items of work provided in this schedule but not covered in this specification shall be executed strictly as per instruction of the engineer.
4.0	Unless specifically mentioned otherwise in the tender document, the tenderer shall quote for the finished items and shall provide for the complete cost towards power, fuel, tools, tackles, equipment, constructional plants, temporary works, labour, dismantling of all temporary piping, structures, valves, pumps, tanks & other misc. equipment, strengthening of roads/culverts/bridges etc. including arranging all clearances etc. required for carrying out different activities & tests, materials, levies, taxes, transport, layout, repairs, rectification, maintenance till handing over, supervisions, colonies, shops, establishments, overheads, profits and all incidental items not specifically mentioned but reasonably implied and necessary to complete the work according to the tender document and this schedule.
5.0	Unless otherwise specified & except for tender on lumpsum basis, for all item rate based tenders, the quantities of the various items mentioned in price schedule are approximate, based on very preliminary information and may vary to any extent or to be deleted altogether. The quoted/ accepted rates shall remain firm and valid as long as variation in total value of work executed under this contract including extra items, but excluding any price escalation, remains within +/- 30% (thirty percent) of the contract price given in the LOI/ WO.
6.0	The rates quoted shall be inclusive of cleaning of site of any vegetation, dressing and leveling etc including fixing of grid pillars, benchmarks etc required for commencement of site activities. No separate payment will be made towards the same.
7.0	Rates shall be quoted in figures and in words in clear legible writing. No overwriting is allowed. All scoring and cancellations should be countersigned and in case of illegibility the interpretation of engineer shall be final. All entries shall be in English language.
8.0	All works item wise shall be measured upon completion and paid for at the rates quoted and accepted.
9.0	The tender shall be deemed to have studied the specifications, details of work to be done within the time schedule attached and to have acquainted himself of the conditions prevailing at site.
10.0	Engineer's decision shall be final and binding on the contractor regarding clarification of items in the schedule with respect to the other sections/volumes of the contract.
11.0	Evaluation & awarding will be done separately on PKG-A & PKG-B. PKG-A shall be decided first and who-so-ever is successful in PKG-A shall not be considered for PKG-B (They will not be considered for Reverse Auction/ price bid opening of PKG-B).

**VOLUME-III
PRICE SCHEDULE, REV-3
(PACKAGE-A)**

PKG-A: CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS INCLUDING PILING AND GROUND IMPROVEMENT FOR MAIN POWER HOUSE, TG FOUNDATION, TRANSFORMER YARD, MILL AND BUNKER BAY FOUNDATION AND SUPER STRUCTURE , BOILER FOUNDATIONS, ESP FOUNDATIONS, BFP DECK, PA FAN FD FAN SA FAN & ID FAN FOUNDATIONS, TRANSFORMER YARD, ALL CABLE/PIPE RACKS- TRENCHES-CW PIPE CORRIDOR- ROAD & DRAINS WITHIN POWER BLOCK-1, ESP CONTROL ROOM, AIR COMPRESSOR HOUSE, BOILER AREA PAVING, ACW PUMP HOUSE, LUBE OIL ROOM, DG BUILDING, SERVICE BUILDING, COMPRESSOR HOUSE, CST TANK FOUNDATIONS, ALL MISCELLANEOUS STRUCTURE AND FOUNDATIONS WITHIN POWER BLOCK 1X250 MW UNIT # 8 FOR 2X250 MW UNITS AT BARAUNI TPP,BEGUSARAI, BIHAR.

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-1 - TOTAL PRICE

SL NO	DESCRIPTION	AMOUNT ()
1.0	TOTAL PRICE OF SERVICE PART OF PKG-A AS PER OF SCH-2.	
2.0	TOTAL PRICE OF SUPPLY PART OF PKG-A AS PER OF SCH-3.	
3.0	GRAND TOTAL PRICE (SCH-2 & SCH-3 TOGETHR)	

NOTE

1.0	Bidder's quoted grand total price at SL NO 3.0 above shall be taken into account for evaluation and awarding and hence, shall be complete in all respect for the full scope defined in specification and in accordance with all terms & conditions of tender.
2.0	Price format shall not be changed by bidder in any case, since it may lead to cancellation of offer.
3.0	Bidder's quoted rates for non-schedule items under sl no 28.0 of SCH-2 shall also be applicable for scope under SCH-3.

VOLUME-III
PRICE SCHEDULE, REV-3
(PACKAGE-A)

PKG-A: CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS INCLUDING PILING AND GROUND IMPROVEMENT FOR MAIN POWER HOUSE, TG FOUNDATION, TRANSFORMER YARD, MILL AND BUNKER BAY FOUNDATION AND SUPER STRUCTURE , BOILER FOUNDATIONS, ESP FOUNDATIONS, BFP DECK, PA FAN FD FAN SA FAN & ID FAN FOUNDATIONS, TRANSFORMER YARD, ALL CABLE/PIPE RACKS- TRENCHES-CW PIPE CORRIDOR- ROAD & DRAINS WITHIN POWER BLOCK-1, ESP CONTROL ROOM, AIR COMPRESSOR HOUSE, BOILER AREA PAVING, ACW PUMP HOUSE, LUBE OIL ROOM, DG BUILDING, SERVICE BUILDING, COMPRESSOR HOUSE, CST TANK FOUNDATIONS, ALL MISCELLANEOUS STRUCTURE AND FOUNDATIONS WITHIN POWER BLOCK 1X250 MW UNIT # 8 FOR 2X250 MW UNITS AT BARAUNI TPP,BEGUSARAI, BIHAR.

TENDER NO. PSER:SCT:BRM-C1273:11

SCH-3- SUPPLY PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
1.0	704 S	Supply and delivery at site mild steel foundation bolt of various diameter conforming to IS:2062 and grade 1 of IS:432 in concrete along with nuts, lock nuts (as per IS:1363, 1364 and IS:3138), washers, anchor plates, stiffner plates, protective tape, pipe sleeves, templates etc. including welding, cutting, grinding, threading, drilling etc. all complete.	MT	20.0		

TENDER NO. PSER:SCT:BRM-C1273:11

SCH-3- SUPPLY PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
2.0	1501 S	Designing and supply permanently color coated galvanised MS troughed metal sheet decking plate of approved colour and conforming to class3 of IS 14246 over roof purlins for cast-in-situ roof slab as per relevant IS code and specification. Bare metal thickness of deck plate shall be minimum 0.8mm with minimum trough depth of 44 mm having minimum yield strength of 250 MPa and shall serve as permanent shuttering to the roof slab 100mm thick measured over crest of metal decking & shall have adequate strength to support weight of green concrete and imposed loads of min 150 kg/sqm during construction between purlins as per manufacturer's recommendations/ calculations/ test certificates for approval including fixing of plates to purlins, side lapping, end lapping etc. all complete for below mentioned spans. The sheet shall be permanently coated with silicon modified polyester paint of minimum 20 micron DFT on exposed surface (facing operating floor) and minimum 7 micron on other face over epoxy primer applied over hoithout extra cost to BHEL/Owner) etc all complete as per specification, drawing and as directed by the engineer-in-charge for the following. (Cement & Reinforcement will be supplied by BHEL as per SCC free of cost). sting - 10%.sealing with epoxy sealant. Measurement of profile sheeting shall be of the plan area of roof covered by MS trough metal decking.				
2.1	a	Span Upto 1800mm	SQM	3589.0		
2.2	b	Span Exceeding 1800mm and upto 2500 mm	SQM	3500.0		

PAGE 68 OF 71

VOLUME-IIIA

PRICE SCHEDULE, REV-3

(PKG-A)

SCH-3 - SUPPLY PRICE BU

TENDER NO - PSER:SCT:BRM-C1273:11

SIGNATURE WITH SEAL OF BIDDER

TENDER NO. PSER:SCT:BRM-C1273:11

SCH-3- SUPPLY PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
3.0	1504 S	Designing and supply External sheet of Permanent colour coated metal cladding with high strength tensile steel sheet 0.5mm bare metal thickness having minimum yield strength 350 MPa and zinc-aluminium alloy coating not less than 275 gm/sqm total on both sides including fixing to supports / rails by concealed fixing system, corrosion resistant self tapping / self drilling type fasteners with suitable cap, flashing etc. all complete. The exposed face of the sheet shall be permanently colour coated with Polyfluro Vinyl Coating (PVF2) of minimum dry film thickness (DFT) 20 microns over suitable primer. Inner face of the sheet shall be provided with suitable pre-coating of minimum DFT 7 microns over suitable primer. The permanent colour coated sheet shall meet the general requirements of IS : 14246 and shall conform to class 3 for the durability.	SQM	3550.0		
4.0	1505 S	Design and supply Inner sheet of Permanent colour coated metal cladding with troughed M.S. sheets of 0.6mm bare metal thickness having minimum yield strength 250 MPa and zinc-aluminium alloy coating not less than 275 gm/sqm total on both sides of both sheets including fixing to supports / rails by concealed fixing system, corrosion resistant self tapping / self drilling type fasteners with suitable cap, flashing etc. all complete. The exposed surface of the sheet shall be permanently colour coated with silicon modified polyester paint of minimum dry film thickness (DFT) 20 microns over suitable primer. Other face of the sheet shall be provided with suitable pre-coating of minimum DFT 7 microns over suitable primer. The permanent colour coated sheet shall meet the general requirements of IS : 14246 and shall conform to class 3 for the durability. The sheet shall be fixed directly to side runners and Z spacers as per IS : 277. The sheet shall be fixed at the rate not more than 1500mm center to center to hold the insulation and external sheeting.	SQM	2650.0		
5.0	1707 S	Supply GI down take pipes conforming to IS:1239 /IS:3589 of medium duty all complete for following diameters.				
5.1	b	150 mm Dia	RM	3635.0		

TENDER NO. PSER:SCT:BRM-C1273:11

SCH-3- SUPPLY PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
	2307 S	Supplying factory made electroforged galvanised grating units with mild steel (having minimum galvanisation of 610 g/sqm) conforming to IS:2062 in flooring, platforms, drain and trench covers, walk-ways, passages, staircases with edge binding strips and anti-skid nosing in treads etc. including fixing clamps, fittings, fixtures, all taxes, duties, packing etc. all complete.	MT	30.0		
6						
7.0	2308 S	Supplying factory made galvanised welded grating units with mild steel conforming to IS:2062 in flooring, platforms, drain and trench covers, walk-ways, passages, staircases with edge binding strips and anti-skid nosing in treads etc. - fixing clamps, fittings, fixtures, all taxes, duties, packing etc. all complete.	MT	15.0		
8.0	2310 S	Supply permanent mild steel bolts (class 4.6 as per IS : 1367 and grade `C' as per IS: 1363) and nuts, washers etc. up to and inclusive of 39 mm diameter and upto 300mm long for structural steel work etc.	Quintal	150.0		
9.0	2311 S	Supply high strength structural bolts (of property class 8.8 and product grade `C' as per IS: 1367) and conforming to IS: 3757 and high strength structural hardened and tempered nuts (of property class `8' as per IS:1367) conforming to IS:6623 with hardened and tempered washers as per IS:6649 etc. up to and inclusive of 39 mm diameter and upto 300 mm long for structural steel work etc.	Quintal	375.0		
10.0	2320 S	Supply GI pipe for hand railing (900 mm high) of 32 mm/40 mm dia (Medium Grade) including transportation, loading/unloading, etc.	MT	36.0		
11.0	2742	Providing service for manpower, for running and maintenance of BOREWELL pump set without supply of major equipment / parts.	Man-month	48.0		
12	2743	General purpose crawler crane (150T) with lattice boom & minimum 10M length jib suitable for strutral erection. (crane should be available at site for continuous and erection work including sundays and holidays without any additional cost).				
12.1	2743A	Mobilisation and de-mobilisation charge. Payments: a) 70% on mobilisation, b) Balance 30% on demobilisation.	LOT	1.0		
12.2	2743B	Monthly lumpsum crane hire charge including fuel, opertor and all other charges.	CRANE-MONTH	8.0		

TENDER NO. PSER:SCT:BRM-C1273:11						
SCH-3- SUPPLY PRICE BREAK UP						
SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
14	2744.0	Heavy lift crawler crane (250T) with lattice boom & minimum 10/12M length jib suitable for erection of millbuilding and bunker structure. (crane should be available at site for continuous erection work including sundays and holidays without any additional cost).				
14.1	2744A	Mobilisation and de-mobilisation charge. Payments: a) 70% on mobilisation, b) Balance 30% on demobilisation.	LOT	1.0		
14.2	2744B	Monthly lumpsum crane hire charge including fuel, operator and all other charges.	CRANE-MONTH	12.0		
12.0		Supply, installation, erection, testing, commissioning, operation & maintenance of electronic road weigh bridge pitless type, 60Tx100kg with platform size of 16 Mx3 M with necessary supporting structures, control room with proper digital indicator, recorder, printer, PC with keyboard, display unit (15"), UPS (500VA), accuracy $\pm 0.25\%$ of actual weight, minimum graduation 10kg, maximum weight 60T, AVERY or equivalent make.	SET	1		
TOTAL						

**VOLUME-III A
PRICE SCHEDULE, REV-3
(PACKAGE-A)**

PKG-A: CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS INCLUDING PILING AND GROUND IMPROVEMENT FOR MAIN POWER HOUSE, TG FOUNDATION, TRANSFORMER YARD, MILL AND BUNKER BAY FOUNDATION AND SUPER STRUCTURE , BOILER FOUNDATIONS, ESP FOUNDATIONS, BFP DECK, PA FAN FD FAN SA FAN & ID FAN FOUNDATIONS, TRANSFORMER YARD, ALL CABLE/PIPE RACKS- TRENCHES-CW PIPE CORRIDOR- ROAD & DRAINS WITHIN POWER BLOCK-1, ESP CONTROL ROOM, AIR COMPRESSOR HOUSE, BOILER AREA PAVING, ACW PUMP HOUSE, LUBE OIL ROOM, DG BUILDING, SERVICE BUILDING, COMPRESSOR HOUSE, CST TANK FOUNDATIONS, ALL MISCELLANEOUS STRUCTURE AND FOUNDATIONS WITHIN POWER BLOCK 1X250 MW UNIT # 8 FOR 2X250 MW UNITS AT BARAUNI TPP,BEGUSARAI, BIHAR.

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
1.0	100	EARTH WORK (Earth work In excavation, backfilling and disposal including necessary men/women, materials, equipment, loading, transportation, unloading, dewatering etc as per specification, drawing and as directed by engineer- in-charge for the following.)				
1.1	101	Earth work in excavation in all types of soil including ash which can be excavated by any means including setting out, levelling, dewatering (but excluding special type of dewatering viz. well point method), shoring & strutting (wherever required), dressing the sides & bottom, all lifts, ramming/compacting the excavated bottom, stacking, disposal of surplus excavated materials within a lead upto 500 m, spreading/levelling of disposed materials etc all complete for following depths below ground level.				
1.1.1	a	Depth from ground level but not exceeding 2 m	CUM	51340.0		
1.1.2	b	Depth exceeding 2 m but not exceeding 4 m	CUM	29250.0		
1.1.3	c	Depth exceeding 4 m but not exceeding 6 m	CUM	9143.0		
1.2	102	Extra over ST No. 101 for dewatering of ground water by well point method as per IS 9759.	CUM	9143.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
1.3	107	Back filling upto any depth below ground level around foundations, plinths, trenches, drains etc to proper grade and level in layers not exceeding 250 mm thickness using/with selected materials from compulsorily excavated soil available within a lead upto 500m and compacted as specified including re-excavation of stacked earth, watering, ramming/compaction by manual/mechanical means, dressing etc all complete.for the following.				
1.3.1	a	Each layer compacted so as to achieve at least 95% maximum dry density as per IS-2720 (Part-VII)	CUM	11325.0		
1.3.2	b	Each layer compacted so as to achieve at least 90% maximum dry density as per IS-2720 (Part-VII)	CUM	36367.0		
1.4	108	Back filling upto any depth below ground level around foundations, plinths, trenches, drains etc to proper grade and level in layers not exceeding 250 mm thickness using/with selected materials directly from excavation and compacted as specified includ watering, ramming/compaction by manual/mechanical means, dressing etc all complete for the following.				
1.4.1	b	Each layer compacted so as to achieve at least 90% maximum dry density as per IS-2720 (Part-VII)	CUM	3150.0		
1.5	109	Extra over ST No. 101 and 107 for carriage of excavated earth/selected materials for carriage beyond an initial lead of 500m.				
1.5.1	a	Carriage beyond 500 m and not exceeding 1 Km	CUM	30000.0		
1.5.2	b	Carriage beyond 1 Km and not exceeding 2 Km	CUM	30000.0		
1.5.3	c	Carriage beyond 2 Km and not exceeding 3 Km	CUM	2000.0		
1.6	111	Supplying and filling sand upto any depth under floors, around foundations, plinths etc. in layers not exceeding 250 mm thickness and compacted so as to achieve at least 80% relative density as per IS-2720 (Part-XIV) including spreading, watering, ramming/compaction by manual / mechanical means, dressing, royalty (if any) etc. all complete.	CUM	8470.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
2.0	200	CONCRETE WORKS(Providing and placing concrete work including cost of labour, materials and equipment for handling, transportation, batching, mixing, placing, vibrating and curing, (excluding cost of centering, shuttering and reinforcement) with mechanised equipments like batching plant, transit mixer, concrete pump etc. complete as per drawing, specifications and as per direction of engineer in charge for the following.(Cement will be supplied by BHEL as per SCC free of cost):)				
2.1	201	Concrete of grade M7.5 (1 part cement, 4 part sand, 8 parts of 40 mm graded aggregate by volume) as filling course at any depth below finished floor level, under and around foundations/floors, mass fill etc.	CUM	50.0		
2.2	202	Concrete of grade M10 (1 part cement, 3 part sand, 6 parts of 40 mm graded aggregate by volume) as lean concrete, levelling course, mud mat under and around foundations/floors at any depth below finished floor level etc.	CUM	3574.0		
2.3	204	Concrete under floors, paving, plinth protection, pipe encasing etc complete with 20 mm nominal size graded aggregate at any depth below finished floor level for the following grades.				
2.3.1	b	M25 Grade	CUM	1153.0		
2.4	205	Providing and laying Design Mix cement concrete conforming to IS:456 & IS 10262-2009 for reinforced concrete works with coarse sand and graded hard stone aggregate of 20mm nominal size in foundations/substructure, grade slab, paving, drains, under floors etc at any level below finished floor level, any shape, position or thickness etc complete including use of plasticizer/ superplasticizer conforming to IS:9103 (latest) to achieve required slump in concrete all complete as per specification & drawing for the following.				
2.4.1	a	M25 Grade	CUM	5565.0		
2.4.2	b	M30 Grade	CUM	17021.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
2.5	206	Providing and laying Design Mix cement concrete conforming to IS:456 & IS 10262-2009 for reinforced concrete works with coarse sand and graded hard stone aggregate of 20mm nominal size in superstructure at any level above finished floor level, any shape, position or thickness etc complete including use of plasticizer/ superplasticizer conforming to IS:9103 (latest) to achieve required slump in concrete all complete as per specification & drawing for the following.				
2.5.1	a	M25 Grade	CUM	7613.0		
2.6	A207	Providing and laying Design Mix cement concrete confirming to IS:456 & IS 10262-2009 for reinforced concrete works of grade M-30 Grade in machine foundations for TG, Gas Turbine, ID/FD/PA fans, BFP, Coal mills at all elevations below/above finished floor level except Top decks supported over Vibration Isolation system, TG deck and TG Columns including addition of suitable plasticizer conforming to IS 9103(latest) to achieve a slump more than 125mm in concrete as per manufacturer's recommendation with 20 mm nominal size graded aggregate in concrete all complete as per specification & drawing.	CUM	6310.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
2.7	A208	Providing and laying Design Mix cement concrete as per IS:456 & IS 10262-2009 of grades mentioned below for reinforced concrete works using graded aggregate in top decks of all machine foundations supported on vibration isolation system (excluding supply and installation of vibration system), top deck of TG foundation, TG Columns at all levels including addition of suitable plasticizers conforming to IS9103 to achieve a slump more than 125 mm in concrete as per manufacturers recommendation, preparation of scheme for concreting, getting it approved by engineer, labour, materials, equipment, handling, batching, transporting, mixing, pumping, placing, leveling, vibrating, compacting, curing, testing, cleaning and rendering the exposed surface with cement sand mortar to give a smooth and even surface, maintaining and submitting records of concreting, petrographic examination and potential reactivity of aggregate etc. all complete as per specification, drawing and instructions of engineer, including UPV testing as directed by engineer in charge, rectification of the defects in concreting observed by ultra-sonic pulse velocity (UPV) testing by cement/epoxy grout etc, but excluding formwork, staging, reinforcement, embedments and temperature control of concrete. Payment terms - a) After casting 75% ; b) After receipt of ultrasonic test report - 25%.				
2.7.1	a	M30 grade (with 20mm nominal size graded stone aggregate)	CUM	750.0		
2.7.2	b	M35 grade (with 20mm nominal size graded stone aggregate)	CUM	150.0		
2.7.3	c	M40 grade (with 20mm nominal size graded stone aggregate)	CUM	10.0		
2.8	209	Extra over St. No. 205,206,A207 & A208 for controlling of temperature of fresh concrete to less than 23 degree centigrade using ice, including all related arrangements for providing, storing and mixing of ice with water, cooling of aggregates etc. All complete as per specification, drawing and instruction of engineer in charge.	CUM	7060.0		
2.9	210	Extra over ST Nos. 205 to 207 for conducting UPV test for concrete at all levels including all equipments, making necessary arrangements, staging, submission of report etc. all complete as directed by engineer in charge and as per specification.	CUM	7060.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
2.10	211	Providing and encasing of structural steel member with concrete using nominal aggregate size of 12.5mm down. Encased member shall be wrapped with welded wire mesh/chicken wire mesh with proper lap etc. complete as per specification for the following grades. (Payment of welded wire mesh, chicken wire mesh shall be made separately)				
2.10.1	a	M20 grade	CUM	284.0		
2.11	212	Screed concrete / bed concrete conforming to IS 456 with coarse sand and graded hard stone aggregate 12.5mm/6 mm nominal size on the roof at any level or thickness, drains etc complete as per following.				
2.11.1	a	1:2:4 (1 part cement, 2 part sand, 4 parts of aggregate by volume)	CUM	335.0		
2.11.2	b	1:1.5:3 (1 part cement, 1.5 part sand, 3 parts of aggregate by volume)	CUM	100.0		
2.12	213	Providing and laying Design Mix cement concrete as per IS:456 & IS 10262-2009 for reinforced concrete works using graded aggregate for Concrete in precast works like roof slabs/trench covers, fins, lintels, chajas, beams, columns, wall panels, facias etc.at all levels in all kinds of work including formwork/moulds, curing, rendering the top exposed surface with cement sand mortar (1:3), handling, storing, transpoting, all leads, erection without damage, setting in position with cement sand mortar (1:3), filling the gaps between adjacent precast units with M30 grade concrete or cement sand mortar (1:3) and including making of holes for bolts for fixing, welding etc.complete with graded aggregate (20/12.5/10 mm) and as per specification and drawing for following grades.				
2.12.1	a	M 25 grade	CUM	437.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
2.13	214	Providing and laying Design Mix cement concrete as per IS:456, IS 3370 & IS 10262-2009 for reinforced concrete works using graded aggregate for Concrete in water retaining/conveying structures including addition of suitable plastisizer cum waterproofing cement additives conforming to IS 9103 latest to achieve a slump more than 125 mm in concrete as per manufacturers recommendation and conforming to limits of permeability as per IS 2545 and specification with 20 mm nominal size graded aggregate for following grades.				
2.13.1	a	M 25 grade	CUM	50.0		
2.14	215	Dismantling concrete work for all types of structures at all levels including stacking of servicable material to a lead of 500 m and disposal of unservicable material upto a lead of 2 km, cutting of reinforcement, labour, equipment, safety precautions etc all complete as per drawings, specification and instructions of engineer in charge.				
2.14.1	a	Plain cement concrete of all grades	CUM	1.0		
2.14.2	b	Reinforced cement concrete of all grades	CUM	13.0		
2.15	216	Chipping of concrete in reinforced concrete work, cutting pockets, making openings at all levels and according to shapes, disposal of waste materials upto a lead of 2 km as directed by engineer including equipment, safety precautions, making good the broken surface etc all complete as per specification, drawing, instructions of engineer in charge but excluding cutting of reinforcement .	CUM	0.5		
2.16	217	Making opening in RCC slab or foundation by core cutter method upto 100mm dia and depth of cutting upto 250mm	NO	150.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
2.17	221	Providing and laying Design Mix cement concrete conforming to IS:456 & IS 10262-2009 for reinforced concrete works with coarse sand and graded hard stone aggregate of 20mm nominal size in sloped surface of canal lining or channel cast in alternate panels with provision of expansion gap/construction joints at any level below finished floor level, any shape, position or thickness etc complete including use of plasticizer/ superplasticizer conforming to IS:9103 (latest) to achieve required slump in concrete, compaction with special equipments, etc all complete as per specification & drawing for the following.				
2.17.1	b	M25 Grade	CUM	15.0		
3.0	300	FORM WORKS(Providing, fixing and removing formwork at any elevations for all structures, as per specifications and including all labour, material, scaffoldings and centering complete including pockets etc. complete as per drawing, specifications and as per direction of engineer in charge for the following.)				
3.1	301	Fairface form work with good quality water proof ply wood of required thickness and smooth surface below finished ground floor level for foundations, footings, base of columns, walls, columns, pilasters, beams, mass concrete, trenches etc.	SQM	44727.0		
3.2	302	Fairface form work with good quality water proof ply wood of required thickness and smooth surface above finished ground floor level for columns, beams, suspended floors, roofs, lintels, cantilevers, staircases, landings, balconies, domes, arches, circular overhead tanks etc. for all heights.	SQM	25275.0		
3.3	303	Fairface Formwork with good quality water proof ply wood of required thickness and smooth surface for TG superstructure (above base raft level) including preparation of scheme, designing, submission and approval of staging drawing with sufficient props, braces and ties at every tier of height of approx. 4m for all heights.	SQM	1400.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
3.4	304	Providing, fixing and removing formwork in block-outs/pockets and openings (below 0.1 sqm plan area) at all elevations including cutting, formation of all shapes and all other operations required for making the required shape and size all complete as per specification, drawing and instruction of engineer in charge.				
3.4.1	a	Upto 150 mm depth	Each	152.0		
3.4.2	b	Pockets of depths more than 150mm and upto 300 mm depth	Each	118.0		
3.4.3	c	Pockets of depths more than 300mm and upto 600 mm depth	Each	526.0		
3.4.4	d	Pockets of depths more than 600mm and upto 1000 mm depth	Each	219.0		
3.4.5	e	Pockets of depths more than 1000mm and upto 1500 mm depth	Each	51.0		
3.4.6	Af	Pockets of depths more than 1500mm and upto 2500 mm depth	Each	36.0		
3.5	A306	Extra over item no.301 for curved form work for foundations, footings, beams, walls, trenches, mass concreting etc as per specification.	SQM	1035.0		
4.0	400	REINFORCEMENT				
4.1	401	Providing, straightening, cutting, bending, placing in position at any level, binding in position of steel reinforcements of TMT steel of grade Fe-500 confirming to IS:1786 including cost of binding wire, labour, scaffolding, transportation to & from stores etc complete all as per specifications, drawings and as directed by Engineer. (Reinforcement to be supplied by contractor from SAIL/ RINL/ TISCO or as approved by BHEL/cutomer).	MT	25.0		
4.2	402	Transport from store, straightening, cutting, bending, placing in position at any level, binding in position of steel reinforcements of TMT steel of grade Fe-500 confirming to IS:1786 including cost of binding wire, labour, scaffolding, transportation to & from stores etc complete all as per specifications, drawings and as directed by Engineer. (Reinforcement will be supplied by BHEL as per SCC free of cost)	MT	10.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
4.3	403	Transport from store, straightening, cutting, bending, placing in position at any level, binding in position of steel reinforcements of TMT steel of grade Fe-500D or 500EQR confirming to IS:1786 including cost of binding wire, labour, scaffolding, transportation to & from stores etc complete all as per specifications, drawings and as directed by Engineer. (Reinforcement will be supplied by BHEL as per SCC free of cost)	MT	3089.0		
4.4	407	Providing, straightening, cutting, bending, placing in position at any level, binding in position high yield strength steel reinforcements in brickwork including cost of reinforcement and binding wire, labour, scaffolding etc. complete all as per specifications & drawings.(Reinforcement to be supplied by contractor from SAIL/ RINL/ TISCO or as approved by BHEL/cutomer).	MT	5.0		
5.0	500	WATER PROOFING WORKS(Water proofing works including all labour, material, equipment, transportation, handling, curing, sampling, testing etc at any level as per specification, drawings and as directed by engineer - in - charge. (Contractor has to furnish a guarantee for material and workmanship for a minimum period of 10 years). (Cement will be supplied by BHEL as per SCC free of cost).)				
5.1	501	Providing and laying underbed grading plaster with cement mortar 1:4 (1 cement : 4 sand) and average thickness of 25 mm including preparation of surface, batching, mixing, leveling etc. all complete.	SQM	7050.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
5.2	502	Providing and laying in-situ light weight foam concrete insulation as per relevant IS Code in suitable panels over roofs followed by a layer of 15 mm thick cement sand plaster 1:5 (1 cement: 5 coarse sand) after the curing period of laid foam concrete and providing of expansion joint at intervals as per the recommendation of manufacturer. The insulating properties shall be such that the thermal conductivity shall not exceed 0.125 Kcal/sqm-hr deg C. Cost shall include making of fillets, cleaning & preparation of surface, expansion joints at suitable intervals etc all complete for following. Sand plaster will be paid separately as per BOQ item.				
5.2.1	c	Average 100 mm thickness	SQM	4200.0		
5.3	503	Providing and applying bitumen felt water proofing for normal treatment having bonding materials consisting of blown type conforming to IS: 702 or residual bitumen conforming to IS: 73 or a mixture of the two with one layer of felt consisting of five courses and with a minimum overlap of 75 to 100 mm of felt including preparation of surfaces etc all complete. (For description of layers refer specification)				
5.3.1	a	With hessian base felt	SQM	7050.0		
5.4	507	Providing and laying wearing course consisting of 25mm thick plain cement concrete of grade M15 (1:2:4) with graded aggregate of 12.5mm size cast in panels of maximum size 1.2mx1.2m and reinforced with 0.56 mm dia. galvanised chicken wire mesh and sealing of joints (in grooves of 6mm X 6mm) using silicon /elastomeric compound etc all complete.	SQM	6418.0		
5.5	508	Providing and laying cement concrete chequered flooring tiles of 22 mm thickness and size 250x250 mm / 300x300 mm conforming to IS 13801 with 8 mm thick 1:4 cement mortar over the top most layer of roofing treatment in pathway and entire equipment area with fine joints including sealing of joints (silicon/elastomeric sealant) etc all complete. (Water proofing paid elsewhere)	SQM	200.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
5.6	509	Providing and applying two coats of bitumen grade 85/25 as per IS 702 (@ 1.7kg/sqm)with 1% antistripping compound conforming to IS 6241 in foundation, wall, column etc on concrete surfaces exposed to soil / ash including surface preparation etc. all complete.	SQM	35244.0		
5.7	511	Providing and mixing water proofing compound conforming to IS:2645 in concrete or cement mortar all complete.	KG	100.0		
5.8	512	Anti termite chemical treatment of soil with Chloropyrifos emulsifiable concentrates (1%) conforming to IS :8944 all complete.	SQM	1160.0		
5.9	513	Providing and applying concrete structures two coats of ERPB (Epoxy resin based anticorrosive and chemical resistant paint) over a coat of CPCI (concrete penetrating bipolar corrosion inhibitor) with 300 to 325 micron DFT for protection of concrete against carbonation and chloride penetration in saline/marine environment all complete of approved make and as per manufacturer's recommendation	SQM	100.0		
6.0	600	JOINTS AND FILLERS (Joints & fillers including all labour, material, equipment, transportation, handling etc at any level as per specification, drawings and as directed by engineer - in - charge.)				
6.1	601	Supplying & installation of bitumen impregnated fibre board conforming to IS 1838 as joint filler at joints in concrete including nailing, coating of both faces with coal tar pitch/bitumin etc. all complete.				
6.1.1	a	12 mm wide joints.	SQM	107.0		
6.1.2	b	20 mm wide joints.	SQM	15.0		
6.1.3	c	25 mm wide joints	SQM	185.0		
6.1.4	d	50 mm wide joints	SQM	140.0		
6.2	602	Providing and applying polysulphide based sealant conforming to IS:12118 in expansion joints in concrete including cleaning of joints, raking out groove, application of primer, scaffolding etc. all complete for following size grooves:				

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
6.2.1	a	12mm X 25mm	RM	3588.0		
6.2.2	b	20mmX25mm	RM	15.0		
6.2.3	c	25mmX25mm	RM	180.0		
6.2.4	d	50mmX25mm	RM	695.0		
6.3	603	Supplying and filling in position hot applied bitumin sealing compound (Grade A) conforming to IS 1834 including cleaning, mixing, heating, pouring/injecting sealing compound in gaps in joints including application of primer etc. all complete.				
6.3.1	b	12mm X 25mm	RM	2.0		
6.4	606	Providing and fixing PVC water stops in joints conforming to IS 12200 & IS 15058 all complete for the following:				
6.4.1	a	150 mm wide and 8 mm thick	RM	165.0		
6.4.2	b	230 mm wide and 8 mm thick	RM	90.0		
7.0	700	MS EMBEDMENTS (Embedments including all labour, material, equipment, transportation, handling etc. at any level as per specification, drawings and as directed by engineer - in - charge.)				
7.1	701	Supply, fabricating and fixing of mild steel embedments, inserts, pipe sleeves, beams, angle pieces, rungs of various diameters, plates of dimensions as required etc. including welding, bolting, cutting, drilling, scaffolding, setting etc. all complete.(Contractor to supply all materials) Payment terms - a) On receipt of raw materials at site - 70%; b) On completion of erection & fixing - 30%.	MT	8.5		
7.2	702	Transport from store, fabricating and fixing of mild steel embedments, inserts, pipe sleeves, angle pieces, plates of dimensions as required etc. including welding, bolting, cutting, drilling, scaffolding, setting etc. all complete. BHEL will supply plates, angles, channel & ISMB etc. free of cost as per SCC	MT	100.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
7.3	703	Assembly,welding, fixing of embedments, inserts, pipe sleeves, angle pieces, anchor bolts of various diameters, plates of dimensions as required etc. including scaffolding, setting in position, transportation from BHEL site stores to work spot etc. all complete.BHEL WILL SUPPLY FABRICATED MATERIALS.	MT	5.0		
7.4	704	Transportation,erection, installation and alignment of mild steel foundation bolt assembly conforming to IS:2062 and grade 1 of IS:432 in concrete along with nuts, lock nuts (as per IS:1363, 1364 and IS:3138), washers, anchor plates, stiffner plates, protective tape, pipe sleeves, templates etc. including welding, cutting, grinding, threading, drilling etc. all complete.	MT	20.0		
7.5	705	Supplying, fabricating, erecting and installing following items in concrete/brickwall for all kind of works, including setting material in concrete, layout, scaffolding, cutting, forming, grinding, drilling, bolting, welding, jointing, testing etc. all complete.Contractor to supply all materials. Payment terms - a) On receipt of materials at site - 70%; b) On completion of erection & fixing - 30%.				
7.5.1	a	MS pipes of all diameters	Quintal	2.0		
7.5.2	b	PVC pipes / conduits of all diameters	Quintal	1.0		
7.5.3	c	UPVC pipes / conduits of all diameters	Quintal	1.0		
7.5.4	d	Expansion fasteners (mechanical galvanised) of HILTI make or equivalent of safe tensile capacity as specified below for brick work with expansion sleeve of A6 polyamide:				
7.5.4.1	i	Upto 250 kg	Each	10.0		
7.5.4.2	ii	Beyond 250 Kg and upto 500 kg	Each	10.0		
7.5.4.3	iii	Beyond 500 Kg and upto 750 kg	Each	10.0		
7.5.5	e	Expansion fasteners (mechanical galvanised) of HILTI make or equivalent of safe tensile capacity as specified below for concrete work with expansion sleeve of stainless steel:		0.0		
7.5.5.1	i	Upto 250 kg	Each	10.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
7.5.5.2	ii	Beyond 250 Kg and upto 500 kg	Each	10.0		
7.5.5.3	iii	Beyond 500 Kg and upto 750 kg	Each	10.0		
7.5.6	A705e	Expansion fasteners chemical adhesive type (mechanical galvanised) of HILTI make or equivalent of safe tensile capacity as specified below for concrete work with expansion sleeve of stainless steel:				
7.5.6.1	i	Upto 250 kg	Each	10.0		
7.5.6.2	ii	Beyond 250 Kg and upto 500 kg	Each	10.0		
7.5.6.3	iii	Beyond 500 Kg and upto 1000 kg	Each	10.0		
8.0	800	GROUTING (Grouting including all labour, material, equipment, roughening surface, cleaning, ramming, curing etc. at any level unless otherwise specified as per specification, drawings and as directed by engineer - in - charge.)				
8.1	801	Providing & grouting with cement slurry mix of approved ratio using pressure pump for water retaining concrete structures as per approved procedure including cost of nipples/ nozzles, cement, admixture, curing, pressure pumps, slurry agitator etc. all complete. Cost shall include fixing of nipples at minimum 500 mm centre to centre spacing, cutting of nipples after completing of grouting, making good of the nipple hole with appropriate non-shrink cement paste, water tightness test etc. all complete wherever specified in the drawing. (Cement will be supplied by BHEL as per SCC free of cost).	SQM	3.0		
8.2	802	Providing & grouting of pocket holes, pipe sleeves under base plates, machinery, pipe supporting structures etc. with mix 1:1 (1 cement :1 sand) using non shrink admixture etc. all Complete.(Cement will be supplied by BHEL as per SCC free of cost).	CUM	9.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
8.3	803	Providing & grouting of pocket holes, pipe sleeves and under base plate of structural steel work/ machinery/ pipe supporting structures including roughening of surface, cleaning, ramming, curing etc. all complete with mix 1:1:2 (1 cement : 1 coarse sand : 2 aggregate of 6 mm down graded stonechips) using non shrink admixture. (Cost of all material and cleaning the pocket by compressed air shall be in the scope of the contractor).(Cement will be supplied by BHEL as per SCC free of cost).	CUM	162.0		
8.4	804	Providing & grouting of pocket holes, pipe sleeves and under base plates of structural steel work/ machinery/ pipe supporting structures including roughening of surface, cleaning, ramming, curing etc. all complete with ConbextraGP-1 or equivalent . (Cost of all material and cleaning of the pockets by compressed air shall be in the scope of the contractor).	CUM	51.0		
8.5	805	Providing & grouting of pocket holes, pipe sleeves and under base plates of structural steel work/ machinery/ pipe supporting structures including roughening of surface, cleaning, ramming, curing, etc. all complete with Conbextra GP-2 or equivalent . (Cost of all material and cleaning of the pockets by compressed air shall be in the scope of the contractor).	CUM	10.0		
9.0	900	DOORS, WINDOWS, VENTILATORS, LOUVERS (Doors, windows, ventilators, louvers, roof ventilators, rolling shutters, partitions including all labour, material, equipments, transportation, handling, preparation of working drawings etc. at any level as per specification, drawings and as directed by engineer - in - charge.)				

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
9.1	902	Providing and fixing teakwood frame panel door shutter as per IS 1003 with 35 mm x 150 mm vertical rail & 35mm x 125 mm horizontal rail and 12 mm thick interlocked panels of teakwood with proper wood joinery including beading, preparation of working drawings, godrej or equivalent make mortice lock with handels on both sides, approved ISI mark anodised fittings like door stopper, 300mm long tower bolts, 16x300mm long aldrops, 125mm long handles on both sides etc. butt hinges, sliding bolt, knobs, (all fitting shall be anodised aluminium color dyed), screws, primer and finish painting / polishing etc. all complete. (Finish painting / polishing paid separately)	SQM	20.0		
9.2	903	Providing, fitting and fixing solid core flush door shutter as per IS 2202 part II, 35mm thick homogenous particle board bonded with BWP type phenolformaldehyde synthetic resin, particle board core conforming to IS 3087 type I, 35x12 mm thick teakwood beading all around including preparation of working drawings. godrej or equivalent make mortice lock with handels on both sides, approved ISI mark anodised fittings like door stopper, 300mm long tower bolts, 16x300mm long aldrops, 125mm long handles on both sides etc. butt hinges, sliding bolt, knobs, (all fittings shall be anodised aluminium color dyed), finish synthetic paint over primer, screws etc. all complete as per drawing, specification and instruction of engineer in charge. with commercial faces and teak wood edges. (Finish painting paid separately)	SQM	45.0		
9.3	904	Providing and fixing single or double steel door shutters with 45mm thk flush design shutter comprising of two outer sheets of 18 gauge steel sheets rigidly connected and reinforced inside with continuous vertical 20 gauge stiffeners, spot welded in position at not more than 150mm on centres including void filled with mineral wool (density as per specification), all fittings, Godrej or equivalent make mortice lock with handle on both sides, shop and final painting etc all complete. Payment terms - a) On receipt of materials at site - 70%; b) On completion of erection & fixing - 30%.	SQM	199.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
9.4	905	Providing and fixing single or double steel door shutters with 18 gauge M.S. sheets shutter presenting a flush surface on the outside and inside stiffened with semitubular edge and central stiffening rail which shall convey the lock including fixtures, Godrej or equivalent make mortice lock with handle on both sides, shop and final painting etc all complete.	SQM	15.0		
9.5	A906	Providing and fixing anodized extruded aluminium doors (single or double shutter) conforming to IS:1948, IS:1949 fabricated from extruded sections of HINDALCO/JINDAL or equivalent make having minimum 3mm wall thickness as per IS:1285, IS:733 and anodized and electro color coating of required shade as per IS 1868 (minimum anodized coating of grade AC15). fixed with rawl plugs, expansion fasteners,SS screws / fixing clips necessary filling of gaps at Junctions, at top, bottom & sides with required PVC / neoprene felt for bi-metallic protection etc. Glazing shall be clear toughened glass of 6mm thickness including snap fit type beading, concealed screws, fixtures, Godrej or equivalent make Mortice lock with handle on both sides, etc all complete. Aluminium section shall be smooth, free of stains, straight, mitred & jointed mechanically wherever required. (Glazing shall be paid separately)	SQM	85.0		
9.6	907	Providing and fixing fire proof steel doors (single or double shutter) with panic devices shall be 45mm thk flush design comprising of two outer sheets of 18 gauge steel sheets rigidly connected and reinforced inside with continuous vertical 20 gauge stiffeners, spot welded in position at not more than 150mm on centers including all fittings, shop painting with approved post office/signal red color fire resistant paint and mineral wool insulation (64 kg/cum density) complete and shall be fire proof as per IS:3614, TAC requirements and as per specification. Minimum ratings shall be 2 Hrs.Payment terms - a) On receipt of materials at site - 70%; b) On completion of erection & fixing - 30%.	SQM	40.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
9.7	908	Providing and fixing steel windows/ventilator with steel sections as per IS:1038, IS:1361 & IS:7452 latest revision.including all fittings, metal beadings, hold fasts, shop and final painting ,glazing etc. all complete. (Glazing shall be paid separately)				
9.7.1	a	openable type	SQM	405.0		
9.7.2	b	fixed type	SQM	355.0		
9.8	909	Providing and fixing anodised aluminium work of Jindal, Hindalco or other equivalent approved make for door frames, windows, ventilators, partitions, railing etc with extruded standard tubular and other sections including all fittings & fixtures and accessories of approved make conforming to IS733 and IS1285, anodised and electro color dyed to required shade according to IS 1868 (minimum anodic coating of grade AC15), fixed with rawl plugs, expansion fasteners, SS screws or with fixing clips, including necessary filling of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt for bi-metallc protection etc.including preperation of working drawings, aluminium cleat angle, aluminium snap-on-beading for glazing/panelling, stair case tread nosing, with all fittings and fixtures (like tower bolts, handles, door stopper with rubber shoes, 'L' drops, stays, floor springs, hydraulic door closures etc.), CP brass/stainless steel screws, providing and fixing hinges/pivots, and making provision for fixing of fitting wherever required including cost of PVC/neoprene gasket, all complete as per drawing, specification and instructions of engineer in charge (Glazing and panelling shall be paid seperately).Weight of aluminium section only shall be measure.	Kg	675.0		
9.9	910	Providing and fixing of aluminium composite panel(ACP) of following thickness with PVDF or polyester coating for interior partition of approved shade ,color etc all complete as per specification.				
9.9.1	c	5mm	SQM	150.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
9.10	911	Providing and fixing of door closers as per IS 3564 ,of approved make & quality all complete of following type :				
9.10.1	a	Over head hydraulic door closures	Each	50.0		
9.11	912	Providing and fixing pressed steel frames fabricated from 16 gauge M.S sheet mortised, reinforced drilled and tapped for hinges and locks bolts strikes, hold fasts adjustable floor anchors, floor tiles/weather bars ,paintings etc all complete as per specifications.	Kg	1200.0		
9.12	913	Providing and fixing in position rolling shutter of hot rolled double dipped galvanised steel lath section of 18 SWG tested mild steel strips at 75mm rolling centres interlocked together through their entire length and jointed together at the end by end locks mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation including wire springs, top cover, primer & shop coats of approved enamel paint etc, all complete as per IS 6248 and specification of approved make of following types: The bottom lath shall be coupled to a lock plate fabricated from 3mm thick galvanised steel plate and securely rivetted with stiffening angles.(partly coiled and lath/full lath).Payment terms - a) On receipt of materials at site - 70%; b) On completion of erection & fixing - 30%.				
9.12.1	a	Hand Operated	SQM	10.0		
9.12.2	b	Mechanically Operated	SQM	86.0		
9.12.3	c	Electrically operated	SQM	344.0		
9.13	914	Providing and fixing PVC doors(25 thk double skin) of sintex or equivalent make including all fitting & fixtures as per specification, drawing and instructions of engineer in charge.	SQM	45.0		
9.14	915	Providing, fixing and fitting of glazing of first grade class in steel/aluminium/wooden frames, where ever required, cleaning after fixing including hardware, gaskets, clips, beadings etc. all complete.				

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
9.14.1	b	4 mm thick clear float glass	SQM	50.0		
9.14.2	d	6 mm thick wired glass	SQM	647.0		
9.14.3	f	4 mm thick ground glass	SQM	32.0		
9.14.4	g	6 mm thick tinted heat reflecting type float glass	SQM	200.0		
9.14.5	h	6 mm thick clear toughened safety glass	SQM	10.0		
9.14.6	i	Two nos. 6 mm thick clear toughened float glass hermetically sealed and separated by 12 mm thick air gap for thermal insulation (only single elevation area to be measured)	SQM	125.0		
9.15	917	Providing and fixing 12 mm thick BWP particle board , decorative veneer (prelaminated) on both sides, as panels in aluminium framed door shutter, fixed with necessary snap-on-beading etc. all complete (excluding aluminium works).	SQM	100.0		
9.16	918	Providing and fixing steel louvered window with ISMC 100 frame all round including verticals with 18G pressed steel louvers, painting etc. all complete.	SQM	17.0		
9.17	919	Providing and fixing 1 mm thk. MS sheet sliding shutters with frame and diagonal braces of 50X50X6 angle iron, 3 mm MS gusset plates at junction and corners, 25 mm dia pulley, 50X50X6 angle and T-iron guide at the top and bottom respectively including painting etc. all complete.	SQM	15.0		
10.0	1000	BRICKWORK (Brickwork masonry including all labour, material, equipment, transportation, handling, scaffolding etc. at all levels as per specification, drawings and as directed by engineer - in - charge. (Cement will be supplied by BHEL as per SCC free of cost).)				
10.1	1001	Providing brick work in cement mortar 1:6 (1 part cement 6 parts coarse sand) in walls, chambers etc. in thickness varying from 230mm to 460mm at all depths, places and positions below plinth including raking out joints, curing, scaffolding etc. complete excluding plastering and painting.				
10.1.1	c	Using burnt clay bricks of class designation 7.5 of nominal dimension	CUM	611.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
10.2	1002	Providing brick work in cement mortar 1:6 (1 cement 6 coarse sand) in walls, chambers etc. in thickness 230mm at all heights, places and position above plinth including raking out joints, curing, scaffolding etc complete excluding plastering and painting.				
10.2.1	c	Using burnt clay bricks of class designation 7.5 of nominal dimension	CUM	5095.0		
10.3	1003	Providing brick work in cement mortar 1:4 (1 cement 4 coarse sand) in partition walls , chambers etc. in thickness 115mm at all heights, places and position above or below plinth/graded level including providing two nos. 6 mm diameter MS bars at every third layer, raking out joints, curing, scaffolding etc complete excluding plastering and painting as per specification.				
10.3.1	c	Using burnt clay bricks of class designation 7.5 of nominal dimension	SQM	1975.0		
10.3.2	d	Using burnt clay bricks of class designation 5.0 of nominal dimension	SQM	100.0		
10.4	1005	Providing brick soling including spreading of earth, ramming, watering including 25mm thick cushion of sand complete but excluding excavation and disposal of surplus earth (excavation and disposal of surplus earth shall be measured under applicable item.)- Using flat bricks.				
10.4.1	d	Using burnt clay bricks of class designation 5.0 of nominal dimension	SQM	250.0		
10.5	1006	Breaking of existing brick work at all levels including plastering, removing the rubbish up to a distance of 500 m including transportation, loading, unloading etc. all complete as directed by the engineer.	CUM	10.0		
10.6	1007	Providing and encasing of structural steel member with masonry work around flanges, webs etc. and filling the gap between steel and masonry by minimum 12mm thick mortar. Encased member shall be wrapped with chicken wire mesh with 50mm lap etc. complete as per specification. (Chicken wire mesh to paid separately)	CUM	25.0		
10.7	1009	Making openings in existing brick wall or partition wall including making good the broken edges/surface with cement mortar etc. complete.	CUM	50.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
10.8	1011	Filling existing brick wall/ partition wall opening at all level including making good the broken edges/surface with cement mortar, painting, finishing to match with existing finishing, scaffolding/supporting at any level, removal of debris upto a lead of 1 km including loading, unloading, transportation etc. all complete.	SQM	25.0		
10.9	1012	Providing and filling brick bats in soak pits all complete.	CUM	10.0		
11.0	1100	DAMP PROOF COURSE (Damp proof course including all labour, material, equipment, transportation, handling, shuttering, centering, curing etc at any level as per specification, drawings and as directed by engineer - in - charge.)				
11.1	1101	Providing Damp Proof Course 40mm thick 1:1.5:3 concrete (10mm and down graded aggregate) with 2% of approved admixture of water proofing compound all complete. Two layers of hot bitumen coating 85/25 grade as per IS:702 @ 1.7Kg./sqm shall be applied one before & one after the DPC. (Cement will be supplied by BHEL as per SCC free of cost).	SQM	275.0		
12.0	1200	CEMENT MORTAR PLASTER (Cement mortar plaster including making grooves wherever required including all labour, material, scaffolding, curing etc at any level as per specification, drawings and as directed by engineer - in - charge. (Cement will be supplied by BHEL as per SCC free of cost).				
12.1	1201	Providing 18mm thick plaster in two layers outside the building/boundary wall in cement mortar 1:6 on walls, finished to a smooth finish including providing 3mmx3mm size grooves at junctions of two dissimilar materials all complete.	SQM	16982.0		
12.2	1202	Providing 12mm thick plaster inside the building/boundary wall in cement mortar 1:6 on walls finished to a smooth finish as per specification all complete.	SQM	16982.0		
12.3	1204	Providing 6mm thick plaster on ceiling in cement mortar 1:4 finished to a smooth all complete.	SQM	5400.0		
12.4	1205	Providing 12mm thick plaster in walls, drains/culverts with a paste of neat cement @ 1kg/sqm and rubbed smooth with trowel etc. all complete.	SQM	900.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
12.5	1207	Forming groove of uniform size from 12X12 mm upto 20X15 mm in plastered surface as per approved pattern, using wooden battens nailed to the under layer, including removal of wooden battons, repair of the edges of plaster panel and finishing the groove etc. complete as per specification, drawing and the instructions of engineer in charge.	RM	50.0		
12.6	1208	Providing drip coarse on plastered surface at all elevations for all type of work such as chajjas, parapet, projections etc. including scaffolding, finishing etc. complete with all labour, tools and plants as per specification, drawing and instructions of engineer in charge.	RM	100.0		
12.7	1209	Providing and laying encasement to box type steel beams at all levels with lath plaster 50 mm nominal thickness with cement plaster (1:4) over chicken wire mesh including all labour, materials, equipment, handling, transporting, mixing, placing, leveling, curing and cleaning, finishing the exposed surfaces etc including centering and shuttering all complete as per specification, drawing and instructions of engineer in charge (chicken wire mesh to be paid separately)	SQM	2110.0		
12.8	1210	Ruled pointing in masonry in CM 1:3 (1 cement and 3 fine sand) including raking out joints, curing etc. complete.	SQM	5.0		
13.0	1300	FINISHES TO CONCRETE / PLASTERED SURFACES (Finishes, painting to concrete, plastered surfaces including all labour, material, equipment, surface preparation, scaffolding etc. at any level as per specification, drawings and as directed by engineer - in - charge. (PAINTS OF REPUTED BRAND OF REPUTED MANUFACTURER LIKE ICI/BURGER/ASIAN PAINTS OR EQUIVALENT))				
13.1	1301	Two or more coats of white wash/ colour wash as per IS 627 of approved brand and manufacture to give an even shade including a priming coat as per specifications.	SQM	960.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
13.2	1302	Two or more coats of Exterior masonry paint (water or solvent base) of special resins, adhesives and additives mixed with fine, hard stone aggregate and suitable pigment. The paint shall be applied on a coat of primer over dried, prepared plaster surface as manufacturers guidelines. The final finished coating shall be fungus resistant, UV resistant, water repellent, alkali resistant and extremely durable with color fastness as per specification.	SQM	250.0		
13.3	1303	Providing and applying two or more coats of oil bound destemper as per IS 428 of approved brand, shade and manufacture to give smooth, hard, durable & glossy finish over a coat of primer over prepared plaster surface as per manufacturers guideline.	SQM	16252.0		
13.4	1305	Providing and applying two or more coats of acrylic emulsion paint as per IS 5411 of approved brand, shade and manufacture to give smooth, hard, durable & glossy finish over a coat of primer over prepared plaster surface as per manufacturers guideline.	SQM	4725.0		
13.5	1306	Providing and applying 2 or more coats of acid/alkali resistant paint of approved brand and colour to floors, walls and ceiling including preparation of surface to receive paint, providing and applying bitumen primer conforming to IS 158 complete all as per manufacturer's recommendations and as approved by engineer, at all heights above or below grade level, complete as per specifications.	SQM	160.0		
13.6	1307	Two or more coats of fire resistant transparent paint as per IS 162 on all woodwork over french polish as per IS 348 or flat oil paint as per IS 137 of approved grade and manufacture to give an even shade as per specifications.	SQM	10.0		
13.7	1308	Two or more coats of black anti-corrosive bitumastic painting of approved brand and manufacture to give an even shade complete.	SQM	50.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
13.8	1309	Two or more coats of synthetic enamel paint of approved make made from synthetic resins and drying oil with rutile titanium dioxide and other selected pigments to give smooth, hard, durable & glossy finish to all interior and exterior surfaces complete.	SQM	50.0		
13.9	1310	Providing and applying 3 coats of water proof cement paint of approved make and color on exterior surface at all heights including material, labour, scaffolding, curing etc including primer coat complete as per specification.	SQM	16282.0		
13.10	1312	Providing and applying 2 mm thick plaster of paris punning on walls including preparation of surface, staging, etc. to achieve a smooth even surface all complete as per specification and as directed by Engineer.	SQM	16252.0		
13.11	1313	Providing and applying ready made Epoxy Paint over areas other than steel structure with suitable pigments of approved shade as per specification and direction of Engineer. The epoxy paint shall be a two pack material and shall be resistant to water, splash, spillage & acidic environment. The epoxy paint coating shall be of 150micron thickness over epoxy primer.	SQM	400.0		
13.12	1315	Providing and applying two or more coats of Acrylic based weather coat paint of approved brand and manufacture and required shade over one coat of primer after necessary cleaning/ washing, preparing the surface using coir brush/ wire brush, sand paper, including filling of cracks with putty wherever required etc. all complete to give smooth, hard, durable & glossy finish over a coat of primer over prepared plaster surface as per manufacturers guidelines. The final finished coating shall be fungus resistant, UV resistant, water repellent and extremely durable with color fastness as per specification.	SQM	20.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
14.0	1400	FLOORING AND SKIRTING (Flooring and skirting at any level including base layer, labour, material, equipments, transportation, handling, curing, polishing etc. at any level as per specification, drawings and as directed by engineer - in - charge. (Under bed concrete will be paid separately under relevant item). (Cement will be supplied by BHEL as per SCC free of cost).)				
14.1	1401	Providing and laying 50 mm thick heavy duty cement concrete in flooring with metallic hardener pigmented topping 12mm thick uniform graded treated iron particles in flooring. Under layer of 38mm thick cement concrete mix 1:2:4 (1 cement: 2 sand : 4 stone aggregates 12.5mm well graded) and top layer of 12mm thick metallic concrete of mix 1:2 (1 cement hardner mix with approved quality metallic hardening compound :2 stone aggregate 6mm nominal size) by volume including cement slurry, rounding off edges, aluminium strips etc. all complete for following (Quoted item rate shall be inclusive of providing glass joint strips):	SQM	9970.0		
14.2	A1401	Providing and laying 50 mm thick IPS heavy duty cement concrete in flooring. cement concrete mix 1:2:4 (1 cement: 2 sand : 4 stone aggregates 12.5mm well graded) by volume including cement slurry, rounding off edges, aluminium strips etc. all complete for following (Quoted item rate shall be inclusive of providing glass joint strips):	SQM	3525.0		
14.3	1402	Providing and laying 25 mm thick heavy duty cement concrete mix 1:2:4 (1 cement: 2 sand : 4 stone aggregates) flooring with metallic hardener pigmented topping of 10 mm thick uniform graded treated iron particles in skirting and dado complete as per specification.	SQM	25.0		
14.4	1405	Providing and laying 50 mm thick floor finish with 25mm thk Terrazo Tiles including cement mortar bedding of 1:3 (1 cement : 3 sand) with neat cement slurry etc. all complete.	SQM	200.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
14.5	1406	Providing and laying polished Kota stone 18mm to 20mm thk in flooring . Under bed shall average 30mm thk of 1 cement : 2 sand : 4 stone aggregates by volume and brought to proper level. The kota stone slabs/tiles laid over under bed, pressed and tapped down with wooden mallet to the proper level, lifted and pressed again with thick cement slurry spread over the surface with fine joint finished including pigments, curing, grinding, granite polishing etc. all complete.	SQM	3800.0		
14.6	1409	Providing polished Kota stone 14mm to 16mm thk in skirting projecting 6mm from adjacent plaster including cutting brickwall upto the required depth, edging, finishing etc. all complete.	SQM	40.0		
14.7	1410	Marble stone Flooring laid in 50mm overall thickness with 18-20mm thick marble slabs (grade -1) with minium 30mm thick underbed of 1 cement : 2 sand : 4 stone aggregate by volume and brought to proper level.The marbel slabs/tiles laid over underbed with mortar 1:3, pressed and tapped down with wooden mallet to the proper level, lifted and pressed again with thick cement slurry spread over the surface with fine joint finished including pigments, curing, grinding, granite polishing etc. all complete.	SQM	200.0		
14.8	1412	Providing and laying 18-20mm thick polished Granite stone flooring overall thickness 40mm of approved color and texture in flooring with brass/ stainless steel strips. Under bed shall average 30mm thk of 1 cement : 2 sand : 4 stone aggregate by volume and brought to proper level. The granite stone slabs/tiles laid over under bed, pressed and tapped down with wooden mallet to the proper level, lifted and pressed again with thick cement slurry spread over the surface with fine joint finished including pigments, curing, grinding, granite polishing etc. all complete.	SQM	300.0		
14.9	1415	Providing and laying polished Granite stone 14-16mm thk in skirting and dado with 6mm thick projection from adjacent plaster including mortar ,cement slurry ,pigments, curing, grinding,moulding, granite polishing etc. all complete.	SQM	70.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
14.10	1416	Providing and laying vitrified ceramic tiles of polished variety of size 600x600 from reputed / approved manufacturer, complete including underbed of cement mortar 1:3, 40 mm thick, with neat cement slurry etc. all complete for following				
14.10.1	a	7mm thick tiles In flooring	SQM	40.0		
14.10.2	b	10mm thick tiles In flooring	SQM	1450.0		
14.11	1417	Providing and laying vitrified ceramic tiles of matt finish of size 600x600mm from reputed / approved manufacturer including underbed of cement mortar 1:3, 40mm thick, with neat cement slurry etc. all complete for following.				
14.11.1	a	7mm thick tiles In flooring	SQM	20.0		
14.11.2	b	10mm thick tiles In flooring	SQM	350.0		
14.12	1418	Providing and laying 10 mm thk non-skid fully vitrified tiles of make 'MARBONITE' or 'FERRASTONE of BOSS Profile limited' or equivalent in flooring and skirting over 30 mm thick underbed of 1 part cement and 3 parts coarse sand by weight mixed with sufficient water, complete as per specification laid in pattern of following sizes				
14.12.1	b	600X600 mm	SQM	100.0		
14.12.2	Ac	600X300 mm	SQM	25.0		
14.13	1419	Providing and laying granite stone slab of 20mm thickness single piece for wash basin / sink slab /facia of black or approved colour with cutting,making corners,moulding and opening etc. all complete.	SQM	20.0		
14.14	1420	Providing and laying Heavy Duty dust pressed Ceramic Tiles of 7mm thick of reputed manufacturer of approved finish shade and colour including underbed of cement mortar 1:3 with neat cement slurry etc. all complete.				
14.14.1	a	300X300 mm	SQM	175.0		
14.14.2	b	600X600 mm	SQM	375.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
14.15	1422	Providing & fixing Acid / Alkali resistant (Chemical resistant) tiles confirming to IS:4457 in flooring/Dado and shall be laid over bitumastic lining of min 12mm thick (to be laid in layers of 6mm each). The tiles shall be applied with 6mm thick Potassium Silicate bedding mortar as per IS:4441, 4443 & 4832 and including preparation of surface, application of bitumen primer, curing etc. all complete for following thicknesses. The tiles should be abrasion resistant & durable.				
14.15.1	a	20mm thick	SQM	350.0		
14.16	1425	Providing and laying polished Marble slabs (Aranga white or equivalent approved shade/color /design) 20 mm thk in staircase landing/skirting and corridors over minimum 20 mm thick underbed of 1 cement : 2 sand : 4 stone aggregates by volume mixed with sufficient water to form a stiff workable mass. The marble slabs shall be laid over under-bed, pressed and tapped down with wooden mallet to the proper level, lifted and pressed again with thick cement slurry spread over the surface with fine joint finished including moulded marbel nosing, pigments, curing, grinding, making corners, granite polishing etc. complete.	SQM	50.0		
14.16	1427	Providing and fixing glazed ceramic tiles of approved color and design of size 200x300mm / 300x300mm in dado of approved size , projecting 6mm uniformly from adjacent plaster or wall finish. The mix for underbed plaster shall consist of 1part cement and 3 parts sand by weight. fairly moist but firm, tiles shall be pressed over under bed by applying cement slurry including pigments, curing etc all complete for following thicknesses:				
14.16.1	b	7mm thick	SQM	100.0		
14.15	1429	Providing and fixing removable type flooring system consisting of fire resistant particle board of size 600X600X35 mm with 0.05 mm thick aluminium foil lining at bottom and with 2 mm thick anti static PVC topping including proprietary floor supporting system complete as per specification.	SQM	100.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
14.16	1430	Providing and fixing dividing strips in joints of cast in situ floorings at various elevations, finishing, all labour, material etc. complete as per drawing, specification and instructions of engineer in charge.				
14.16.1	a	Glass strips 40 mm wide and minimum 6 mm thick.	RM	15.0		
14.16.2	b	Aluminium strips 40 mm wide and minimum 3 mm thick	RM	5.0		
15.0	1500	ROOFING / SIDE CLADDING (Roofing / side cladding work including all labour, material, equipment, transportation, handling, scaffolding, laps, hooks, washers, corner pieces etc. at any level as per specification, drawings and as directed by engineer - in - charge.)				

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
15.1	A1501	Transport and fixing permanently color coated galvanised MS troughed metal sheet decking plate of approved colour and conforming to class3 of IS 14246 over roof purlins for cast-in-situ roof slab as per relevant IS code and specification. Bare metal thickness of deck plate shall be minimum 0.8mm with minimum trough depth of 44 mm having minimum yield strength of 250 MPa and shall serve as permanent shuttering to the roof slab 100mm thick measured over crest of metal decking & shall have adequate strength to support weight of green concrete and imposed loads of min 150 kg/sqm during construction between purlins as per manufacturer's recommendations/ calculations/ test certificates for approval including fixing of plates to purlins, side lapping, end lapping etc. all complete for below mentioned spans. The sheet shall be permanently coated with silicon modified polyster paint of minimum 20 micron DFT on exposed surface (facing operating floor) and minimum 7 micron on other face over epoxy primer applied over hot dipped galvanising @ 275 gm/sqm including fixing of sheet to purlin with self drilling white zinc plated heat treated carbon steel screws of minimum 5.6 mm dia @ 260mm c/c in the trough and stich screws between two adjacent sheets and sealing with epoxy sealant. Measurement of profile sheeting shall be of the plan area of roof covered by MS trough metal decking.				
15.1.1	a	Span Upto 1800mm	SQM	3589.0		
15.1.2	b	Span Exceeding 1800mm and upto 2500 mm	SQM	3500.0		
15.2	1502	Providing and fixing shear connectors of mild steel studs having 16mm dia and minimum 75 mm projected length above purlin passing through metal decking as per relevant IS codes and specification.	QUINTAL	10.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
15.3	1504	Transport and fixing External sheet of Permanent colour coated metal cladding with high strength tensile steel sheet 0.5mm bare metal thickness having minimum yield strength 350 MPa and zinc-aluminium alloy coating not less than 275 gm/sqm total on both sides including fixing to supports / rails by concealed fixing system, corrosion resistant self tapping / self drilling type fasteners with suitable cap, flashing etc. all complete. The exposed face of the sheet shall be permanently colour coated with Polyfluro Vinyl Coating (PVF2) of minimum dry film thickness (DFT) 20 microns over suitable primer. Inner face of the sheet shall be provided with suitable pre-coating of minimum DFT 7 microns over suitable primer. The permanent colour coated sheet shall meet the general requirements of IS : 14246 and shall conform to class 3 for the durability.	SQM	3550.0		
15.4	1505	Transport and fixing Inner sheet of Permanent colour coated metal cladding with troughed M.S. sheets of 0.6mm bare metal thickness having minimum yield strength 250 MPa and zinc-aluminium alloy coating not less than 275 gm/sqm total on both sides of both sheets including fixing to supports / rails by concealed fixing system, corrosion resistant self tapping / self drilling type fasteners with suitable cap, flashing etc. all complete. The exposed surface of the sheet shall be permanently colour coated with silicon modified polyester paint of minimum dry film thckness (DFT) 20 microns over suitable primer. Other face of the sheet shall be provided with suitable pre-coating of minimum DFT 7 microns over suitable primer. The permanent colour coated sheet shall meet the general requirements of IS : 14246 and shall conform to class 3 for the durability. The sheet shall be fixed directly to side runners and Z spacers as per IS : 277. The sheet shall be fixed at the rate not more than 1500mm center to center to hold the insulation and external sheeting.	SQM	2650.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
15.5	1506	Providing and fixing insulation of resin bonded mineral wool of 50 mm nominal thickness conforming to IS 8183 having a density of 32 kg/cum glass wool or 48 kg/cum for rock wool, for cladding/under deck insulation including application of glue and tying with lacing wire, for glass/rock wool as per manufacturer's recommendations.	SQM	2650.0		
15.6	1508	Providing and installing under deck insulation using minimum 0.05 mm thick aluminium foil on exposed surface followed by 0.56 mm dia and 25 mm mesh GI wire netting, fixed at various elevations with rawl plugs including clips but excluding cost of insulation.	SQM	250.0		
16.0	1600	FALSE CEILING (False ceiling including all labour, material, equipment, transportation, handling, suspension system etc at any level as per specification, drawings and as directed by engineer - in - charge.)				
16.1	1601	Providing and fixing glass fibre reinforced gypsum plaster board (GRG) ceiling (having gypsum core mixed with glass fibre) system consisting of metal supporting grid system forming panels of specified size, suspended from RCC slab/structural steel or catwalkway grid above with 4 mm (minimum) galvanised wires (rods) with special height adjustment clips, including preparation of working drawing, providing openings for AC ducts, return air grills, light fixtures etc (but excluding the cost of catwalkway grid) all complete as per drawings, specification and instructions of the engineer.				
16.1.1	a	12 mm thick GRG board with galvanised light gauge steel load bearing supporting GI frame and finished flat (seamless).	SQM	325.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
16.2	1603	Providing and fixing permanently colour coated aluminium false ceiling of approved colour and Luxalon 84 C or approved equivalent with corrosion resistant aluminium alloy panels of minimum thickness 0.5mm including 50mm thick mineral wool insulation(density 48 kg/cum) conforming to IS:8183 bound in polythene bags on top of panels. Additional hangers and height adjustment clips shall be provided for return air grills, light fixtures, A.C. ducts etc all complete. Suitable M.S. channel grid with minimum MC 75 shall also be provided above the false ceiling level for movement of personnel to facilitate maintenance of lighting fixtures, AC ducts etc. (Materials for structural platform grid made up of MS Channels/ Beams / Angles shall be supplied by BHEL and shall be paid under ST No 2301) Payment terms - a) On receipt of aluminium false ceiling at site - 50%; b) On completion of erection & fixing - 50%.	SQM	1150.0		
16.3	1604	Providing, fixing and laying permanently colour coated aluminium false ceiling of approved colour with stove enamel finish of approved make in LINEAR and SQUARE type with corrosion resistance aluminium alloys panels of minimum thickness 0.5mm including 50mm thick mineral wool insulation (as per IS:8183) bound in polythene bags on top of panels. Additional hangers and height adjustment clips shall be provided for return air grills, light fixtures. A.C. ducts etc. suitable M.S. channel (minimum MC 75) grid 1200 c/c maximum shall also be provided above the false ceiling level for movement of personnel to facilitate maintenance of lighting fixtures, AC ducts etc.The work to be complete as per specifications, drawings and direction of engineer.(Materials for structural platform grid for movement made up of MS Channels shall be supplied by BHEL and shall be paid under ST No 2301) Payment terms - a) On receipt of aluminium false ceiling at site - 50%; b) On completion of erection & fixing - 50%.	SQM	100.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
16.4	1606	Providing and Fixing 12mm thick Gypsum board plain/perforated false ceiling tiles(600x600mm) of India Gypsum or equivalent make in plan or elevation with aluminium grid, metal suspension system, anchor fastener adjustable hangers etc. including two or more coats of acrylic emulsion paint of approved colour to give an even shade with smooth finish all complete.as per architectural design and detail.metal suspension system as per ASTM C-635 shall be hot dipped M.S.galvanized (grade 180 as per is :277) nominal size of T-section shall be 24 x 38 mm or 24 x 25 mm cross runners. 24mm wide exposed flange surface shall be permanently color coated.suspension system shall be as per manufacturer's specification supported over movement platform.The work to be complete as per specifications, drawings and direction of engineer.(Materials for structural platform grid for movement made up of MS Channels/ Beams / Angles shall be supplied by BHEL and shall be paid under ST No 2301)	SQM	600.0		
17.0	1700	RAIN WATER DOWN TAKE PIPES (Rain water down take pipes including all labour, material, transportation, 2 coats of approved paint over one primary coat, fixtures, accessories etc at any level as per specification, drawings and as directed by engineer - in charge.)				
17.1	1702	Providing and fixing galvanised MS down take pipes of 100 mm dia- Medium quality as per IS:1239(part-I) / IS:3589 all complete.	RM	50.0		
17.2	1703	Providing and fixing HCl down take pipes of 150mm dia with water tight lead joint etc. all complete.	RM	160.0		
17.3	1704	Providing and fixing galvanised MS down take pipes of 150 mm dia- Medium quality as per IS:1239(part-I) all complete.	RM	50.0		
17.4	1706	Providing and fixing UPVC down take pipes of 160mm diameter- Class 3 as per IS:4985 all complete.	RM	200.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
17.5	1707	Transport and fixing GI down take pipes conforming to IS:1239 /IS:3589 of medium duty all complete for following diameters.				
17.5.1	b	150 mm Dia	RM	3635.0		
18.0	1800	MISCELLANEOUS WORKS (Miscellaneous works including all labour, material, equipment etc. at any level unless otherwise specified as per specification, drawings and as directed by engineer - in - charge.)				
18.1	1801	Providing and Filling in trenches, plinths, area paving and other underground structures with graded stone aggregate of size range 63 mm to 45 mm in layers not exceeding 230 mm in thickness including breaking of stone boulders to required sizes, filling the interstices with selected sand and compacting to 85 % of original volume of stone stack for all lifts etc. all complete. Payment shall be made for the measurement of the volume of the compacted fill.	CUM	7031.0		
18.2	1805	Providing 50mm thick premix carpet surfacing laid to slope in two layers 30mm and 20mm respectively with 12mm downgraded stone chips mixed with 80/100 grade bitumen @ 52 Kg/Cu.M including compaction etc. all complete.	SQM	400.0		
18.3	1806	Providing 50mm thick anti corrosive layer laid to required slope consisting of clean & well graded coarse sand mixed with A90 grade bitumen for softening point upto 45 degree Celcius or A65 grade bitumen for softening point above 45 degree celcius as per IS: 73 or its equivalent quality 8 to 10% by volume and rolled or compacted all complete.	SQM	400.0		
18.4	1810	Providing, laying and fixing rails and guide rails in concrete for transformer, rail track including cutting of rails, joining of rails, anchoring lugs etc all complete.	MT	27.0		
18.5	1812	Laying of earthing mats/rods including risers, transportation from yard stores, loading, unloading, cutting to length, welding, protective painting of joints etc. all complete. (Excavation & Back filling shall be paid separately under respective item of earth work. Earthing rods shall be supplied by BHEL free of cost).	MT	30.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
18.6	1812B	Construction of below ground earthing system test pits as per drawing / sketches including concreting, reinforcement, formwork, providing & fixing GI strip etc as per drawing and specification (excavation & backfilling only will be paid under applicable BOQ items).	NO	20.0		
18.7	1812C	Construction of below ground earthing system test links as per drawing/ sketches including concreting, reinforcement, formwork, providing & fixing GI strip etc as per drawing & specification (excavation & backfilling only will be paid under applicable BOQ items).	NO	10.0		
18.8	1812D	Construction of below ground earthing system earth electrodes as per drawing and specification. (Excavation and backfilling only will be paid under applicable BOQ items.)	NO	30.0		
18.9	1812E	Construction of below ground earthing system - Earth connection and riser pig tails as per drawing and specification. (Excavation and backfilling only will be paid under applicable BOQ items.)	NO	50.0		
18.10	1813	Providing Earthing pit as per drawing with charcoal & salt, GI pipes, GI earth electrodes, GI wire, GI strips, brick chamber with covers including associated earthwork etc. all complete.	EACH	25.0		
18.11	1817	Providing and fixing HDPE pipes in concrete/ brick work of following sizes including cutting, fixing and levelling in position etc. all complete.				
18.11.1	a	Upto 75 mm dia	RM	100.0		
18.11.2	b	100 mm dia	RM	100.0		
18.11.3	c	150 mm dia	RM	25.0		
18.11.4	d	200 mm dia	RM	25.0		
18.12	1822A	Cutting of groove of 10mm X 40mm size with groove cutting machine in concrete paving all complete.	RM	700.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
18.13	1822B	Cutting of existing concrete/ RCC work inside control room/ pump house or anywhere inside boundary using power tools of (DD2E of HILTI/ BOSCH make) with low noise and dust including cutting reinforcements, removing the rubbish within a lead of 1 km, including making good the broken edges/ surface with cement mortar, painting, finishing to match with existing finishing, scaffolding/ supporting at any level, all complete and as directed by Engineer (measurements shall be taken as per cutting surface area).	SQM	20.0		
18.14	A1834	Design, supply, fabrication, erection of stoplog/sluice/screw gates gates in Pumps Houses with embedments required, lifting beams, special tools & plants, spare parts for three years, machining, casting, all materials such as structural steel, cast steel, stainless steel, brass used for seals, rubber seals, gears, ball and roller bearing, branch bushings, greasing, bolts, nuts, lugs, threaded fastners etc., cleaning, sand blasting, applying Two Coates of ZINC RICH Premier (EPILUX 4 or equivalent) of 30 Micron each followed by Two Coates of ZINC RICH Premier Intermediate Paint (MIO) (60 Micron Each) followed by three Coates of coal tar epoxy 30 Microns each and dipping in black bitumen as per B.S. 3416, erection along with a second stage concreting to true plumb and levels, submission of drawings / fabrication drawings for engineers approval etc all complete. The leakage through rubber seal shall not be more than 5 lit/min/metre length of seal under maximum head.(only weight of structural steel including embedments shall be considered for payment purpose) (SS component shall be measured separately for payment) Payment terms - a) Design & engg - 4%; b) Materials receipt at site- 60%; c) On completion of ern & fixing - 26%; d) On testing - 10%.	MT	1.0		
18.15	A1836	Providing and laying cinder filling in the toilets complete as directed by engineer in charge.	CUM	30.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
18.16	A1837	Providing and laying foam concrete blocks in the toilets/sunken slab etc. complete as directed by engineer in charge.	CUM	30.0		
18.17	1838	Sprinkling of water by water tanker fitted with perforated GI Pipe (portable tanker minimum 3000 litre capacity) for roads and miscellaneous area within plant boundary, for dust suppression and reduction of suspended material at site for day to day work, as directed by BHEL Site Engineer (water for this purpose shall be provided by BHEL free of cost and utilisation of machine will be in terms of Tank-hour put in actual use for water sprinkling.	TANK-HR	2916.0		
19.0	2000	FENCING AND GATES(Fencing and gates including all labour, material, equipment etc at any level as per specification, drawings and as directed by engineer - in - charge.)				
19.1	2002	Supplying and erecting in position 2.4 m high galvanised chain linked fencing conforming to IS 2761 of 10G hot dip galvanised steel wires woven in the form of zig-zag mesh giving an opening size of 50 mm square. GI barbed wire fencing of height of 600 mm confirming to IS 298 at top of chain link fencing shall be provided with 4 strands of barbed wire hot dip galvanised wire of 12G comprising of 2 ply of wires with barbs of 16G spaced at 100mm. Cost to include for GI hook bolts, rings & washers, hot dip galvanised tension wires, 25X6 mm GI flat stretcher bar at end posts, accessories etc. all complete. (Structural post shall be separately under ST No. 2007)	RM	50.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
19.2	2003	Supplying and erecting in position 2.4 m high PVC coated galvanised chain linked fencing of minimum 8 gauge (including PVC coating) of mesh size 75mm x 75mm. The diameter of the hot dip galvanised steel wire for chain link fencing excluding PVC coating shall not be less than 12 gauge. Concertina of height of 600 mm at top of chain link fencing shall be provided with all accessories. Concertinal shall be from tensile serrated galvanised wire (HTSW) made with wire diameter of 2.5 mm which will be stretched to 6m and attached on two strands of galvanised HTSSW (high tensile spring steel wire) of 2.5mm dia by means of clips at 1m interval. These two HTSSW strands will be attached to the fence posts/ angles with 12 mm security fasteners. Cost to include for GI hook bolts, rings & washers, hot dip galvanised tension wires, 25X6 mm GI flat stretcher bar at end posts etc. all complete. (Structural post shall be separately under ST No. 2007)Payment terms - a) On receipt of chain link fencing at site - 50%; b) On completion of erection & fixing - 50%.	RM	250.0		
19.3	2009	Supply, fabrication and installing in position and testing galvanised MS Gates out of channels, joists, angles, flats, plates, pipes, welded steel wire mesh & sheets including stiffeners, bracings, fabricated hinges, MS Aldrops with locking arrangement, tempered steel pivot, guide track of MS Tee, bronze aluminium ball bearing arrangements, castor wheels, paintings etc. all complete.	MT	15.0		
20.0	2100	WATER SUPPLY (Water supply work including men, material, equipment etc. at any level as per specification, drawings and as directed by engineer - in - charge.)				
20.1	2101	Providing and fixing in position tested heavy duty type chromium plated (CP) brass long neck bib cocks including sockets, union, nuts etc all complete - 15mm nominal bore.	EACH	20.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
20.2	2102	Providing and fixing in position heavy duty brass stop cock of approved quality including all specials etc all complete - 15mm nominal bore.	EACH	11.0		
20.3	2103	Providing and fixing in position heavy duty brass full way valve with wheel of approved quality including all specials etc all complete for following sizes:		0.0		
20.3.1	a	25mm nominal bore.	EACH	16.0		
20.4	2104	Providing and fixing GI pipes class B medium class conforming to IS:1239 pipes shall be concealed and painted with anticorrosive paint, complete for internal works with GI sockets, unions, elbows, tees, nipples etc and clamps including cutting and making good the walls etc all complete for following sizes:		0.0		
20.4.1	a	15 mm nominal bore.	RM	180.0		
20.4.2	b	20 mm nominal bore.	RM	350.0		
20.4.3	c	25 mm nominal bore.	RM	150.0		
20.5	2105	Providing and fixing GI pipes class B complete for external work with GI sockets, unions, elbows, tees, nipples etc including trenching & refilling, anti-corrosive paint etc all complete for following sizes:		0.0		
20.5.1	a	15 mm nominal bore.	RM	230.0		
20.5.2	b	20 mm nominal bore.	RM	225.0		
20.5.3	c	25 mm nominal bore.	RM	165.0		
20.5.4	d	50 mm nominal bore.	RM	125.0		
20.6	2106	Providing and fixing 610mmx453mmx6mm thk mirror from reputed mirror manufacturer. Mirror shall be mounted with glass adjustable revolving CP brackets with CP screws etc all complete.	EACH	13.0		
20.7	2107	Providing and fixing 610mmx127mmx6mm thk clear glass with C.P Guard rails and mounted on C.P. brackets etc all complete.	EACH	16.0		
20.8	2108	Providing and fixing 25 mm diameter stainless steel towel rails (600mm X 25mm) all complete.	EACH	16.0		
20.9	2109	Providing and fixing 20mm dia chromium plated M.S. pipes wall mounted towel rod with C.P. Brackets etc all complete.	EACH	7.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
20.10	2110	Providing and fixing C.P. soap holder mounted with C.P. screws etc all complete.	EACH	16.0		
20.11	2111	Providing and fixing stainless steel / C.P. liquid soap dispenser. Dispenser shall be round and easily revolving with removable threaded nozzle and mounted on C.P. brackets etc all complete.	EACH	16.0		
20.12	2112	Providing and fixing glazed vitreous wall mounted paper holder with suitable cover cum cutter fitted with CP screws etc. sll complete.	EACH	30.0		
20.13	2113	Providing and fixing chromium plated brass shower rose with 15 or 20 mm inlet all complete.	EACH	1.0		
20.14	2114	Providing & fixing in position P.V.C. water tank of Syntex or approved equivalent including making all necessary inlet & outlet pipes, fixture, ball cocks, valves etc all complete for following capacities. GI pipes shall be paid separately under ST No. 2105.		0.0		
20.14.1	a	1000 litres capacity	EACH	6.0		
20.14.2	b	2000 litres capacity	EACH	1.0		
20.14.3	Ad	500 litres capacity	EACH	6.0		
20.15	2115	Providing and fixing approved stainless steel sink with integrated drainboard as per IS:13983 of size 915x460x178mm with CI brackets, stainless steel chain with rubber plug 40mm, cp brass waste trap with necessary union complete including painting the fittings, cutting and making good the wall where required etc. all complete.	EACH	4.0		
21.0	2200	SANITARY WORKS (Sanitary work including all labour, material, equipment etc. at any level as per specification, drawings and as directed by engineer - in - charge.)				

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
21.1	2201	Supply and fixing glazed vitreous china Wash Basin conforming to IS:2556 part 4 of oval shape with R.S. or C.I. brackets painted white, 15mm chromium plated brass hot & cold faucets with nylon washers, chromium plated brass chain with rubber plug, 32mm chromium plated brass bottle trap and waste of standard pattern, 32mm dia chromium plated brass trap unions, plastic connection pipe with chromium plated nuts, fittings, cutting and making good the walls where required etc all complete.				
21.1.1	a	White	EACH	18.0		
21.1.2	b	Colored	EACH	2.0		
21.2	2202	Providing and fixing approved vitreous china laboratory sink of size 600x400x200mm conforming to IS:2556 (part-5) with R.S. or C.I. brackets, chromium plated brass chain with rubber plug 40mm, CP brass waste and 40mm CP brass trap with necessary union complete including painting the fittings, cutting and making good the wall where required etc. all complete.	EACH	1.0		
21.3	2203	Providing and fixing stainless steel kitchen sink of size 610x510x200mm conforming to IS: 13983 including all fittings etc. all complete.	EACH	8.0		
21.4	2204	Providing and fixing colour glazed vitreous china European type water closet conforming to IS:2556 with siphon, open front solid plastic seat and plastic cover, low level 12.5 litre PVC flushing cistern (same colour as WC) with valveless fittings, necessary C.P connections etc all complete.		0.0		
21.4.1	a	Floor mounted	EACH	11.0		
21.4.2	b	Wall mounted	EACH	3.0		
21.5	2205	Providing and fixing colour glazed vitreous indian type Orissa pattern (580x440mm) water closet conforming to IS:2556 part 3 with all fittings including foot rests, low level 12.5 litre PVC flushing cistern with valveless fittings, necessary C.P connections etc all complete.	EACH	7.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
21.6	2206	Providing and fixing white flat back glazed vitreous china urinals of size 440x265x355 mm with photo voltaic control flushing system as per IS:2556 (part 6, section 1) with flush pipes, lead pipes, gratings, traps and necessary C.P. fittings etc. all complete.	EACH	14.0		
21.7	2207	Supply, laying and jointing UPVC pipes of class 3 as per IS:4985 including bends, branches and all other necessary fittings, M.S holder bats/clamps, cutting and making good the walls and floors, jointing, testing etc all complete for following.				
21.7.1	a	75mm dia pipes	RM	475.0		
21.7.2	b	110mm dia pipes	RM	675.0		
21.7.3	c	160mm dia pipes	RM	1190.0		
21.7.4	d	200mm dia pipes	RM	1050.0		
21.8	2208	Providing, laying light duty non pressure NP3 class RCC pipes with collars jointed with stiff mixture of cement mortar 1:2 including testing of joints etc all complete for following. Payment terms - a) On receipt of material at site - 50%; b) On completion of erection & fixing - 50%. Excavation, backfilling shall be paid as per BOQ items.				
21.8.1	a	200mm dia	RM	75.0		
21.8.2	b	300mm dia	RM	150.0		
21.8.3	c	450mm dia	RM	75.0		
21.8.4	b	600mm dia	RM	35.0		
21.8.5	e	900mm dia	RM	25.0		
21.9	2209	Providing, laying light duty non pressure NP2 class RCC pipes with collars jointed with stiff mixture of cement mortar 1:2 including testing of joints etc complete for following. Payment terms - a) On receipt of material at site - 50%; b) On completion of erection & fixing - 50%. Excavation, backfilling shall be paid as per BOQ items.				
21.9.1	a	150mm dia	RM	300.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
21.9.2	b	250mm dia	RM	450.0		
21.9.3	c	300mm dia	RM	785.0		
21.9.4	d	500mm dia	RM	725.0		
21.10	2211	Providing and fixing C.I Manhole heavy duty cover of size 600mmx450mm including frame from reputed manufacture etc. all complete.	EACH	6.0		
21.11	2212	Providing and fixing circular heavy duty C.I. manhole cover of 600 mm dia with frame etc. all complete.	EACH	4.0		
21.12	2213	Providing and fixing square mouth S.W Gully trap grade 'A' complete with CI grating, brick masonry chamber and water tight CI cover with 300x300mm (inside). The weight of cover to be not less than 4.53 Kg and frame to be not less than 2.72 Kg etc all complete for following sizes:				
21.12.1	a	100x100mm P or S Type.	EACH	14.0		
21.12.2	b	150x100mm P or S Type.	EACH	1.0		
21.12.3	c	150x150mm P or S Type.	EACH	6.0		
21.13	2214	Providing and fixing square mouth S.W Gully trap grade 'A' complete with CI grating, brick masonry chamber and water tight CI cover with 300x300mm (inside). The weight of cover to be not less than 4.53 Kg and frame to be not less than 2.72 Kg etc all complete for following sizes:				
21.13.1	a	100x100mm P or S Type.	EACH	10.0		
21.13.2	b	150x100mm P or S Type.	EACH	10.0		
21.13.3	c	150x150mm P or S Type.	EACH	8.0		
21.14	2215	Providing and fixing C.I. floor traps with C.P jalli all complete.	EACH	11.0		
21.15	2216	Providing and fixing heavy duty UPVC floor traps with C.P jalli all complete.	EACH	11.0		
21.16	2217	Providing and installing approved brand single tap water cooler of 80 L cooling capacity all complete.	EACH	11.0		
21.17	2218	Providing and installing approved brand single tap water cooler of 150 L cooling capacity all complete.	EACH	1.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
21.18	2219	Providing and fixing white vitreous urinal partitions of size 675x325x85mm all complete.	EACH	13.0		
21.19	A2221	Providing, laying sand CI pipes with lead joints conforming to IS 1729 complete for following.				
21.19.1	a	50mm dia	RM	20.0		
21.19.2	b	75mm dia	RM	20.0		
21.19.3	c	100mm dia	RM	20.0		
21.19.4	d	150mm dia	RM	10.0		
21.20	A2222	Providing, laying spun CI pipes with conforming to IS 1536 complete for following.				
21.20.1	a	75mm dia	RM	20.0		
21.20.2	b	100mm dia	RM	20.0		
21.20.3	c	150mm dia	RM	20.0		
21.20.4	d	200mm dia	RM	20.0		
21.20.5	e	250mm dia	RM	20.0		
21.20.6	f	300mm dia	RM	15.0		
22.0	2300	STRUCTURAL STEEL (Structural steel works including all labour, material, equipments, transportation, handling etc. at any level as per specification, drawings and as directed by engineer - in - charge.)				

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
22.1	A2301	Transport, fabrication and erection of structural steel with mild steel rolled section / built up section / combination of both conforming to IS:2062, pipes conforming to IS:1161/ IS:1239, chequered plate conforming to IS: 3052, mild steel rounds, monorails, stays, ladders etc. in columns, beams, gantry girders, bunkers, silos, hoppers, roof trusses, portals, laced purlins, space frames, hangers, struts, monorails, galleries, stiffeners, wall beams, sheeting runners, brackets, stub columns, bracings, cleats, trestles, base plates, splice plates, chequered plate flooring, decking and seal plates, steel frame grid over false ceiling, walkway platforms, ladders, stairs, stringers, treads, landings, hand-rails etc including 2 coats of redoxide zinc-chromate primer (one coat at shop and one coat after erection) (DFT not less than 25 Microns for each coat) , connection design & preparation of fabrication drgs, collection of steel from stores, fabrication, straightening, cutting, bending, rolling, grinding, machining, drilling, welding, electrodes and other consumables, alignment, erection bolts & nuts (weight of erection bolts, nuts and welds not payable),				

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
		assembly, edge preparation, preheating (min preheat and interpass temperature of 200 C for welding over 20 mm and upto 40 mm & 660 C for welding over 40 mm and upto 63 mm & 1100 C for thickness over 63 mm & use of low hydrogen/ radiogenic electrodes), post heating, testing of welders, inspection of welds, visual inspection, non destructive and special testing, rectification and correction of defective welding works, production test plate, inspection and testing, erection scheme, protection against damage in transit, stability of structures, installation of temporary structures, setting column bases, surface preparation by means of manual or mechanical power tools as per IS:1477 part 1, touch-up painting, rectification, dismantling and removal of all temporary structures (weight of temporary structures not payable), return of surplus / waste steel materials to store etc all complete. Including appointment of a separate agency, approved by BHEL, for review and approval of fabrication drgs, in consultation with BHEL. (MS PLATE, ISMB, ANGLE, CHANNEL, STAINLESS STEEL PLATE, CHOD PLATE SHALL BE SUPPLIED BY BHEL FREE OF COST AS PER TCC). Payments terms - a). Fabrication - 65%; b) Erection - 25%; c) Alignment - 10%.	MT	10138.0		
22.2	A2302	Extra over ST NO. A2301 for blast cleaning of steel structures to near white metal surface(Sa 2 1/2) before applying the primer all complete.	MT	10138.0		
22.3	2304	Providing and applying two coats of synthetic enamel paint with minimum 50 micron total dry film thickness (DFT) of approved make and shade to achieve an even shade over steel sections already having primer coats and keeping overall DFT with primer not less than 110 microns including protection and cleaning, scaffolding etc. all complete.	MT	10138.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
22.5	2307	Transport, erection and alignment of factory made electroforged galvanised grating units with mild steel (having minimum galvanisation of 610 g/sqm) conforming to IS:2062 in flooring, platforms, drain and trench covers, walk-ways, passages, staircases with edge binding strips and anti-skid nosing in treads etc. including fixing clamps, fittings, fixtures, all taxes, duties, packing, grinding, drilling, welding, edge preparation, etc. all complete.	MT	30.0		
22.6	2308	Transport, erection and alignment of factory made galvanised welded grating units with mild steel conforming to IS:2062 in flooring, platforms, drain and trench covers, walk-ways, passages, staircases with edge binding strips and anti-skid nosing in treads etc. fixing clamps, fittings, fixtures, all taxes, duties, packing, grinding, drilling, welding, edge preparation, etc. all complete.	MT	15.0		
22.7	2310	Transport, erection and fixing in position of permanent mild steel bolts (class 4.6 as per IS : 1367 and grade `C' as per IS: 1363) and nuts, washers etc. up to and inclusive of 39 mm diameter and upto 300mm long for structural steel work etc all complete.	Quintal	150.0		
22.8	2311	Transport, erection and fixing in positing of high strength structural bolts (of property class 8.8 and product grade `C' as per IS: 1367) and conforming to IS: 3757 and high strength structural hardened and tempered nuts (of property class `8' as per IS:1367) conforming to IS:6623 with hardened and tempered washers as per IS:6649 etc. up to and inclusive of 39 mm diameter and upto 300 mm long for structural steel work etc all complete.	Quintal	375.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
22.9	2312	Dismantling of steel structure , lowering of material and carriage of the dismantled material up to field fabrication shop / projects storage including temporary dismantling, cutting, re-welding, supporting, and restoring to correct position all temporarily dismantled members, re-alignment of all adjacent connected members to their correct positions (weight of such adjacent members and temporarily dismantled members not payable), scaffolding, staging, tools & tackles, gas cutting, welding, consumables etc all complete. (MS PLATE, ISMB, ANGLE, CHANNEL, STAINLESS STEEL PLATE, CHQD PLATE SHALL BE SUPPLIED BY BHEL FREE OF COST AS PER TCC).	MT	25.0		
22.10	2313	Addition to, alterations in and/or modification of " Erection Marks " including cutting of parts, gauging of welds, cutting, grinding, fabrication, welding, drilling holes, straightening, removal of bends, raising to the required level, painting, transportation, return of unutilised steel pieces to the project store, temporarily dismantling, cutting, re-welding, supporting and restoring to correct position of all the temporarily dismantled members, realignment of adjacent connected members (weight of such temporarily dismantled and adjacent members not payable) etc all complete for the following: (MS PLATE, ISMB, ANGLE, CHANNEL, STAINLESS STEEL PLATE, CHQD PLATE SHALL BE SUPPLIED BY BHEL FREE OF COST AS PER TCC).				
22.10.1	a	In erected position	MT	25.0		
22.10.2	b	In fabrication yard	MT	25.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
22.11	2314	Re-erection of dismantled fabricated structural steel members including carriage of modified "Erection Marks" from the field fabrication shop to erection site, lifting to required position, aligning in position, tack welding, final welding and touch up painting including temporary dismantling and re-erection of temporarily dismantled members, cutting, rewelding, supporting and restoring to the correct position of all temporarily dismantled members, re-alignment of adjacent connected members(weight of such temporarily dismantled members and adjacent members not payable), scaffolding, staging, tools & tackles, gas cutting, welding, consumables etc all complete.	MT	25.0		
22.12	2316	Transport, fabrication and erection of minimum 4 mm thick stainless steel liner of grade AISI-304 ; Finish Grade 2B (Cold rolled, Annealed & Pickled and Skin passed) on M.S. plate for inside surfaces of hopper & mouth of hopper of bunkers including fixing with stainless steel studs, bolting (including countersunk), welding with electrode classification E308L for welding of stainless steel to stainless steel and E309 for stainless steel to mild steel etc. all complete.BHEL WILL SUPPLY STAINLESS STEEL PLATE FREE OF COST AS PER SCC	MT	6.0		
22.13	2317	Providing and fixing in position PTFE type sliding bearings of reputed manufacturer, individual bearing suitable for required vertical loads as per the construction drawings and for maximum displacement of ± 50 mm including all taxes, duties, transportation, installation, drilling, bolting, erecting, aligning etc all complete for following vertical loads.				
22.13.1	a	20 Tons	EACH	15.0		
22.13.2	b	25 Tons	EACH	20.0		
22.13.3	c	40 Tons	EACH	3.0		
22.13.4	d	50 Tons	EACH	3.0		
22.13.5	e	60 Tons	EACH	3.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
22.14	2319	Supply, fabrication and fixing of stainless steel (AISI-316 quality) pipe hand railing of 32 mm/40 mm dia including transportation, loading/unloading etc. all complete. Payments terms- a)on receipt of materials at site- 65%; b) Erection & fixing- 35%.	MT	1.0		
22.15	2320	Transport, fabrication and fixing painting of GI pipe hand railing (900 mm high) of 32 mm/40 mm dia (Medium Grade) including all labour, painting etc. all complete.	MT	36.0		
22.16	2321	Conducting radiography test on welds wherever specified including equipments, measuring devices, gauges, test report etc. all complete as per written instruction of BHEL engineer. (over and above the work already specified in FQP).	RM	100.0		
22.17	2322	Conducting ultasonic test on welds wherever specified including equipments, measuring devices, gauges, test report etc. all complete as per written instruction of BHEL engineer. (over and above the work already specified in FQP).	RM	100.0		
22.18	2323	Conducting ultasonic test on steel plates as per ASTM-A435 or equivalent wherever specified including equipments, measuring devices, gauges, test report etc. all complete as per written instruction of BHEL engineer. (over and above the work already specified in FQP).	SQM	50.0		
22.19	2324	Conducting magnetic particle test on welds wherever specified including equipments, measuring devices, gauges, test report etc. all complete as per written instruction of BHEL engineer. (over and above the work already specified in FQP).	RM	100.0		
22.20	2325	Conducting dye penetration test on welds wherever specified by the engineer including provision of necessary equipments, measuring devices, gauges etc. all complete as per written instruction of BHEL engineer. (over and above the work already specified in FQP).	RM	60.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
22.21	2326	Supply, fixing lightning arrester and air terminal over roof of power house building, pump house and other dtructures including all materials, labour, electrodes etc complete (all materials to be supplied by the vendor).	NO	20.0		
23.0	2400	ROAD WORKS(Providing Road Work including necessary material, labour, machinery, transportation etc as per specification, drawing, relevant IRC & IS codes and as directed by the Engineer-in-charge for the following.)				
23.1	2401A	Preparation of sub grade by excavating earth to required depth in all types of soil including ash, dressing to camber and consolidating the base including making good the undulation etc and disposal of surplus earth within a lead upto 1km etc all complete as per specification.	CUM	15613.0		
23.2	2402	Supplying and filling with selected good earth of approved quality in layers not exceeding 300 mm loose thickness using borrowed soil (borrowed soil to be arranged by the bidder) and compacted so as to achieve at least 95 % maximum dry density as per IS-2720 (Part-VII) including royalty/seignorage fee (if any), sorting, spreading, breaking clods, watering, ramming/compaction by manual/mechanical means, dressing, finishing to required lines, grades and slopes, tesing etc all complete.	CUM	14502.0		
23.3	2403	Providing, stacking & laying granular morrum for shoulder including watering, compaction with road roller to required camber etc all complete.	CUM	565.0		
23.4	2404	Providing & laying water bound macadam sub base course in layers of required thickness with crushed stone aggregates 90 to 40 mm down size, stone screening & blinding material including screening, sorting, spreading to template & consolidation with road roller including carriage, spreading & consolidation of blinding material moorum etc all complete.	CUM	1414.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
23.5	2405	Providing & laying water bound macadam base course in layers of required thickness with stone aggregate 63mm to 40mm size, stone screening and blinding material including screening sorting, spreading to template and consolidation with road roller including carriage, spreading and consolidation of blinding material moorum etc all complete.	CUM	464.0		
23.6	2406	Laying water bound macadam base course with stone aggregate 50mm to 20mm size stone screening & binding material including screening, sorting, spreading to template & consolidation with road roller including carriage spreading & consolidation of blinding material moorum etc all complete.	CUM	857.0		
23.7	2408	Providing & applying tack coat of low viscosity liquid bitumen of grade 80/100 conforming to IS 73, 217 or 454 as applicable @ 6 kg/ 10 sqm for bituminous surface including cleaning with compressed air etc all complete.	SQM	5715.0		
23.8	2409	Providing, mixing & laying of dense bituminous macadam (DBM) course of specified thickness using bitumen of grade 60/70 conforming to IS 73, aggregates and binder material including hot mixing, hot laying, rolling etc all complete for the following.				
23.8.1	2409.a	55mm compacted thickness	SQM	5715.0		
23.9	2410A	Providing, mixing & laying 25 mm thick semi dense bituminous concrete(SDBC) in a single course composed of suitable small size aggregate premixed with bituminous binder using medium setting grade bitumen on a prepared base including mixing, applying, rolling etc all complete.	SQM	5715.0		
23.10	2411	Providing and applying liquid seal coat comprising of an application of a layer of bituminous binder using medium setting grade bitumen at the rate of 9.8kg/10sqm followed by a cover of stone chips at the rate of 0.09 cum/10sqm including rolling etc all complete.	SQM	5715.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
23.11	2412	Supplying and laying 400mmx150mmx350mm deep precast concrete kerb stone of grade M-20 with 20 mm nominal size stone aggregate and of shape as per detailed drawing including fixing with cement mortar (1:2) in 13mm thick joints, finishing of joints with neat cement paste, making drainage opening where required etc all complete. Cement will be supplied by BHEL free of cost as per TCC.	RM	1790.0		
23.12	2413	Providing & laying edge protection on both edges of black topping using brick on edge (bricks with crushing strength of 75 kg/cm ²) with full brick width (230 mm) etc all complete.	RM	10.0		
23.13	2414	Supply and laying 150mm dia R.C.C NP-2 type Hume pipe in raised shoulders as rain water drains as per detailed drawing including fixing with cement mortar (1:2) in 13mm thick joints, finishing of joints with neat cement paste etc all complete.	RM	258.0		
23.14	2417	Providing and laying of plain cement concrete of grade M15 using 40 mm graded stone aggregate including providing and fixing formwork, compaction etc. all complete. Cement will be supplied by BHEL free of cost as per TCC.	CUM	30.0		
23.16	2419	Providing & laying dry lean cement concrete of grade M15 with 20 mm nominal size graded stone aggregate over a prepared sub-grade including compaction, finishing, curing etc all complete. Cement will be supplied by BHEL free of cost as per TCC.	CUM	5.0		
23.17		REINFORCEMENT				
23.17.1	2420	Providing and fixing in position MS dowel bar reinforcement including surface painted with bitumen and greasing , dowel end caps with cotton fills etc all complete as per specification, drawing and as directed by Engineer. Contractor to supply reinforcement from SAIL /TISCO / RINL or as approved by BHEL/CUSTOMER).	MT	3.0		
23.18		MISCELLANEOUS				

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
23.18.1	2423	Providing & installation of bitumen impregnated fibre board of specified thickness confirming to IS 1838 as joint filler including nailing, coating of both faces with coal tar pitch/bitumin etc. all complete as per specification, drawing and as directed by engineer.	RM	40.0		
23.18.2	2424	Providing and filling in position hot applied bitumen sealing compound (Grade A) of specified thick confirming to IS 1834 including cleaning, mixing, heating, pouring/injecting sealing compound in gaps in joints, sealant primer etc all complete as per specification, drawing and as directed by Engineer.	RM	40.0		
23.18.3	2425	Providing and laying debonding strip/tape of specified thickness before applying sealant including cleaning etc all complete as per specification, drawing and as directed by Engineer.	RM	15.0		
23.18.4	2426	Providing & laying 75 mm thick precast interlocking concrete pavers of approved colour and pattern as per specification and recommendation of manufacturer.	SQM	150.0		
23.18.5	2427	Providing and laying 50mm thick sand layer below concrete pavers including compaction etc all complete as per specification, drawing and as directed by Engineer.	SQM	525.0		
24.0	2500	PILING WORKS				
24.1	2501A	Mobilisation of Driven cast in situ RCC piling rigs and all accessories capable of installing 500mm/550mm diameter piles in all types of soil, ash to project site and demobilisation of the same after completion of piling works etc all complete. Payments: a) mobilisation and commissioning of rig- 80%, b) demobilisation- 20%)	SET	6.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
24.2	2503A	Installation of driven cast-in-situ RCC vertical pile as per IS 2911 (Part 1, Sec. 1) by driving a suitable MS casing pipe (removable) having detachable MS shoe (flat/conical) at the bottom and driving using atleast 5 MT hammer for the length as specified (length to be measured from pile cut-off level to the bottom of pile)/for the desired set criteria (to be finalised during contract stage) so as to acheive the safe load carrying capacity as mentioned using cement concrete grade M30 conforming to IS:456 with 20 mm nominal size stone aggregates with a minimum cement content of 400Kg per cum of concrete including providing all materials (but excluding reinforcement steel for which measurement/payment shall be made separately), providing plasticser wherever required, breaking pile head to cut off level and exposing pile reinforcement for embedment in pile cap, empty driving etc including providing approved MS shoe(design and drawing of MS shoe shall be submitted by bidder for approval without extra cost to BHEL/Owner) etc all complete as per specification, drawing and as directed by the engineer-in-charge for the following. (Cement & Reinforcement will be supplied by BHEL as per SCC free of cost).				
24.2.1	b	Pile with 550 mm diameter and 18 m length below cut off level	Each	3341.0		
24.3	A2504	Extra over ST. No. 2503 for pile length more than the specified length of 18m below cut off level for the following.				
24.3.1	Ac	For 550 mm diameter pile	Rm	3341.0		
24.4	2505	Rebate on ST.No.2503 for pile length less than the specified length of 18m below cut off level for the following.				
24.4.1	Ac	For 550 mm diameter pile	Rm	5012.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
24.5	2507A	Conducting initial load test upto a maximum test load of 2.5 times the safe load capacity on single pile as specified in accordance with IS 2911 Part-4 including preparation of pile head for testing, necessary excavation, all arrangements of loading, unloading, test equipments/ accessories, jacks, recording of results, labour, submission of test report but excluding the cost of installation of pile (installation of pile shall be paid separately) etc. all complete as per specification, drawing and as directed by engineer in - charge for the following:				
24.5.1	a	For vertical compression test by cyclic load method				
24.5.1.1	ii	550 mm diameter pile	Each	3.0		
24.5.2	b	For lateral load test				
24.5.2.1	ii	550 mm diameter pile	Each	3.0		
24.5.3	c	For tension/uplift test				
24.5.3.1	ii	550 mm diameter pile	Each	3.0		
24.6	2508A	Conducting routine load test on single job pile as specified in accordance with IS 2911 (Part-4) including preparation of pile head for testing, necessary excavation, providing all arrangements of loading, unloading, test equipments/accessories, jacks, recording of results, labour, submission of test report etc but excludng the cost of installation of job pile complete as per specification, drawing and as directed by the engineer-in-charge for the following.				
24.6.1		For vertical compression test by maintained load method				
24.6.1.1	a	For vertical compression test				
24.6.1.1.1	ii	550 mm diameter pile	Each	34.0		
24.6.1.2	b	For lateral load test				
24.6.1.2.1	ii	550 mm diameter pile	Each	34.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
24.7	2509A	Carrying out pile integrity test on 550mm diameter pile including all arrangements for test, equipments/accessories, materials, labour, submission of test report etc but excluding the cost of installation of job pile all complete as per specification and as directed by the engineer-in-charge.	Each	3341.0		
24.8	2511	Driving a 550mm diameter empty MS casing pipe with bottom closed with approved detachable MS shoe down to a maximum depth of 20 m below ground level using at least 5MTweigh drop hammer and furnishing the set calculation to establish a safe load carrying capacity of 115 MT in vertical compression including providing detachable MS shoe etc all complete	Each	5.0		
25.0	3000	GROUND IMPROVEMNET BY COMPACTION STONE COLUMN				
25.1	3001A	Providing and installing 500 /550 mm diameter and 12 m long driven cast-in-situ compaction stone column with vibro compacting rig and filling in layers of 1m using graded gravel shall be 63mm & down and each layer be well compacted by dynamic compaction method and shall be thoroughly compacted. This procedure shall be repeated for every layer till the ground level is reached) for ground improvement of pond ash deposit at desired location including all materials, equipments etc complete as per specification, drawings and as directed by the engineer-in-charge.	Each	6228.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
25.2	3001B	Providing and installing 500 mm/550mm diameter and 12 m long driven cast-insitu compaction stone column by driving of suitable MS casing pipe (removable) having a detachable M.S.shoe (flat/conical) at the bottom and filling inside the casing pipe in layers of 1m using 1 (sand) : 2 (gravel; gravel shall be 50mm & down) and each layer be well compacted by dynamic compaction method before compaction, lift the casing for about 800mm from bottom and then the backfill shall be thoroughly compacted. This procedure shall be repeated for every layer till the ground level is reached) for ground improvement of pond ash deposit at desired location including all materials, equipments etc complete as per specification, drawings and as directed by the engineer-in-charge.	Each	6228.0		
25.3	3002	Conducting plate load Test at specified depth using 600mmx600mmx25mm Mild steel plate as per IS-1888 and submission of approved test report etc as per specification. (earth work in excavation and back filling shall be paid extra as per relevant applicable item)	Each	3.0		
25.4	3003	Conducting Dynamic cone penetration Test at specified location as per IS-4968,Part-1 for a maximum depth up to 15m below ground level submission of approved test report etc as per specification .	Each	15.0		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
25.5	3004	Making 150mm nominal diameter bore hole up to a maximum depth of 15 m below ground level at various locations in all types of soil including laterite using suitable approved method of boring including chiselling, cleaning, providing casing pipes as required or as directed; performing standard penetration test at every 1.0m interval alternate to collection of undisturbed soil samples up to 15m depth below ground level ; collection of undisturbed sample (UDS) at every 1.0m interval alternate to conducting standard penetration test up to 15 m depth below ground level; collection of disturbed soil samples and water samples, sealing and packing of samples, observation such as ground water table etc; transportation of all the collected samples to the laboratory and back filling of boreholes with sand on completion of the same etc all complete as per specification and as directed by the engineer-in-charge for depth below ground level as given below .	Rm	45.0		
25.6	3005	Conducting laboratory test on soil samples at an approved laboratory including preparation of soil samples to determine the following properties etc all complete as per specification.				
25.6.1		a)Bulk density and moisture content	Each	8.0		
25.6.2		b) Relative Density	Each	8.0		
26.0		LEVELLING & GRADING				
26.1	2	Earth work in stripping of top soil upto a minimum depth of 0.30m below ground level so as to exclude all debris, grass, vegetation, bushes, trees having girth upto 300mm including roots and organic materials etc for leveling and grading including dressing to specified levels & grades and compacting the graded/stripped surface by manual/mechanical means, disposal of stripped materials within a lead upto 1km etc all complete as per specification, drawing and as directed by the engineer-in-charge.	SQM	50000		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
26.2	3	Earth work in excavation upto any depth below ground level in all types of soil including moorum, pond ash/fly ash which can be excavated by any means for grading including setting out, levelling, dewatering (wherever required), dressing the sides & bottom, levelling to grade, all lifts, ramming/compacting the excavated bottom/graded surface, stacking/disposal of surplus excavated materials within a lead upto 1km , spreading/levelling of disposed materials etc all complete as per specification, drawing and as directed by the engineer-in-charge.	CUM	100000		
26.3	9	Earth work in filling upto any depth below ground level for grading to proper grade and level in layers not exceeding 300mm loose thickness with selected approved quality of pond ash/fly ash/soil from compulsorily excavated soil available within a lead upto 1km and compacted as specified including re-excavation of stacked earth, all lifts, sorting, spreading, breaking clods, watering, ramming/compaction by manual/mechanical means, dressing, finishing to required lines, grades and slopes, tesing etc all complete as per specification, drawing and as directed by the engineer for the following.				
26.3.1	a	Each layer compacted so as to achieve at least 95% maximum dry density as per IS-2720 (Part-VII)	CUM	100000		
27.0		MISCELLANEOUS				
27.1	MS-1	Pumping out water from CW Pit, Feed Pool, Cooling Tower Basin, Water logged areas etc. as an when required to facilitate erection & commissioning including provision of delevary pipe upto 150m etc. all complete as per site condition and instruction of engineer.	HP-Hour	1000		
27.2	MS-2	Providing service for manpower for cleaning and house keeping with all equipments, T & P etc. from various floor of power house and other buildings, boiler, ESP, Mill area and stacking at designated place.	Man HOUR	40000		

TENDER NO - PSER:SCT:BRM-C1273:11

SCH-2- SERVICE PRICE BREAK UP

SL NO	ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (INR)	AMOUNT (INR)
27.3	MS-3	Removal and disposal of scrap steel, scrap wood, broken packing crates, cable scrap, debris and other waste materials etc. from project site to a designated place within 5 KM range, with all manpower T & P etc. including loading and unloading as directed by BHEL Engineer.				
27.3.1		a) Steel	MT	100		
27.3.2		b) Wood / Cable scrap	CUM	650		
27.3.3		c) Debris & Other waste materials.	CUM	1000		
TOTAL						
28.0	2800	Quote % above or % below or at par for items not covered as above of this schedule. The rate shall be derived from Delhi schedule of rate 2007(Reprint-2010).				
28.1	a	Rate of complete item	%			
28.2	b	Rate of supply of material at site only	%			
28.3	c	Rate for execution complete excluding supply of materials.	%			