



BHARAT HEAVY ELECTRICALS LIMITED  
(A GOVERNMENT OF INDIA UNDERTAKING)  
BOILER AUXILIARIES PLANT, RANIPET – 632 406  
CIVIL PROJECTS & SERVICES DEPARTMENT

**TENDER NOTICE NO: BAP: CF: 01 / 2011-12 Date 06.04.2011**

Sealed tenders are invited from the registered vendors (Class I to Class III) of BHEL / BAP, Ranipet for the following work:

SI No	Name of work	Estimated cost (Rs in Lakhs)	Earnest Money Deposit (Rs)	Period of completion	Last date for Receipt of tender documents	Date of Tender opening
01	Laying of sewer line from Zone III to collection well near DAV school in BHEL-Township.	22.53	60,000	SIX months	21.04.2011 up to 3.00PM	21.04.2011 at 3.00PM

BHEL will not be responsible for any loss / delay of documents sent by post / Courier.

BHEL reserves the right to accept / reject any / all the tenders without assigning any reason.

The EMD shall be collected in cash (as permissible under Income Tax Act), Pay order or Demand Draft only drawn in favour of BHEL,BAP,Ranipet – 6 Payable at Ranipet- 632 406,Tamil Nadu.

**Please note that if any tenderers already paid Standing EMD (ie, One time EMD) with BHEL, Ranipet, they are requested to mention the cash receipt No, Date and the amount paid in their quote preferably in the first page or enclose a Xerox copy of the same.**

**Please visit our BHEL Web site for tender updates**

[http://www.bhel.com/tender/list\\_tender.php](http://www.bhel.com/tender/list_tender.php)

Place: Ranipet – 6  
Date : April 6, 2011  
Phone Nos: 04172 – 242026, 284694, 284995 & 284087.  
Email: [vdinakar@bhelrpt.co.in](mailto:vdinakar@bhelrpt.co.in)  
Cell No:94433 89051 (or) 99439 77151  
Telefax: 04172 - 242026

Dy Manager (Civil Projects & Services)

**Encl.: Tender Document**

## **1. Eligibility criteria:**

The tender is uploaded in our BHEL WEB site as per CVC guide lines vide Office Order No. 10/02/04.

Only those vendors who have already enlisted with BHEL, Ranipet through enlistment procedure is allowed to participate in this tender.

Interested Vendors may contact with their credentials to AGM (Civil Factory & Township) BHEL, BAP Ranipet – 632 406 for due enlistment for future such tenders.

Enlistment Application forms can be obtained from office of the Additional Deputy General Manager / Civil Factory & Township or can be downloaded from BHEL WEB page.

[http://www.bhel.com/tender/view\\_tender.php?tenderid=8353](http://www.bhel.com/tender/view_tender.php?tenderid=8353)

Enlistments Applications are invited in sealed cover for **Registration of Contractors for Civil works in Factory & Township and Electrical works in Township.**

**AGM (Civil Factory & Township)**

**Bharat Heavy Electricals Limited**

**Boiler Auxiliaries Plant**

**Ranipet – 632 406 Tamil Nadu**

**E-mail: [ccdurai@bhelrpt.co.in](mailto:ccdurai@bhelrpt.co.in)**

**MobileNo.9443389051**

**Ph:04172-284694**

**Earnest Money Deposit : (Clause 8.1)**

- (i) The Earnest Money Deposit for the above work is given in the above column and will be accepted as CASH (at BHEL Cash Office, Ranipet – 6) (as permissible under Income tax Act) or PAY ORDER or DEMAND DRAFT drawn in favour of, BHEL / RANIPET – 6 payable at SBI / BHEL Project, Mukundapuram (Bank Code No : 7013).
- (ii) The EMD will be refunded to unsuccessful tenderers within 15 days of acceptance of award of work by the successful tenderer. **The same will be refunded thro Electronic Fund Transfer only.** Other modes of refund like Demand draft, Cheque, Pay order etc., will not be made.
- (iii) For successful Tender, the EMD shall be converted / adjusted against the Security Deposit.
- (iv) The EMD shall not carry any interest
- (v) Without EMD, your tender will not be considered

**Security Deposit : (Clause 8.2)**

- (i) The rate of security deposit will be as below (w.r.t. Total contract value):
- Up to Rs 10 lakhs : **10%**
  - Above Rs 10 Lakhs Up to Rs 50 lakhs : **Rs 1 Lakh + 7.50% of the amount exceeding Rs 10 Lakhs**
  - Above Rs 50 Lakhs : **Rs 4 lakhs + 5.00% of the amount exceeding Rs 50 Lakhs**
- (ii) 50% of SD should be deposited before start of the work. Balance SD will be recovered at the rate of 10% from running bills. Anyhow the contract value not exceeding Rs 10 Lakhs can be started before SD is collected, provided the payment can be released only after collection / recovery of initial 50% SD.
- (iii) The SD shall not carry any interest.
- (iv) SD may be furnished in any one of the following forms :
- Cash (as permissible under Income tax Act)
  - Pay order or Demand draft drawn in favour of, BHEL / RANIPET – 6 payable at SBI / BHEL Project, Mukundapuram (Bank Code No : 7013).
  - Local cheques of scheduled banks, subject to realization.
  - Securities available from post offices such as National Savings Certificates, Kisan Vikas patras etc., (Certificates should be held in the name of Contractor furnishing the security and duly pledged in favour of BHEL and discharged on the back)
  - Bank guarantee from scheduled banks / Public financial institutions as defined in the Companies act. The Bank guarantee format should have the approval of BHEL.
  - Fixed Deposit Receipt issued by scheduled banks / Public financial institutions as defined in the Companies act. The FDR should be in the name of the contractor, A/c BHEL, duly discharged on the back.
- (v) Refund of SD : 50% of SD may be refunded to the contractor in respect of all contract on satisfactory completion of work and after payment of final bill and the balance 50% on expiry of the maintenance period, provided that the contractor shall have rendered a “ No Demand” certificate. In case of work where maintenance period is not involved 100% of the SD may be refunded after payment or final bill provided that the contractor shall have rendered a “ No Demand” certificate.

**Electronic Fund Transfer (EFT Form) : (as per CVC guide lines)**

- The enclosed EFT form should be duly filled and submitted along with tender documents. Without EFT form your tender will not be considered and will be rejected.
- **Suppose if you already submitted the EFT form to BHEL(Ranipet) this may be ignored.**

**Advance payment :**

- No advance payment shall be paid to the contractor.
- **For payment, M Book system shall be adopted as per the norms of the company**

(Contd.....4)

**General :**

- The envelop / cover containing duly filled in tender documents along with necessary enclosures should neatly be indicated the following :
  - a. Name of work : To be mentioned in the left hand side top corner of the envelop in first line.
  - b. Tender Notice No : To be mentioned in the left hand top corner of the envelop in second line.
  - c. To be addressed to : **Sri V.Rajendran, -** To be mentioned in the right side  
**Manager,** middle or bottom of the envelop  
**Civil Projects & Services,**  
**BHEL / BAP / Ranipet – 632 406.**  
**Vellore Dist., / Tamil Nadu.**
  - d. From / self address : To be mentioned in the left hand side bottom corner of the envelop.



# BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

## ESTIMATE

ESTIMATE REF NO : CF/C/10/66

NAME OF WORK : LAYING OF SEWER LINE FROM ZONE III TO COLLECTION WELL NEAR DAV SCHOOL IN TOWNSHIP.

[AMOUNT IN Rs.]

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE RS P	AMOUNT RS P
19.1	01	Providing, laying and jointing glazed stoneware pipes grade `A₂ with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete				
19.1.1	01A	100 mm diameter	1200.000	metre	94.67	113604.30
19.1.2	01B	150 mm diameter	200.000	metre	134.93	26986.95
19.1.3	01C	200 mm diameter	800.000	metre	224.74	179793.80
19.1.5	01D	250 mm diameter	50.000	metre	314.91	15745.25
19.6	02	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :				
19.6.3	02A	250 mm dia. R.C.C. pipe	120.000	metre	253.54	30425.10
19.9	03	Constructing brick masonry circular type manhole 0.91m internal dia at bottom and 0.56m dia at top in cement mortar 1:4 (1 cement : 4 coarse sand), in side cement plaster 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement, foundation concrete 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size), and making necessary channel in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) finished with a floating coat of neat cement all complete as per standard design :				
19.9.1	03A	0.91 m deep with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560 mm internal diameter conforming to I.S.12592, total weight				

CONTRACTOR/ TENDERER

ACCEPTING OFFICER



# BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

## ESTIMATE

ESTIMATE REF NO : CF/C/10/66

NAME OF WORK : LAYING OF SEWER LINE FROM ZONE III TO COLLECTION WELL NEAR DAV SCHOOL IN TOWNSHIP.

[AMOUNT IN Rs.]

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE		AMOUNT	
					RS	P	RS	P
		of cover and frame to be not less than 182 kg., fixed in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including centering shuttering all complete. (Excavation, foot rests and 12mm thick plaster at the external surface shall be paid separately).						
19.9.1.1	03A1	With F.P.S. bricks class designation 75	40.000	each	3510.38		140415.00	
19.10	04	Extra depth for circular type manhole 0.91m internal dia (at bottom) with beyond 0.91m to 1.67m metre						
19.10.1	04A	With F.P.S. bricks class designation 75	20.000	metre	421.63		8432.50	
19.11	05	Constructing brick masonry circular manhole 1.22m internal dia at bottom and 0.56m dia at top in cement mortar 1:4 (1 cement :4 coarse sand) inside cement plaster 12mm thick with cement mortar 1:3 (1 cement :3 coarse sand) finished with a floating coat of neat cement foundation concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size) and making necessary channel in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) finished with a floating coat of neat cement all complete as per standard design :						
19.11.1	05A	1.68 m deep with SFRC Cover and frame (heavy duty HD-20 grade designation) 560mm internal diameter conforming to I.S. 12592, total weight of cover and frame to be not less than 182kg. fixed in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) including centering shuttering all						

CONTRACTOR/ TENDERER

ACCEPTING OFFICER



# BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

## ESTIMATE

ESTIMATE REF NO : CF/C/10/66

NAME OF WORK : LAYING OF SEWER LINE FROM ZONE III TO COLLECTION WELL NEAR DAV SCHOOL IN TOWNSHIP.

[AMOUNT IN Rs.]

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE		AMOUNT	
					RS	P	RS	P
		complete. (Excavation, foot rests and 12 mm thick cement plaster at the external surface shall be paid for separately) :						
19.11.1.1	05A I	With F.P.S. bricks class designation 75	5.000	each	6156.93			30784.63
19.12	06	Extra depth for circular type manhole 1.22m internal dia (at bottom) beyond 1.68 m to 2.29 m						
19.12.1	06A	With F.P.S. bricks class designation 75	5.000	metre	2214.73			11073.63
19.13	07	Constructing brick masonry circular manhole 1.52 m internal dia at bottom and 0.56 m dia at top in cement mortar 1:4 (1 cement : 4 coarse sand) inside cement plaster 12mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement, foundation concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size) and making necessary channel in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) finished with a floating coat of neat cement all complete as per standard design :						
19.13.1	07A	2.30m deep with SFRC Cover and frame (heavy duty HD-20 grade designation) 560mm internal diameter conforming to I.S. 12592, total weight of cover and frame to be not less than 182 kg. fixed in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) including centering shuttering all complete. (Excavation, foot rests and 12 mm thick cement plaster at the external surface shall be paid for						

CONTRACTOR/ TENDERER

ACCEPTING OFFICER



# BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

## ESTIMATE

ESTIMATE REF NO : CF/C/10/66

NAME OF WORK : LAYING OF SEWER LINE FROM ZONE III TO COLLECTION WELL NEAR DAV SCHOOL IN TOWNSHIP.

[AMOUNT IN Rs.]

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE RS P	AMOUNT RS P
		separately) :				
19.13.1.1	07A I	With F.P.S. bricks class designation 75	5.000	each	12661.55	63307.75
19.14	08	Extra depth for circular type manhole 1.52 m internal dia (at bottom) beyond 2.30 m				
19.14.1	08A	With F.P.S. bricks class designation 75	5.000	metre	5346.63	26733.13
19.16	09	Providing orange colour safety foot rest of minimum 6 mm thick plastic encapsulated as per IS : 10910 on 12mm dia steel bar conforming to IS : 1786 having minimum cross section as 23 mmx25mm and over all minimum length 263 mm and width as 165mm with minimum 112 mm space between protruded legs having 2 mm tread on top surface by ribbing or chequering besides necessary and adequate anchoring projections on tail length on 138 mm as per standard drawing and suitable to with stand the bend test and chemical resistance test as per specifications and having manufacture's permanent identification mark to be visible even after fixing, including fixing in manholes with 30x20x15 cm cement concrete block 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) complete	720.000	each	172.15	123950.52
13.2	10	15 mm cement plaster on the rough side of single or half brick wall of mix :				
13.2.1	10A	1:4 (1 cement: 4 fine sand)	1272.000	sqm	56.51	71875.00
2.8	11	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift				

CONTRACTOR/ TENDERER

ACCEPTING OFFICER



# BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

## ESTIMATE

ESTIMATE REF NO : CF/C/10/66

NAME OF WORK : LAYING OF SEWER LINE FROM ZONE III TO COLLECTION WELL NEAR DAV SCHOOL IN TOWNSHIP.

[AMOUNT IN Rs.]

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE		AMOUNT	
					RS	P	RS	P
		upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.						
2.8.1	11A	All kinds of soil.	5300.000	cum	103.40		548020.00	
2.9	12	Excavation work by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains not exceeding 1.5 m in width or 10 sqm on plan including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50m.						
2.9.1	12A	Ordinary rock	400.000	cum	162.65		65060.00	
2.9.2	12B	Hard rock (requiring blasting)	200.000	cum	272.95		54590.00	
2.9.3	12C	Hard rock (blasting prohibited)	50.000	cum	332.45		16622.50	
2.26	13	Extra for every additional lift of 1.5 m or part thereof in.						
2.26.1	13A	All kinds of soil.	200.000	cum	18.90		3780.00	
2.26.2	13B	Ordinary or hard rock.	650.000	cum	33.85		22002.50	
2.25	14	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	4200.000	cum	45.70		191940.00	
2.33	15	Felling trees of the girth (measured at a height of 1 m above ground level) including cutting of trunks and branches removing the roots and stacking of serviceable material and disposal of unserviceable material.						
2.33.1	15A	Beyond 30 cm girth upto and including 60 cm girth	5.000	each	81.70		408.50	

CONTRACTOR/ TENDERER

ACCEPTING OFFICER



# BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

## ESTIMATE

ESTIMATE REF NO : CF/C/10/66

NAME OF WORK : LAYING OF SEWER LINE FROM ZONE III TO COLLECTION WELL NEAR DAV SCHOOL IN TOWNSHIP.

[AMOUNT IN Rs.]

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE		AMOUNT	
					RS	P	RS	P
2.33.2	15B	Beyond 60 cm girth upto and including 120 cm girth	5.000	each	359.80		1799.00	
2.33.3	15C	Beyond 120 cm girth upto and including 240 cm girth	2.000	each	1658.85		3317.70	
15.7	16	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.						
15.7.4	16A	In cement mortar	5.000	cum	310.75		1553.75	
15.9	17	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge:						
15.9.2	17A	In cement mortar	5.000	cum	370.75		1853.75	
15.2	18	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.						
15.2.2	18A	1:4:8 or leaner mix	5.000	cum	226.90		1134.50	
15.3	19	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	2.000	cum	537.55		1075.10	
97160650704	20	Providing and fixing on wall face unplasticised rigid PVC rain water pipes, air vent conforming to IS 14735 Type A including jointing with seal ring conforming to IS 5382 leaving 10 mm gap for thermal expansion.					.00	
IT 02	20A	160mm dia single socketed pipes	80.000	RM	329.17		26333.60	
IT 02C	20B	160mm dia bend	30.000	EACH	176.18		5285.40	
97160650704	21	Fabrication and erection of structural steel clamps for fixing of 160mm dia rain water down take pipes / air vent	10.000	EACH	6.25		62.50	

CONTRACTOR/ TENDERER

ACCEPTING OFFICER



# BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

## ESTIMATE

ESTIMATE REF NO : CF/C/10/66

NAME OF WORK : LAYING OF SEWER LINE FROM ZONE III TO COLLECTION WELL NEAR DAV  
SCHOOL IN TOWNSHIP.

[AMOUNT IN Rs.]

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE RS P	AMOUNT RS P
		pipes as directed by the Engineer - in - charge. Rate to include cost of all materials such as bolts, nuts, incidental charges etc. complete. Structural steel materials required for the work alone will be supplied by BHEL stores at free of cost.				
97160650704	22	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work.	0.010	MT	634.87	6.35

CONTRACTOR/ TENDERER

ACCEPTING OFFICER



# BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT  
RANIPET - 632406

## ESTIMATE

ESTIMATE REF NO : CF/C/10/66

NAME OF WORK : LAYING OF SEWER LINE FROM ZONE III TO COLLECTION WELL NEAR DAV  
SCHOOL IN TOWNSHIP.

[AMOUNT IN Rs.]

TOTAL ESTIMATED VALUE BEFORE ESCALATION 1787972.71

ESCALATION @ 26.00 % 464872.90

TOTAL ESTIMATED VALUE (A) 2252845.61

CONTRACTOR TENDER PERCENTAGE @ ABOVE  1  
BELOW  2  
AT PAR  3

\_\_\_\_\_ % (B)  4

(Percentage in words )

SUB TOTAL if above (A) + (B) (C)  5

if below (A) - (B) (C)  6

if at par (A) (C)  7

\*SERVICE TAX @ \_\_\_\_\_ % (D)  8

SERVICE HEAD :

TOTAL VALUE OF WORK [ (C) + (D) ] (E)  9

(Rupees in words )

- NOTE :**
- 1) Instead of subtraction (for tender % quoted below), Total value of work is calculated by addition erroneously, L1 will be decided based on amount arrived by subtraction only. In the same way, instead of addition (for tender % quoted above), Total value of work is calculated by subtraction erroneously, L1 will be decided based on amount arrived by addition only. Any calculation error will be corrected at actuals.
  - 2) Tick whichever is applicable. In case of omission in Ticking, figures indicated in the amount column will be considered.
  - 3) Boxes 1,2,3 any one box is to be ticked as per quote. Boxes 5,6,7 any one box is to be filled in with appropriate figures. Box 9 value is equal to Box 5 or 6 or 7 plus box 8.
  - \*4) Service Tax at applicable percentage shall be quoted by tenderers. In case Service Tax at composite rate quoted, it will be applicable on BHEL free issue of materials also. In case Service Tax % or Service tax amount is not mentioned, it is presumed that service tax at normal rate is included in the quoted rate.
  - 5) If any discrepancy between figures & words, L1 will be decided based on words.

CONTRACTOR/ TENDERER

ACCEPTING OFFICER



**BHARAT HEAVY ELECTRICALS LIMITED**

BOILER AUXILIARIES PLANT

RANIPET - 632406

**ESTIMATE**

ESTIMATE REF NO : CF/C/10/66

NAME OF WORK : LAYING OF SEWER LINE FROM ZONE III TO COLLECTION WELL NEAR DAV  
SCHOOL IN TOWNSHIP.

[AMOUNT IN Rs.]

**SPECIAL CONDITION**

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

## SPECIAL CONDITION

<b>1. Items of work other than those mentioned in Bill of Quantities will have to be carried out at the rates to be fixed by this organization .The same offered &amp; accepted percentage will be applicable with reference to CPWD DSR 2007.</b>
<b>2. Safety precautions should be taken while doing the work. You will have to follow all safety requirements to carry out the work inside the factory premises.</b>
<b>3. CONTRACT CONDITIONS ON TAXES &amp; DUTIES.</b>
<b>3a The Tenderer shall have been Registered under Excise, Sales Tax, VAT, Service Tax regulations if applicable and provide a copy of such registration to BHEL as part of the tender document. In case of fresh registration/amendment thereon, the same shall be carried out before start of the work. PAN no shall be submitted as part the tender document. (copy to be enclosed)</b>
<b>3b. If payment of statutory dues are not made in accordance with the applicable provisions of the relevant Act within the time specified and Penalty, Interest etc paid/payable by the Contractor, the same shall not be reimbursed by BHEL and the entire implication is only to be borne by the Contractor. The Tenderer shall clearly indicate the rate of applicable taxes and duties for the work to be executed.</b>
<b>3c. The Tenderer shall indicate all exemptions on account of threshold limits or special notification under any stature. Any modification thereon shall also be intimated immediately on changes.</b>
<b>3d. The quote submitted shall include all taxes and duties of whatsoever in nature but exclusive of Service Tax which shall be quoted separately if applicable. The existing rate shall be quoted clearly. If reduced rates are applicable on account of material, labour if any the same shall be indicated clearly. After tender opening addition of any taxes &amp; duties are not admissible.</b>
<b>3e. If any composition scheme is to be availed by the Tenderer, the all relevant terms and conditions shall be indicated clearly in the offer. The required compliance under relevant statue shall be carried out.</b>
<b>3f. Any statutory variation will be to the account of BHEL. But if the variation is effective during the delayed/extended period of execution for reasons attributable to the vendor, the same shall be borne by the vendor only.</b>
<b>4. All materials shall confirm to the latest IS/IRC specifications</b>
<b>5. All works shall be carried out as per standard specifications and instructions of Engineer-in-charge.</b>
<b>6. All materials, colour, shade, brand, etc. shall be got approved from the Engineer-in-charge before the start of the work and shall confirm to the latest IS/IRC specifications.</b>
<b>7. The minimum wages applicable as per the Tamil Nadu minimum wages Act from time to time is to be paid.</b>
<b>8. The contractor have to follow all statutory requirements like PF, ESI etc., throughout the contract period.</b>
<b>9. The General conditions of contract in force shall apply to this contract.</b>
<b>10.The contractor is required to engage a qualified Engineer with sufficient knowledge of the work throughout the contract period.</b>

**11. Time is essence of the contract. Any delay beyond the delivery date will be subjected to LD.**

**12. BHEL will provide water at free of cost by identifying the water source (Open well) within the BHEL premises subject to availability and the contractor has to make their own arrangement for pumping the water from well and using the same after ensuring the suitability for the purpose. In case BHEL is not able to provide water as stated above, the contractor has to make their own arrangement for bringing the required quality of water at their own cost from outside BHEL premises for construction & testing purpose.**

**13. The contractor has to make their own arrangement for the required power supply for the execution of work. However BHEL will issue No-Objection Certificate for getting the temporary power service connection if required.**

**14. Cement, Reinforcement steel, structural steel & AC sheets will be issued free of cost for theoretical consumption. Recover will be made up to 5% over and above the theoretical consumption at a recovery rate of Rs. 6,325.00 / MT, Rs. 41,975.00 / MT, Rs. 46,500.00 / MT and Rs. 140.00 / Sq.m respectively beyond which penal recovery will be effected at double the rates specified above.**