

SCOPE & SPECIFIC TECHNICAL REQUIREMENTS

1.1.0 SCOPE

- 1.1.1 The scope of work under this specification is Gravelling works for 400/132kV Substation at BARH in BIHAR, being executed by BHEL on turnkey basis. The Customer is National Thermal Power Corporation (NTPC).
- 1.1.2 The Gravelling Works shall generally include, *but not limited to*, following:
(a) Site preparation, soil sterilization/antiweed treatment and gravel filling , spreading in switchyard area excluding major leveling as per drawings issued by the Owner.

1.2.0 SPECIFIC TECHNICAL REQUIREMENT

- 1.2.1 The specific technical requirements for the execution of civil works shall be as per Customer's Technical Specification. In the absence of any standard in the above, the work shall be executed according to latest CPWD practices. In case of any variance in CPWD and Customer's specification for any item, the specification of Customer shall prevail.

1.3.0 BILL OF QUANTITIES

- 1.3.1 The quantities indicated in the 'Bill of Quantity' are indicative and can vary to any extent. Contractor shall not be entitled for any claim for any such variation in the quantities.
- 1.3.2 The provision of Bill of Quantity, specifications and drawings shall be read in conjunction with each other and in case of conflict amongst them, the clarification shall be obtained from the Engineer-in-charge whose decision shall be final and binding.