

**BILL OF QUANTITY-CUM-PRICE SCHEDULE**

**Name of Project**

**: 400kV Substation at BARH**

**Name of Work**

**: Gravelling Works of Yard .**

S.No.	Description of Item	Unit	Quantity	Unit Rate (Rs)	Amount (Rs)
1	Providing all material, labour, equipment required for soil sterilization/ anti-weed treatment including clearing all grass, trees,vegetation etc. & mixing/injecting chemicals to achieve the guaranteed effectiveness of the treatment at least up to five years as required/recommended by the manufacturer of the chemical used for soil sterilization/anti-weed treatment including rolling, dressing, compacting the earth to achieve the sub-base required for laying base course and surface course complete as per specification and instructions of the Engineer.	Sq.m.	175000		
	Notes :				
i)	The bidders are required to furnish necessary details pertaining to the antiweed treatment such as the manufacturer's name, their specification, test certificates, etc.alongwith the bid for Owner's approval.				
ii)	Any modification, if required shall have to be done by the Bidder at no extra cost to Owner. The bidders shall be required to furnish a performance guarantee of three years for antiweed treatment.				
2	Providing, supplying and laying minimum 150mm thick gravel filling in two layers i.e first layer of 75 mm thick base course of 20mm nominal size and second layer of surface course of 75 mm thickness of brokenstone fill of 40 mm nominal size which shall be laid over first layer including dressing, rolling, compacting, etc complete as per specification, drawings and directions of the Engineer. All stone used shall be granite stone free from dirt or organic material.	Sq.m.	175000		
	<b>TOTAL AMOUNT (Rs.)</b>				