

	<p style="text-align: right;"><b><u>Annexure-I</u></b></p> <p style="text-align: center;"><b><u>Technical specification on Gravelling.</u></b></p> <p>1 The material required for gravel filling shall be free from all types of organic materials and shall be of approved quality, and as directed, and as directed by Engineer.</p> <p>2 After the soil sterilization material is applied and surface is prepared, a final surface course minimum 100mm uniform layer of broken stones of 20mm nominal size as specified shall be spread over the entire area of switchyard. This surface course shall then be compacted by light roller (by 1/2 tonne roller and 4 to 5 passes) or any other means with water sprinkling as directed by engineer.</p> <p>3 In areas that are considered by consultant/Engineer to be too congested with foundations and structures for proper rolling of the site base course material by compacted by hand if necessary. Due care shall be exercised so as not to damage any foundation structure or equipment during rolling compaction.</p>