

SECTION - 1

SCOPE, SPECIFIC TECHNICAL REQUIREMENTS & QUANTITIES

1.1.0 SCOPE

1.1.1 The scope of work under this specification is Yard treatment and fencing for **220/33kV Substation at Masjid Moth** in Delhi, being executed by BHEL on turnkey basis. The Customer is Delhi Transco Limited (DTL).

1.1.2 The Civil Works shall generally include, *but not limited to*, following:

- (i) Yard treatment and Fencing.
- (ii) Any other item required for completion of the project.

1.1.3 The works to be performed in the above constructions include execution of the work including providing of all labour, supervision, materials, scaffolding, power, fuel, construction equipments, tools and plants, supplies, transportation, all incidental items necessary for successful completion of the work including contractor's supervision and in strict accordance with the drawings and specifications and with inspection and testing standards. The nature of work shall generally involve excavation in all type of soil including dewatering, ,backfilling, concreting, flat brick flooring ,PCC and fencing etc. all complete as per detailed specification, drawings and directions of Engineer-in-charge.

1.2.0 SPECIFIC TECHNICAL REQUIREMENT

1.2.1 The specific technical requirements for the execution of civil works shall be as per DTL Technical Specification and latest CPWD/IS Specifications. **In case of any difference between DTL Technical Specification & latest CPWD/IS Specifications, the provisions of DTL Specification shall be considered.**

1.3.0 BILL OF QUANTITIES

1.3.1 The Bill of Quantity shall be as per page 1.2.

1.3.2 The quantities indicated in the Bill of Quantity are indicative and can vary to any extent. Contractor shall not be entitled for any claim for any such variation in the quantities.