

**BOQ:-**

- 1) CI PIPE ELECTRODES - 2 NOS, 3 M LONG EACH
- 2) 50X8 GI FLAT - 6 M
- 3) 70 SQ MM AL CABLE - 20 M
- 4) BENTONITE CLAY - 2 M<sup>3</sup> (To be arranged at Site)

**NOTE:-**

- 1) The above BOQ is for one circuit.
- 2) Earth Pit Cover is not envisaged.

**ELECTRONIC EARTHING FOR CONTROLLER****ELECTRONIC EARTHING DETAILS**

COMPUTER REF. NO.

DRG. No.

TB-04-292-509-051

REV. 00

SHEET No.  
1