

TENDER SPECIFICATION

NO: BHE/PW/PUR/KKRN-ENB/1071

DEVELOPMENT OF OPEN STORAGE YARD (25,000 SQM) WITH INTERNAL ROADS, DRAINS, HARD SURFACING BY MURUM, FENCING ALONG WITH ITS ILLUMINATION, CONSTRUCTION OF RAISED CONCRETE PLATFORM, CONSTRUCTION OF OFFICE BUILDING (SIZE 40Mx10M) INCLUDING ITS ELECTRIFICATION, CLOSED STORE SHED (1 No. OF SIZE 60Mx15Mx5.25M Ht.), CLOSED STORE SHED WITH STORE OFFICE AND C&I STORE ROOM (1 No. OF SIZE 60MX15Mx5.25M) ETC. INCLUDING ITS INTERNAL/EXTERNAL ELECTRIFICATION.

AT

2X700 MWe NPCIL –KAKARAPARA ATOMIC POWER PROJECT
DIST. SURAT, GUJARAT.

VOLUME :II – PRICE BID

BOOK NO.



BHARAT HEAVY ELECTRICALS LIMITED

(A GOVERNMENT OF INDIA UNDERTAKING)

POWER SECTOR - WESTERN REGION

SHREEMOHINI COMPLEX

345, KINGSWAY - NAGPUR 440 001

BHARAT HEAVY ELECTRICALS LIMITED

(A GOVERNMENT OF INDIA UNDERTAKING)

POWER SECTOR - WESTERN REGION

SHREEMOHINI COMPLEX

345, KINGSWAY - NAGPUR 440 001

Tender Specification Issue Details

Tender Specification No: BHE/PW/PUR/KKRN-ENB/1071

DEVELOPMENT OF OPEN STORAGE YARD (25,000 SQM) WITH INTERNAL ROADS, DRAINS, HARD SURFACING BY MURUM, FENCING ALONG WITH ITS ILLUMINATION, CONSTRUCTION OF RAISED CONCRETE PLATFORM, CONSTRUCTION OF OFFICE BUILDING (SIZE 40Mx10M) INCLUDING ITS ELECTRIFICATION, CLOSED STORE SHED (1 No. OF SIZE 60Mx15Mx5.25M Ht.), CLOSED STORE SHED WITH STORE OFFICE AND C&I STORE ROOM (1 No. OF SIZE 60MX15Mx5.25M) ETC. INCLUDING ITS INTERNAL/EXTERNAL ELECTRIFICATION.

AT

**2X700 MWe NPCIL –KAKARAPARA ATOMIC POWER PROJECT
DIST. SURAT, GUJARAT.**

EARNEST MONEY DEPOSIT: Please see Notice Inviting Tender.

LAST DATE FOR: Please see Notice Inviting Tender.

TENDER SUBMISSION:

THESE TENDER SPECIFICATION DOCUMENTS CONTAINING **VOLUME-I-Tech Bid** , **VOLUME- II-Price Bid** AND **VOLIME-IBCD** ARE ISSUED TO:

M/s.

PLEASE NOTE:

THESE TENDER SPECS DOCUMENTS ARE NOT TRANSFERABLE.

For Bharat Heavy Electricals Limited

AGM (Purchase)

Place: Nagpur

Date:

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
RATE SCHEDULE, SECTION - A							
SEC. A	1	SUB GRADE PREPARATION: CUTTING & DISPOSAL OF GRASS, VEGETATIONS, BUSHES, TREES (GIRTH LESS 300MM), LEVELLING, WATERING AND CONSOLIDATION (90% OF PROCTOR DENSITY) BY MEANS OF 10-12 MT CAPACITY POWER/VIBRO ROLLER FOR SUB BASE PREPARATION. THIS WILL INCLUDE AVERAGE CUTTING & FILLING UP TO ± 250MM THICK, GRADING THE AREA WITH PROPER SLOPE FOR DRAINING OUT THE RAIN WATER WITH ALL T&P, LABOURS, MATERIALS, DEWATERING (IF REQUIRED) ETC. COMPLETE. FOR DEVELOPMENT OF OPEN STORAGE YARD.	SQM	25000			
SEC. A	2	BACK FILLING FOR LAND DEVELOPMENT IN LAYERS NOT EXCEEDING 15 CM THICKNESS FOR THE AREA OF OPEN STORAGE YARD WHEREVER REQUIRED TO BE DEVELOPED INCLUDING WATERING AND CONSOLIDATING, ROYALTY ETC. COMPLETE AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.					
SEC. A	2A	WITH GOOD AVAILABLE EARTH FROM EXCAVATION WORK	CUM	4125			
SEC. A	2B	WITH GOOD EARTH BROUGHT FROM CONTRACTOR'S OWN SOURCE (OUTSIDE OF PLANT)	CUM	155			
SEC. A	3	EXCAVATION /CUTTING OF EARTH BEYOND INITIAL 250MM THICK WHICH IS COVERED UNDER ITEM NO.(1) ABOVE IF REQUIRED AND SPREADING THE SAME IN LOW LYING AREA. WATERING, COMPACTION BY MEANS OF 10-12 MT CAPACITY POWER/VIBRO ROLLER FOR DEVELOPMENT OF OPEN STORAGE YARD AS PER INSTRUCTION OF BHEL ENGINEER.	CUM	625			
SEC. A	4	PROVIDING & FILLING OF 200 MM COMPACTED THICK GRANULAR HARD MURUM IN LAYERS (THICKNESS OF EACH LAYER SHOULD NOT EXCEED 100MM) FOR PREPARING HARD SURFACE FOR STORAGE OF MATERIALS DURING MONSOON PERIOD IN THE SPECIFIED AREA AS SHOWN IN INDICATIVE DRAWING/SKETCH "AS MONSOON YARD", WATERING AND COMPACTION WITH 8-10T POWER/VIBRO ROLLER COMPLETE. RATE SHALL INCLUDE TRANSPORTATION, ROYALTY, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER. <i>(APPROX. 2100SQM. AREA TO BE DEVELOPED BY 200MM THICK MURUM FOR CONSTRUCTION OF MONSOON YARD)</i>	CUM	420			
SEC. A	5	EXCAVATION FOR ROADWAY IN ALL TYPES OF SOILS, SAND AND GRAVEL OR SOFT MURUM INCLUDING DRESSING OF SECTION TO THE REQUIRED GRADE, CAMBER & SIDE SLOPES AND SPREADING OF SURPLUS EXCAVATED EARTH UNIFORMLY OVER THE SPECIFIED AREA FOR SITE LEVELING & DEVELOPMENT OF REQUIRED DEPTH TO MAINTAIN UNIFORM GROUND LEVEL AS DIRECTED BY THE BHEL & CONSOLIDATION OF THE SURFACE INCLUDING SUB- BASE BY ROLLING THE SURFACE WITH 8 - 10 MT CAPACITY POWER/VIBRO ROLLER, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.AS PER DRAWINGS & SPECIFICATIONS.	CUM	3870			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW_e NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC. A	6	EXCAVATION FOR SIDE DRAIN/DRAINS AND CULVERTS AND WATER TANK IN ALL KINDS OF SOILS, TO THE SPECIFIED SECTION AS PER DRAWINGS & SPECIFICATIONS. INCLUDING SPREADING OF SURPLUS EXCAVATED EARTH UNIFORMLY OVER THE SPECIFIED AREA FOR SITE LEVELING & DEVELOPMENT OF REQUIRED DEPTH TO MAINTAIN UNIFORM GROUND LEVEL, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE. DIRECTED BY THE BHEL ENGINEER.					
SEC. A	6A	IN ORDINARY SOIL	CUM	1033			
SEC. A	6B	IN SOFT/HARD ROCK	CUM	266			
SEC. A	7	BACK FILLING THE SIDES OF DRAINS, CULVERTS WITH GOOD EXCAVATED SOIL AVAILABLE FROM WORK IN LAYERS NOT EXCEEDING 15 CM THICKNESS INCLUDING WATERING AND CONSOLIDATING ETC. COMPLETE AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.	CUM	205			
SEC. A	8	DISPOSAL OF EXCAVATED EARTH/ROCK (NOT SUITABLE FOR BACK FILLING) UPTO A MAXIMUM LEAD OF 2 KM OR PART THEREOF INCLUDING LOADING,UNLOADING ,CONVEYING AND SPREADING AS PER DIRECTION OF ENGINEER INCHARGE.AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.	CUM	842			
SEC. A	9	PROVIDING & FILLING OF 300MM COMPACTED THICK GRANULAR MURUM IN LAYERS (THICKNESS OF EACH LAYER SHOULD NOT EXCEED 150MM) IN SUB-BASE OF ROAD BELOW SOLING, WATERING AND COMPACTION WITH 8-10 T POWER ROLLER COMPLETE. RATE SHALL INCLUDE TRANSPORTATION, ROYALTY, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE ETC.	CUM	1760			
SEC. A	10	PROVIDING AND LAYING SOLING 230 MM COMPACTED THICK WITH 150 -200 MM THICK BOULDER SIZE AND FILLING OF VOIDS WITH HAND BROKEN METAL OF SIZE 40-60 MM , SPREADING & PACKING MURRUM , ROLLING AND COMPACTION INCLUDING WATERING, WITH 8 - 10 MT CAPACITY ROAD ROLLER.	CUM	1350			
SEC. A	11	PROVIDING 150 MM COMPACTED THICK WATER BOUND MACADAM (WBM) IN TWO LAYERS OF EACH 75 MM, WITH 40MM TO 60MM METAL (STONE AGGREGATE) INCLUDING SUPPLYING AND SPREADING GRAVEL/MURRUM OVER THE SOLING/CONSOLIDATED BASE, COMPACTION THE SAME WITH POWER ROLLER INCLUDING NECESSARY LABOUR, WATERING, MATERINGS ETC. COMPLETE, ALL AS PER RELEVANT SPECIFICATIONS AND DIRECTIONS OF BHEL ENGINEER (RATE SHALL BE INCLUSIVE OF ALL LABOUR, MATERIALS ETC., COMPLETE).	CUM	880			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC. A	12	PROVIDING AND LAYING OF PLAIN CEMENT CONCRETE OF MIX 1:4:8 USING 20MM & DOWN SIZE HARD BROKEN GRANITE STONE JELLY FOR DRAINS, CULVERTS ETC. INCLUDING SHUTTERING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	CUM	190			
SEC. A	13	PROVIDING AND LAYING OF RCC OF MIX 1:2:4 USING 20MM DOWN SIZE HARD BROKEN GRANITE STONE AGGREGATE FOR RCC SLAB OF CULVERT, RCC COPING OVER BRICK WALL OF DRAIN INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK AND CENTERING AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER	CUM	30			
SEC. A	14	PROVIDING AND FIXING OF REINFORCEMENT INCLUDING CUTTING, BENDING AND FABRICATION OF REINFORCEMENT USING HIGH TENSILE TOR STEEL (Fe-415) AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER INCLUDING COST OF ALL LEADS, LIFT AND MATERIALS, LABOUR AND MS BINDING WIRE 18/20 GAUGE ETC. COMPLETE.	MT	4			
SEC. A	15A	PROVIDING BRICK WORK IN CM 1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 WITH LOCALLY AVAILABLE BURNT CLAY BRICKS (MIN STRENGTH 35 KG/CM²) AS PER DRAWING AND SPECIFICATION FOR DRAINS, CULVERTS , WATER TANK AND WHERE REQUIRED INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER .	CUM	323			
SEC. A	15B	PROVIDING BRICK WORK IN CM 1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 WITH FLY ASH LIME BRICKS (FAL-MIN STRENGTH 35 KG/CM²) AS PER DRAWING AND SPECIFICATION FOR DRAINS, CULVERTS, WATER TANK AND WHERE REQUIRED INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER .	CUM	108			
SEC. A	16	PROVIDING AND PLASTERING WITH CEMENT MORTAR 1:6 (12MM THICK) OVER BOTH INTERNAL AND EXTERNAL FACES OF BRICKWORK AND CONCRETE SURFACES ETC. OF ALL HEIGHTS INCLUDING PREPARING THE SURFACE, RAKING JOINTS, SCAFFOLDING, CURING, COST OF ALL MATERIALS, LABOUR ETC. COMPLETE.	SQM	2520			
SEC. A	17	40MM THICK COPING OVER THE DRAIN WALL AND WATER TANK WALL TOP USING MIX - 1:2:4	CUM	25			
SEC. A	18	PROVIDING 2 MM THICK NEAT CEMENT FINISH OVER CONCRETE BASE FOR FLOORING PAVING AND INTERNAL SURFACE OF BRICK DRAINS AND WATER TANK ETC.	SQM	2520			
SEC. A	19	PROVIDING & FIXING OF WEEP HOLES WITH 75MM DIA. AC PIPES AT 3M C/C ON BOTH SIDES OF DRAIN WALL WITH FILTER MEDIA USING 40MM SIZE STONE GRIT OF SIZE (300X300X300MM).	RM	300			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC. A	20	SUPPLYING & FIXING IN POSITION OF RCC HUME PIPE OF NP2 WHEREVER DRAIN CROSSES THE ROADS INCLUDING ALIGNING, LEVELLING ETC. COMPLETE AS PER THE DIRECTION OF ENGINEER. INCLUDING P.C. & INCLUDING COLLAR JOINTS, ENCASEMENT WITH CONCRETE 1:3:6 OF 300 MM DIA , ENCASING SHALL BE PAID EXTRA UNDER RESPECTIVE ITEMS OF CONCRETE..					
SEC. A	20A	400 MM DIA.	RM	60			
SEC. A	20B	600 MM DIA.	RM	30			
SEC. A	21	PROVIDING AND FIXING BARBED WIRE FENCING AROUND OPEN STORAGE YARD AS PER BHEL DRAWING . POSTS SHALL BE SPACED AT 3M CENTRES AND STRUTS AT 30M CENTRES AND AT ALL TURNINGS WITH FOUNDATIONS, SUPPLYING AND FIXING GI BARBED WIRES, 10 HORIZONTAL LINES, TWO DIAGONALS BETWEEN POSTS BY MEANS OF GI STAPLES AS PER STANDARD PRACTICE. THE BARBED WIRE SHALL CONFORM TO IS 278 AND BE MADE OF TWO STRANDS OF GALVANISED TWISTED 2.5MM DIA (12.5 GAUGE) STEEL WIRE WITH FOUR POINT BARS. RATE QUOTED SHALL BE INCLUSIVE OF EXCAVATION, DISPOSAL OF SURPLUS EARTH, CONCRETE (1:3:6), FORM WORK AND ALL MATERIALS, COST OF POSTS, BARBED WIRES, TRANSPORTING, FIXING IN POSITION ETC. INCLUDING COST OF ALL LABOUR AND TWO COATS OF ENAMEL PAINT OF APPROVED SHADE WITH A SHOP COAT OF PRIMER IN ALL STRUCTURAL MEMBERS ETC COMPLETE.	RM	795			
SEC. A	22	REMOVAL OF WILD GROWTH , BUSHES VEGETATIONS AND DISPOSAL AS PER INSTRUCTION WITHIN THE PLANT BOUNDARY (SIZE OF STEM FROM 150MM TO 600MM DIA.)	NOS	100			
SEC. A	23	SUPPLY FABRICATION, AND FIXING IN POSITION OF MS GATES WITH STRUCTURAL/TUBULAR STEEL FRAMES AS PER BHEL DRAWING INCLUDING COST OF FOUNDATION & POSTS, PAINTING TWO COATS BY SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER, COST OF ALL MATERIALS, LABOUR, TRANSPORT ETC. COMPLETE.	MT	5			
SEC. A	24	SUPPLYING AT SITE OF WORK, TRENCHING, CARRYING TO TRENCHES AND LOWERING INTO TRENCHES AND ON WALLS, FLOORS ETC., LAYING TO PROPER ALIGNMENT, GRADE, LEVEL AND JOINTING WITH ALL NECESSARY SPECIALS, TEES, ELBOWS, UNIONS AND APPURTENANCES AND INCLUDING PRESSURE TESTING OF THE FOLLOWING SIZES OF GI PIPE LINES INCLUDING REFILLING OF TRENCHES WITH EXCAVATED EARTH IN LAYERS, WATERING AND RAMMING AND RESTORATION OF GROUND, ALL COMPLETE AS PER SPECIFICATIONS. RATE TO INCLUDE EARTH WORK EXCAVATION IN ALL SOILS, EXCEPT HARD ROCK REQUIRING BLASTING , SHORING, BALLING OR PUMPING OUT OF WATER WHEREVER REQUIRED, REMOVAL OF SLUSH ETC. REMOVING AND DEPOSITING SURPLUS EARTH AS DIRECTED BY THE BHEL ENGINEER INCLUDING ALL LEADS AND LIFTS AS PER SITE CONDITIONS.					
SEC. A	24A	40MM DIA GI PIPE LINE WITH ALL SPECIALS	RM	330			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MWe NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC. A	24B	25MM DIA GI PIPE LINE WITH ALL SPECIALS	RM	130			
SEC. A		CONSTRUCTION OF RAISED CONCRETE PLATFORM OF 8M WIDE AND75M LONG -- 1NO.					
SEC. A	25	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH IN ALL KINDS OF SOIL (EXCEPT SOFT ROCK AND HARD ROCK) FOR FOUNDATIONS, RAMPS ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	CUM	365			
SEC. A	26	PROVIDING & FILLING OF 300MM COMPACTED THICK GRANULAR MURUM IN LAYERS (THICKNESS OF EACH LAYER SHOULD NOT EXCEED 150MM) IN THE BASE OF SOLING INCLUDING WATERING AND COMPACTION WITH 8-10 T POWER ROLLER COMPLETE. RATE SHALL INCLUDE TRANSPORTATION, ROYALTY, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE ETC.	CUM	190			
SEC. A	27	PROVIDING AND LAYING SOLING 250 MM COMPACTED THICK WITH 150 -200 MM THICK BOULDER SIZE AND FILLING OF VOIDS WITH HAND BROKEN METAL OF SIZE 40-60 MM , SPREADING & PACKING MURRUM , ROLLING AND COMPACTION INCLUDING WATERING, WITH 10-12 MT CAPACITY ROAD ROLLER.	CUM	160			
SEC. A	28	PROVIDING AND LAYING OF 150MM THICK PLAIN CEMENT CONCRETE OF MIX 1:3:6 BY USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY WITH TROWEL FINISH & REQUIRED CAMBER/SLOPE FOR RAISED CONCRETE PLATFORM ETC. INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	CUM	95			
SEC. A		TOTAL VALUE OF SECTION-A IN Rs.					

BHEL:PSWR:NAGPUR

RATE SCHEDULE, SECTION - B

NAME OF WORK:- ILLUMINATION OF OPEN STORAGE YARD 25,000 SQM AT 2X700MWe NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
---------	-------	---------------------	------	------	----------------------------	---------------	--------

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC B	1	<p>SUPPLY & INSTALLING 3 PHASE METERING AND POWER DISTRIBUTION BOARD COMPLETE WITH :</p> <p>(1) INCOMING SFU TPN 400 AMPS- 1NO, (2) OUTGOING SFU TPN 200 AMPS -2NOS. (3) OUTGOING SFU TPN 100 AMPS -2NOS. (4) OUTGOING SFU TPN 32 AMPS -2NOS.</p> <p>3 PHASE ELECTRONIC ENERGY METER - BHEL / L&T / GEC MAKE. AMMETER, VOLTMETER AND SELECTOR SWITCHES FOR BOTH - AE AND KAYCEE MAKE. PHASE INDICATION LAMPS, HRC FUSES FOR IC AND OG FEEDERS, CABLE GLANDS, POWER TERMINALS FOR CABLES TERMINATION, CABLE LUGS AND PROVISION FOR DOUBLY EARTHING THE PANEL ENCLOSURE.</p> <p>PANEL ENCLOSURE SHALL BE MADE OF SHEET METAL THICHNNES NOT LESS THAN 1.6 MM AND SUITABLE FOR OUT DOOR INSTALLATION, MODULAR CONSTRUCTION, HINGED DOOR WITH LOCKING ARRANGEMENT, BASE FRAME, SHOULD HAVE SLOPPED CANOPY, DULY PAINTED WITH FIRST COAT OF PRIMER AND TWO COATS OF SYNTHETIC ENAMEL PAINT (INTERIOR WITH WHITE PAINT AND EXTERIOR WITH LIGHT GREY AS PER SHADE 5, IS 630) INTERNAL POWER DISTRIBUTION TO DEVICES SHALL BE WITH AL BUSBARS OR COPPER FLEXIBLE SINGLE CORE PVC CABLES OF 1.1 KV GRADE, CONTROL WIRING WITH 1.5 SQMM, SUITABLE STOOL MADE OUT OF MS STRUCTURE OF 1.2 METER HIGH FOR MOUNTING OF PANEL WITH ANCHORING ARRAGEMENT AT FOUNDATION, SUITABLE FOR BOTTOM ENTRY OF CABLES.</p>	NOS.	1			
SEC B	2	<p>PROVIDING SUITABLE FOUNDATION FOR MOUNTING AC DISTRIBUTION BOARD AS SPECIFIED IN SL. NO.15 , INSTALLATION & COMMISSIONING OF PANEL</p>	NOS.	1			
SEC B	3	<p>SUPPLY OF 415 VOLT AC, 3 PHASE /FOUR WIRE POWER FEEDER PILLAR BOARD , BOARD SHALL BE COMPRISES OF THREE NUMBER AND ONE NUMBER ALUMINIUM BUS BAR FOR PHASE & NEUTRAL RESPECTIVELY. BUS BAR RATING SHALL BE 200 AMPS AND SHALL BE MOUNTED ON EPOXY INSULATOR OF 1.1 KV GRADE, EACH BUS BAR SHALL HAVE DRILLED HOLE FOR CONNECTING INCOMING / OUT GOING CABLES, PROVISION FOR EARTHING THE PANEL ENCLOSURE. PANEL ENCLOSURE SHALL BE MADE OF SHEET METAL THICHNNES NOT LESS THAN 1.6 MM AND SUITABLE FOR OUT DOOR INSTALLATION, HINGED DOOR WITH LOCKING ARRAGEMENT , BASE FRAME , SHOULD HAVE SLOPPED CANOPY, DULY PAINTED WITH FIRST COAT WITH PRIMER AND TWO COATS OF SYNTHETIC ENAMEL PAINT (INTERIOR WITH WHITE PAINT AND EXTERIOR WITH SMOKE GREY AS PER IS), SUITABLE STOOL MADE OUT OF MS STRUCTURE OF 1.2 METER HIGH FOR MOUNTING OF PANEL WITH ANCHORING ARRAGEMENT AT FOUNDATION .</p>	NOS.	1			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC B	4	PROVIDING SUITABLE FOUNDATION FOR MOUNTING 415 VOLT AC POWER FEEDER PILLAR BOARD AS SPECIFIED IN SL. NO.12 , INSTALLATION & COMMISSIONING OF PANEL	NOS.	1			
SEC B	5	SUPPLYING, INSTALLATION & COMMISSIONING OF SODIUM VAPOUR LAMP STREET LIGHT FITTING 150 WATT SSG-2315 IH OF CROMPTON OR SIMILAR PHILIPS MAKE, COMPLETE WITH ONE PIECE CANOPY, INTEGRAL CONTROLGEAR COMPRISING OF COPPER WOUND CHOKE , IGNITOR , HPF CAPACITOR, HPSV LAMP AND SUITABLE FOR DIRECTLY SLIPPING OVER LIGHT MOUNTING BRACKET MADE OUT OF 40 MM OD PIPE AND SUITABLE FOR LAMPS, CONTROL GEAR BOX CABLING & TERMINATION OF ITEMS SUPPLIED (TO BE MOUNTED ON 9 MTR POLE - ITEM NO. 2).	NOS.	23			
SEC B	6	SUPPLY AND ERECTING STEEL TUBULAR SWAGED POLES, 9 MTR LONG MADE OF SHEET STEEL HAVING ULTIMATE TENSILE STRENGTH 42 KG F/SQ.MM CONFIRMING TO BIS :2713 (RPART-II) COMPLETE WITH 300X300X6 MM THICK M. S. BASE PLATE FOR WELDING AT SITE AND SIZE AS PER CONFIGURATION GIVEN IN BIS FOR 410 SP-28 (113 KG- POLE WEIGHT) WITH 1.5 MTR. DEEP EXACAVATION, CONCRETING IN 1:4:8 RATIO SIZE 45 CMS X 45 CMS X 150 CMS AND POLE PLINTH IN 1:3:6 CEMENT CONCRETING HAVING 300 MM HEIGHT AND 300 MM DIA .INCLUDING DOUBLE EARTHING OF POLE WITH SUITABLE ARRANGEMENT, DULY PAINTED WITH TWO COATS OF RED OXIDE PAINT AND ONE COAT OF ALUMINIUM PAINT TO BE APPLIED AFTER ERECTION; THE LENGTH OF POLE BELOW GROUND TO BE PAINTED WITH TWO COATS OF BLACK BITUMINUS PAINT. THE POLE SHALL BE COMPLETE WITH JB, FUSE AND MINOR FABRICATION AS BELOW : I) DRILING 20 MM DIA HOLE AT ABOUT 2.5 MTR FROM GROUND LEVEL FOR WIRE LEADS FROM JUNCTION BOX TO LIGHT FIXTURE . II) DRILING 15MM DIA HOLES AT ABOUT 0.7 AND AT 2.5 MTR FROOM GROUND LEVEL AND WELDING 12 MM NUTS FOR USING A 12 MM G.I BOLT FOR FASTENING EARTH CONDUCTERS. III) WELDING REQUIORED HOLES FOR FIXING POLE CAP OF STREET LIGHT BRACKET. IV) WELDING DIAMETRALLY 10 MM M.S. ROUND 30 MM BELOW POLE TOP EDGE FOR CLIPPING WIRE LEADS .	NOS.	28			
SEC B	7	SUPPLY OF WEATHER PROOF FLOOD LIGHT LUMINIARIES OF CROMPTON MAKE (FBD 1425/40-WITH HIGH PRESSURE SODIUM VAPOUR LAMP 1X 400 WATT ALONG WITH NON-INTEGRAL TYPE CONTROL GEAR BOX HAVING ADEQUATE NUMBER OF TERMINAL CONNECTORS FOR TERMINATING TWO CABLE OF 3X 10 SQMM AL AND SUITABLE FOR OUT DOOR APPLICATION) OR EQUIVALENT IN BAJAJ, PHILLIPS ONLY , INCLUDING SUPPLY & FIXING CABLES BETWEEN THE CONTROL GEAR BOX AND LIGHT LUMINIARIES AND MOUNTING FIXTURE WITH HARDWARE FOR MOUNTING OF LIGHT LUMINIARIES AND CONTROL GEAR BOX ON POLE TYPE 410 SP-28.	NOS.	5			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC B	8	INSTALLATION & COMMISSIONING OF FLOOD LIGHT LUMINIARIES , CONTROL GEAR BOX , CABLING & TERMINATION FOR SR.NO.03 (ITEMS SUPPLIED ABOVE)	NOS.	5			
SEC B	9	ENGINEERING , SUPPLY AND INSTALLATION OF LATTICE TYPE STRUCTURAL TOWER OF HEIGHT 15M .TOWER SHALL BE FABRICATED IN THREE SECTION OF EQUAL LENGHT OF 5 METER EACH.PREPARATION OF FABRICATION DRAWING & ITS APPROVAL FROM BHEL. BRIEF DETAILS ARE AS GIVEN BELOW : TOWER SHALL BE ADEQUATELY STRONG TO WITHSTAND HEAVY WIND . NO STAY/GUY ROPES SHALL BE TIED WITH IT. AT TOP OF THE TOWER ADEQUATE SIZE OF PLATEFORM SHALL BE PROVIDED WITH RAILING AROUND THE PLATFORM FOR MOUNTING OF LIGHTING LUMINIARIES(TENTATIVELY TWEVEL FITTING ON EACH TOWER) AND MAITENANCE PURPOSE , FLOOR OF PLATFORM SHALL BE COVERED WITH CHEQURED PLATE. A LADDER ALONG WITH PROTECTIVE CAGE SHALL BE PROVIDED ALONG THE HEIGHT OF TOWER. IT SHOULD BE PAINTED WITH ONE COAT RED OXIDE PRIMER AND TWO COATS OF ALUMINIUM PAINT AFTER INSTALLATION. EACH TOWER SHALL BE PROVIDED WITH POWER DISTRIBUTION BOX OUT DOOR TYPE AND SHOULD HAVE PROVISION OF TERMINATING ONE NUMBER INCOMING AND EIGHT OUT GOING CABLE .ERECTING AT SITE INCLUDING ALL CIVIL WORKS LIKE EXCAVATION, CASTING OF FOUNDATION OF REQUIRED SIZE AND DEPTH WITH CONCRETE OF GRADE 1:2:4 WITH BASE PLATES, GROUTING OF LATTICE STRUCTURE, ONE EARTH PIT AS PER BIS STANDARD IS TO BE MADE NEAR THE TOWER AND EARTHING OF THE TOWER INCLUDING SUPPLY OF MATERIAL ETC. COMPLETE.	NOS.	1			
SEC B	10	SUPPLY, INSTALLATION & COMMISSIONING OF FLOOD LIGHT LUMINIARIES OF BAJAJ MAKE TYPE BGENF 22 OR EQUIVALENT IN CROMPTON , PHILLIPS ONLY, EACH LUMINIARIES SHALL BE WITH TWO NUMBER 400 WATT HPSV LAMPS AND CONTROL GEAR BOX INTEGRAL/ NON ITEGRAL TYPE INCLUDING CABLES FOR INTERCONNECTION . (THESE FITTING SHALL BE MOUNTED ON LIGHTING MAST /TOWER , ON EACH TOWER 8 SUCH FITTING SHALL BE MOUNTED).	NOS.	8			
SEC B	11	SUPPLY OF CABLES 3 -1/2 COREX 185 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 (PART -I)	RM	450			
SEC B	12	INSTALLATION OF CABLES 3 -1/2 COREX 185 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC. CABLES ARE TO BE LAID FROM TRANSFORMER SUB STATION TO 415 VOLT AC DISTRIBUTION BOARD.	RM	450			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC B	13	SUPPLY OF CABLES 3-1/2 CORE X 95 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 (PART -I) (TO BE USED FORM SHEDS AS WELL AS OPEN STORAGE YARD WHEREVER REQUIRED)	RM	240			
SEC B	14	INSTALLATION OF CABLES 3 -1/2 CORE X 95 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND, EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC COMPLETE. CABLES ARE TO BE LAID FROM 415 VOLT AC DISTRIBUTION BOARD TO FEEDER PILLAR BOARD .	RM	240			
SEC B	15	SUPPLY OF CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 (PART -I)	RM	120			
SEC B	16	INSTALLATION OF CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC. CABLES ARE TO BE LAID FROM FEEDER PILLER TO HIGH MAST TOWER	RM	120			
SEC B	17	SUPPLY OF CABLES 2 CORE X 10 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I)	RM	1200			
SEC B	18	INSTALLATION OF CABLES 2 CORE X 10 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC COMPLETE. CABLES ARE TO BE LAID FROM 415 VOLT AC POWER FEEDER PILLAR BOARD TO LIGHTING POLES & POLE TO POLE	RM	1200			
SEC B	19	SUPPLY AND INSTALLATION SUITABLE ELECTRICAL PUMP FOR MINIMUM HEAD OF 10M (BUT NOT LESS THAN 2 H.P.) OF REPUTED MANUFACTURER LIKE SUGUNA/ CRI/ KILOSKAR/ SHAKTI/SHARP/ CROMPTON INCLUDING ALL ACCESSORIES, STARTER, D.B., ETC. AND TO BE CONNECTED TO OVER HEAD TANK FROM WATER STORAGE TANK BELOW G.L. GURRANTY/WARRANTY CARD TO BE SUBMMITTED TO BHEL. SUCTION, DISCHARGE GI PIPES SHALL BE PAID SEPERATLY UNDER RELEVANT ITEMS.	NOS.	1			
SEC B		TOTAL VALUE OF SECTION-B IN Rs.					

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MWe NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
BHEL:PSWR:NAGPUR							
RATE SCHEDULE, SECTION - C							
NAME OF WORK: CONSTRUCTION OF 1 NO. - CLOSED STORAGE SHEDS (60 M X 15 M) AT AT 2X700MWe NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC C	1A	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH IN ALL KINDS OF SOIL (EXCEPT SOFT ROCK AND HARD ROCK) FOR FOUNDATIONS, RAMPS ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	CUM	310			
SEC C	1B	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH FOR SOFT ROCK AND HARD ROCK (BY MANUALLY OR MECHANICALLY BUT WITHOUT BLASTING) FOR FOUNDATIONS, RAMPS ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	CUM	80			
SEC C	1C	EARTH WORK EXCAVATION FROM 2.0M TO 4.0 M DEPTH IN ALL KINDS OF SOIL (EXCEPT HARD ROCK AND SOFT ROCK) FOR FOUNDATIONS, RAMPS ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	CUM	15			
SEC C	1D	EXCAVATION IN ALL KINDS OF SOIL INCLUDING SOFT & HARD ROCK ((BY MANUAL CHISELING OR BY MECHANICAL MEANS BUT WITHOUT BLASTING) FROM 2 TO 4M DEPTH FOR FOUNDATIONS, RAMPS ETC) WHEREVER REQUIRED INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	CUM	30			
SEC C	1E	SUB GRADE PREPARATION: CUTTING & DISPOSAL OF GRASS, VEGITATIONS, BUSHES, TREES (GIRTH LESS 300MM), LEVELLING, WATERING AND CONSOLIDATION (90% OF PROCTOR DENSITY) BY MEANS OF 10-12 MT CAPACITY POWER/VIBRO ROLLER FOR SUB BASE PREPARATION. THIS WILL INCLUDE AVERAGE CUTTING & FILLING UP TO ± 250MM THICK, GRADING THE AREA WITH PROPER SLOPE FOR DRAINING OUT THE RAIN WATER WITH ALL T&P, LABOURS, MATERIALS, DEWATERING (IF REQUIRED) ETC. COMPLETE.	SQM	120			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC C	2	DISPOSAL OF EXCAVATED EARTH/ROCK (NOT SUITABLE FOR BACK FILLING) BEYOND INITIAL LEAD OF 50M AND UPTO A MAXIMUM LEAD OF 2 KM OR PART THEREOF INCLUDING LOADING, UNLOADING , TRANSPORTING AND SPREADING AS PER DIRECTION OF BHEL ENGINEER .	CUM	115			
SEC C	3	BACKFILLING OF FOUNDATION ,FLOORS AND PLINTH IN LAYERS NOT EXCEEDING 150MM THICK. INCLUDING WATERING AND CONSOLIDATING ETC. COMPLETE AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.					
SEC C	3A	WITH GOOD EXCAVATED SOIL AVAILABLE FROM THE EARTH WORK.	CUM	320			
SEC C	3B	WITH GRANULAR MURUM IN LAYERS (THICKNESS OF EACH LAYER SHOULD NOT EXCEED 150MM) BELOW FOUNDATIONS AND RAMP AS PER STANDARD SPECIFICATION, RELEVANT DRAWINGS AND INSTRUCTED BY BHEL ENGINEER INCLUDING ROYALTY. CONTRACTOR HAS TO SUBMIT ROYALTY CERTIFICATE FROM CONCERNED STATE GOVT. MINING DEPARTMENT	CUM	40			
SEC C	3C	WITH GOOD EARTH BROUGHT FROM OUTSIDE FROM CONTRACTOR'S OWN SOURCE INCLUDING ROYALTY ETC.	CUM	80			
SEC C	3D	PROVIDING STONE SOLING OF REQUIRED THICKNESS AS PER DRAWING BELOW FLOORING, RAMP, COLUMN FOUNDATIONS OF STORAGE SHED ETC. BY USING 80 MM SIZE HARD BROKEN BLACK GRANITE/QUARTZITE/GNEISS/TRAP STONE METAL INCLUDING GRANULAR MURRUM PACKING, WATERING & COMPACTION ETC COMPLETE.AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER	CUM	275			
SEC C	4	PROVIDING AND LAYING OF PLAIN CEMENT CONCRETE OF MIX 1:4:8 USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY FOR FOUNDATION, FLOORING, COLUMN ETC. INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	CUM	20			
SEC C	5	PROVIDING AND LAYING OF 100 MM THICK PLAIN CEMENT CONCRETE OF MIX 1:3:6 USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY WITH TROWEL FINISH FOR PLINTH PROTECTION WITH TROWEL FINISH INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	CUM	105			
SEC C	6	PROVIDING AND LAYING OF RCC MIX 1:2:4 USING OPC GRADE 43/53, 20MM DOWN SIZE HARD BROKEN GRANITE STONE AGGREGATE INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK & CENTERING AS PER DRAWING AND SPECIFICATION AND DIRECTED BY BHEL ENGINEER BUT EXCLUDING COST OF REINFORCEMENTS.	CUM	110			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC C	7	PROVIDING AND LAYING DPC (DAMP PROOF COURSE) 50MM THICK IN 1:2:4 CEMENT CONCRETE LAYER USING OPC GRADE 43/53 AND WITH 6MM DOWN AGGREGATE, INCLUDING FORMWRK, BITUMEN FELT USING CEMENT WITH WATER PROOFING COMPOUND ETC. COMPLETE	SQM	50			
SEC C	8	PROVIDING , CUTTING, BENDING AND FIXING IN POSITION REINFORCEMENT OF VARIOUS DIA. USING HIGH TENSILE TOR STEEL (Fe -415/500) FOR FOUNDATIONS, COLUMNS, BEAMS, FLOORS, SUNSHED, SLAB ETC. AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER INCLUDING COST OF ALL MATERIALS, LEADS, LIFT, LABOURS, MS BINDING WIRE 18/20 GAUGE, TACK WELDING AND SUPPORTING AS REQUIRED COMPLETE.	MT	7			
SEC C	9A	PROVIDING BRICK WORK IN CM 1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND LOCALLY AVAILABLE BURNT CLAY BRICKS (MIN STRENGTH 35 KG/CM ²) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, SUPER STRUCTURE, SEPTIC TANK ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	CUM	125			
SEC C	9B	PROVIDING BRICK WORK IN CM 1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND FLY ASH LIME BRICKS (MIN STRENGTH 35 KG/CM ²) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL, SEPTIC TANK ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	CUM	45			
SEC C	10	DESIGN, SUPPLY, FABRICATING, AND ERECTION OF TUBULAR TRUSSES (BY USING CLASS B , MEDIUM QUALITY PIPE) AS PER BHEL DRAWING WITH PPGI ROOFING SHEETS AND WIND TIES (USING FLAT OF SIZE 40X5MM) TO BE PROVIDED ABOVE SHEETS AND PROVIDING AND FIXING BASE PLATES WITH HOLDING DOWN BOLTS ON RCC COLUMNS, GUSSETS, RIBS, PINS, SPLICES ETC. AS REQUIRED INCLUDING TRANSPORT, LOADING, UNLOADING CHARGES FROM FABRICATION SHOP TO SITE ETC. COMPLETE. RATE IS INCLUSIVE OF ALL MATERIALS, LOADING & UNLOADING, FABRICATION, FIXING IN POSITION, LABOUR CHARGES, T&Ps AND COST OF RED OXIDE PRIMER AT FACTORY AND TWO COATS OF SYNTHETIC ENAMEL PAINTS (OVER PRIMER COAT OF RED OXIDE) OF APPROVED COLOUR AND QUALITY AT SITE. HALLOW TRUSS (OUTER MAIN FRAME EXCEPT VERTICAL & CROSS BRACING/TUBES/CROSS STUD) SHALL BE PROVIDED ON BOTH SIDE OF GABLE END TO FIX THE PURLINS AND ROOFING MATERIAL.	MT	16			
SEC C	11	PROVIDING AND FIXING 0.5MM THICK PPGI SHEETS OVER THE ROOF OF OFFICE BUILDING AS PER BHEL DRAWING INCLUDING GALVANISED IRON J OR L HOOK , BOLTS, BITUMINOUS WASHERS, GI CRAMP BOLTS, NUTS, SCAFFOLDING ETC. COMPLETE, ALL AS PER LATEST IS 459, 3307 AND 730.	SQM	1055			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC C	12	PROVIDING AND FIXING OF TRANSLUCENT RMP/FRP (FIBRE GLASS REINFORCED PLASTIC) SHEETS - 2.00 MM THICK OF APPROVED MAKE INCLUDING COST OF GI J OR L HOOKS, BOLTS, NUTS, WASHERS, BITUMEN WASHERS, SCAFFOLDING ETC. COMPLETE SO AS TO MATCH WITH PPGI ROOFING SHEETS.	SQM	70			
SEC C	13	SUPPLYING, MANUFACTURING AND FIXING IN POSITION OF STEEL VENTILATORS INCLUDING FRAMES & IRON BARRED (GUARD BAR OF SQUARE SECTION @ 100 MM C/C) AND GLAZED WITH 4MM PLAIN GLASS AS PER STANDARD SPECIFICATIONS & RELEVANT IS CODE AND INSTRUCTIONS OF BHEL ENGINEER. THE COST SHALL BE INCLUSIVE OF ALL ACCESSORIES FITTINGS, HOLD FASTS, PAINTING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER ETC. COMPLETE.					
SEC C		STEEL LOUVERED VENTILATORS :-	SQM	9			
SEC C	14	PROVIDING AND FIXING OF IPS FLOORING 40MM THICK USING OPC GRADE 43/53 WITH CEMENT CONCRETE 1:2:4 (USING 12 MM DOWN AGGREGATES) AS PER STANDARD PRACTICE IN PANELS OF SIZE NOT EXCEEDING 2.0 x 2.0 SQ.M BY PROVIDING, FIXING GLASS STRIPS 40MM WIDE & 4MM THICK INCLUDING CURING & CLEANING.	SQM	920			
SEC C	15	PROVIDING 2MM THICK NEAT CEMENT FINISH USING OPC GRADE 43/53 OVER CONCRETE BASE FOR FLOORING, PAVING ,PLASTERED SURFACE ETC.INCLUDING CURING & CLEANING AND SCAFFOLDING COMPLETE.	SQM	920			
SEC C	16	PROVIDING PLASTERING WITH CEMENT MORTAR -1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 OVER BOTH INTERNAL AND EXTERNAL FACES OF BRICKWORK AND CONCRETE SURFACES, PARTITION WALLS ETC. AT ALL LEVELS INCLUDING PREPARING THE SURFACE, RAKING JOINTS, SCAFFOLDING, CURING, COST OF ALL MATERIALS, LABOUR ETC. COMPLETE.					
SEC C	16A	EXTERNAL PLASTERING - 18MM THICK	SQM	960			
SEC C	16B	INTERNAL PLASTERING -12MM THICK	SQM	860			
SEC C	17A	PROVIDING & APPLYING COLOUR WASH -THREE COATS ON NEWLY PLASTERED EXTERNAL SURFACE OF SHED BY USING BEST SHALL LIME TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , COLOURING AGENT, BASE COAT OF WHITE WASH,APPROVED ADHESIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	SQM	960			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW_e NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC C	17B	PROVIDING & APPLYING WHITE WASH - THREE COATS ON NEWLY PLASTERED INTERNAL SURFACE OF SHED BY USING BEST SHALL LIME TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , COLOURING AGENT, APPROVED ADDESSIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	SQM	860			
SEC C	18	MANUFACTURING, SUPPLYING AND FIXING OF 20 GAUGE MS ROLLING SHUTTERS OF SIZE 5M X 5 M AS PER I.S. SPECIFICATIONS, COMPLETE, MECHANICALLY OPERATED FROM IN AND OUTSIDE BOTH AS INSTRUCTED BY BHEL ENGINEER INCLUDING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER LOCKING ARRANGEMENT. RATE SHALL BE INCLUSIVE OF ALL THE ABOVE COMPLETE.	SQM	30			
SEC C		TOTAL VALUE OF SECTION-C IN Rs.					

BHEL:PSWR:NAGPUR

RATE SCHEDULE, SECTION D

NAME OF THE WORK : INTERNAL ELECTRIFICATION WORK OF 1 NOS. CLOSED SHEDS (60M X 15M) AT 2X700MW_e NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC D	1	SUPPLYING & FIXING WALL MOUNTING TYPE LIGHTING PANELS , EACH WITH : (1) INCOMING MCB TPN -32 AMPS - 1NO. (2) RCCB DP 32 AMPS - 3NOS (3) MCB SP 6AMPS - 30 NOS. ALL MCBS AND RCCBS SHALL BE OF MDS / INDO KOPP MAKE. LIGHTING PANEL SHALL BE SIEMENS/MDS/INDO KOPP MAKE WITH INTERNAL BUSBARS, 2 NOS. EARTHING TERMINALS, EARTH CONNECTIONS, INCLUDING GLANDS, LUGS & WIRING FROM MAIN DB.	SET	1			
SEC D	2	PROVIDING EARTHING PITS WITH 2 " DIA , 2 M LONG GI PIPES WITH FLANGE & GI WIRES WITH CHARCOAL, SALT AND AS PER THE STANDARD PRACTICE FOR ELECTRICAL CONNECTION.RATE SHALL BE INCLUSIVE OF ALL MATERIALS, LABOURS, ETC COMPLETE.	NOS.	1			
SEC D	3	PROVIDING & FIXING ALUMINIUM DISPERSIVE LUMINAIRE ENAMELED GREEN AND WHITE WITH CAST ALUMINIUM FLANGE AND NIPPLE SUITABLE FOR USE WITH GLS LAMP, DOME 12" DIAMETER, WITH HANGING BRACKET AND 200W GLS LAMP OF CROMPTON OR EQUIVALENT BAJAJ/PHILIPS MAKE, COMPLETE.	NOS.	35			
SEC D	4	WIRING WITH 2.5 SQ MM ISI MARK COPPER WIRE FOR ABOVE IN PVC CONDUIT ALONG WITH GI EARTH WIRE INCLUSIVE OF ALL MATERIAL, LABOUR ETC. COMPLETE	PER POINT	35			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW_e NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC D	5	SUPPLY OF CABLES 2 CORE X 10 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I)	RM	10			
SEC D	6	INSTALLATION OF CABLES 2 CORE X 10 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC COMPLETE. CABLES ARE TO BE LAID FROM 415 VOLT AC POWER FEEDER PILLAR BOARD TO LIGHTING POLES & POLE TO POLE	RM	10			
SEC D	7	SUPPLY OF CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 (PART -I)	RM	80			
SEC D	8	INSTALLATION OF CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC. CABLES ARE TO BE LAID FROM FEEDER PILLER TO HIGH MAST TOWER	RM	80			
SEC D		TOTAL VALUE OF SECTION-D IN Rs.					

BHEL:PSWR:NAGPUR

RATE SCHEDULE, SECTION - E

NAME OF THE WORK :CONSTRUCTION OF 1 NO. OF CLOSED SHED WITH STORE OFFICE (60MX15M) INCLUDING C&I STORE ROOM (15MX6M) AT 2X700MW_e NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC E	1A	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH IN ALL KINDS OF SOIL (EXCEPT SOFT ROCK AND HARD ROCK) FOR FOUNDATIONS, RAMPS ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	CUM	350			
SEC E	1B	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH FOR SOFT ROCK AND HARD ROCK (BY MANUALLY OR MECHANICALLY BUT WITHOUT BLASTING) FOR FOUNDATIONS, RAMPS ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	CUM	110			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC E	1C	EARTH WORK EXCAVATION FROM 2.0M TO 4.0 M DEPTH IN ALL KINDS OF SOIL (EXCEPT HARD ROCK AND SOFT ROCK) FOR FOUNDATIONS, RAMPS ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	CUM	20			
SEC E	1D	EXCAVATION IN ALL KINDS OF SOIL INCLUDING SOFT & HARD ROCK ((BY MANUAL CHISELING OR BY MECHANICAL MEANS BUT WITHOUT BLASTING) FROM 2 TO 4M DEPTH FOR FOUNDATIONS, RAMPS ETC WHEREVER REQUIRED INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	CUM	45			
SEC E	1E	SUB GRADE PREPARATION: CUTTING & DISPOSAL OF GRASS, VEGITATIONS, BUSHES, TREES (GIRTH LESS 300MM), LEVELLING, WATERING AND CONSOLIDATION (90% OF PROCTOR DENSITY) BY MEANS OF 10-12 MT CAPACITY POWER/VIBRO ROLLER FOR SUB BASE PREPARATION. THIS WILL INCLUDE AVERAGE CUTTING & FILLING UP TO ± 250MM THICK, GRADING THE AREA WITH PROPER SLOPE FOR DRAINING OUT THE RAIN WATER WITH ALL T&P, LABOURS, MATERIALS, DEWATERING (IF REQUIRED) ETC. COMPLETE.	SQM	125			
SEC E	2	DISPOSAL OF EXCAVATED EARTH/ROCK (NOT SUITABLE FOR BACK FILLING) BEYOND INITIAL LEAD OF 50M AND UPTO A MAXIMUM LEAD OF 2 KM OR PART THEREOF INCLUDING LOADING, UNLOADING , TRANSPORTING AND SPREADING AS PER DIRECTION OF BHEL ENGINEER .	CUM	170			
SEC E	3	BACKFILLING OF FOUNDATION ,FLOORS AND PLINTH IN LAYERS NOT EXCEEDING 150MM THICK. INCLUDING WATERING AND CONSOLIDATING ETC. COMPLETE AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.					
SEC E	3A	WITH GOOD EXCAVATED SOIL AVAILABLE FROM THE EARTH WORK.	CUM	200			
SEC E	3B	WITH GRANULAR MURUM IN LAYERS (THICKNESS OF EACH LAYER SHOULD NOT EXCEED 150MM) BELOW FOUNDATIONS AND RAMP AS PER STANDARD SPECIFICATION, RELEVANT DRAWINGS AND INSTRUCTED BY BHEL ENGINEER INCLUDING ROYALTY. CONTRACTOR HAS TO SUBMIT ROYALTY CERTIFICATE FROM CONCERNED STATE GOVT. MINING DEPARTMENT	CUM	40			
SEC E	3C	WITH GOOD EARTH BROUGHT FROM OUTSIDE FROM CONTRACTOR'S OWN SOURCE INCLUDING ROYALTY ETC.	CUM	35			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC E	3D	PROVIDING & FILLING IN SOAK PIT WITH BRICK BATS 40-80MM INCLUDING SAND PACKING ETC. COMPLETE, AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.	CUM	9			
SEC E	3E	PROVIDING STONE SOLING OF REQUIRED THICKNESS AS PER DRAWING BELOW FLOORING, RAMP, COLUMN FOUNDATIONS OF STORAGE SHED ETC. BY USING 80 MM SIZE HARD BROKEN BLACK GRANITE/QUARTZITE/GNEISS/TRAP STONE METAL INCLUDING GRANULAR MURRUM PACKING, WATERING & COMPACTION ETC COMPLETE.AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER	CUM	300			
SEC E	4	PROVIDING AND LAYING OF PLAIN CEMENT CONCRETE OF MIX 1:4:8 USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY FOR FOUNDATION, FLOORING, COLUMN ETC. INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	CUM	130			
SEC E	5	PROVIDING AND LAYING OF 100 MM THICK PLAIN CEMENT CONCRETE OF MIX 1:3:6 USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY WITH TROWEL FINISH FOR PLINTH PROTECTION AND WATER TANKWITH TROWEL FINISH INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	CUM	14			
SEC E	6	PROVIDING AND LAYING OF RCC MIX 1:2:4 USING OPC GRADE 43/53, 20MM DOWN SIZE HARD BROKEN GRANITE STONE AGGREGATE INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK & CENTERING AS PER DRAWING AND SPECIFICATION AND DIRECTED BY BHEL ENGINEER BUT EXCLUDING COST OF REINFORCEMENTS.	CUM	120			
SEC E	7	PROVIDING AND LAYING DPC (DAMP PROOF COURSE) 50MM THICK IN 1:2:4 CEMENT CONCRETE LAYER USING OPC GRADE 43/53AND WITH 6MM DOWN AGGREGATE, INCLUDING FORMWRK, BITUMEN FELT USING CEMENT WITH WATER PROOFING COMPOUND ETC. COMPLETE	SQM	75			
SEC E	8	PROVIDING , CUTTING, BENDING AND FIXING IN POSITION REINFORCEMENT OF VARIOUS DIA. USING HIGH TENSILE TOR STEEL (Fe -415/500) FOR FOUNDATIONS, COLUMNS, BEAMS, FLOORS, SUNSHED, SLAB ETC. AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER INCLUDING COST OF ALL MATERIALS, LEADS, LIFT, LABOURS, MS BINDING WIRE 18/20 GAUGE, TACK WELDING AND SUPPORTING AS REQUIRED COMPLETE.	MT	9			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC E	9A	PROVIDING BRICK WORK IN CM 1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND LOCALLY AVAILABLE BURNT CLAY BRICKS (MIN STRENGTH 35 KG/CM ²) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, SUPER STRUCTURE, SEPTIC TANK ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	CUM	165			
SEC E	9B	PROVIDING BRICK WORK IN CM 1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND FLY ASH LIME BRICKS (MIN STRENGTH 35 KG/CM ²) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL, SEPTIC TANK ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	CUM	90			
SEC E	10A	PROVIDING HALF BRICK WORK PARTITION WALL IN CM 1:4 (1 CEMENT & 4 COARSE SAND) USING OPC GRADE 43/53 AND LOCALLY AVAILABLE BURNT CLAY BRICKS (MIN STRENGTH 35 KG/CM ²) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL ETC INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, RAKING OUT JOINTS,CURING AS PER DRAWING AND DIRECTED BY BHEL ENGINEER.	SQM	5			
SEC E	10B	PROVIDING HALF BRICK WORK FOR PARTITION WALL IN CM 1:4 (1 CEMENT & 4 COARSE SAND) USING OPC GRADE 43/53 AND FLY ASH LIME BRICKS (FAL - MIN STRENGTH 35 KG/CM ²) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL ETC INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, RAKING OUT JOINTS,CURING AS PER DRAWING AND DIRECTED BY BHEL ENGINEER.	SQM	5			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC E	11A	DESIGN,SUPPLY,FABRICATION, AND ERECTION OF TUBULAR TRUSSES (BY USING CLASS B ,MEDIUM QUALITY PIPE) AS PER BHEL DRAWING WITH PPGI SHEETS AND WIND TIES (USING FLAT OF SIZE 40X5MM) TO BE PROVIDED ABOVE SHEETS AND PROVIDING AND FIXING BASE PLATES WITH HOLDING DOWN BOLTS ON RCC COLUMNS, GUSSETS, RIBS, PINS, SPLICES ETC. AS REQUIRED INCLUDING TRANSPORT, LOADING, UNLOADING CHARGES FROM FABRICATION SHOP TO SITE ETC. COMPLETE. RATE IS INCLUSIVE OF ALL MATERIALS, LOADING & UNLOADING, FABRICATION, FIXING IN POSITION, LABOUR CHARGES , T&Ps AND COST OF RED OXIDE PRIMER AT FACTORY AND TWO COATS OF SYNTHETIC ENAMEL PAINTS (OVER PRIMER COAT OF RED OXIDE) OF APPROVED COLOUR AND QUALITY AT SITE. HALLOW TRUSS (OUTER MAIN FRAME WITH CENTER POST EXCEPT OTHER VERTICAL & CROSS BRACING/TUBES/CROSS STUD) SHALL BE PROVIDED ON BOTH SIDE OF GABLE END TO FIX THE PURLINS AND ROFFING MATERIAL.	MT	16			
SEC E	11B	SUPPLY, FABRICATING, AND ERECTION OF STRUCTURAL STEEL STAGING (APPROX. Ht. 4.0M) FOR INSTALLATION OF PVC OVER HEAD WATER TANK (OHT) OF CAPACITY- 1000 LITRES. AS PER BHEL DRAWING . RATE IS INCLUSIVE OF ALL MATERIALS, LOADING & UNLOADING, FABRICATION, FIXING IN POSITION, LABOUR CHARGES , T&Ps AND COST OF RED OXIDE PRIMER AT FACTORY AND TWO COATS OF SYNTHETIC ENAMEL PAINTS (OVER PRIMER COAT OF RED OXIDE) OF APPROVED COLOUR AND QUALITY AT SITE.	MT	1			
SEC E	12	PROVIDING AND FIXING 0.5MM THICK PPGI SHEETS OVER THE LEAN TO ROOF OF TOILET/PANTRY BLOCK AS PER BHEL DRAWING INCLUDING GALVANISED IRON J OR L HOOK , BOLTS, BITUMINOUS WASHERS, GI CRAMP BOLTS, NUTS,SCAFOLDING ETC. COMPLETE, ALL AS PER LATEST IS 459, 3307 AND 730.	SQM	1020			
SEC E	13	PROVIDING AND FIXING OF TRANSLUCENT RMP/FRP (FIBRE GLASS REINFORCED PLASTIC) SHEETS - 2.00 MM THICK OF APPROVED MAKE INCLUDING COST OF GI J OR L HOOKS, BOLTS, NUTS, WASHERS, BITUMEN WASHERS, SCAFFOLDING ETC. COMPLETE SO AS TO MATCH WITH PPGI ROOFING SHEETS.	SQM	70			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW_e NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC E	14	PROVIDING AND FIXING OF FALSE CEILING OF 12.5 MM THICK TAPERED EDGE GYPSUM PLAIN BOARD CONFORMING TO IS:2095-PART I OF APPROVED QUALITY AND DESIGN OF SIZE 600x600 MM PANELS WITH SQUARE EDGES SUPPORTED BY ANODISED ALUMINIUM FRAMES OF TEES 35x23.5x1.5 MM THICK AS MAIN MEMBER AND 19x23.5x1.5 MM TEES AS CROSS SUPPORTING MEMBERS AND WALL ANGLES OF 23.5x23.5x1.5MM. THE MAIN RUNNERS SHALL BE SUSPENDED FROM ROOF AT 1200 MM CENTRE TO CENTRE BY MEANS OF MS RODS WITH GI 'J' THREADED HOOK FOR ADJUSTMENTS. THE CROSS RUNNERS SHALL BE FIXED TO MAIN RUNNER TO FORM 'A' GRID PATTERN OF 600x600MM AND PROVIDING 25 MM WIDE ALUMINIUM STRIP TEES OR MOULDED SECTIONS AT ALL JOINTS. THE RATE SHALL BE INCLUSIVE OF TWO COATS OF APPROVED OBD ON GYPSUM BOARD, SUPPLY & FIXING OF ALUMINIUM FRAME AND SCAFFOLDING ETC. COMPLETE.	SQM	195			
SEC E	15	PROVIDING AND FIXING OF BEST QUALITY COUNTRY WOOD DOORS COMPRISING OF FRAME 95 X 70MM AND 38/40MM THICK FLUSH SHUTTERS OF SOLID CORE TYPE USING COMMERCIAL PLY INCLUDING HOLD FASTS, WIND APPLIANCES, HANDLES, TOWER BOLTS AND ALDROPS, MORTISE OR SUITABLE LOCKS ETC. AS PER THE STANDARD PRACTICE AND APPLYING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED SHADE & COLOR OVER A COAT OF PRIMER AS DIRECTED BY BHEL ENGINEER.	SQM	20			
SEC E	16	PROVIDING AND FIXING OF BEST QUALITY PVC PANELLED DOORS OF THICKNESS 29MM, SINTEX/BAJAJ MAKE OR APPROVED EQUIVALENT FOR TOILETS INCLUDING ALL FITTINGS AND FIXTURES. MS ANGLE FRAME OF SIZE 40x40x6MM ETC. ALL COMPLETE AS PER DRAWINGS AND SPECIFICATIONS.	SQM	2			
SEC E	17	PROVIDING AND FIXING OF 18 GAUGE M.S. SHEET DOOR WITH FRAME WORK 40 X 40 X 6 MM M.S. ANGLE INCLUDING LOCKING ARRANGEMENTS, HOLD FAST , APPLYING ANTICORROSSIVE PRIMER COAT OF RED LEAD PAINT AND 2 COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR COMPLETE AS DIRECTED BY BHEL ENGINEER.	SQM	3			
SEC E	18	SUPPLING, MANUFACTURING AND FIXING IN POSITION OF STEEL WINDOWS AND VENTILATORS INCLUDING FRAMES & IRON BARRED (GUARD BAR OF SQUARE SECTION @ 100 MM C/C) AND GLAZED WITH 4MM PLAIN GLASS AS PER STANDARD SPECIFICATIONS & RELEVANT IS CODE AND INSTRUCTIONS OF BHEL ENGINEER. THE COST SHALL BE INCLUSIVE OF ALL ACCESSORIES FITTINGS, HOLD FASTS, PAINTING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER ETC. COMPLETE.					
SEC E	18A	STEEL WINDOWS	SQM	10			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC E	18B	STEEL LOUVERED VENTILATORS :-	SQM	10			
SEC E	19	PROVIDING AND FIXING OF IPS FLOORING 40MM THICK USING OPC GRADE 43/53 WITH CEMENT CONCRETE 1:2:4 (USING 12 MM DOWN AGGREGATES) AS PER STANDARD PRACTICE IN PANELS OF SIZE NOT EXCEEDING 2.0 x 2.0 SQ.M BY PROVIDING, FIXING GLASS STRIPS 40MM WIDE & 4MM YHICKINCLUDING CURING & CLEANING.	SQM	820			
SEC E	20	PROVIDING 2MM THICK NEAT CEMENT FINISH USING OPC GRADE 43/53 OVER CONCRETE BASE FOR FLOORING, PAVING, PLASTERED SURFACE ETC. INCLUDING CURING & CLEANING AND SCAFFOLDING COMPLETE.	SQM	895			
SEC E	21	PROVIDING AND LAYING OF 5.5 MM THICK CERAMIC TILES OF REQUIRED SIZE LAID OVER THE BED OF CM - 1:4 (1 CEMENT & 4 COARSE SAND) USING OPC GRADE 43/53.TILES FROM REPUTED MANUFACTURER LIKE JOHNSON OR EQUIVALENT INCLUDING ALL MATERIALS COMPLETE AS PER STANDARD PRACTICE AND SPECIFICATION.					
SEC E	21A	FLOORING - 300MM X 300MM	SQM	82			
SEC E	21B	SKIRTING - 300MM X 150MM	SQM	7			
SEC E	22	SUPPLYING AND FIXING OF WHITE GLAZED TILES OF REQUIRED SIZES LAID OVER THE BED OF CM - 1:4 (1 CEMENT & 4 COARSE SAND) USING OPC GRADE 43/53 . DADO IN TOILET & PANTRY ROOM UP TO 1.5 M ELEVATIONS INCLUDING PEREPARATION OF BASE LAYING UNDERBED, FINISHING AND ROUNDING CORNERS AND JUNCTIONS, CURING ETC. COMPLETE AS PER DRAWINGS AND SPECIFICATIONS.					
SEC E	22A	FLOORING (5.0MM TO 6.0MM THICK OF SIZE 300MM X 300MM)	SQM	28			
SEC E	22B	DADO (5MM TO 6MM THICK OF SIZE 150MM X 150MM) - 1.5M HEIGHT FROM FINISHED FLOOR LEVEL	SQM	32			
SEC E	23	PROVIDING PLASTERING WITH CEMENT MORTAR -1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 OVER BOTH INTERNAL AND EXTERNAL FACES OF BRICKWORK AND CONCRETE SURFACES, PARTITION WALLS ETC. AT ALL LEVELS INCLUDING PREPARING THE SURFACE, RAKING JOINTS, SCAFFOLDING, CURING, COST OF ALL MATERIALS, LABOUR ETC. COMPLETE.					
SEC E	23A	EXTERNAL PLASTERING - 18MM THICK	SQM	865			
SEC E	23B	INTERNAL PLASTERING - 12MM THICK	SQM	1250			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC E	24A	PROVIDING & APPLYING COLOUR WASH -THREE COATS ON NEWLY PLASTERED EXTERNAL SURFACE OF SHED BY USING BEST SHALE LIME TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , COLOURING AGENT, BASE COAT OF WHITE WASH,APPROVED ADDESSIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	SQM	865			
SEC E	24B	PROVIDING & APPLYING WHITE WASH - THREE COATS ON NEWLY PLASTERED INTERNAL SURFACE OF SHED (EXCLUDING INNER WALL OF OFFICE/C&I ROOM) BY USING BEST SHALE LIME TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , APPROVED ADDESSIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	SQM	815			
SEC E	24C	PROVIDING & APPLYING TO INTERIOR SURFACES OF STORE OFFICE AND C&I ROOM BY TWO COATS OF OIL BOUND DISTEMPER (OBD) OF APPROVED SHADE ,COLOR AND MAKE CONFIRMING TO IS : 428 TO OBTAIN A EVEN FINISH AND UNIFORM COLOR OVER A COAT OF PRIMER AS PER MANUFACTURE RECOMMENDATION INCLUDING COST OF PAINT, SURFACE PREPARATION LIKE CLEANING AND BRUSHING & BROOMING OF WALLS , SCAFFOLDING AT ALL LEVEL ETC, COMPLETE. SURFACE PREPARATION SHALL BE DONE BY APPLYING PUTTY/PLASTER OF PARISH (POP) INCLUDING COST OF MATERIAL, LABOUR ETC. COMPLETE.	SQM	450			
SEC E	25	PROVIDING AND FIXING OVER HEAD HYDRAULIC DOOR CLOSER (HEAVY DUTY) OF APPROVED BRAND AND SIZE ON NECESSARY DOORS AS DIRECTED BY BHEL ENGINEER.	NOS.	7			
SEC E	26	PROVIDING AND FIXING WHITE GLAZED VITREOUS CHINA WASH HAND BASIN OF 55 CM X 40 CM SIZE INCLUDING COLD WATER PILLER TAP, BRACKETS, STOP TAP, CHROMIUM PLATED BOTTLE TRAP AND NECESSARY PIPE CONNECTIONS INCLUDING UPVC WASTE PIPE AND TRAP UPTO THE OUT SIDE FACE OF THE WALL, MAKING GOOD THE DAMAGED SURFACE, TESTING ETC. COMPLETE. PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.	NOS.	1			
SEC E	27	PROVIDING AND FIXING EUROPEAN TYPE WHITE GLAZED VITREOUS CHINA W.C.PAN WITH UPVC SEAT AND LID WITH CHROMIUM PLATED BRASS HINGES AND RUBBER BUFFERS INCLUDING UPVC VENT PIPE (APPROX. 2M. HT. WITH COWL)) ON THE OUTSIDE FACE OF WALL, 10 LITRE PVC LOW LEVEL FLUSHING CISTERN WITH ALL FITTINGS, PIPE AND STOP COCK, BRACKETS FOR FIXING CISTERN, 32 MM DIA. UPVC FLUSH PIPE WITH FITTINGS AND CLAMPS, 20 MM DIA. UPVC OVERFLOW PIPE, FLOAT VALVES, CUTTING AND MAKING GOOD TO THE WALLS AND FLOORS, TESTING ETC. COMPLETE. PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.	NOS.	1			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC E	28	PROVIDING AND FIXING IN POSITION OF WHITE GLAZED EARTHENWARE FLAT BACK/CORNER TYPE LIPPED FRONT URINALS OF 430MM X 260MM X 350MM / 340X460X265 MM OF APPROVED MAKE AND QUALITY WITHOUT FLUSHING CISTERN, GI FLUSH PIPE AND SPREADERS WITH BRASS UNIONS, GI CLAMPS, CUTTING OF WALLS AND MAKING GOOD OF ALL DAMAGES AND FINISHING TO MATCH THE EXISTING WORK ETC. COMPLETE. RATE QUOTED SHALL INCLUDE COST OF ALL MATERIALS AND LABOUR FOR CARRYING, LAYING & FIXING AND ALL OTHER INCIDENTAL CHARGES ETC. COMPLETE.	NOS.	2			
SEC E	29	PROVIDING AND FIXING IN POSITION OF HIGH CLASS BELGIUM OR SUPERIOR MAKE BEVELLED EDGE MIRROR OF SIZE 450MM X 550MM X 6MM WITH 16 MM DIA & 550MM LENGTH NICKEL PLATED TOWEL ROD MOUNTED ON 6 MM THICK PLYWOOD OR PLASTIC FOLDER SHEET. RATE TO INCLUDE COST OF ALL MATERIALS, LABOUR FOR FIXING THE WOODEN PLUGS WITH CP BRASS SCREWS AND WASHERS ETC. COMPLETE.	NOS.	1			
SEC E	30	PROVIDING AND FIXING IN POSITION OF 15 MM DIA CONCUSSION PUSH BUTTON TYPE BRASS/ GUN MATEL SELF CLOSING TAP INCLUDING NECESSARY SOCKET,TESTING ETC COMPLETE FOR URINALS AS DIRECTION OF BHEL ENGINEER.	NOS.	2			
SEC E	31A	PROVIDING AND FIXING IN POSITION OF 15 MM DIA NOMINAL SIZE SCREW DOWN TYPE CHROMIUM PLATES BRASS BIB COCKS OF STANDARD TYPE OF APPROVED MAKE AND QUALITY (LEADER MAKE OR EQUIVALENT) AS PER STANDARD SPECIFICATION.RATE INCLUDES JOINTING MATERIALS,SOCKETS,UNION NUT,TESTING, LABOURS FOR CARRYING AND FIXING ETC. COMPLETE	NOS.	3			
SEC E	31B	PROVIDING AND FIXING IN POSITION OF 25 MM DIA GATE VALVE.INCLUDING ALL NECESSARY FITTING & FIXTURE ETC. COMPLETE AS PER STANDARD SPECIFICATION.	NOS.	1			
SEC E	31C	PROVIDING AND FIXING IN POSITION OF 40 MM DIA GATE VALVE.INCLUDING ALL NECESSARY FITTING & FIXTURE ETC. COMPLETE AS PER STANDARD SPECIFICATION.	NOS.	1			
SEC E	32	PROVIDING AND FIXING IN POSITION OF 15 MM DIA NOMINAL SIZE SCREW DOWN TYPE CHROMIUM PLATES BRASS STOP COCKS OF APPROVED MAKE AND QUALITY (LEADER MAKE OR EQUIVALENT) AS PER STANDARD SPECIFICATION.RATE INCLUDES COST OF JOINTING MATERIALS, SOCKETS,UNION NUT,TESTING, LABOURS FOR CARRYING AND FIXING ETC. COMPLETE	NOS.	4			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC E	33	PROVIDING AND FIXING IN POSITION OF 100MM X 50MM HCI "NAHANI" TRAP WITH HCI GRATINGS, BENDS, CONNECTING PIECES OF CI PIPE UPTO OUTSIDE FACE OF THE WALL. MAKING GOOD THE DAMAGED SURFACE,TESTING ETC COMPLETE AS PER STANDARD SPECIFICATIONS. RATE TO BE ALL INCLUSIVES.	NOS.	4			
SEC E	34	PROVIDING AND FIXING IN POSITION OF 150MM SALT GLAZED STONE WARE GULLY TRAP WITH HCI GRATINGS AND CI COVER OF SIZE 300X300 MM OF APPROVED MAKE (WEIGHT NOT LESS THAN 2 KG) AND QUALITY AS PER STANDARD SPECIFICATIONS. RATE TO BE ALL INCLUSIVE.	NOS.	2			
SEC E	35	PROVIDING AND LAYING WITH REQUIRED GRADING & LEVELING IN TRENCHES MEDIUM GRADE (TYPE) GALVANISED IRON (G I) PIPE HAVING EMBOSSED ISI MARK ON IT, OF REQUIRED DIAMETER WITH SCREWED, SOCKETS, JOINTS, NECESSARY GALVANISED IRON FITTINGS SUCH AS SOCKETS, BACK NUTS, ELBOWS, BENDS, TEES, REDUCERS, ENLARGERS, PLUGS, CLAMPS ETC. INCLUDING ALL NECESSARY EXCAVATION, BACK FILLING, FIXING WITH CLAMPS, TESTING ETC. COMPLETE. (PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.)					
SEC E	35A	40MM DIA	RM	100			
SEC E	35B	25MM DIA	RM	50			
SEC E	35C	20MM DIA	RM	25			
SEC E	35D	15MM DIA	RM	20			
SEC E	36	PROVIDING AT WORKING SITE, CARRYING AND LOWERING INTO TRENCHES, LAYING TO PROPER ALIGNMENT, LEVEL AND GRADE, JOINTING WITH CM (1:1) AND TESTING OF JOINTS ETC. OF THE FOLLOWING SIZE OF SALT GLAZED STONWARE PIPE INCLUSIVE OF ALL NECESSARY SPECIALS TARRED HEMP YARN AND ALL JOINTING MATERIALS COMPLETE AS PER STANDARD SPECIFICATIONS INCLUDING ALL NECESSARY EXCAVATION ,BACKFILLING,DISPOSAL OF SURPLUS EARTH ,LEAD AND LIFT AS PER SITE CONDITIONS. RATE SHALL INCLUDE COST OF ALL MATERIALS, LABOUR CHARGES AND INCIDENTAL CHARGES ETC. COMPLETE.					
SEC E	36A	100MM DIA STONWARE PIPELINE INCLUDING ALL SPECIALS COMPLETE.	RM	50			
SEC E	37	PROVIDING AND FIXING IN POSITION OF PVC OVERHEAD WATER TANK OF SYNTEX OR ANY APPROVED MAKE OF 1000 LITRE CAPACITY WITH PROVISION FOR OVERFLOW ARRANGEMENT VALVES, INLET AND OUTLET ETC. COMPLETE. SUPPORTING STEEL STRUCTURE FOR FIXING THE TANK SHELL BE PAID IN THE RELAVENT ITEM.	NOS.	1			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC E	38	CONSTRUCTION OF 230MM THICK BURNT CLAY / FLY ASH LIME BRICK CHAMBER (USING OPC GRADE 43/53) OF THE FOLLOWING DIMENSIONS (INNER DIMENSION) WITH 20MM THICK INTERNAL & EXTERNAL CEMENT PLASTER OF MIX CM 1:5 (1 CEMENT & 5 COARSE SAND) , NEAT CEMENT FINISH , TOP CI – COVER AND CONNECTORS FOR SEWER LINES. RATE SHALL BE INCLUSIVE OF ALL NECESSARY EXCAVATION & FILLING, PCC-100 MM THICK OF 1:3:6 FOR BEDDING ON 100MM THICK OVERSIZER SOLING WITH 80 MM METALETC. COMPLETE.					
SEC E	38A	600X450X450 WITH C.I COVER	NOS.	2			
SEC E	38B	900X600X450 WITH C.I. COVER	NOS.	3			
SEC E	39	PROVIDING AND FIXING OF PRECAST 80 MM THICK RCC COVER OF MIX 1:1.5:3 FOR MAN HOLES OF VARIOUS SIZES WITH REINFORCEMENT OF 10 MM DIA BOTH WAY TIED WITH TACK WELDING @ 150 MM C/C WITH 2 HOOKS OF 12 MM DIA BARS ETC.COMPLETE.					
SEC E	39A	750MM x 600MM	NOS.	2			
SEC E	39B	1050MM x 750MM	NOS.	3			
SEC E	40	PROVIDING AND FIXING CHROMIUM PLATED TOWEL ROD 16 MM DIA. AND 75CM. IN LENGTH INCLUDING ALL ACCESSORIES COMPLETE. (PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE).	NOS.	1			
SEC E	41	PROVIDING & FIXING OF LIQUID SOAP DISPENSER AT ALL WASH BASIN LOCATION.	NOS.	1			
SEC E	42	PROVIDING & FIXING OF WOODEN FRAME OF BEST QUALITY COUNTRY WOOD (2.5"x3.0") FOR INSTALLING PORTABLE 1.5T AIR CONDITIONAR ON THE WALL OPENING (31"x22"), SO AS TO MAKE A FRAME OF INSIDE CLEAR DIMENSION 26"x17" WITH COMPLETE FINISHING, PAINTING, HOLD FAST ETC. RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR, MAKING GOOD THE DAMAGED SURFACE ETC. COMPLETE. AS APPROVED BY BHEL ENGINEER.	NOS.	6			
SEC E	43	PROVIDING & FIXING IN POSITION OF CI VENT PIPE OF DIA. 100MM (APPROX. HT. 3M) IN SEPTIC TANK. RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR ETC.	RM	4			
SEC E	44	PROVIDING AND FIXING OF METALLIC DECORATIVE TYPE HEAVY DUTY PELMET ROD FOR DOORS AND WINDOWS. RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR ETC. AS APPROVED BY BHEL ENGINEER.	EACH	5			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MWe NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC E	45	PROVIDING AND FIXING OF AQUA-GUARD OR EQUIVALENT WATER PURIFIER . ALONG WITH ALL FITTINGS. RATE TO INCLUDE ALL NECESSARY FITTINGS & FIXTURES, LABOUR ETC.AS APPROVED & DIRECTED BY BHEL ENGINEER.	NOS.	1			
SEC E	46	PROVIDING AND FIXING OF 1 No. 18"X24" SIZE STAINLESS STEEL SINK WITH ALL FITTINGS LIKE DRAIN PIPE, STOP VALVE ETC.RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR ETC.AS APPROVED & DIRECTED BY BHEL ENGINEER.	NOS.	1			
SEC E	47	PROVIDING , SUPPLYING AND FIXING OF 20 GAUGE MS ROLLING SHUTTERS OF SIZE 4.6 M X 4.7 M (APPROX.) AS PER I.S. SPECIFICATIONS, COMPLETE, MECHANICALLY OPERATED FROM IN AND OUTSIDE BOTH AS INSTRUCTED BY BHEL ENGINEER INCLUDING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER LOCKING ARRANGEMENT. RATE SHALL BE INCLUSIVE OF ALL THE ABOVE COMPLETE.	SQM	25			
SEC E	48	PROVIDING,SUPPLYING AND FIXING OF SPLIT AIR CONDITIONER OF 2 TON CAPACITY OF GODREJ,VOLTAS,LG,SAMSUNG,HITACHI ETC .RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR ETC.AS APPROVED & DIRECTED BY BHEL ENGINEER.	NOS.	2			
SEC E		TOTAL VALUE OF SECTION-E IN Rs.					

BHEL:PSWR:NAGPUR

RATE SCHEDULE, SECTION F

NAME OF THE WORK : INTERNAL ELECTRIFICATION WORK OF 1 NO. CLOSED SHED WITH STORE OFFICE (60MX15M)AND C&I STORE ROOM (15MX6M) AT 2X700MWe NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
---------	-------	---------------------	------	------	----------------------------	---------------	--------

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC F	1	SUPPLYING & INSTALLING POWER DISTRIBUTION BOARD COMPLETE WITH: COMMON BOARD FOR ALL SHEDS. 1) INCOMING MCB TPH 100 AMPS. - 1 NO. 2) OUTGOING MCB TPH 32 AMPS. -2NOS. 3) RCCB DP 25/20 AMPS. - 2NOS. 4) OUTGOING MCB SP 6 AMPS - 6NOS. All RCCBs, MCBs SHALL BE MDS/INDO KOPP MAKE. DISTRIBUTION BOARDS SHALL BE SIEMENS / MDS / INDO KOPP MAKE WITH INTERNAL BUSBARS, INTERNAL WIRING, 2 NOS. EARTHING TERMINALS, EARTH CONNECTIONS, INCLUDING GLANDS, LUGS.	NOS.	1			
SEC F	2	PROVIDING AND INSTALLING WIRING USING 2.5 SQ.MM COPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR COMPUTER ROOM, OFFICE SHED & FOR REST OF SHEDS OPEN AND WHRERVER REQUIRED IN PVC CONDUIT OF REQUIRED SIZE.	PER POINT	30			
SEC F	3	PROVIDING AND INSTALLING WIRING FOR USING 4.0 SQ.MMCOPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR COMPUTER ROMM, OFFICE SHED & FOR REST OF SHEDS OPEN AND WHRERVER REQUIRED IN PVC CONDUIT OF REQUIRED SIZE.	PER POINT	10			
SEC F	4	PROVIDING AND INSTALLING WIRING FOR MAINS USING 6.00 SQ.MM COPPER CONDUCTOR OF ISI MAKE. USING CONCEALED TYPE WIRING/PVC CONDUIT OF REQUIRED SIZE.	PER POINT	8			
SEC F	5	PROVIDING AND INSTALLING WIRING FOR MAINS USING 16.00 SQ.MM COPPER CONDUCTOR OR ISI MAKE USING CONCEALED TYPE WIRING/PVC CONDUIT OF REQUIRED SIZE.	PER POINT	5			
SEC F	6	PROVING AND INSTALLATION OF WIRING FOR FANS/COOLERS USING 2.5SQ.MM COPPER CONDUCTOR OF ISI MARK THROUGH PVC CONDUITS WITH ACCESSORIES AND FIXTURES. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	PER POINT	6			
SEC F	7	POVIDING AND INSTALLATION OF PLUG POINT OF 5A SOCKET (ANCHOR OR EQUIV.) OUTLET INCLUDING WIRING TERMINATION. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NOS.	15			

T.S. NO. BHE/PW/PUR/KKRN-ENB/1071VOLUME-II-PRICE BID

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC F	8	PROVIDING AND INSTALLATION OF PLUG POINT OF 15A SOCKET (ANCHOR OR EQUIV.) OUTLET INCLUDING WIRING TERMINATION. THIS INCLUDES TUBE LIGHT FITTINGS V	NOS.	7			
SEC F	9	PROVIDING AND FIXING ORDINARY TUBELIGHT WITH FRAME OF STANDARD MANUFACTURER LIKE PHILIPS/BAJAJ OR EQUIVALENT AS APPROVED BY BHEL. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NOS.	20			
SEC F	10	PROVIDING AND FIXING EXHAUST FANS 12" DIAMETER WITH FRAME OF STANDARD MANUFACTURER LIKE CROMPTAN GREEVES OR EQUIVALENT AS APPROVED BY BHEL.	NOS.	3			
SEC F	11	PROVIDING AND FIXING HEAVY DUTY PLUG POINT 15 AMPS (ANCHOR MAKE OR EQUIV.) WITH ONE SWITCH FOR COMPUTER ,ONE FOR AC CONNECTION WITH BORD ETC COMPLETE.	NOS.	6			
SEC F	12	PROVIDING AND FIXING METAL CLAD PLUG AND MCB OF 30AMPS. (CROMPTON/MDS MAKE) FOR AIR CONDITIONER WITH BOARD ETC COMPLETE.	NOS.	4			
SEC F	13	PROVIDING AND FIXING CEILING FAN 48" DIAMETER OF APPROVED COMPANY SUCH AS CROMTAN GREEVES OR ANY OTHER STANDARD MANUFACTURER AS DIRECTED BY BHEL. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NOS.	6			
SEC F	14	PROVIDING AND FIXING CALLING BELLS (WITH INDICATOR LIGHT)	NOS.	2			
SEC F	15	PROVIDING EARTHING PITS WITH 2 " DIA , 2 M LONG GI PIPES WITH FLANGE & GI WIRES WITH CHARCOAL, SALT AND AS PER THE STANDARD PRACTICE FOR ELECTRICAL CONNECTION.RATE SHALL BE INCLUSIVE OF ALL MATERIALS, LABOURS, ETC COMPLETE.	NOS.	3			
SEC F	16	PROVIDING & FIXING ALUMINIUM DISPERSIVE LUMINAIRE ENAMELED GREEN AND WHITE WITH CAST ALUMINIUM FLANGE AND NIPPLE SUITABLE FOR USE WITH GLS LAMP, DOME 12" DIAMETER, WITH HANGING BRACKET AND 200W GLS LAMP OF CROMPTON OR EQUIVALENT BAJAJ/PHILIPS MAKE, COMPLETE.	NOS.	35			
SEC F	17	WIRING WITH 2.5 SQ MM ISI MARK COPPER WIRE FOR ABOVE IN PVC CONDUIT ALONG WITH GI EARTH WIRE INCLUSIVE OF ALL MATERIAL, LABOUR ETC. COMPLETE	PER POINT	35			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MWe NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC F	18	SUPPLYING & FIXING WALL MOUNTING TYPE LIGHTING PANELS, EACH WITH. (1) INCOMING MCB TPN -32 AMPS - 1NO. (2) RCCB DP 32 AMPS - 3NOS (3) MCB SP 6AMPS - 30 NOS. ALL MCBS AND RCCBS SHALL BE OF MDS / INDO KOPP MAKE. LIGHTING PANEL SHALL BE SIEMENS/MDS/INDO KOPP MAKE WITH INTERNAL BUSBARS, 2 NOS. EARTHING TERMINALS, EARTH CONNECTIONS, INCLUDING GLANDS, LUGS & WIRING FROM MAIN DB.	NOS.	1			
SEC F		TOTAL VALUE OF SECTION-F IN Rs.					

BHEL:PSWR:NAGPUR

RATE SCHEDULE, SECTION - G

CONSTRUCTION OF SITE OFFICE BUILDING (45M X 10 M) WITH VERANDAH 2M WIDE, TOILET BLOCK (AS SHOWN IN THE PLAN) -- 1 NO AT 2X700MWe NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC G	1A	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH IN ALL KINDS OF SOIL (EXCEPT HARD ROCK AND SOFT ROCK) FOR FOUNDATION , SEPTIC TANK, SOAK PIT ETC., SPREADING THE EARTH UNIFORMLY AROUND THE OPEN STROAGE YARD ETC. AS DIRECTED BY BHEL ENGINEER AND INCLUDING DISPOSAL OF SURPLUS EARTH (IF ANY) , DEWATERING WITH ALL T&P, LABOURS, MATERIALS ETC. COMPLETE.	CUM	175			
SEC G	1B	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH IN ALL KINDS OF SOIL INCLUDING SOFT ROCK AND HARD ROCK (MANUALLY OR MECHANICALLY WITHOUT BLASTING) FOR FOUNDATION,SEPTIC TANK, SOAK PIT ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING , ALL T&P, LABOURS, MATERIALS ETC. COMPLETE.	CUM	25			
SEC G	1C	EARTH WORK EXCAVATION FROM 2.0M TO 4.0 M DEPTH IN ALL KINDS OF SOIL (EXCEPT HARD ROCK AND SOFT ROCK) FOR SEPTIC TANK, SOAK PIT ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	CUM	25			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW_e NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC G	1D	EXCAVATION IN ALL KINDS OF SOIL INCLUDING SOFT & HARD ROCK ((BY MANUAL CHISELING OR BY MECHANICAL MEANS BUT WITHOUT BLASTING) FROM 2 TO 4M DEPTH FOR SEPTIC TANK AND SOAK PIT , WHEREVER REQUIRED INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	CUM	25			
SEC G	1E	SUB GRADE PREPARATION: CUTTING & DISPOSAL OF GRASS, VEGITATIONS, BUSHES, TREES (GIRTH LESS 300MM), LEVELLING, WATERING AND CONSOLIDATION (90% OF PROCTOR DENSITY) BY MEANS OF 10-12 MT CAPACITY POWER/VIBRO ROLLER FOR SUB BASE PREPARATION. THIS WILL INCLUDE AVERAGE CUTTING & FILLING UP TO ± 250MM THICK, GRADING THE AREA WITH PROPER SLOPE FOR DRAINING OUT THE RAIN WATER WITH ALL T&P, LABOURS, MATERIALS, DEWATERING (IF REQUIRED) ETC. COMPLETE.	SQM	750			
SEC G	2	DISPOSAL OF EXCAVATED EARTH/ROCK (NOT SUITABLE FOR BACK FILLING) BEYOND INITIAL LEAD OF 50M AND UPTO A MAXIMUM LEAD OF 2 KM OR PART THEREOF INCLUDING LOADING, UNLOADING , TRANSPORTING AND SPREADING AS PER DIRECTION OF BHEL ENGINEER .	CUM	110			
SEC G	3	BACKFILLING OF FOUNDATION ,FLOORS AND PLINTH IN LAYERS NOT EXCEEDING 150MM THICK. INCLUDING WATERING AND CONSOLIDATING ETC. COMPLETE AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.					
SEC G	3A	WITH EXCAVATED SOIL AVAILABLE AT SITE	CUM	120			
SEC G	3B	WITH GOOD EARTH BROUGHT FROM OUTSIDE FROM CONTRACTOR'S OWN SOURCE INCLUDING ROYALTY ETC.	CUM	80			
SEC G	3C	PROVIDING & FILLING IN SOAK PIT WITH BRICK BATS 40-80MM INCLUDING SAND PACKING ETC. COMPLETE, AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.	CUM	15			
SEC G	3D	WITH GRANULAR MURUM IN LAYERS (THICKNESS OF EACH LAYER SHOULD NOT EXCEED 150MM) BELOW FOUNDATIONS, AND RAMP AS PER STANDARD SPECIFICATION, RELEVANT DRAWINGS AND INSTRUCTED BY BHEL ENGINEER INCLUDING ROYALTY. CONTRACTOR HAS TO SUBMIT ROYALTY CERTIFICATE FROM CONCERNED STATE GOVT. MINING DEPARTMENT	CUM	5			
SEC G	3E	PROVIDING STONE SOLING OF REUIRED THICKNESS AS PER DRAWING BELOW FLOORING, RAMP, COLUMN FOUNDATIONS OF STORAGE SHED ETC. BY USING 80 MM SIZE HARD BROKEN BLACK GRANITE/ QUARTIZITE/ GNEISS/ TRAP STONE METAL INCLUDING GRANULAR MURRUM PACKING, WATERING & COMPACTION ETC COMPLETE.AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER	CUM	320			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC G	4A	PROVIDING AND LAYING OF PLAIN CEMENT CONCRETE OF MIX 1:4:8 USING 40MM & DOWN SIZE HARD BROKEN GRANITE STONE JELLY FOR BASE OF BRICK FOUNDATION , FOOT PATH (REF. DRAWING) ETC. INCLUDING SHUTTERING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	CUM	30			
SEC G	4B	PROVIDING AND LAYING CONCRETE OF MIX 1:3:6 USING 20MM DOWN SIZE HARD BROKEN GRANITE STONE AGGREGATE FOR PLINTH PROTECTION . INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK AND CENTERING AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER BUT EXCLUDING COST OF REINFORCEMENTS FOR FLOORING.	CUM	15			
SEC G	4C	PROVIDING AND LAYING REINFORCED CONCRETE OF MIX 1:2:4 USING 20MM DOWN SIZE HARD BROKEN GRANITE STONE AGGREGATE FOR OFFICE , TOILET AND PANTRY BLOCK FLOORING AND ROOF SLAB FOR TOILET AND PANTRY BLOCK , STUB COLUMN ETC . INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK AND CENTERING AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER BUT EXCLUDING COST OF REINFORCEMENTS FOR FLOORING.	CUM	140			
SEC G	5	PROVIDING AND LAYING DPC (DAMP PROOF COURSE) 50MM THICK IN 1:2:4 CEMENT CONCRET LAYER USING OPC GRADE 43/53AND WITH 6MM DOWN AGGREGATE, INCLUDING FORMWRK, BITUMEN FELT USING CEMENT WITH WATER PROOFING COMPOUND ETC. COMPLETE	SQM	60			
SEC G	6	PROVIDING , CUTTING, BENDING AND FIXING IN POSITION REINFORCEMENT OF VARIOUS DIA. USING HIGH TENSILE TOR STEEL (Fe - 415/500) . AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER INCLUDING COST OF ALL MATERIALS, LEADS, LIFT, LABOURS, MS BINDING WIRE 18/20 GAUGE, TACK WELDING AND SUPPORTING IF REQUIRED COMPLETE.	MT	5			
SEC G	7A	PROVIDING BRICK WORK IN CM 1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND LOCALLY AVAILABLE BURNT CLAY BRICKS (MIN STRENGTH 35 KG/CM ²) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, SUPER STRUCTURE ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	CUM	230			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC G	7B	PROVIDING BRICK WORK IN CM 1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND FLY ASH LIME BRICKS (FAL - MIN STRENGTH 35 KG/CM ²) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	CUM	100			
SEC G	8A	PROVIDING HALF BRICK WORK IN CM 1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND LOCALLY AVAILABLE BURNT CLAY BRICKS (MIN STRENGTH 35 KG/CM ²) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, SUPER STRUCTURE ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	SQM	30			
SEC G	8B	PROVIDING HALF BRICK WORK IN CM 1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND FLY ASH LIME BRICKS (FAL - MIN STRENGTH 35 KG/CM ²) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS . RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	SQM	15			
SEC G	9	DESIGN, SUPPLY, FABRICATING, AND ERECTION OF STRUCTURAL TRUSS WITH TUBULAR POST & PURLINS (BY USING CLASS B ,MEDIUM QUALITY PIPE) AS PER BHEL DRAWING FOR FIXING OF PPGI ROOFING SHEET AND WIND TIES TO BE PROVIDED ABOVE SHEETS AND PROVIDING AND FIXING BASE PLATES WITH HOLDING DOWN BOLTS ON RCC COLUMNS, GUSSETS, RIBS, PINS, SPLICES ETC. AS REQUIRED INCLUDING TRANSPORT, LOADING, UNLOADING CHARGES FROM FABRICATION SHOP TO SITE ETC. COMPLETE. RATE IS INCLUSIVE OF ALL MATERIALS, LOADING & UNLOADING, FABRICATION, FIXING IN POSITION, LABOUR CHARGES , T&Ps AND COST OF RED OXIDE PRIMER AT FACTORY AND TWO COATS OF SYNTHETIC ENAMEL PAINTS (OVER PRIMER COAT OF RED OXIDE) OF APPROVED COLOUR AND QUALITY AT SITE.	MT	8			
SEC G	10	PROVIDING AND FIXING 0.5MM THICK PPGI SHEETS OVER THE LEAN TO ROOF OF TOILET/PANTRY BLOCK AS PER BHEL DRAWING INCLUDING GALVANISED IRON J OR L HOOK , BOLTS, BITUMINOUS WASHERS, GI CRAMP BOLTS, NUTS,SCAFFOLDING ETC. COMPLETE, ALL AS PER LATEST IS 459, 3307 AND 730.	SQM	670			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC G	11	PROVIDING AND FIXING OF FALSE CEILING OF 12.5 MM THICK TAPERED EDGE GYPSUM PLAIN BOARD CONFORMING TO IS:2095-PART I OF APPROVED QUALITY AND DESIGN OF SIZE 600x600 MM PANELS WITH SQUARE EDGES SUPPORTED BY ANODISED ALUMINIUM FRAMES OF TEES 35x23.5x1.5 MM THICK AS MAIN MEMBER AND 19x23.5x1.5 MM TEES AS CROSS SUPPORTING MEMBERS AND WALL ANGLES OF 23.5x23.5x1.5MM. THE MAIN RUNNERS SHALL BE SUSPENDED FROM ROOF AT 1200 MM CENTRE TO CENTRE BY MEANS OF MS RODS WITH GI 'J' THREADED HOOK FOR ADJUSTMENTS. THE CROSS RUNNERS SHALL BE FIXED TO MAIN RUNNER TO FORM 'A' GRID PATTERN OF 600x600MM AND PROVIDING 25 MM WIDE ALUMINIUM STRIP TEES OR MOULDED SECTIONS AT ALL JOINTS. THE RATE SHALL BE INCLUSIVE OF TWO COATS OF APPROVED OBD ON GYPSUM BOARD, SUPPLY & FIXING OF ALUMINIUM FRAME AND SCAFFOLDING ETC. COMPLETE.	SQM	570			
SEC G	12A	PROVIDING AND FIXING OF BEST QUALITY COUNTRY WOOD DOORS COMPRISING OF FRAME 95 X 70MM AND 38/40MM THICK FLUSH SHUTTERS OF SOLID CORE TYPE USING COMMERCIAL PLY INCLUDING HOLD FASTS, WIND APPLIANCES, HANDLES, TOWER BOLTS AND ALDROPS, MORTISE OR SUITABLE LOCKS ETC. AS PER THE STANDARD PRACTICE AND APPLYING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED SHADE & COLOR OVER A COAT OF PRIMER AS DIRECTED BY BHEL ENGINEER.	SQM	20			
SEC G	12B	PROVIDING AND FIXING OF BEST QUALITY PVC PANELLED DOORS OF THICKNESS 29MM, SINTEX/BAJAJ MAKE OR APPROVED EQUIVALENT FOR TOILETS INCLUDING ALL FITTINGS AND FIXTURES, MS ANGLE FRAME OF SIZE 40x40x6MM ETC. ALL COMPLETE AS PER DRAWINGS AND SPECIFICATIONS.	SQM	12			
SEC G	12C	PROVIDING AND FIXING OF 18 GAUGE M.S. SHEET DOOR WITH FRAME WORK 40 X 40 X 6 MM M.S. ANGLE INCLUDING LOCKING ARRANGEMENTS, HOLD FAST , APPLYING ANTICORROSSIVE PRIMER COAT OF RED LEAD PAINT AND 2 COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR COMPLETE AS DIRECTED BY BHEL ENGINEER.	SQM	6			
SEC G	13	SUPPLING, MANUFACTURING AND FIXING IN POSITION OF STEEL WINDOWS AND VENTILATORS INCLUDING FRAMES & IRON BARRED (GUARD BAR OF SQUARE SECTION @ 100 MM C/C) AND GLAZED WITH 4MM PLAIN GLASS AS PER STANDARD SPECIFICATIONS & RELEVANT IS CODE AND INSTRUCTIONS OF BHEL ENGINEER. THE COST SHALL BE INCLUSIVE OF ALL ACCESSORIES FITTINGS, HOLD FASTS, PAINTING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER ETC. COMPLETE.					
SEC G	13A	STEEL WINDOWS	SQM	6			
SEC G	13B	STEEL LOUVERED VENTILATORS :-	SQM	600			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC G	14	PROVIDING AND FIXING OF IPS FLOORING 40MM THICK USING OPC GRADE 43/53 WITH CEMENT CONCRETE 1:2:4 (USING 12 MM DOWN AGGREGATES) AS PER STANDARD PRACTICE IN PANELS OF SIZE NOT EXCEEDING 2.0 x 2.0 SQ.M BY PROVIDING, FIXING GLASS STRIPS.INCLUDING CURING & CLEANING.	SQM	602			
SEC G	15	PROVIDING AND LAYING OF 5.5 MM THICK CERAMIC TILES OF REQUIRED SIZE LAID OVER THE BED OF CM - 1:4 (1 CEMENT & 4 COARSE SAND) USING OPC GRADE 43/53.TILES FROM REPUTED MANUFACTURER LIKE JONSON OR EQUIVALENT INCLUDING ALL MATERIALS COMPLETE AS PER STANDARD PRACTICE AND SPECIFICATION.					
SEC G	15A	FLOORING -600MM X600MM	SQM	75			
SEC G	15B	FLOORING -300MM X300MM	SQM	30			
SEC G	15C	SKIRTING - 300MM X 150MM	SQM	11			
SEC G	16	PROVIDING 2MM THICK NEAT CEMENT FINISH OVER CONCRETE BASE AND BRICK WALL FOR SEPTIC TANK ETC.	SQM	105			
SEC G	17	SUPPLYING AND FIXING OF WHITE GLAZED TILES OF REQUIRED SIZES LAID OVER THE BED OF CM - 1:4 (1 CEMENT & 4 COARSE SAND) USING OPC GRADE 43/53 . DADO IN TOILET & PANTRY ROOM UP TO 1.5 M ELEVATIONS INCLUDING PEREPARATION OF BASE LAYING UNDERBED, FINISHING AND ROUNDING CORNERS AND JUNCTIONS, CURING ETC. COMPLETE AS PER DRAWINGS AND SPECIFICATIONS.					
SEC G	17A	FLOORING (5.0MM TO 6.0MM THICK OF SIZE 300MM X 300MM)	SQM	60			
SEC G	17B	DADO (5MM TO 6MM THICK OF SIZE 150MM X 150MM) - 1.5M HEIGHT FROM FINISHED FLOOR LEVEL	SQM	70			
SEC G	18	PROVIDING PLASTERING WITH CEMENT MORTAR -1:6 (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 OVER BOTH INTERNAL AND EXTERNAL FACES OF BRICKWORK AND CONCRETE SURFACES, PARTITION WALLS ETC. AT ALL LEVELS INCLUDING PREPARING THE SURFACE, RAKING JOINTS, SCAFFOLDING, CURING, COST OF ALL MATERIALS, LABOUR ETC. COMPLETE.					
SEC G	18A	EXTERNAL PLASTERING - 18MM THICK	SQM	345			
SEC G	18B	INTERNAL PLASTERING - 12MM THICK	SQM	1430			
SEC G	18C	CEILING PLASTERING - 6MM THICK	SQM	30			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC G	19A	PROVIDING & APPLYING COLOUR WASH -THREE COATS ON NEWLY PLASTERED EXTERNAL SURFACE OF WALL BY USING BEST SHALE LIME TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , COLOURING AGENT, BASE COAT OF WHITE WASH,APPROVED ADDESSIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	SQM	210			
SEC G	19B	PROVIDING & APPLYING WHITE WASH - THREE COATS ON NEWLY PLASTERED INTERNAL SURFACE OF WALL BY USING BEST SHALE LIME TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , APPROVED ADDESSIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	SQM	140			
SEC G	19C	PROVIDING & APPLYING TO INTERIOR SURFACES OF OFFICE BUILDING , TOILET AND PANTRY BLOCK BY TWO COATS OF OIL BOUND DISTEMPER (OBD) OF APPROVED SHADE ,COLOR AND MAKE CONFIRMING TO IS : 428 TO OBTAIN A EVEN FINISH AND UNIFORM COLOR OVER A COAT OF PRIMER AS PER MANUFACTURE RECOMMENDATION INCLUDING COST OF PAINT, SURFACE PREPARATION LIKE CLEANING AND BRUSHING & BROOMING OF WALLS , SCAFFOLDING AT ALL LEVEL ETC. COMPLETE. SURFACE PREPARATION SHALL BE DONE BY APPLYING PUTTY/PLASTER OF PARISH (POP) INCLUDING COST OF MATERIAL, LABOUR ETC. COMPLETE.	SQM	1430			
SEC G	20	PROVIDING AND FIXING OVER HEAD HYDRAULIC DOOR CLOSER (HEAVY DUTY) OF APPROVED BRAND AND SIZE ON NECESSARY DOORS AS DIRECTED BY BHEL ENGINEER.	NOS.	18			
SEC G	21	PROVIDING AND FIXING WHITE GLAZED VITREOUS CHINA WASH HAND BASIN OF 55 CM X 40 CM SIZE INCLUDING COLD WATER PILLER TAP, BRACKETS, STOP TAP, CHROMIUM PLATED BOTTLE TRAP AND NECESSARY PIPE CONNECTIONS INCLUDING UPVC WASTE PIPE AND TRAP UPTO THE OUT SIDE FACE OF THE WALL, MAKING GOOD THE DAMAGED SURFACE, TESTING ETC. COMPLETE. PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.	NOS.	4			
SEC G	22	PROVIDING AND FIXING EUROPEAN TYPE WHITE GLAZED VITREOUS CHINA W.C.PAN WITH UPVC SEAT AND LID WITH CHROMIUM PLATED BRASS HINGES AND RUBBER BUFFERS INCLUDING UPVC VENT PIPE (APPROX. 2M. HT. WITH COWL)) ON THE OUTSIDE FACE OF WALL, 10 LITRE PVC LOW LEVEL FLUSHING CISTERN WITH ALL FITTINGS, PIPE AND STOP COCK, BRACKETS FOR FIXING CISTERN, 32 MM DIA. UPVC FLUSH PIPE WITH FITTINGS AND CLAMPS, 20 MM DIA. UPVC OVERFLOW PIPE, FLOAT VALVES, CUTTING AND MAKING GOOD TO THE WALLS AND FLOORS, TESTING ETC. COMPLETE. PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.	NOS.	6			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW_e NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC G	23	PROVIDING AND FIXING IN POSITION OF WHITE GLAZED EARTHENWARE FLAT BACK/CORNER TYPE LIPPED FRONT URINALS OF 430MM X 260MM X 350MM / 340X460X265 MM OF APPROVED MAKE AND QUALITY WITHOUT FLUSHING CISTERN, GI FLUSH PIPE AND SPREADERS WITH BRASS UNIONS, GI CLAMPS, CUTTING OF WALLS AND MAKING GOOD OF ALL DAMAGES AND FINISHING TO MATCH THE EXISTING WORK ETC. COMPLETE. RATE QUOTED SHALL INCLUDE COST OF ALL MATERIALS AND LABOUR FOR CARRYING, LAYING & FIXING AND ALL OTHER INCIDENTAL CHARGES ETC. COMPLETE.	NOS.	10			
SEC G	24	PROVIDING AND FIXING IN POSITION OF HIGH CLASS BELGIUM OR SUPERIOR MAKE BEVELLED EDGE MIRROR OF SIZE 450MM X 550MM X 6MM WITH 16 MM DIA & 550MM LENGTH NICKEL PLATED TOWEL ROD MOUNTED ON 6 MM THICK PLYWOOD OR PLASTIC FOLDER SHEET. RATE TO INCLUDE COST OF ALL MATERIALS, LABOUR FOR FIXING THE WOODEN PLUGS WITH CP BRASS SCREWS AND WASHERS ETC. COMPLETE.	NOS.	4			
SEC G	25A	PROVIDING AND FIXING IN POSITION OF 15 MM DIA NOMINAL SIZE SCREW DOWN TYPE CHROMIUM PLATES BRASS BIB COCKS OF STANDARD TYPE OF APPROVED MAKE AND QUALITY (LEADER MAKE OR EQUIVALENT) AS PER STANDARD SPECIFICATION.RATE INCLUDES JOINTING MATERIALS,SOCKETS,UNION NUT,TESTING, LABOURS FOR CARRYING AND FIXING ETC. COMPLETE	NOS.	11			
SEC G	25B	PROVIDING AND FIXING IN POSITION OF 25 MM DIA GATE VALVE INCLUDING ALL NECESSARY FITTING & FIXTURE ETC. COMPLETE AS PER STANDARD SPECIFICATION.	NOS.	10			
SEC G	25C	PROVIDING AND FIXING IN POSITION OF 40 MM DIA GATE VALVE INCLUDING ALL NECESSARY FITTING & FIXTURE ETC. COMPLETE AS PER STANDARD SPECIFICATION.	NOS.	4			
SEC G	26	PROVIDING AND FIXING IN POSITION OF 15 MM DIA NOMINAL SIZE SCREW DOWN TYPE CHROMIUM PLATES BRASS STOP COCKS OF APPROVED MAKE AND QUALITY (LEADER MAKE OR EQUIVALENT) AS PER STANDARD SPECIFICATION.RATE INCLUDES COST OF JOINTING MATERIALS, SOCKETS,UNION NUT,TESTING, LABOURS FOR CARRYING AND FIXING ETC. COMPLETE	NOS.	11			
SEC G	27	PROVIDING AND FIXING IN POSITION OF 100MM X 50MM HCI "NAHANI" TRAP WITH HCI GRATINGS, BENDS, CONNECTING PIECES OF CI PIPE UPTO OUTSIDE FACE OF THE WALL. MAKING GOOD THE DAMAGED SURFACE,TESTING ETC COMPLETE AS PER STANDARD SPECIFICATIONS. RATE TO BE ALL INCLUSIVES.	NOS.	14			
SEC G	28	PROVIDING AND FIXING IN POSITION OF 150MM SALT GLAZED STONE WARE GULLY TRAP WITH HCI GRATINGS AND CI COVER OF SIZE 300X300 MM OF APPROVED MAKE (WEIGHT NOT LESS THAN 2 KG) AND QUALITY AS PER STANDARD SPECIFICATIONS. RATE TO BE ALL INCLUSIVE.	NOS.	7			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC G	29	PROVIDING AND LAYING WITH REQUIRED GRADING & LEVELING IN TRENCHES MEDIUM GRADE (TYPE) GALVANISED IRON (G I) PIPE HAVING EMBOSSED ISI MARK ON IT, OF REQUIRED DIAMETER WITH SCREWED, SOCKETS, JOINTS, NECESSARY GALVANISED IRON FITTINGS SUCH AS SOCKETS, BACK NUTS, ELBOWS, BENDS, TEES, REDUCERS, ENLARGERS, PLUGS, CLAMPS ETC. INCLUDING ALL NECESSARY EXCAVATION, BACK FILLING, FIXING WITH CLAMPS, TESTING ETC. COMPLETE. (PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.)					
SEC G	29A	40MM DIA	RM	100			
SEC G	29B	25MM DIA	RM	100			
SEC G	29C	20MM DIA	RM	100			
SEC G	29D	15MM DIA	RM	100			
SEC G	30	PROVIDING AT WORKING SITE, CARRYING AND LOWERING INTO TRENCHES, LAYING TO PROPER ALIGNMENT, LEVEL AND GRADE, JOINTING WITH CM (1:1) AND TESTING OF JOINTS ETC. OF THE FOLLOWING SIZE OF SALT GLAZED STONWARE PIPE INCLUSIVE OF ALL NECESSARY SPECIALS TARRED HEMP YARN AND ALL JOINTING MATERIALS COMPLETE AS PER STANDARD SPECIFICATIONS INCLUDING ALL NECESSARY EXCAVATION ,BACKFILLING,DISPOSAL OF SURPLUS EARTH ,LEAD AND LIFT AS PER SITE CONDITIONS. RATE SHALL INCLUDE COST OF ALL MATERIALS, LABOUR CHARGES AND INCIDENTAL CHARGES ETC. COMPLETE.					
SEC G		100MM DIA STONWARE PIPELINE INCLUDING ALL SPECIALS COMPLETE.	RM	100			
SEC G	31	PROVIDING AND FIXING IN POSITION OF PVC OVERHEAD WATER TANK OF SINTEX OR ANY APPROVED MAKE OF FOLLOWING CAPACITY WITH PROVISION FOR OVERFLOW ARRANGEMENT VALVES, INLET AND OUTLET ETC. COMPLETE. SUPPORTING STEEL STRUCTURE FOR FIXING THE TANK SHELL BE PAID IN THE RELAVENT ITEM.					
SEC G		500 LITRE	NOS.	3			
SEC G	32	CONSTRUCTION OF 230MM THICK BURNT CLAY / FLY ASH LIME BRICK CHAMBER (USING OPC GRADE 43/53) OF THE FOLLOWING DIMENSIONS (INNER DIMENSION) WITH 20MM THICK INTERNAL & EXTERNAL CEMENT PLASTER OF MIX CM 1:5 (1 CEMENT & 5 COARSE SAND) , NEAT CEMENT FINISH , TOP CI – COVER AND CONNECTORS FOR SEWER LINES. RATE SHALL BE INCLUSIVE OF ALL NECESSARY EXCAVATION & FILLING, PCC-100 MM THICK OF 1:3:6 FOR BEDDING ON 100MM THICK OVERSIZER SOLING WITH 80 MM METALETC. COMPLETE.					
SEC G	32A	600X450X450 WITH C.I COVER	NOS.	5			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC G	32B	900X600X450 WITH C.I. COVER	NOS.	3			
SEC G	33	PROVIDING AND FIXING OF PRECAST 80 MM THICK RCC COVER OF MIX 1:1.5:3 FOR MAN HOLES OF VARIOUS SIZES WITH REINFORCEMENT OF 10 MM DIA BOTH WAY TIED WITH TACK WELDING @ 150 MM C/C WITH 2 HOOKS OF 12 MM DIA BARS ETC.COMPLETE.					
SEC G	33A	750MM x 600MM	NOS.	5			
SEC G	33B	1050MM x 750MM	NOS.	3			
SEC G	34	PROVIDING AND FIXING CHROMIUM PLATED TOWEL ROD 16 MM DIA. AND 75CM. IN LENGTH INCLUDING ALL ACCESSORIES COMPLETE. (PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE).	NOS.	4			
SEC G	35	PROVIDING & FIXING OF LIQUID SOAP DISPENSER AT ALL WASH BASIN LOCATION.	NOS.	4			
SEC G	36	PROVIDING AND FIXING OF METALLIC DECORATIVE TYPE HEAVY DUTY PELMET ROD FOR DOORS AND WINDOWS. RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR ETC. AS APPROVED BY BHEL ENGINEER.	EACH	29			
SEC G	37	PROVIDING AND FIXING OF AQUA-GUARD OR EQUIVALENT WATER PURIFIER, ALONG WITH ALL FITTINGS. RATE TO INCLUDE ALL NECESSARY FITTINGS & FIXTURES, LABOUR ETC.AS APPROVED & DIRECTED BY BHEL ENGINEER.	NOS.	3			
SEC G	38	PROVIDING AND FIXING OF 1 No. 18"X24" SIZE STAINLESS STEEL SINK WITH ALL FITTINGS LIKE DRAIN PIPE, STOP VALVE ETC.RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR ETC.AS APPROVED & DIRECTED BY BHEL ENGINEER.	NOS.	1			
SEC G	39	PROVIDING AND FIXING 40MM THICK BEST QUALITY KADDAPPA SLAB OF REQUIRED SHAPE FOR FIXING SS SINK FOR KITCHEN COUNTER AND RACKS FOR KITCHEN STORE AREA ETC.COST INCLUSIVE OF MAKING OPENING AND FINISHING COMPLETE.	SQM	15			
SEC G	40	PROVIDING & FIXING IN POSITION OF CI VENT PIPE OF DIA. 100MM (APPROX. HT. 3M) IN SEPTIC TANK. RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR ETC.	RM	18			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW_e NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC G	41A	TRENCHING IN ORDINARY SOIL UPTO A DEPTH OF 60 CM INCLUDING REMOVAL AND STACKING OF SERVICEABLE MATERIALS AND THE DISPOSING OF SURPLUS SOIL,BY SPREDAING AND NEATLY LEVELLING WITHIN A LEAD OF 50 M AND MAKING UP THE TRENCHES AREA TO PROPER LEVELS BY SUPPLYING AND STACKING OF GOOD EARTH,SLUDGE,MANURE AT SITE INLUDING ROYALITY AND CARRIAGE UPTO 1 KM(INCLUDING FILLING, SPREADING, MIXING OF GOOD EARTH WITH SLUDGE AND MANURE(IN REQUIRED PROPORTION AND MANURE SCREENED THROUGH SIEVE OF I.S. DESIGNATION 20 MM) BEFORE AND AFTER FLOODING TRENCH WITH WATER.	CUM	300			
SEC G	41B	GRASSING WITH SELECTION NO. 1 GRASS INCLUDING WATERING AND MAINTENANCE OF THE LAWN FOR 30 DAYS OR MORE TILL THE GRASS FORMS A THICK LAWN, FREE FROM WEEDS AND FIT FOR MOWING INCLUDING SUPPLYING					
SEC G		WITH GRASS TURF	SQM	500			
SEC G		TOTAL VALUE OF SECTION-G IN Rs.					

BHEL:PSWR:NAGPUR

RATE SCHEDULE, SECTION - H

NAME OF THE WORK : INTERNAL AND EXTERNAL ELECTRIFICATION WORK OF BHEL SITE OFFICE BUILDING (45M X 10 M) WITH VERANDAH (2M WIDE), PANTRY AND TOILET BLOCK -- 1 NO. AT 2X700MW_e NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC H	1	SUPPLY OF 415 VOLT AC , 3 PHASE /FOUR WIRE POWER FEEDER PILLAR BOARD , BOARD SHALL BE COMPRISES OF THREE NUMBER AND ONE NUMBER ALUMINIUM BUS BAR FOR PHASE & NEUTRAL RESPECTIVELY. BUS BAR RATING SHALL BE 200 AMPS AND SHALL BE MOUNTED ON EPOXY INSULATOR OF 1.1 KV GRADE, EACH BUS BAR SHALL HAVE DRILLED HOLE FOR CONNECTING INCOMING / OUT GOING CABLES, PROVISION FOR EARTHING THE PANEL ENCLOSURE. PANEL ENCLOSURE SHALL BE MADE OF SHEET METAL THICHNNES NOT LESS THAN 1.6 MM AND SUITABLE FOR OUT DOOR INSTALLATION, HINGED DOOR WITH LOCKING ARRAGEMENT , BASE FRAME , SHOULD HAVE SLOPPED CANOPY, DULY PAINTED WITH FIRST COAT WITH PRIMER AND TWO COATS OF SYNTHETIC ENAMEL PAINT (INTERIOR WITH WHITE PAINT AND EXTERIOR WITH SMOKE GREY AS PER IS), SUITABLE STOOL MADE OUT OF MS STRUCTURE OF 1.2 METER HIGH FOR MOUNTING OF PANEL WITH ANCHORING ARRAGEMENT AT FOUNDATION .	NOS.	1			
SEC H	2	PROVIDING SUITABLE FOUNDATION FOR MOUNTING 415 VOLT AC POWER FEEDER PILLAR BOARD AS SPECIFIED IN SL. NO.12 , INSTALLATION & COMMISSIONING OF PANEL	NOS.	1			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC H	3	SUPPLYING & FIXING WALL MOUNTING TYPE LIGHTING PANELS , EACH WITH : (1) INCOMING MCB TPN -32 AMPS - 1NO. (2) RCCB DP 32 AMPS - 2NOS (3) MCB SP 6AMPS - 30 NOS.. All RCCBs, MCBs SHALL BE MDS/INDO KOPP MAKE. LIGHTING PANEL SHALL BE SIEMENS/MDS/INDO KOPP MAKE WITH INTERNAL BUSBARS, 2 NOS. EARTHING TERMINALS, EARTH CONNECTIONS, INCLUDING GLANDS, LUGS & WIRING FROM MAIN DB	PER POINT	1			
SEC H	4	PROVIDING AND INSTALLING WIRING USING 2.5 SQ.MM COPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR WHRERVER REQUIRED AS PER INSTRUCTION OF BHEL ENGINEER IN PVC CONDUIT OF REQUIRED SIZE.THE MAKE OF THE WIRE SHALL BE ONLY FROM KEI / POLY CAP/ HAVELLS/ FINOLEX/L&T/STANDARD.	PER POINT	128			
SEC H	5	PROVIDING AND INSTALLING WIRING FOR USING 4.0 SQ.MM COPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR WHRERVER REQUIRED AS PER INSTRUCTION OF BHEL ENGINEER IN PVC CONDUIT OF REQUIRED SIZE. THE MAKE OF THE WIRE SHALL BE ONLY FROM KEI / POLY CAP/ HAVELLS/ FINOLEX/L&T/STANDARD.	PER POINT	20			
SEC H	6	PROVIDING AND INSTALLING WIRING FOR USING 6.0 SQ.MM COPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR WHRERVER REQUIRED AS PER INSTRUCTION OF BHEL ENGINEER IN PVC CONDUIT OF REQUIRED SIZE. THE MAKE OF THE WIRE SHALL BE ONLY FROM KEI / POLY CAP/ HAVELLS/ FINOLEX/L&T/STANDARD.	PER POINT	56			
SEC H	7	PROVIDING AND INSTALLING WIRING FOR USING 16.0 SQ.MM COPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR WHRERVER REQUIRED AS PER INSTRUCTION OF BHEL ENGINEER IN PVC CONDUIT OF REQUIRED SIZE. THE MAKE OF THE WIRE SHALL BE ONLY FROM KEI / POLY CAP/ HAVELLS/ FINOLEX/L&T/STANDARD.	NOS.	40			
SEC H	8	POVIDING AND INSTALLATION OF PLUG POINT OF 5A SOCKET (ANCHOR OR EQUIV.) OUTLET INCLUDING WIRING TERMINATION. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NOS.	56			
SEC H	9	POVIDING AND INSTALLATION OF PLUG POINT OF 15A SOCKET (ANCHOR OR EQUIV.) OUTLET INCLUDING WIRING TERMINATION. THIS INCLUDES TUBE LIGHT FITTINGS V	NOS.	40			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC H	10	PROVIDING AND FIXING ORDINARY TUBELIGHT WITH FRAME OF STANDARD MANUFACTURER LIKE PHILIPS/BAJAJ OR EQUIVALENT AS APPROVED BY BHEL. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NOS.	75			
SEC H	11	PROVIDING AND FIXING CEILING FAN 48" DIAMETER OF APPROVED COMPANY SUCH AS CROMTAN GREEVES OR ANY OTHER STANDARD MANUFACTURER AS DIRECTED BY BHEL. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NOS.	20			
SEC H	12	PROVIDING AND FIXING WALL MOUNTED FAN 48" DIAMETER OF APPROVED COMPANY SUCH AS CROMTAN GREEVES OR ANY OTHER STANDARD MANUFACTURER AS DIRECTED BY BHEL. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NOS.	20			
SEC H	13	PROVIDING AND FIXING EXHAUST FANS 12" DIAMETER WITH FRAME OF STANDARD MANUFACTURER LIKE CROMPTAN GREEVES OR EQUIVALENT AS APPROVED BY BHEL.	NOS.	8			
SEC H	14	PROVIDING AND FIXING CALLING BELLS (WITH INDICATOR LIGHT)	NOS.	2			
SEC H	15	SUPPLYING, INSTALLATION & COMMISSIONING OF SODIUM VAPOUR LAMP STREET LIGHT FITTING 150 WATT SSG-2315 IH OF CROMPTON OR SIMILAR PHILIPS MAKE, COMPLETE WITH ONE PIECE CANOPY, INTEGRAL CONTROLGEAR COMPRISING OF COPPER WOUND CHOKE , IGNITOR , HPF CAPACITOR, HPSV LAMP AND SUITABLE FOR DIRECTLY SLIPPING OVER LIGHT MOUNTING BRACKET MADE OUT OF 40 MM OD PIPE AND SUITABLE FOR LAMPS, CONTROL GEAR BOX CABLING & TERMINATION OF ITEMS SUPPLIED (TO BE MOUNTED ON 9 MTR POLE - ITEM NO. 13).	NOS.	6			
SEC H	16	SUPPLY AND ERECTING STEEL TUBULAR SWAGED POLES, 9 MTR LONG MADE OF SHEET STEEL HAVING ULTIMATE TENSILE STRENGTH 42 KG F/SQ.MM CONFIRMING TO BIS :2713 (RPART-II) COMPLETE WITH 300X300X6 MM THICK M. S. BASE PLATE FOR WELDING AT SITE AND SIZE AS PER CONFIGURATION GIVEN IN BIS FOR 410 SP-28 (113 KG- POLE WEIGHT) WITH 1.5 MTR. DEEP EXACAVATION, CONCRETING IN 1:4:8 RATIO SIZE 45 CMS X 45 CMS X 150 CMS AND POLE PLINTH IN 1:3:6 CEMENT CONCRETING HAVING 300 MM HEIGHT AND 300 MM DIA .INCLUDING DOUBLE EARTHING OF POLE WITH SUITABLE ARRANGEMENT, DULY PAINTED WITH TWO COATS OF RED OXIDE PAINT AND ONE COAT OF ALUMINIUM PAINT TO BE APPLIED AFTER ERECTION; THE LENGTH OF POLE BELOW GROUND TO BE PAINTED WITH TWO COATS OF BLACK BITUMINUS PAINT. THE POLE SHALL BE COMPLETE WITH JB, FUSE AND MINOR FABRICATION AS BELOW : I) DRILING 20 MM DIA HOLE AT ABOUT 2.5 MTR FROM GROUND LEVEL FOR WIRE LEADS FROM JUNCTION BOX TO LIGHT FIXTURE . II) DRILING 15MM DIA HOLES AT ABOUT 0.7 AND AT 2.5 MTR FROOM GROUND LEVEL AND WELDING 12 MM NUTS FOR USING A 12 MM G.I BOLT FOR FASTENING EARTH CONDUCTERS. III) WELDING REQUIORED HOLES FOR FIXING POLE CAP OF STREET LIGHT BRACKET. IV) WELDING DIAMETRALLY 10 MM M.S. ROUND 30 MM BELOW POLE TOP EDGE FOR CLIPPING WIRE LEADS .	NOS.	6			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW _e NPCIL KAKRAPARA NUCLEAR POWER PROJECT							
SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC H	17	PROVIDING EARTH PITS WITH 2" DIA., 2.5 MTR. LONG GI PIPES WITH FLANGE AND 8 SWG GI WIRE WITH CHARCOAL, SALT AND AS PER IS 3043. RATE SHALL BE INCLUSIVE OF ALL MATERIAL, LABOUR ETC. COMPLETE. A BRICK WALL CHAMBER WITH CI COVER FOR ALL EARTH PITS SHALL BE PROVIDED.	NOS.	1			
SEC H	18	SUPPLY OF CABLES 3 -1/2 CORE X 95 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 (PART -I) THE MAKE OF THE CABLE SHALL BE ONLY FROM KEI / POLY CAP/ HAVELLS/ FINOLEX/L&T/STANDARD.	RM	300			
SEC H	19	INSTALLATION OF CABLES 3 -1/2 CORE X 95 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND, EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC COMPLETE. CABLES ARE TO BE LAID FROM 415 VOLT AC DISTRIBUTION BOARD TO FEEDER PILLAR BOARD.	RM	300			
SEC H	20	SUPPLY OF CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 (PART -I) THE MAKE OF THE CABLE SHALL BE ONLY FROM KEI / POLY CAP/ HAVELLS/ FINOLEX/L&T/STANDARD.	RM	100			
SEC H	21	INSTALLATION OF CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured PVC INSULATED CABLE CONFIRMING TO IS 1554 (PART -I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC. CABLES ARE TO BE LAID FROM FEEDER PILLAR BOARD TO LIGHTING PANEL.	RM	100			
SEC H		TOTAL VALUE OF SECTION-H IN Rs.					
BHEL:PSWR:NAGPUR							
RATE SCHEDULE, SECTION - I							
NAME OF WORK- PROVIDING 6" DIA.BOREWELL WITH SUBMERSIBLE PUMP OF 3HP CAPACITY -- 1 NOs.							
SECTION		DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC I	1	PROVIDING 6 " DIA. BORING UPTO DEPTH OF 150 FT. WITH TRUCK MOUNTED MECHANICAL RIG MACHINE WITH YIELD TEST OF WATRE.	EACH	1			
SEC I	2	EXTRA FOR BORING OVER 150 FT. DEPTH FOR EVERY ADDITIONAL 10 FT. OR PART THERE OF.	PER FT.	50			

NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 25,000 SQM. WITH INTERNAL ROADS, MONSOON YARD, DRAINAGE AND FENCING, ETC COMPLETE AT 2X700MW_e NPCIL KAKRAPARA NUCLEAR POWER PROJECT

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN RS. (IN FIGURES)	RATE IN WORDS	AMOUNT
SEC I	3	SUPPLY & FIXING 6" DIA. PVC HEAVY DUTY (8-10 KG PRESSURE) CASING PIPE OF STANDARD MAKE (KISHAN / KASTA OR EQUIVALENT) WITH APPROVAL OF BHEL IN BORING.	PER FT.	120			
SEC I	4	INSTALLATION OF ELECTRICAL SUBMERSIBLE PUMP (MINIMUM 3 HP) OF STANDARD MAKE (CROMPTON GREAVES/ CRI PUMP OR EQUIVALENT) AS PER APPROVAL OF BHEL WITH ALL ACCESSORIES, CONSOLE PANEL, PVC COATED SLING WIRE, SUBMERSIBLE CABLE OF REQUIRED LENGTH & 1 ^{1/4} " DIA. HDPE SUCTION PIPE 120 FT. LENGTH	EACH	1			
SEC I	5	EXTRA OVER LENGTH OF HDPE SUCTION PIPE BEYOND 120 FT.	PER FT.	30			
SEC I		TOTAL VALUE OF SECTION-I IN Rs.					

SUMMARY OF PRICE BID - TS : 1071

SR NO	PARTICULARS	AMOUNT IN RS
1	TOTAL VALUE OF SECTION-A IN RS	
2	TOTAL VALUE OF SECTION-B IN RS	
3	TOTAL VALUE OF SECTION-C IN RS	
4	TOTAL VALUE OF SECTION-D IN RS	
5	TOTAL VALUE OF SECTION-E IN RS	
6	TOTAL VALUE OF SECTION-F IN RS	
7	TOTAL VALUE OF SECTION-G IN RS	
8	TOTAL VALUE OF SECTION -H IN RS	
9	TOTAL VALUE OF SECTION -I IN RS	
	GRAND TOTAL VALUE OF ALL SECTIONS (A TO I) IN RS	
	GRAND TOTAL VALUE OF ALL SECTIONS (A TO I) IN WORDS (RS	