

**ANNEXURE I TO CORIGENDUM 01 DATED 08/02/2013  
TO T.S.NO BHE/PW/PUR/VIOCI-MECH/1103  
REVISED TERMS OF PAYMENT FOR GT, GTG & AUXL (CLAUSE 7.3 OF CHAPTER VII OF VOL IA 'TCC')**

<b>7.3 TERMS OF PAYMENT FOR ERECTION, TESTING AND COMMISSIONING OF GT, GTG &amp; AUXILIARIES PACKAGE</b>		
SN	Activity / Milestone	Payment Percentage
<b>1</b>	<b>GAS TURBINE, DUCTING, AUXILIARIES AND INTEGRAL PIPING (48 %)</b>	
1	Preparation and chipping of Fdn., leveling and centering of Gas Turbine	2.00%
1	Placement, leveling & centering of Gas Turbine with accessories on foundation	6.00%
1	Erection of load gear box	1.00%
1	Alignment of GT with Load Gear Box	1.00%
2	Grouting of foundation	2.00%
2	Erection of GT off base enclosure	3.00%
2	Erection of lube oil & gas fuel modules/Skids, Air Processing Skid, L.O. centrifuge, lube oil drain pump, water injection skid	3.00%
2	Erection of GT vent Fans with enclosure & exhaust blowers with frame, Lube oil mist eliminator etc.	3.00%
2	Erection of GT CO <sub>2</sub> fire protection systems	2.00%
1	Erection of Main Filter House with inlet filter, GT air filter system	3.00%
1	Erection of GT inlet ducting with silencers, expansion joints, Supports structure etc.	3.00%
1	Erection of Exhaust ducting with silences, Bypass Stack with Support structure, Aviation lamp & Lightening arrestors etc.	6.00%
1	Erection of dampers/diverter dampers with seal air fans with accessories & Aux.	4.00%
1	Erection of Integral Piping	5.00%
1	Erection of miscellaneous works on GT	2.00%
	<b>SUB TOTAL OF 1.0</b>	<b>46.00%</b>
<b>2</b>	<b>GAS TURBINE GENERATOR &amp; AUX (17%)</b>	
2	Preparation of foundation and levelling of base plates & packers etc.	1.00%
2	Placement of generator on foundation, centering & levelling	6.00%
2	Alignment of Generator with load gear box	1.00%
2	Erection of exciter and alignment	1.00%
3	Grouting of foundation	2.00%
3	Erection of air filter, Air cooler duct with air cooling elements etc.	2.00%
3	Erection of staircase, walkway & enclosure	2.00%
3	Miscellaneous items	1.00%
	<b>Sub total of 2.0</b>	<b>16.00%</b>
<b>3</b>	<b>BALANCE OF PLANT (MECHANICAL) AND OTHER RELATED EQUIPMENTS &amp; AUX. (20%)</b>	
3	Erection of BFPs with auxiliaries	5.00%
3	Erection of Naphtha Filter Skids with aux	1.00%
3	Erection of HSD Filter Skid with Aux. and HSD Centrifuge	1.00%
3	Erection of Hitech Additive Skid and Naphtha Fuel forwarding Skid, Naphtha Calescent Skid with Aux.	2.00%
3	Erection HSD Fuel forwarding Skid and Drain tank	1.50%

**ANNEXURE I TO CORIGENDUM 01 DATED 08/02/2013  
TO T.S.NO BHE/PW/PUR/VIOCI-MECH/1103  
REVISED TERMS OF PAYMENT FOR GT, GTG & AUXL (CLAUSE 7.3 OF CHAPTER VII OF VOL IA 'TCC')**

<b>7.3 TERMS OF PAYMENT FOR ERECTION, TESTING AND COMMISSIONING OF GT, GTG &amp; AUXILIARIES PACKAGE</b>		
SN	Activity / Milestone	Payment Percentage
4	Erection of Water to Water Heat Exchanger	0.50%
4	Erection of DM water circulating Pumps skids and DM water Pump GT Atomising Cooler	2.00%
4	Erection of Deaerator with Heater, fittings and Platform structure	4.00%
4	Erection of LP Dosing Skids	2.00%
4	Erection of Miscellaneous items	1.00%
	<b>Sub total of 3.0</b>	<b>20.00%</b>
<b>4</b>	<b>FINAL PAINTING (5%)</b>	
4	Progressive final painting of equipments under scope	3.00%
	<b>Sub total of 4.0</b>	<b>3.00%</b>
<b>5</b>	<b>Commissioning 15%</b>	
5	Oil flushing completion of GT system	2.00%
5	Cranking of GT	2.00%
5	Full speed no load sum of GT	1.00%
5	Synchronisation of GT set	2.00%
6	Commissioning of feed water system	2.00%
6	Commissioning of BFPs	2.00%
6	Combined Trial operation of GT in Co-Gen operation	1.00%
6	Completion of all facilities of GT systems	2.00%
6	Completion of of all Facilities and Handing Over / Contractual Obligation	1.00%
	<b>SUB TOTAL OF 5.0</b>	<b>15.00%</b>
	<b>GRAND TOTAL OF 1.0,2.0,3.0,4.0, AND 5.0</b>	<b>100.00%</b>