

ANNEXURE:01**BOQ-CUM-PRICE SCHEDULE FOR LT PVC CONTROL CABLE****4 X 270 MW BHADRADRI TPS****1.1 kV Copper conductor PVC insulated Armoured Control cables**

S.No.	Item name	UOM	Order Quantity	LOT-1 Quantity	Drum Length	UNIT EX-WORKS PRICE (DULY PACKED)	TOTAL EX-WORKS PRICE (DULY PACKED)	ED INCLUDING CESS @----- %	CST @----- % AGAINST FORM-C/E/EE/II OR VAT @----- % whichever is applicable	FREIGHT CHARGES (INCLUDING SERVICE TAX) @----- % OF TOTAL EXWORKS	TOTAL F.O.R. SITE PRICE
1	5C-1.5-ARMOURED	MTR	72000 (72 drums)	50000 (50 drums)	1000						
2	3C-1.5-ARMOURED	MTR	42000 (42 drums)	30000 (30 drums)	1000						
3	2C-1.5-ARMOURED	MTR	90000 (90 drums)	63000 (63 drums)	1000						
4	7C-1.5-ARMOURED	MTR	94000 (94 drums)	66000 (66 drums)	1000						
5	12C-1.5-ARMOURED	MTR	40000 (40 drums)	28000 (28 drums)	1000						
6	5C-2.5-ARMOURED	MTR	49000 (49 drums)	34000 (34 drums)	1000						

Notes :

- Quantities indicated above shall be known as Order Quantities. The variation in quantities of all sizes put together shall be limited to (+/-)30% of the total contract value as per GCC rev 06
- The bidder shall indicate the unit price of each type and size of cables listed as per the BOQ-Cum-Price Schedule. The unit prices shall apply for adjustment of variation in quantity as stipulated above.
- Lot-I quantities indicated above (in case the cable quantities are to be released for manufacture in more than one lot), or Order Quantity (in case the quantities are cleared for manufacture in one lot only) shall be cleared for manufacturing along with LOI. However, manufacturing of the cables shall be taken up by the successful bidder only after approval of technical and quality documentation. Subsequent lots shall be cleared for manufacture based on progress of engineering and site requirements.
- Delivery schedule of LOT-1 and subsequent lots shall be as per NIT.
- The standard drum length for control cables shall not be less than mentioned against each cable size above. The length per drum shall be subjected to a maximum tolerance of +/- 5% of the standard drum length.
- Overall tolerance on total dispatched quantity of each size shall be (-) 2% and (+) 0% Cables consumed for testing and inspection shall be to bidder's account.
- For each individual cable size, one short length of not less than 200m may be accepted only in the final drum length to complete the supply. The overall tolerance limits stipulated above shall continue to apply (in case short lengths are accepted).
- Bidder shall indicate unit price of cables inclusive of type test charges. No separate charges shall be payable for type tests.
- In case the quantities cleared by BHEL for manufacturing (in a lot) are manufactured and offered for inspection by successful bidder in more than one batch, BHEL reserves the right to witness type testing on all batches without any price implication.

Bhaskar