

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
100 EARTH WORK				
Earth work In excavation, backfilling and disposal including necessary men/women, materials, equipment, loading, transportation, unloading, dewatering etc as per specification, drawing and as directed by engineer- in-charge for the following.				
101	Earth work in excavation in all types of soil including ash which can be excavated by any means including setting out, levelling, dewatering (but excluding special type of dewatering viz. well point method), shoring & strutting (wherever required), dressing the sides & bottom, all lifts, ramming/compacting the excavated bottom, stacking, disposal of surplus excavated materials within a lead upto 500 m, spreading/levelling of disposed materials etc all complete for following depths below ground level.			
a	Depth from ground level but not exceeding 2 m	CUM	64250	2.62800038
b	Depth exceeding 2 m but not exceeding 4 m	CUM	57825	3.21686633
c	Depth exceeding 4 m but not exceeding 6 m	CUM	11364	0.82276705
d	Depth exceeding 6 m but not exceeding 8 m	CUM	2395	0.25470932
e	Depth exceeding 8 m but not exceeding 10 m	CUM	1916	0.20533485
103	Earth work in excavation in soft rock (rock without any recovery of excavated materials in the form of hard stone/boulder) including weathered rock which can be excavated by means of crow bar, pick axe, pneumatic rock breaker attachment with excavator machine etc but does not require chiselling or blasting including setting out, levelling, dewatering (wherever required), shoring & strutting (wherever required), dressing the sides & bottom, all lifts, ramming/compacting the excavated bottom, stacking, disposal of surplus excavated materials within a lead upto 500 m, spreading / levelling of disposed materials etc all complete for following depths below ground level.			
b	Depth exceeding 2 m but not exceeding 4 m	CUM	6425	0.60971762
c	Depth exceeding 4 m but not exceeding 6 m	CUM	7576	0.85529166
d	Depth exceeding 6 m but not exceeding 8 m	CUM	7185	0.92282648
e	Depth exceeding 8 m but not exceeding 10 m	CUM	7185	0.99923687
106	Earth work in excavation in hard rock requiring chiselling including wedging, line drilling, pre shearing etc as required, setting out, levelling, deawtering (wherever required), dressing the sides & bottom, all lifts, stacking/disposal of surplus excavated material within a lead upto 500m, spreading / levelling of disposed materials etc all complete for following depths below ground level.			
e	Depth exceeding 8 m but not exceeding 10 m	CUM	479	0.19475495
107	Back filling upto any depth below ground level around foundations, plinths, trenches, drains etc to proper grade and level in layers not exceeding 250 mm thickness using/with selected materials from compulsorily excavated soil / from Stock Pile of other sources available within a lead upto 500m and compacted as specified including re-excavation of stacked earth, watering, ramming/compaction by manual/mechanical means, dressing etc all complete.for the following.			
a	Each layer compacted so as to achieve at least 95% maximum dry density as per IS-2720 (Part-VII)	CUM	35231	1.19606657
b	Each layer compacted so as to achieve at least 90% maximum dry density as per IS-2720 (Part-VII)	CUM	18150	0.61617917
108	Back filling upto any depth below ground level around foundations, plinths, trenches, drains etc to proper grade and level in layers not exceeding 250 mm thickness using/with selected materials directly from excavation and compacted as specified including watering, ramming/compaction by manual/mechanical means, dressing etc all complete for the following.			
a	Each layer compacted so as to achieve at least 95% maximum dry density as per IS-2720 (Part-VII)	CUM	8808	0.28821699
b	Each layer compacted so as to achieve at least 90% maximum dry density as per IS-2720 (Part-VII)	CUM	4537	0.14846054
109	Extra over ST No. 101, 103 and 107 for carriage of excavated earth/selected materials beyond an initial lead of 500m as below;			

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.

PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work

ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
a	Carriage beyond initial lead of 500m or part thereof but not exceeding 2 km	CUM	11565	0.17029442
b	Carriage beyond 2 km or part thereof but not exceeding 3 km	CUM	11565	0.34058884
c	Carriage beyond 3 km or part thereof but not exceeding 4 km	CUM	3855	0.17029442
d	Carriage beyond 4 km or part thereof but not exceeding 5 km	CUM	3855	0.22707215
e	Carriage beyond 5 km or part thereof but not exceeding 6 km	CUM	1928	0.14191848
f	Carriage beyond 6 km or part thereof but not exceeding 7 km	CUM	1928	0.17030088
g	Carriage beyond 7 km or part thereof but not exceeding 8 km	CUM	1928	0.19868329
h	Carriage beyond 8 km or part thereof but not exceeding 9 km	CUM	1928	0.22706569
i	Carriage beyond 9 km or part thereof but not exceeding 10 km	CUM	1928	0.25544809
110	Back filling upto any depth below ground level around foundations, plinths, trenches, drains etc to proper grade and level in layers not exceeding 250 mm thickness using/with approved borrowed soil (borrowed soil to be arranged by the bidder) and compacted as specified including supplying borrowed soil, royalty (if any), watering, ramming/compaction by manual/mechanical means, dressing etc all complete for the following.			
a	Each layer compacted so as to achieve at least 95% maximum dry density as per IS-2720 (Part-VII)	CUM	495	0.05689531
b	Each layer compacted so as to achieve at least 90% maximum dry density as per IS-2720 (Part-VII)	CUM	255	0.02930970
111	Supplying and filling sand upto any depth under floors, around foundations, plinths etc. in layers not exceeding 250 mm thickness and compacted so as to achieve at least 80% relative density as per IS-2720 (Part-XIV) including spreading, watering, ramming/compaction by manual / mechanical means, dressing, royalty (if any) etc. all complete.	CUM	12880	3.13997622
200 CONCRETE WORKS				
Providing and placing concrete work including cost of labour, materials and equipment for handling, transportation, batching, mixing, placing, vibrating and curing, (excluding cost of centering, shuttering and reinforcement) with mechanised equipments like batching plant, transit mixer, concrete pump etc. complete as per drawing, specifications and as per direction of engineer in charge for the following.				
201	Concrete of grade M7.5 (1 part cement, 4 part sand, 8 parts of 40 mm graded aggregate by volume) as filling course at any depth below finished floor level, under and around foundations/floors, mass fill etc.	CUM	600	0.45060659
202	Concrete of grade M10 (1 part cement, 3 part sand, 6 parts of 40 mm graded aggregate by volume) as lean concrete, levelling course , mud mat under and around foundations/floors at any depth below finished floor level etc.	CUM	1306	1.20999209
203	Concrete of grade M15 (1 part cement, 2 part sand, 4 parts of 40 mm graded aggregate by volume) as lean concrete, levelling course , mud mat under and around foundations/floors at any depth below finished floor level etc.	CUM	100	0.11346920
204	Concrete under floors, paving, plinth protection, pipe encasing etc complete with 20 mm nominal size graded aggregate at any depth below finished floor level for the following grades.			
b	M20 Grade	CUM	250	0.28449189
205	Providing and laying Design Mix cement concrete conforming to IS:456 & IS 10262-2009 for reinforced concrete works with coarse sand and graded hard stone aggregate of 20mm nominal size in foundations/substructure, grade slab, paving, drains, under floors etc at any level below finished floor level, any shape, position or thickness etc complete including use of plasticizer/ superplasticizer conforming to IS:9103 (latest) to achieve required slump in concrete all complete as per specification & drawing for the following.			
a	M25 Grade	CUM	12510	16.65120805
b	M30 Grade	CUM	50	0.11643314

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
206	Providing and laying Design Mix cement concrete conforming to IS:456 & IS 10262-2009 for reinforced concrete works with coarse sand and graded hard stone aggregate of 20mm nominal size in superstructure at any level above finished floor level, any shape, position or thickness etc complete including use of plasticizer/ superplasticizer conforming to IS:9103 (latest) to achieve required slump in concrete all complete as per specification & drawing for the following.			
a	M25 Grade	CUM	2995	4.24738316
b	M30 Grade	CUM	50	0.11183141
211	Providing and encasing of structural steel member with concrete using nominal aggregate size of 12.5mm down. Encased member shall be wrapped with welded wire mesh/chicken wire mesh with proper lap etc. complete as per specification for the following grades. (Payment of welded wire mesh, chicken wire mesh shall be made separately)			
a	M20 grade	CUM	100	0.10663844
b	M25 grade	CUM	200	0.31054626
212	Screed concrete conforming to IS 456 with coarse sand and graded hard stone aggregate 12.5mm/6 mm nominal size on the roof at any level or thickness, drains etc complete as per following.			
a	1:2:4 (1 part cement, 2 part sand, 4 parts of aggregate by volume)	CUM	250	0.35269803
213	Providing and laying Design Mix cement concrete as per IS:456 & IS 10262-2009 for reinforced concrete works using graded aggregate for Concrete in precast works like roof slabs/trench covers, fins, lintels, chajas, beams, columns, wall panels, facias etc.at all levels in all kinds of work including formwork/moulds, curing, rendering the top exposed surface with cement sand mortar (1:3), handling, storing, transpoting, all leads, erection without damage, setting in position with cement sand mortar (1:3), filling the gaps between adjacent precast units with M30 grade concrete or cement sand mortar (1:3) and including making of holes for bolts for fixing, welding etc.complete with graded aggregate (20/12.5/10 mm) and as per specification and drawing for following grades.			
a	M 25 grade	CUM	10	0.02406807
b	M 30 grade	CUM	10	0.01437794
214	Providing and laying Design Mix cement concrete as per IS:456, IS 3370 & IS 10262-2009 for reinforced concrete works using graded aggregate for Concrete in water retaining/conveying structures including addition of suitable plastisizer cum waterproofing cement additives confirming to IS 9103 latest to achieve a slump more than 125 mm in concrete as per manufacturers recommendation and conforming to limits of permeability as per IS 2545 and specification with 20 mm nominal size graded aggregate for following grades.			
b	M 30 grade	CUM	14128	23.31820110
215	Dismantling concrete work for all types of structures at all levels including stacking of servicable material to a lead of 500 m and disposal of unservicable material upto a lead of 2 km, cutting of reinforcement, labour, equipment, safety precautions etc all complete as per drawings, specification and instructions of engineer in charge.			
a	Plain cement concrete of all grades	CUM	5	0.00370181
b	Reinforced cement concrete of all grades	CUM	5	0.00522547
216	Chipping of concrete in reinforced concrete work, cutting pockets, making openings at all levels and according to shapes, disposal of waste materials upto a lead of 2 km as directed by engineer including equipment, safety precautions, making good the broken surface etc all complete as per specification, drawing, instructions of engineer in charge but excluding cutting of reinforcement .	CUDM	1	0.00003803
217	Extra over and above St No 216 for cutting of reinforcement , all sizes and types including labour, equipment, return of cut reinforcement to store etc all complete as per specification, drawings and instructions of engineer in charge. Measurement shall be on the cross sectional area of reinforcement cut.	SQCM	1	0.00004335
219	Providing and applying curing compound of approved make where ever required as per manufacturer's specification.	SQM	3200	0.05628215

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
300 FORM WORKS				
Providing, fixing and removing formwork at any elevations for all structures, as per specifications and including all labour, material, scaffoldings and centering complete including pockets etc. complete as per drawing, specifications and as per direction of engineer in charge for the following.				
301	Fairface form work with good quality water proof ply wood of required thickness and smooth surface below finished ground floor level for foundations, footings, base of columns, walls, columns, pilasters, beams, mass concrete, trenches etc.	SQM	38917	4.93474621
302	Fairface form work with good quality water proof ply wood of required thickness and smooth surface above finished ground floor level for columns, beams, suspended floors, roofs, lintels, cantilevers, staircases, landings, balconies, domes, arches, circular overhead tanks etc. for all heights.	SQM	11400	1.83256231
304	Providing, fixing and removing formwork in block-outs/pockets and openings (below 0.1 sqm plan area) at all elevations including cutting, formation of all shapes and all other operations required for making the required shape and size all complete as per specification, drawing and instruction of engineer in charge.			
a	Upto 150 mm depth	Each	15	0.00227015
b	Pockets of depths more than 150mm and upto 300 mm depth	Each	15	0.00235604
c	Pockets of depths more than 300mm and upto 600 mm depth	Each	15	0.00374883
d	Pockets of depths more than 600mm and upto 1000 mm depth	Each	15	0.00520297
e	Pockets of depths more than 1000mm and upto 1500 mm depth	Each	10	0.00510073
400 REINFORCEMENT				
401	Taking delivery of steel from BHEL stores/ store yard, loading, transporting and unloading at site, straightening, cutting, bending, placing in position at any level, binding of mild steel reinforcements conforming to grade 1 of IS:432 part 1 in concrete including cost of binding wire, labour, scaffolding, transportation to & from stores etc. all complete as per specifications & drawings.	MT	15	0.30277933
402	Taking delivery of steel from BHEL stores/ store yard, loading, transporting and unloading at site, straightening, cutting, bending, placing in position at any level, binding in position of steel reinforcements of TMT steel of grade Fe-500/Fe-500D confirming to IS:1786 including cost of binding wire, labour, scaffolding, transportation to & from stores etc complete all as per specifications, drawings and as directed by Engineer.	MT	2978	7.82725345
500 WATER PROOFING WORKS				
Water proofing works including all labour, material, equipment, transportation, handling, curing, sampling, testing etc at any level as per specification, drawings and as directed by engineer - in - charge.				
A501	Providing and laying underbed grading plaster with cement mortar 1:4 (1 cement : 4 sand) and average thickness of 15 mm including preparation of surface, batching, mixing, leveling etc. all complete.	SQM	2890	0.06891965
A502	Providing and laying rigid insulation (extruded polystyrene blocks) as per relevant IS Code in suitable panels over roofs followed by a layer of 15 mm thick cement sand plaster 1:4 (1 cement: 4 coarse sand) and providing of expansion joint at intervals and filling with sealant in both directions as per the recommendation of manufacturer. The block shall be strong enough to withstand without deformation the workload and standard loads expected on the roof. Cost shall include making of fillets, cleaning & preparation of surface, expansion joints including filling with sealants at suitable intervals etc all complete as per specification for following.			
a	Average 50 mm thickness	SQM	2890	0.89088807

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
A506	Providing and applying PU based water proofing treatment with elastomeric, seamless waterproof membrane applied in 2 coats to a DFT of 1.2 mm thick having a elongation capacity of over 600% and average tensile strength of 1 MPa, tear resistance as per GBT 19250-2003 >20N/m. The material shall comply with – ASTM C 836 National Std. of Canada 37.58 – M86 by CGSB. All complete as per specifications and directions of engineer in charge.	SQM	2890	0.68563093
B506	Providing and applying a separation layer of non-woven polypropylene geo-textile membrane of 120 gsm for water proofing as per technical specification.	SQM	2890	0.10047755
C506	Providing and applying 4 mm thick APP modified Bituminous Polyester membrane for waterproofing manufactured from a rich mixture of bitumen and selected polymers blended together to obtain excellent heat resistant, flexibility, UV resistance etc. Modified bitumen then coated onto a dimensionally stable carrier to obtain excellent tensile strength, tear and puncture resistance etc complete as per technical specification.	SQM	2890	0.36334699
A508	Providing and laying pressed precast concrete tiles of 20 mm thickness and size 600x600 mm conforming to IS 13801 with 15 mm thick 1:4 cement mortar over the top most layer of roofing treatment with fine joints including sealing of joints (silicon/elastomeric sealant) etc all complete. (Water proofing paid elsewhere)	SQM	2890	0.64662199
509	Providing and applying two coats of bitumen grade 85/25 as per IS 702 (@ 1.7kg/sqm)with 1% antistripping compound conforming to IS 6241 in foundation, wall, column etc on concrete surfaces exposed to soil / ash including surface preparation etc. all complete.	SQM	19459	1.17803604
510	Providing and applying water proofing with blown bitumen bonding material conforming to IS:702 of 65/25 grade in Basements, ducts, pits, tunnels etc below the ground level on the concrete surfaces exposed to soil / ash and up to 150 mm above ground level on outside of walls and top of RCC slab including preparation of surface, brick lining single brick thick with 1:4 cement mortar etc. all complete with following number of layers of bitumen felts :			
512	Anti termite chemical treatment of soil with Chloropyrifos emulsifiable concentrates (1%) conforming to IS :8944 all complete.	SQM	400	0.01276165
600 JOINTS AND FILLERS				
Joints & fillers including all labour, material, equipment, transportation, handling etc at any level as per specification, drawings and as directed by engineer - in - charge.				
601	Supplying & installation of bitumen impregnated fibre board confirming to IS 1838 as joint filler at joints in concrete including nailing, coating of both faces with coal tar pitch/bitumin etc. all complete.			
a	12 mm wide joints.	SQM	100	0.04037233
b	20 mm wide joints.	SQM	100	0.05350244
c	25 mm wide joints	SQM	100	0.06540547
d	50 mm wide joints	SQM	100	0.08426230
602	Providing and applying polysulphide based sealant conforming to IS:12118 in expansion joints in concrete including cleaning of joints, raking out groove, application of primer, scaffolding etc. all complete for following size grooves:			
a	12mm X 25mm	RM	250	0.01462356
b	20mmX25mm	RM	250	0.02290636
c	25mmX25mm	RM	200	0.03239563
d	50mmX25mm	RM	200	0.06479193
603	Supplying and filling in position hot applied bitumin sealing compound (Grade A) confirming to IS 1834 including cleaning, mixing, heating, pouring/injecting sealing compound in gaps in joints including application of			

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
	primer etc. all complete.			
a	10mm X 40mm	RM	250	0.00122708
b	12mm X 25mm	RM	200	0.00073624
c	20mmX25mm	RM	200	0.00122708
604	Supplying and filling in position hot applied bitumin sealing compound (Grade B) confirming to IS 1834 including cleaning, mixing, heating, pouring/injecting sealing compound in gaps in joints including application of primer etc. all complete.			
a	10mm X 40mm	RM	250	0.00102256
b	12mm X 25mm	RM	200	0.00065444
c	20mmX25mm	RM	200	0.00106347
606	Providing and fixing PVC water stops in joints conforming to IS 12200 & IS 15058 all complete for the following:			
a	150 mm wide and 8 mm thick	RM	100	0.01227115
b	230 mm wide and 8 mm thick	RM	100	0.01689349
c	150 mm wide and 6 mm thick	RM	200	0.01930675
d	230 mm wide and 6 mm thick	RM	200	0.05898374
700 MS EMBEDMENTS				
Embedments including all labour, material, equipment, transportation, handling etc. at any level as per specification, drawings and as directed by engineer - in - charge.				
701	Fabricating and fixing of mild steel embedments, inserts, pipe sleeves, angle pieces, rungs of various diameters, plates of dimensions as required etc. including welding, bolting, cutting, drilling, scaffolding, setting etc. all complete.	MT	15	0.12713010
702	Same as above with BHEL supplied material free of cost including loading, transportation, unloading etc. all complete from BHEL store to plant site.	MT	15	0.13329579
703	Fixing of embedments, inserts, pipe sleeves, angle pieces, anchor bolts of various diameters, plates of dimensions as required etc. including scaffolding, setting in position, transportation from BHEL site stores to work spot etc. all complete.	MT	25	0.14900294
704	Transportation from BHEL store and erection, installation and alignment of mild steel foundation bolt assembly conforming to IS:2062 and grade 1 of IS:432 in concrete along with nuts, lock nuts (as per IS:1363, 1364 and IS:3138), washers, anchor plates, stiffner plates, protective tape, pipe sleeves, templates etc. including welding, cutting, grinding, threading, drilling etc. all complete as per specification.	MT	20	0.70060307
705	Supplying, fabricating, erecting and installing following items in concrete/brickwall for all kind of works, including setting material in concrete, layout, scaffolding, cutting, forming, grinding, drilling, bolting, welding, jointing, testing etc. all complete.			
a	MS pipes of all diameters	Quintal	10	0.03553736
b	PVC pipes / conduits of all diameters	Quintal	10	0.07202779
c	UPVC pipes / conduits of all diameters	Quintal	10	0.07593035
d	Expansion fasteners (mechanical galvanised) of HILTI make or equivalent of safe tensile capacity including SS Clamps wherever required as specified below for brick work with/without expansion sleeve of A6 polyamide:			
i	Upto 250 kg	Each	10	0.00111667
ii	Beyond 250 Kg and upto 500 kg	Each	10	0.00173434
iii	Beyond 500 Kg and upto 750 kg	Each	10	0.00279784

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.

PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work

ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
e	Expansion fasteners (mechanical galvanised) of HILTI make or equivalent of safe tensile capacity as specified below for concrete work with expansion sleeve of stainless steel:			
i	Upto 250 kg	Each	10	0.00132119
ii	Beyond 250 Kg and upto 500 kg	Each	10	0.00201248
iii	Beyond 500 Kg and upto 750 kg	Each	10	0.00316188
A705	Anchor fasteners (Chemical type, galvanised) of HILTI make or equivalent of safe tensile capacity as specified below for concrete work.:			
i	Upto 250 kg	Each	10	0.00213897
ii	Beyond 250 Kg and upto 500 kg	Each	10	0.00275483
iii	Beyond 500 Kg and upto 750 kg	Each	10	0.00340713
800 GROUTING				
Grouting including all labour, material, equipment, roughening surface, cleaning, ramming, curing etc. at any level unless otherwise specified as per specification, drawings and as directed by engineer - in - charge.				
801	Providing & grouting with cement slurry mix of approved ratio using pressure pump for water retaining concrete structures as per approved procedure including cost of nipples/ nozzles, cement, admixture, curing, pressure pumps, slurry agitator etc. all complete. Cost shall include fixing of nipples at minimum 500 mm centre to centre spacing, cutting of nipples after completing of grouting, making good of the nipple hole with appropriate non-shrink cement paste, water tightness test etc. all complete wherever specified in the drawing.	SQM	25	0.00475510
802	Providing & grouting of pocket holes, pipe sleeves under base plates, machinery, pipe supporting structures etc. with mix 1:1 (1 cement :1 sand) using non shrink admixture etc. all Complete.	CUM	10	0.07833171
803	Providing & grouting of pocket holes, pipe sleeves and under base plate of structural steel work/ machinery/ pipe supporting structures including roughening of surface, cleaning, ramming, curing etc. all complete with mix 1:1:2 (1 cement : 1 coarse sand : 2 aggregate of 6 mm down graded stonechips) using non shrink admixture. (Cost of all material and cleaning the pocket by compressed air shall be in the scope of the contractor).	CUM	5	0.02327658
804	Providing & grouting of pocket holes, pipe sleeves and under base plates of structural steel work/ machinery/ pipe supporting structures including roughening of surface, cleaning, ramming, curing etc. all complete with ConbextraGP-1 or equivalent. (Cost of all material and cleaning of the pockets by compressed air shall be in the scope of the contractor).	CUM	10	0.21708141
805	Providing & grouting of pocket holes, pipe sleeves and under base plates of structural steel work/ machinery/ pipe supporting structures including roughening of surface, cleaning, ramming, curing, etc. all complete with Conbextra GP-2 or equivalent. (Cost of all material and cleaning of the pockets by compressed air shall be in the scope of the contractor).	CUM	10	0.24105933
A805	Providing & grouting of pocket holes, pipe sleeves and under base plates of structural steel work/ machinery/ pipe supporting structures including roughening of surface, cleaning, ramming, curing, etc. all complete with Conbextra GPX-2 or equivalent. (Cost of all material and cleaning of the pockets by compressed air shall be in the scope of the contractor).	CUM	5	0.12052966
900 DOORS, WINDOWS, VENTILATORS, LOUVERS				

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.

PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work

ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
Doors, windows, ventilators, louvers, roof ventilators, rolling shutters, partitions including all labour, material, equipments, transportation, handling, preparation of working drawings etc. at any level as per specification, drawings and as directed by engineer - in - charge.				
901	Providing and fixing wooden frame conforming to IS 4021 made of best quality seasoned CP teakwood free from large or loose knots, cracks or other defects including sand paper smoothening, hold fasts, beading, primer and finish painting / polishing etc. all complete with proper wood joinery, accurately set to required lines or levels and rigidly secured in place. (Finish painting / polishing paid separately)	CUM	5	0.21361889
A901	Providing and fixing wooden frame conforming to IS 4021 made of best quality seasoned hardwood free from large or loose knots, cracks or other defects including sand paper smoothening, hold fasts, beading, primer and finish painting / polishing etc. all complete with proper wood joinery, accurately set to required lines or levels and rigidly secured in place. (Finish painting / polishing paid separately)	CUM	5	0.06489774
902	Providing and fixing teakwood frame panel door shutter as per IS 1003 with 35 mm x 150 mm vertical rail & 35mm x 125 mm horizontal rail and 12 mm thick interlocked panels of teakwood with proper wood joinery including beading, preperation of working drawings,godrej or equivalent make mortice lock with handels on both sides,approved ISI mark anodised fittings like door stopper,300mm long tower bolts,16x300mm long aldrops ,125mm long handles on both sides etc. butt hinges, sliding bolt ,knobs, (all fitting shall be anodised aluminium color dyed), screws, primer and finish painting / polishing etc. all complete. (Finish painting / polishing paid separately)	SQM	24	0.03559623
A902	Providing and fixing teakwood frame panel door shutter as per IS 1003 with 35 mm x 150 mm vertical rail & 35mm x 125 mm horizontal rail and 12 mm thick interlocked panels of teakwood with proper wood joinery including beading, preperation of working drawings,godrej or equivalent make mortice lock with handels on both sides,approved ISI mark anodised fittings like door stopper,300mm long tower bolts,16x300mm long aldrops ,125mm long handles on both sides etc. butt hinges, sliding bolt ,knobs, (all fitting shall be anodised aluminium color dyed), screws, primer and finish painting / polishing etc. all complete. (Finish painting / polishing paid separately)	SQM	10	0.01483176
B902	Providing and fixing teakwood frame panel door with PVC lamination on both sides shutter as per IS 1003 with 35 mm x 150 mm vertical rail & 35mm x 125 mm horizontal rail and 12 mm thick interlocked panels of teakwood with proper wood joinery including beading, preperation of working drawings,godrej or equivalent make mortice lock with handels on both sides,approved ISI mark anodised fittings like door stopper,300mm long tower bolts,16x300mm long aldrops ,125mm long handles on both sides etc. butt hinges, sliding bolt ,knobs, (all fitting shall be anodised aluminium color dyed), screws, primer and finish painting / polishing etc. all complete. (Finish painting / polishing paid separately)	SQM	10	0.01488902
903	Providing, fitting and fixing solid core flush door shutter as per IS 2202 part II, 35mm thick homogenous particle board bonded with BWP type phenolformaldehyde synthetic resin, partical board core conforming to IS 3087 type I, 35x12 mm thick teakwood beading all around including preparation of working drawings. godrej or equivalent make mortice lock with handels on both sides,approved ISI mark anodised fittings like door stopper,300mm long tower bolts,16x300mm long aldrops ,125mm long handles on both sides etc. butt hinges, sliding bolt, knobs, (all fittings shall be anodised aluminium color dyed), finish synthetic paint over primer,	SQM	10	0.01559668

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
	screws etc. all complete as per drawing, specification and instruction of engineer in charge. with commercial faces and teak wood edges. (Finish painting paid separately)			
A903	Providing, fitting and fixing solid core wooden flush door shutter with PVC lamination on both sides as per IS 2202 part II, 35mm thick homogenous particle board bonded with BWP type phenolformaldehyde synthetic resin, particle board core conforming to IS 3087 type I, 35x12 mm thick teakwood beading all around including preparation of working drawings. godrej or equivalent make mortice lock with handles on both sides, approved ISI mark anodised fittings like door stopper, 300mm long tower bolts, 16x300mm long aldrops, 125mm long handles on both sides etc. butt hinges, sliding bolt, knobs, (all fittings shall be anodised aluminium color dyed), finish synthetic paint over primer, screws etc. all complete as per drawing, specification and instruction of engineer in charge. with commercial faces and teak wood edges. (Finish painting paid separately)	SQM	40	0.06266485
904	Providing and fixing single or double steel door shutters with 45mm thk flush design shutter comprising of two outer sheets of 18 gauge steel sheets rigidly connected and reinforced inside with continuous vertical 20 gauge stiffeners, spot welded in position at not more than 150mm on centres including void filled with mineral wool (density as per specification), all fittings, Godrej or equivalent make mortice lock with handle on both sides, shop and final painting etc all complete.	SQM	40	0.09455772
906	Providing and fixing anodized extruded aluminium doors (single or double shutter) conforming to IS:1948, IS:1949 fabricated from extruded sections of HINDALCO/JINDAL or equivalent make having minimum 3mm wall thickness as per IS:1285, IS:733 and anodized and electro color coating of required shade as per IS 1868 (minimum anodized coating of grade AC15). fixed with rawl plugs, expansion fasteners, SS screws / fixing clips necessary filling of gaps at Junctions, at top, bottom & sides with required PVC / neoprene felt for bi-metallic protection etc. Glazing shall be clear float glass of 6mm thickness including snap fit type beading, concealed screws, fixtures, Godrej or equivalent make Mortice lock with handle on both sides, etc all complete. Aluminium section shall be smooth, free of stains, straight, mitred & jointed mechanically wherever required. (Glazing shall be paid separately)	SQM	50	0.11107471
907	Fixing of fire proof steel doors (single or double shutter) with panic devices shall be 45mm thk flush design comprising of two outer sheets of 18 gauge steel sheets rigidly connected and reinforced inside with continuous vertical 20 gauge stiffeners, spot welded in position at not more than 150mm on centers including all fittings, shop painting with approved post office/signal red color fire resistant paint and mineral wool insulation (64 kg/cum density) complete and shall be fire proof as per IS:3614, TAC requirements and as per specification. Minimum ratings shall be 2 Hrs.	SQM	20	0.11962345

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.

PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work

ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
A907	Fixing of fire proof steel doors (single or double shutter) with panic devices and vision panel shall be 45mm thk flush design comprising of two outer sheets of 18 gauge steel sheets rigidly connected and reinforced inside with continuous vertical 20 gauge stiffeners, spot welded in position at not more than 150mm on centers including all fittings, shop painting with approved post office/signal red color fire resistant paint and mineral wool insulation (64 kg/cum density) complete and shall be fire proof as per IS:3614, TAC requirements and as per specification. Minimum ratings shall be 2 Hrs.	SQM	40	0.23924690
908	Providing and fixing steel windows/ventilator with steel sections as per IS:1038, IS:1361 & IS:7452 latest revision.including all fittings, metal beadings, hold fasts, shop and final painting ,glazing etc. all complete. (Glazing shall be paid separately)			
a	openable type	SQM	50	0.05673376
b	fixed type	SQM	20	0.02174456
A908	Providing and fixing windows/ventilator with M.S. grills as per approved design for security purpose made of 25 mm X 6mm M.S. Flats / 12mm – 20mm M.S. square bar of approved design shall be provided to suit security requirements.	Kg	50	0.00160593
909	Fixing of anodised aluminium work of Jindal, Hindalco or other equivalent approved make for door frames, windows, ventilators, partitions, railing etc with extruded standard tubular and other sections including all fittings & fixtures and accessories of approved make conforming to IS733 and IS1285, anodised and electro color dyed to required shade according to IS 1868 (minimum anodic coating of grade AC15), fixed with rawl plugs, expansion fasteners, SS screws or with fixing clips, including necessary filling of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt for bi-mettalic protection etc.including preperation of working drawings, aluminium cleat angle, aluminium snap-on-beading for glazing/panelling, stair case tread nosing, with all fittings and fixtures (like tower bolts, handles, door stopper with rubber shoes, 'L' drops, stays, floor springs, hydraulic door closures etc.), CP brass/stainless steel screws, providing and fixing hinges/pivots, and making provision for fixing of fitting wherever required including cost of PVC/neoprene gasket, all complete as per drawing, specification and instructions of engineer in charge (Glazing and panelling shall be paid seperately).Weight of aluminium section only shall be measure.	Kg	191	0.01059415
A909	Fixing of anodised aluminium work of Jindal, Hindalco or other equivalent approved make for door/window frames, door/window shutters, ventilators, partitions, railing, grills etc with extruded standard tubular and other sections including all fittings & fixtures and accessories of approved make conforming to IS733 and IS1285, anodised and electro color dyed to required shade according to IS 1868 (minimum anodic coating of grade AC15), fixed with rawl plugs, expansion fasteners, SS screws or with fixing clips, including necessary filling of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt for bi-mettalic protection etc.including preperation of working drawings, aluminium cleat angle, aluminium snap-on-beading for glazing/panelling, stair case tread nosing, with all fittings and fixtures (like tower bolts, handles, door stopper with rubber shoes, 'L' drops, stays, floor springs, hydraulic door closures etc.), CP brass/stainless steel screws, providing and fixing hinges/pivots, and making provision for fixing of fitting wherever required including cost of PVC/neoprene gasket, all complete as per drawing, specification and	Kg	3500	0.19413374

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
	instructions of engineer in charge (Glazing and panelling shall be paid separately).Weight of aluminium section only shall be measure.			
A910	Fixing of aluminium composite panel (ACP) 3mm thick fixed in aluminium frame including sealant with minimum 0.2mm topping of precotaed aluminium foil on both side of approved manufacturer & approved shade, all complete as per specification.	SQM	100	0.12835678
911	Providing and fixing of door closers as per IS 3564 ,of approved make & quality all complete of following type :			
a	Over head hydraulic door closures	Each	20	0.01250027
b	Floor mounted Hydraulic door closers	Each	10	0.01063913
912	Providing and fixing pressed steel frames fabricated from 16 gauge M.S sheet mortised, reinforced drilled and tapped for hinges and locks bolts strikes, hold fasts adjustable floor anchors, floor tiles/weather bars ,paintings etc all complete as per specifications.	Kg	1500	0.06748950
913	Providing and fixing in position rolling shutter of hot rolled double dipped galvanised steel lath section of 18 SWG tested mild steel strips at 75mm rolling centres interlocked together through their entire length and jointed together at the end by end locks mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation including wire springs, top cover, primer & shop coats of approved enamel paint etc, all complete as per IS 6248 and specification of approved make of following types: The bottom lath shall be coupled to a lock plate fabricated from 3mm thick galvanised steel plate and securely rivetted with stiffening angles.(partly coiled and lath/full lath).			
a	Hand Operated	SQM	20	0.02544431
b	Mechanically Operated	SQM	60	0.09422439
914	Providing and fixing PVC doors (25 thk double skin) with PVC frame of sintex or equivalent make including all fitting & fixtures as per specification, drawing and instructions of engineer in charge.	SQM	40	0.04337459
A914	Providing and fixing Solid core PVC doors (25 thk double skin) with PVC frame of sintex or equivalent make including all fitting & fixtures as per specification, drawing and instructions of engineer in charge.	SQM	20	0.04672640
915	Providing, fixing and fitting of glazing of first grade class in steel/aluminium/wooden frames, where ever required, cleaning after fixing including hardware, gaskets, clips, beadings etc. all complete.			
b	4 mm thick clear float glass	SQM	100	0.02159731
c	5.5 mm thick clear float glass	SQM	253	0.07658063
d	6 mm thick wired glass	SQM	100	0.03030992
e	6mm thick Polycarbonate sheet multi (twin) wall fire retardant and ultra violet resistant with sealed open edges.	SQM	15	0.01284181
f	4 mm thick ground glass	SQM	20	0.00459760
A915m	6 mm thick clear float glass with itching	SQM	10	0.00217538
A915n	One outer 6mm thick tinted heat-reflecting type float glass and one inner 6mm thick toughened float glass hermetically sealed and seperated by 12 mm thick gap for thermal insulation (only single	SQM	50	0.01946936

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
	elevation area to be measured).			
916	Supplying and fixing weather stripping of approved make and quality to doors as per instructions of engineer in charge and specification complete.	RM	10	0.00093261
917	Providing and fixing 12 mm thick BWP particle board , decorative veneer (prelaminated) on both sides, as panels in aluminium framed door shutter, fixed with necessary snap-on-beading etc. all complete (excluding aluminium works).	SQM	10	0.00728501
918	Providing and fixing steel louvered window with ISMC 100 frame all round including verticals with 18G pressed steel louvers, painting etc. all complete.	SQM	10	0.01227936
1000 BRICKWORK				
Brickwork masonry including all labour, material, equipment, transportation, handling, scaffolding etc. at all levels as per specification, drawings and as directed by engineer - in - charge.				
A1001	Providing brick work in cement mortar 1:6 (1 part cement 6 parts coarse sand) in walls, chambers etc. in thickness varying from 230mm to 460mm at all depths, places and positions below plinth including raking out joints, curing, scaffolding etc. complete excluding plastering and painting.			
a	Using fly ash lime/cement bricks confirming to IS 12894 with crushing strength of 75 kg/cm ²	CUM	20	0.03036947
A1002	Providing brick work in cement mortar 1:6 (1 cement 6 coarse sand) in walls, chambers etc. in thickness 230mm at all heights, places and position above plinth including raking out joints, curing, scaffolding etc complete excluding plastering and painting.			
a	Using fly ash lime/cement bricks confirming to IS 12894 with crushing strength of 75 kg/cm ²	CUM	680	0.95794112
A1003	Providing brick work in cement mortar 1:4 (1 cement 4 coarse sand) in partition walls , chambers etc. in thickness 115mm at all heights, places and position above or below plinth/graded level including providing two nos. 6 mm diameter MS bars at every third layer, raking out joints, curing, scaffolding etc complete excluding plastering and painting as per specification. (MS bars shall be supplied by BHEL free of cost).			
a	Using fly ash lime/cement bricks confirming to IS 12894 with crushing strength of 75 kg/cm ²	SQM	522	0.10217609
1006	Breaking of existing brick work at all levels including plastering, removing the rubbish up to a distance of 500 m including transportation, loading, unloading etc. all complete as directed by the engineer.	CUM	5	0.00175477
1007	Providing and encasing of structural steel member with masonry work around flanges, webs etc. and filling the gap between steel and masonry by minimum 12mm thick mortar. Encased member shall be wrapped with chicken wire mesh with 50mm lap etc. complete as per specification. (Chicken wire mesh to paid separately)	CUM	5	0.00650782
1008	Providing and laying 75 mm thick bed of dry brick aggregate including of excavation, disposal of surplus earth spreading of earth, ramming, watering etc. complete in all respects as directed by the engineer.	SQM	10	0.00066265
1009	Making openings in existing brick wall or partition wall including making good the broken edges/surface with cement mortar etc. complete.	CUM	5	0.00235197
1010	Supply and placing in position mild steel wire fabric of square mesh 25 mm size and wire diameter of 2 mm for encasing of steel sections in concrete including cutting, bending, fixing etc. complete.	SQM	10	0.00102669
1012	Providing and filling brick bats in soak pits all complete.	CUM	10	0.00438490
1100 DAMP PROOF COURSE				

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
Damp proof course including all labour, material, equipment, transportation, handling, shuttering, centering, curing etc at any level as per specification, drawings and as directed by engineer - in - charge.				
1101	Providing Damp Proof Course 40mm thick 1:1.5:3 concrete (10mm and down graded aggregate) with 2% of approved admixture of water proofing compound all complete. Two layers of hot bitumen coating 85/25 grade as per IS:702 @ 1.7Kg./sqm shall be applied one before & one after the DPC.	SQM	120	0.01477446
1200 CEMENT MORTAR PLASTER				
Cement mortar plaster including making grooves wherever required including all labour, material, scaffolding, curing etc at any level as per specification, drawings and as directed by engineer - in - charge.				
A1201	Providing 20mm thick plaster in two layers outside of the building wall/rough surface of internal wall in 1:4 cement sand mortar of 12mm thick first layer and 1:3 cement sand mortar with 8mm second layer, finished to a smooth finish including providing 3mmx3mm size grooves at junctions of two dissimilar materials all complete.	SQM	2600	0.40388361
A1202	Providing 12mm thick plaster inside the building/boundary wall in cement mortar 1:4 on walls finished to a smooth finish as per specification all complete.	SQM	2735	0.37377988
A1204	Providing 6mm thick plaster on ceiling in cement mortar 1:3 finished to a smooth all complete.	SQM	4621	0.24029250
1205	Providing 12mm thick plaster in walls, drains/culverts with a paste of neat cement @ 1kg/sqm and rubbed smooth with trowel etc. all complete.	SQM	50	0.00253596
1206	Providing and making decorative plaster of all types and design on walls, ceilings, arcs, columns with various thickness upto 18 mm including finishing all complete.	SQM	50	0.00478578
1207	Forming groove of uniform size from 12X12 mm upto 20X15 mm in plastered surface as per approved pattern, using wooden battens nailed to the under layer, including removal of wooden battons, repair of the edges of plaster panel and finishing the groove etc. complete as per specification, drawing and the instructions of engineer in charge.	RM	50	0.00065444
1208	Providing drip coarse on plastered surface at all elevations for all type of work such as chajjas, parapet, projections etc. including scaffolding, finishing etc. complete with all labour, tools and plants as per specification, drawing and instructions of engineer in charge.	RM	50	0.00049083
1209	Providing and laying encasement to box type steel beams at all levels with lath plaster 50 mm nominal thickness with cement plaster (1:4) over chicken wire mesh including all labour, materials, equipment, handling, transporting, mixing, placing, leveling, curing and cleaning, finishing the exposed surfaces etc including centering and shuttering all complete as per specification, drawing and instructions of enginner in charge (chicken wire mesh to be paid separately)	SQM	50	0.00537887
1210	Ruled pointing in masonry in CM 1:3 (1 cement and 3 fine sand) including raking out joints, curing etc. complete.	SQM	50	0.00133704
1300 FINISHES TO CONCRETE / PLASTERED SURFACES				
Finishes, painting to concrete, plastered surfaces including all labour, material, equipment, surface preparation, scaffolding etc. at any level as per specification, drawings and as directed by engineer - in - charge.				
1301	Two or more coats of white wash/ colour wash as per IS 627 of approved brand and manufacture to give an even shade including a	SQM	50	0.00032722

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.

PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work

ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
	priming coat as per specifications.			
1302	Two or more coats of Exterior masonry paint (water or solvent base) of special resins, adhesives and additives mixed with fine, hard stone aggregate and suitable pigment. The paint shall be applied on a coat of primer over dried, prepared plaster surface as manufacturers guidelines. The final finished coating shall be fungus resistant, UV resistant, water repellent, alkali resistant and extremely durable with color fastness as per specification.	SQM	100	0.00441749
1303	Providing and applying two or more coats of oil bound distemper as per IS 428 of approved brand, shade and manufacture to give smooth, hard, durable & glossy finish over a coat of primer over prepared plaster surface as per manufacturers guideline.	SQM	50	0.00153385
1304	Two or more coats of acrylic distemper of approved brand and manufacture to give an even shade including a priming coat with distemper primer complete as per spec.	SQM	1784	0.05472785
1305	Providing and applying two or more coats of acrylic emulsion paint as per IS 5411 of approved brand, shade and manufacture to give smooth, hard, durable & glossy finish over a coat of primer over prepared plaster surface as per manufacturers guideline.	SQM	2130	0.10367614
A1305	Providing and applying two or more coats of external quality acrylic emulsion paint as per IS 5411 of approved brand, shade and manufacture to give smooth, hard, durable & glossy finish over a coat of primer over prepared plaster surface as per manufacturers guideline.	SQM	2030	0.09880872
1306	Providing and applying 2 or more coats of acid/alkali resistant paint of approved brand and colour to floors, walls and ceiling including preparation of surface to receive paint, providing and applying bitumen primer confirming to IS 158 complete all as per manufacturer's recommendations and as approved by engineer, at all heights above or below grade level, complete as per specifications.	SQM	100	0.01288469
1309	Two or more coats of synthetic enamel paint of approved make made from synthetic resins and drying oil with rutile titanium dioxide and other selected pigments to give smooth, hard, durable & glossy finish to all interior and exterior surfaces complete.	SQM	500	0.01840622
1310	Providing and applying 3 coats of water proof cement paint of approved make and color on exterior surface at all heights including material, labour, scaffolding, curing etc including primer coat complete as per specification.	SQM	250	0.00582863
1312	Providing and applying 2 mm thick plaster of paris punning on walls including preparation of surface, staging, etc. to achieve a smooth even surface all complete as per specification and as directed by Engineer.	SQM	300	0.00834415
A1312	Providing and applying 3 mm thick white cement putty punning on walls (Birla White/ JK White or Similar approved) including preparation of surface, staging, etc. to achieve a smooth even surface all complete as per specification and as directed by Engineer.	SQM	500	0.02913816
1314	Providing and applying Synthetic plaster for external applications composed of synthetic fibre and petroleum based chemical similar to RENOVOL or equivalent and of approved natural color/shade applied on cured and dried plaster surface. The final finish Paint shall have UV resistance, fungus, bacterial resistance properties all complete with grooves filled with poly sulfide sealant of matching color and shade as per specification/drawing/approval of engineer in charge.	SQM	200	0.03959518

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
1400 FLOORING AND SKIRTING				
Flooring and skirting at any level including base layer, labour, material, equipments, transportation, handling, curing, polishing etc. at any level as per specification, drawings and as directed by engineer - in - charge.				
1401	Providing and laying 50 mm thick heavy duty cement concrete in flooring with metallic hardener pigmented topping 12mm thick uniform graded treated iron particles in flooring. Under layer of 38mm thick cement concrete mix 1:2:4 (1 cement: 2 sand : 4 stone aggregates 12.5mm well graded) and top layer of 12mm thick metallic concrete of mix 1:2 (1 cement hardner mix with approved quality metallic hardening compound :2 stone aggregate 6mm nominal size) by volume including cement slurry, rounding off edges, aluminium strips etc. all complete for following (Quoted item rate shall be inclusive of providing glass joint strips):	SQM	2100	0.23750874
1402	Providing and laying 25 mm thick heavy duty cement concrete mix 1:2:4 (1 cement: 2 sand : 4 stone aggregates) flooring with metallic hardener pigmented topping of 10 mm thick uniform graded treated iron particles in skirting and dado complete as per specification.	SQM	200	0.02816253
1418	Providing and laying 10 mm thk non-skid fully vitrified tiles of make 'MARBONITE' or 'FERRASTONE of BOSS Profile limited' or equivalent in flooring and skirting over 30 mm thick underbed of 1 part cement and 3 parts coarse sand by weight mixed with sufficient water, complete as per specification laid in pattern of following sizes			
a	400X400 mm	SQM	150	0.08303773
b	600X600 mm	SQM	200	0.10850823
A1423	Providing & fixing Acid / Alkali resistant (Chemical resistant) tiles conforming to IS:4457 in flooring/Dado beded and jointed with epoxy mortar all complete for following thicknesses. The tiles should be abrasion resistant & durable.			
a	20mm thick	SQM	200	0.29204012
1428	Providing and laying 3mm thick antistatic PVC flooring / skirting of approved shade,as per IS:3462 and laying as per IS:5318 all complete.	SQM	100	0.03129159
1430	Providing and fixing dividing strips in joints of cast in situ floorings at various elevations, finishing, all labour, material etc. complete as per drawing, specification and instructions of engineer in charge.			
a	Glass strips 40 mm wide and minimum 6 mm thick.	RM	50	0.00073624
b	Aluminium strips 40 mm wide and minimum 3 mm thick	RM	50	0.00179972
c	Brass strips 20 mm wide and minimum 4 mm thick.	RM	50	0.00247461
1500 ROOFING / SIDE CLADDING				
Roofing / side cladding work including all labour, material, equipment, transportation, handling, scaffolding, laps, hooks, washers, corner pieces etc. at any level as per specification, drawings and as directed by engineer - in - charge.				

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
A1501	Fixing of permanently color coated galvanised MS troughed metal sheet decking plate of approved colour and conforming to class3 of IS 14246 over roof purlins for cast-in-situ roof slab as per relevant IS code and specification. Bare metal thickness of deck plate shall be minimum 0.8mm with minimum trough depth of 44 mm having minimum yield strength of 250 MPa and shall serve as permanent shuttering to the roof slab 100mm thick measured over crest of metal decking & shall have adequate strength to support weight of green concrete and imposed loads of min 150 kg/sqm during construction between purlins as per manufacturer's recommendations/ calculations/ test certificates for approval including fixing of plates to purlins, side lapping, end lapping etc. all complete for below mentioned spans. The sheet shall be permanently coated with silicon modified polyester paint of minimum 20 micron DFT on exposed surface (facing operating floor) and minimum 7 micron on other face over epoxy primer applied over hot dipped galvanising @ 275 gm/sqm including fixing of sheet to purlin with self drilling white zinc plated heat treated carbon steel screws of minimum 5.6 mm dia @ 260mm c/c in the trough and stich screws between two adjacent sheets and sealing with epoxy sealant. Measurement of profile sheeting shall be of the plan area of roof covered by MS trough metal decking.			
a	Span Upto 1800mm	SQM	1900	0.29773834
1502	Providing and fixing shear connectors of mild steel studs having 16mm dia and minimum 75 mm projected length above purlin passing through metal decking as per relevant IS codes and specification.	QUINT AL	5	0.01450249
1508	Providing and installing under deck insulation using minimum 0.05 mm thick aluminium foil on exposed surface followed by 0.56 mm dia and 25 mm mesh GI wire netting, fixed at various elevations with rawl plugs including clips but excluding cost of insulation.	SQM	300	0.05362549
1510	Providing and fixing 1 mm thick corrugated/semicorrugated G.I. sheet in roofs, cladding of minimum galvanisation of 275 gsm total on both sides with minimum 150mm overlapping, 8 dia G.I. hook bolts or 'J' Bolts and nuts @305 mm c/c along with G.I. and bitumen washers including cutting of sheets for opening etc. all complete.	SQM	100	0.06143791
A1511	Providing and installing under deck insulation using Closed Cell Elastomeric Nitrile Rubber of density 40 to 60 kg/cum fixed at various elevations with rawl plugs including clips etc as per specification.	SQM	100	0.01784700
1600 FALSE CEILING				
False ceiling including all labour, material, equipment, transportation, handling, suspension system etc at any level as per specification, drawings and as directed by engineer - in - charge.				
A1601	Providing and fixing Moisture and fire resistant glass fibre reinforced gypsum plaster board (GRG) ceiling (having gypsum core mixed with glass fibre) system consisting of metal supporting grid system forming panels of specified size, suspended from RCC slab/structural steel or catwalkway grid above with 4 mm (minimum) galvanised wires (rods) with special height adjustment clips, including preparation of working drawing, providing openings for AC ducts, return air grills, light fixtures etc (but excluding the cost of catwalkway grid) all complete as per drawings, specification and instructions of the engineer.			
a	12.5 mm thick GRG board with galvanised light gauge steel load bearing supporting GI frame and finished flat (seamless).	SQM	100	0.04630323
b	12.5 mm thick GRG board in profile (dome ,curved profiled etc.) with galvanised light gauge steel load bearing supporting GI frame and finished smooth (seamless).	SQM	100	0.04748941
1603	Providing and fixing permanently colour coated aluminium false ceiling of approved colour and Luxalon 84 C or approved equivalent with corrosion resistant aluminium alloy panels of minimum thickness 0.5mm including 50mm thick mineral wool insulation(density 48 kg/cum) conforming to IS:8183 bound in polythene bags on top of panels. Additional hangers and height adjustment clips shall be provided for return air grills, light fixtures, A.C. ducts etc all complete. Suitable M.S. channel grid with minimum MC 75 shall also be provided above the false ceiling	SQM	100	0.09616533

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
	level for movement of personnel to facilitate maintenance of lighting fixtures, AC ducts etc. (Materials for structural platform grid made up of MS Channels/ Beams / Angles shall be supplied by BHEL and shall be paid under ST No 2301)			
A1604	Providing, fixing and laying Acoustic permanently colour coated aluminium false ceiling of approved colour with stove enamel finish of approved make of either lineal panel system or aluminium tile/plank system with corrosion resistance aluminium alloys panels of minimum thickness 0.5mm including 50mm thick mineral wool insulation (as per IS:8183) bound in polythene bags on top of panels. Additional hangers and height adjustment clips shall be provided for return air grills, light fixtures. A.C. ducts etc. suitable M.S. channel (minimum MC 75) grid 1200 c/c maximum shall also be provided above the false ceiling level for movement of personnel to facilitate maintenance of lighting fixtures, AC ducts etc.The work to be complete as per specifications, drawings and direction of engineer.(Materials for structural platform grid for movement made up of MS Channels/ Beams / Angles shall be supplied by BHEL and shall be paid under ST No 2301)	SQM	200	0.08761230
1700 RAIN WATER DOWN TAKE PIPES				
Rain water down take pipes including all labour, material, transportation, 2 coats of approved paint over one primary coat, fixtures, accessories etc at any level as per specification, drawings and as directed by engineer - in - charge.				
1707	Providing and fixing GI down take pipes conforming to IS:1239 /IS:3589 of medium duty all complete for following diameters.			
a	100 mm Dia	RM	200	0.08589841
b	150 mm Dia	RM	200	0.12393929
c	200 mm Dia	RM	50	0.04697812
A1707	Providing and fixing GI down take pipes conforming to IS:1239 /IS:3589 of heavy duty all complete for following diameters.			
a	100 mm Dia	RM	200	0.11289488
b	150 mm Dia	RM	200	0.14889062
c	200 mm Dia	RM	50	0.05317522
1708	Providing and fixing HDPE down take pipes conforming to IS:4984 as per specification of following diameters.			
a	110 mm Dia	RM	30	0.00427034
b	160 mm Dia	RM	30	0.00602517
c	200 mm Dia	RM	30	0.00803758
1800 MISCELLANEOUS WORKS				
Miscellaneous works including all labour, material, equipment etc. at any level unless otherwise specified as per specification, drawings and as directed by engineer - in - charge.				
1801	Providing and Filling in trenches, plinths, area paving and other underground structures with graded stone aggregate of size range 63 mm to 45 mm in layers not exceeding 230 mm in thickness including breaking of stone boulders to required sizes, filling the interstices with selected sand and compacting to 85 % of original volume of stone stack for all lifts etc. all complete. Payment shall be made for the measurement of the volume of the compacted fill.	CUM	600	0.32567759

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
1803	Anti termite chemical treatment of soil with Chlorpyriphos/Lindane E.C. 20% with 1% concentration conforming to IS:8944 and as per IS 6313 all complete. (Plinth area of building at ground floor only shall be measured for payment)	SQM	100	0.00302680
1806	Providing 50mm thick anti corrosive layer laid to required slope consisting of clean & well graded coarse sand mixed with A90 grade bitumen for softening point upto 45 degree Celcius or A65 grade bitumen for softening point above 45 degree celcius as per IS: 73 or its equivalent quality 8 to 10% by volume and rolled or compacted all complete.	SQM	20	0.00405768
1807	Providing and fixing G.I strips minimum 1.5mm thk and 150mm wide including fixing accessories etc. all complete.	Kg	20	0.00207792
1808	Providing and fixing aluminium strips minimum 18 SWG thk and 300mm wide over expansion joints with minimum lap of 50mm length including brass / aluminium screws, rawl plugs etc. all complete.	Kg	20	0.00379590
1809	Providing Chemical injection grouting with pressure pump for water retaining concrete structures conforming to IS:6494, including fixing nozzles, cost of approved cement, admixture, curing etc. all complete . Payment shall be made as per the consumption of chemical grout.	Kg	500	0.22006339
1812	Laying of earthing mats/rods including risers, transportation from yard stores, loading, unloading, cutting to length, welding, protective painting of joints etc. all complete. (Excavation & Back filling shall be paid separately under respective item of earth work. Earthing mats/rods shall be supplied by BHEL free of cost)	MT	20	0.09986294
1813	Providing Earthing pit as per drawing with charcoal & salt, GI pipes, GI earth electrodes, GI wire, GI strips, brick chamber with covers including associated earthwork etc. all complete.	EACH	5	0.02078738
1814	Construction of below ground earthing system test pits as per drawing/sketches including brickwork, plaster, concreting, reinforcement, formwork, providing & fixing GI strips/pipes, GI wires, covers etc as per drawing & specification including associated earthwork.	EACH	5	0.00967173
1815	Providing and fixing GI rungs in concrete/brick walls having zinc coating of minimum 900 g/sqm etc. all complete.	Kg	100	0.00417207
1816	Providing and fixing PVC pressure release valve of minimum dia 90mm in water retaining structure including 160 mm dia housing pipe of minimum length 3.75 m with perforation as per IS4558, nylon jali, perforated end plug, collar, graded filter, excavation, fixing in concrete slab/wall etc. all complete.	EACH	100	0.24677354
1817	Providing and fixing HDPE pipes in concrete/ brick work of following sizes including cutting, fixing and levelling in position etc. all complete.			
a	Upto 75 mm dia	RM	20	0.00236424
b	100 mm dia	RM	20	0.00269964
c	150 mm dia	RM	20	0.00441762
d	200 mm dia	RM	20	0.00712545
1818	Providing and laying dry stone pitching of 230 mm thickness for slope protection in cement mortar 1:6 including hammer dressing, raking of joints, pointing, preparing the bedding surface and voids filling with stone aggregate etc. all complete.	SQM	15	0.00730289

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.

PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work

ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
1819	Fabrication and erection of stoplog gates in CW Pumps with embedments required, lifting beams, special tools & plants, spare parts for three years, machining, casting, all materials such as structural steel, cast steel, stainless steel, brass used for seals, rubber seals, gears, ball and roller bearing, branch bushings, greasing, bolts, nuts, lugs, threaded fasteners etc., cleaning, sand blasting, hot double dip galvanised with minimum coating of zinc 750 gms/sqm., following by an application of etching primer and dipping in black bitumen as per B.S. 3416, erection along with a second stage concreting to true plumb and levels, submission of drawings / fabrication drawings for engineers approval etc all complete. The leakage through rubber seal shall not be more than 5 lit/min/metre length of seal under maximum head.(only weight of structural steel including embedments shall be considered for payment purpose) (SS component shall be measured separately for payment)	MT	90	1.57817566
1821	Fabricating and erecting in position and testing / examining bolted and / or welded structural steel work for stationary screens made out of rolled sections and / or plates including cutting, straightening if required, edge preparation, bolting / welding of joints, cleaning, sand blasting, hot double dip galvanised with minimum coating of zinc as 750 gms./sqm. followed by application of an etching primer and dipping in black bitumen as per BS 3416 etc all complete.	MT	90	1.44032357
1822	Cutting of groove of 10mm X 40mm size with groove cutting machine in concrete paving all complete.	RM	20	0.00026995
1823	Fire proofing of steel structures with VERMICULITE cementitious coating including supply of all materials for vermiculite materials, reinforcement mesh (3mm thick wire, 50x50 size mesh) , nuts, tie wires, weldings, surface preparation, curing, staging, compatible paintings etc. all complete.	CUM	1	0.02920398
1824	Supply & fixing expanded metal steel sheet conforming to IS:412. Size of mesh shall be 10mmX40mm with strands of 2.5mm width and 1mm thickness to the structural steel for facilitating fireproofing works.	SQM	2	0.00029450
1828	Dismantling old existing reinforced/non-reinforced brickwork/blockwork/stone masonry work in mud/lime/ cement mortar at any level including clearing/cleaning, stacking the serviceable materials at plant site and disposal of unserviceable materials within a lead upto1km all complete.	CUM	5	0.00162593
1829	Dismantling old existing plain/re-inforced concrete work at any level including clearing/cleaning, stacking the serviceable materials at plant site and disposal of unserviceable materials within a lead upto 1km all complete.	CUM	3	0.00289968
1830	Dismantling old existing structural steel work at any level including plates, bolts, cutting rivets, welding, dismembering and stacking the dismantled materials within a lead upto 1km etc all complete.	MT	3	0.01201840
1831	Sprinkling of water by water tanker fitted with perforated GI pipe (portable tanker minimum 3000 litre capacity) for roads and miscellaneous area within plant boundary, for dust suppression and reduction of suspended material at site for day to day work, as directed by BHEL site engineer (water for this purpose shall be provided by BHEL free of cost and utilisation of machine will be in terms of Tank-hour put in actual use for water sprinkling).	TANK-HR	100	0.00903983
1833	Supply & fixing FRP (fibre reinforced plastic) sheets 2 mm thick including GI hooks/ J or L bolts, nuts, washers, bitumen washers etc. complete including overlap 100mm .	SQM	2	0.00071090

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
A1834	Providing and fixing sliding layer of bitumen paper or craft paper over the screed layer for water retaining structures to destroy the bond between the screed and the base slab concrete of the water retaining structure etc all complete.	Sqm	4	0.00012978
2100 WATER SUPPLY				
Water supply work including men, material, equipment etc. at any level as per specification, drawings and as directed by engineer - in - charge.				
2101	Providing and fixing in position tested heavy duty type chromium plated (CP) brass long neck bib cocks including sockets, union, nuts etc all complete - 15mm nominal bore.	EACH	10	0.00310052
2102	Providing and fixing in position heavy duty brass stop cock of approved quality including all specials etc all complete - 15mm nominal bore.	EACH	10	0.00267101
2103	Providing and fixing in position heavy duty brass full way valve with wheel of approved quality including all specials etc all complete for following sizes:			
a	25mm nominal bore.	EACH	5	0.00239492
2104	Providing and fixing GI pipes class B medium class conforming to IS:1239 pipes shall be concealed and painted with anticorrosive paint, complete for internal works with GI sockets, unions, elbows, tees, nipples etc and clamps including cutting and making good the walls etc all complete for following sizes:			
a	15 mm nominal bore.	RM	25	0.00265876
b	20 mm nominal bore.	RM	25	0.00312914
c	25 mm nominal bore.	RM	25	0.00391652
A2104	Providing and fixing Galvanised MS pipes class B medium class conforming to IS:1239 pipes shall be concealed and painted with anticorrosive paint, complete for internal works with MS sockets, unions, elbows, tees, nipples etc and clamps including cutting and making good the walls etc all complete for following sizes:			
a	15 mm nominal bore.	RM	30	0.00313650
b	20 mm nominal bore.	RM	30	0.00370095
c	25 mm nominal bore.	RM	30	0.00464591
2105	Providing and fixing GI pipes class B complete for external work with GI sockets, unions, elbows, tees, nipples etc including trenching & refilling, anti-corrosive paint etc all complete for following sizes:			
a	15 mm nominal bore.	RM	30	0.00356598
b	20 mm nominal bore.	RM	30	0.00397091
c	25 mm nominal bore.	RM	30	0.00497722
d	50 mm nominal bore.	RM	30	0.00793459
A2106	Providing and fixing 450X 750 mm high square edge 6 mm thick float glass mirror of adequate width to match toilet lay-out and interior decor and as per spec.	EACH	10	0.00384086
2107	Providing and fixing 610mmx127mmx6mm thk clear glass with C.P Guard rails and mounted on C.P. brackets etc all complete.	EACH	10	0.00315370
2108	Providing and fixing 25 mm diameter stainless steel towel rails (600mm X 25mm) all complete.	EACH	5	0.00189384
2109	Providing and fixing 20mm dia chromium plated M.S. pipes wall mounted towel rod with C.P. Brackets etc all complete.	EACH	5	0.00126801
2110	Providing and fixing C.P. soap holder mounted with C.P. screws etc all complete.	EACH	5	0.00082625
2111	Providing and fixing stainless steel / C.P. liquid soap dispenser . Dispenser shall be round and easily revolving with removable threaded nozzle and mounted on C.P. brackets etc all complete.	EACH	5	0.00126188
2112	Providing and fixing glazed vitreous wall mounted paper holder with suitable cover cum cutter fitted with CP screws etc. sll complete.	EACH	5	0.00115349
2113	Providing and fixing chromium plated brass shower rose with 15 or 20	EACH	5	0.00182635

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
	mm inlet all complete.			
2114	Providing & fixing in position P.V.C. water tank of Syntex or approved equivalent including making all necessary inlet & outlet pipes, fixture, ball cocks, valves etc all complete for following capacities. GI pipes shall be paid separately under ST No. 2105.			
a	1000 litres capacity	EACH	2	0.00654872
b	2000 litres capacity	EACH	1	0.00642437
c	5000 litres capacity	EACH	1	0.01642457
2115	Providing and fixing approved stainless steel sink with integrated drainboard as per IS:13983 of size 915x460x178mm with CI brackets, stainless steel chain with rubber plug 40mm, cp brass waste trap with necessary union complete including painting the fittings, cutting and making good the wall where required etc. all complete as per spec.	EACH	2	0.00384742
2200 SANITARY WORKS				
Sanitary work including all labour, material, equipment etc. at any level as per specification, drawings and as directed by engineer - in - charge.				
2201	Supply and fixing glazed vitreous china Wash Basin conforming to IS:2556 part 4 of oval shape with R.S. or C.I. brackets painted white, 15mm chromium plated brass hot & cold faucets with nylon washers, chromium plated brass chain with rubber plug, 32mm chromium plated brass bottle trap and waste of standard pattern, 32mm dia chromium plated brass trap unions, plastic connection pipe with chromium plated nuts, fittings, cutting and making good the walls where required etc all complete.			
a	White	EACH	2	0.00380891
b	Colored	EACH	2	0.00436766
2202	Providing and fixing approved vitreous china laboratory sink of size 600x400x200mm conforming to IS:2556 (part-5) with R.S. or C.I. brackets, chromium plated brass chain with rubber plug 40mm, CP brass waste and 40mm CP brass trap with necessary union complete including painting the fittings, cutting and making good the wall where required etc. all complete.	EACH	1	0.00235521
2204	Providing and fixing colour glazed vitreous china European type water closet conforming to IS:2556 with siphon, open front solid plastic seat and plastic cover, low level 12.5 litre PVC flushing cistern (same colour as WC) with valveless fittings, necessary C.P connections etc all complete.			
a	Floor mounted	EACH	2	0.00475201
b	Wall mounted	EACH	2	0.00517414
2205	Providing and fixing colour glazed vitreous indian type Orissa pattern (580x440mm) water closet conforming to IS:2556 part 3 with all fittings including foot rests, low level 12.5 litre PVC flushing cistern with valveless fittings, necessary C.P connections etc all complete.	EACH	2	0.00431434
2206	Providing and fixing white flat back glazed vitreous china urinals of size 440x265x355 mm with photo voltaic control flushing system as per IS:2556 (part 6, section 1) with flush pipes, lead pipes, gratings, traps and necessary C.P. fittings etc. all complete.	EACH	8	0.02967295
2207	Supply, laying and jointing UPVC pipes of class 3 as per IS:4985 including bends, branches and all other necessary fittings, M.S holder bats/clamps, cutting and making good the walls and floors, jointing, testing etc all complete for following.			
a	75mm dia pipes	RM	5	0.00194703
b	110mm dia pipes	RM	36	0.01990878
c	160mm dia pipes	RM	36	0.03012828
2208	Providing, laying light duty non pressure NP3 class RCC pipes with collars jointed with stiff mixture of cement mortar 1:2 including testing of joints etc all complete for following.			
a	200mm dia	RM	15	0.00479804
b	300mm dia	RM	15	0.00744245

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.				
PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work				
ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
c	450mm dia	RM	15	0.01444320
b	600mm dia	RM	15	0.01705080
e	900mm dia	RM	15	0.03254628
2209	Providing, laying light duty non pressure NP2 class RCC pipes with collars jointed with stiff mixture of cement mortar 1:2 including testing of joints etc complete for following.			
a	150mm dia	RM	15	0.00364453
b	250mm dia	RM	15	0.00437776
c	300mm dia	RM	15	0.00600983
d	500mm dia	RM	15	0.00895794
2211	Providing and fixing C.I Manhole heavy duty cover of size 600mmx450mm including frame from reputed manufacture etc. all complete.			
2212	Providing and fixing circular heavy duty C.I. manhole cover of 600 mm dia with frame etc. all complete.			
2213	Providing and fixing square mouth S.W Gully trap grade 'A' complete with CI grating, brick masonry chamber and water tight CI cover with 300x300mm (inside). The weight of cover to be not less than 4.53 Kg and frame to be not less than 2.72 Kg etc all complete for following sizes:			
a	100x100mm P or S Type.	EACH	5	0.00397923
b	150x100mm P or S Type.	EACH	5	0.00433111
c	150x150mm P or S Type.	EACH	5	0.00463380
2214	Providing and fixing square mouth S.W Gully trap grade 'A' complete with CI grating, brick masonry chamber and water tight CI cover with 300x300mm (inside). The weight of cover to be not less than 4.53 Kg and frame to be not less than 2.72 Kg etc all complete for following sizes:			
a	100x100mm P or S Type.	EACH	5	0.00397923
b	150x100mm P or S Type.	EACH	5	0.00433111
c	150x150mm P or S Type.	EACH	5	0.00463380
2215	Providing and fixing C.I. floor traps with C.P jalli all complete.			
2216	Providing and fixing heavy duty UPVC floor traps with C.P jalli all complete.			
2217	Providing and installing approved brand single tap water cooler of 80 L cooling capacity all complete.			
2218	Providing and installing approved brand single tap water cooler of 150 L cooling capacity all complete.			
2219	Providing and fixing white vitreous urinal partitions of size 675x325x85mm all complete.			
2220	Providing and fixing eye and face drinking water fountain (combined unit with receptacle conforming to IS: 10592) all complete as per specification.			
A2221	Providing and fixing heavy duty cast iron pipes for above and below ground sanitary works with water tight lead joint, fixing clamps, excavation, filling, disposal etc. all complete for the following.			
a	75mm dia pipes	RM	10	0.00736272
b	100mm dia pipes	RM	10	0.00920338
c	150mm dia pipes	RM	10	0.01210757
d	200mm dia pipes	RM	10	0.01492993
e	250mm dia pipes	RM	10	0.01791593
2300 STRUCTURAL STEEL				
Structural steel works including all labour, material, equipments, transportation, handling etc. at any level as per specification, drawings and as directed by engineer - in - charge.				

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.

PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work

ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
A2301	Supply, fabrication and erection of structural steel with mild steel rolled section / built up section / combination of both conforming to IS:2062, pipes conforming to IS:1161/ IS:1239, chequered plate conforming to IS: 3052, mild steel rounds, monorails, stays, safety chains, ladders, MS grating etc. in columns, beams, gantry girders, bunkers, silos, hoppers, roof trusses, portals, laced purlins, space frames, hangers, struts, monorails, galleries, stiffeners, wall beams, sheeting runners, brackets, stub columns, bracings, cleats, trestles, base plates, splice plates, chequered plate flooring, decking and seal plates, steel frame grid over false ceiling, walkway platforms, ladders, stairs, stringers, treads, landings, hand-rails etc including 2 coats of zinc-phosphate primer (one coat at shop and one coat after erection), connection design & preparation of fabrication drgs, collection of steel from stores, fabrication, straightening, cutting, bending, rolling, grinding, machining, drilling, welding, electrodes and other consumables, alignment, erection bolts & nuts (weight of erection bolts, nuts and welds not payable), assembly, edge preparation, preheating (min preheat and interpass temperature of 20o C for welding over 20 mm and upto 40 mm & 66o C for welding over 40 mm and upto 63 mm & 110o C for thickness over 63 mm & use of low hydrogen/ radiogenic electrodes), post heating, testing of welders, inspection of welds, visual inspection, non destructive and special testing, rectification and correction of defective welding works, production test plate, inspection and testing, erection scheme, protection against damage in transit, stability of structures, installation of temporary structures, setting column bases, surface preparation by means of manual or mechanical power tools as per IS:1477 part 1, touch-up painting, rectification, dismantling and removal of all temporary structures (weight of temporary structures not payable), return of surplus / waste steel materials to store etc all complete. Including appointment of a seperate agency, approved by BHEL, for review and approval of fabrication drgs, in consultation with BHEL.	MT	10	0.06003042
A2302	Extra over ST NO. A2301 for blast cleaning of steel structures to near white metal surface(Sa 2 1/2) and applying zinc phosphate primer in coats of minimum 25 micron (DFT) at shop and 25 micron (DFT) after erection, instead of primer coat of red oxide zinc-chromate, including touch-up painting etc all complete.	MT	10	0.01543306
2304	Providing and applying two coats of synthetic enamel paint with minimum 50 micron total dry film thickness (DFT) of approved make and shade to achieve an even shade over steel sections already having primer coats and keeping overall DFT with primer not less than 110 microns including protection and cleaning, scaffolding etc. all complete.	MT	10	0.00660599
2400 ROAD WORKS				
Providing Road Work including necessary material, labour, machinery, transportation etc as per specification, drawing, relevant IRC & IS codes and as directed by the Engineer-in-charge for the following.				
2401	Preparation of sub grade by excavating earth to required depth for all types of soil/ rock, dressing to camber and consolidating the base including making good the undulation etc and disposal of surplus earth within a lead upto 1 km etc. all complete.	CUM	8100	0.47203828

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.

PART B.1: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SERVICE portion of work

ST. NO	DESCRIPTION OF ITEM	UNIT	QTY.	% weightage w.r.t. the total price for SERVICE portion of work
2402	Supplying and filling with selected good earth of approved quality in layers not exceeding 300 mm loose thickness using borrowed soil (borrowed soil to be arranged by the bidder) and compacted so as to achieve at least 95 % maximum dry density as per IS-2720 (Part-VII) including royalty, sorting, spreading, breaking clods, watering, ramming/compaction by manual/mechanical means, dressing, finishing to required lines, grades and slopes, tesing etc all complete.	CUM	2400	0.20264151
2402X	Supplying and filling upto any depth below ground level for grading to proper grade and level in layers not exceeding 300 mm loose thickness with Granular Morrur (Granular Morrur to be arranged by the bidder) and compacted as specified including royalty, sorting, spreading, breaking clods, watering, ramming/compaction by manual/mechanical means, dressing, finishing to required lines, grades and slopes, tesing, all lead and lifts etc all complete as per specification, drawing and as directed by the engineer for the following.	CUM	2100	0.30978788
2403	Providing, stacking & laying granular morrum for shoulder including watering, compaction with road roller to required camber etc all complete.	CUM	300	0.07012974
2404	Providing & laying water bound macadam sub base course of total thickness 150mm, should be laid in two layers of 75mm thick each, with crushed stone aggregates 90 to 40 mm down size, stone screening & blinding material including screening, sorting, spreading to template & consolidation with road roller including carriage, spreading & consolidation of blinding material moorum etc all complete.	CUM	975	0.41128868
2405	Providing & laying water bound macadam base course of total thickness 150mm, should be laid in two layers of 75mm thick each, with stone aggregate 63mm to 40mm size, stone screening and blinding material including screening sorting, spreading to template and consolidation with road roller including carriage, spreading and consolidation of blinding material moorum etc all complete.	CUM	975	0.47456411
GRAND TOTAL Weightage (SERVICE PORTION)				99.99999853

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana.

PART B.2: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SUPPLY portion of work

ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	% weightage w.r.t. the total price for SUPPLY portion of work
700 MS EMBEDMENTS				
Embedments including all labour, material, equipment, transportation, handling etc. at any level as per specification, drawings and as directed by engineer - in - charge.				
701	Supply of mild steel embedments, inserts, pipe sleeves, angle pieces, rungs of various diameters, plates of dimensions as required etc. including welding, bolting, cutting, drilling, scaffolding, setting etc. all complete.	MT	15	3.29617986
900 DOORS, WINDOWS, VENTILATORS, LOUVERS				
Doors, windows, ventilators, louvers, roof ventilators, rolling shutters, partitions including all labour, material, equipments, transportation, handling, preparation of working drawings etc. at any level as per specification, drawings and as directed by engineer - in - charge.				
907	Supply of fire proof steel doors (single or double shutter) with panic devices shall be 45mm thk flush design comprising of two outer sheets of 18 gauge steel sheets rigidly connected and reinforced inside with continuous vertical 20 gauge stiffeners, spot welded in position at not more than 150mm on centers including all fittings, shop painting with approved post office/signal red color fire resistant paint and mineral wool insulation (64 kg/cum density) complete and shall be fire proof as per IS:3614, TAC requirements and as per specification. Minimum ratings shall be 2 Hrs.	SQM	20	1.32917142
A907	Supply of fire proof steel doors (single or double shutter) with panic devices and vision panel shall be 45mm thk flush design comprising of two outer sheets of 18 gauge steel sheets rigidly connected and reinforced inside with continuous vertical 20 gauge stiffeners, spot welded in position at not more than 150mm on centers including all fittings, shop painting with approved post office/signal red color fire resistant paint and mineral wool insulation (64 kg/cum density) complete and shall be fire proof as per IS:3614, TAC requirements and as per specification. Minimum ratings shall be 2 Hrs.	SQM	40	2.65834284

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.

PART B.2: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SUPPLY portion of work

ST. NO	DESCRIPTION OF ITEM	UNI T	QTY	% weightage w.r.t. the total price for SUPPLY portion of work
909	Supply of anodised aluminium work of Jindal, Hindalco or other equivalent approved make for door frames, windows, ventilators, partitions, railing etc with extruded standard tubular and other sections including all fittings & fixtures and accessories of approved make conforming to IS733 and IS1285, anodised and electro color dyed to required shade according to IS 1868 (minimum anodic coating of grade AC15), fixed with rawl plugs, expansion fasteners, SS screws or with fixing clips, including necessary filling of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt for bi-mettalic protection etc.including preperation of working drawings, aluminium cleat angle, aluminium snap-on-beading for glazing/panelling, stair case tread nosing, with all fittings and fixtures (like tower bolts, handles, door stopper with rubber shoes, 'L' drops, stays, floor springs, hydraulic door closures etc.), CP brass/stainless steel screws, providing and fixing hinges/pivots, and making provision for fixing of fitting wherever required including cost of PVC/neoprene gasket, all complete as per drawing, specification and instructions of engineer in charge (Glazing and panelling shall be paid seperately).Weight of aluminium section only shall be measure.	Kg	191	0.27467632

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.

PART B.2: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SUPPLY portion of work

ST. NO	DESCRIPTION OF ITEM	UNI T	QTY	% weightage w.r.t. the total price for SUPPLY portion of work
A909	Supply of anodised aluminium work of Jindal, Hindalco or other equivalent approved make for door/window frames, door/window shutters, ventilators, partitions, railing, grills etc with extruded standard tubular and other sections including all fittings & fixtures and accessories of approved make conforming to IS733 and IS1285, anodised and electro color dyed to required shade according to IS 1868 (minimum anodic coating of grade AC15), fixed with rawl plugs, expansion fasteners, SS screws or with fixing clips, including necessary filling of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt for bi-metallic protection etc.including preperation of working drawings, aluminium cleat angle, aluminium snap-on-beading for glazing/panelling, stair case tread nosing, with all fittings and fixtures (like tower bolts, handles, door stopper with rubber shoes, 'L' drops, stays, floor springs, hydraulic door closures etc.), CP brass/stainless steel screws, providing and fixing hinges/pivots, and making provision for fixing of fitting wherever required including cost of PVC/neoprene gasket, all complete as per drawing, specification and instructions of engineer in charge (Glazing and panelling shall be paid seperately).Weight of aluminium section only shall be measure.	Kg	3500	5.03333584
A910	Supply of aluminium composite panel (ACP) 3mm thick fixed in aluminium frame including sealant with minimum 0.2mm topping of precotaed aluminium foil on both side of approved manufacturer & approved shade, all complete as per specification.	SQM	100	1.42627884
1500 ROOFING / SIDE CLADDING				
Roofing / side cladding work including all labour, material, equipment, transportation, handling, scaffolding, laps, hooks, washers, corner pieces etc. at any level as per specification, drawings and as directed by engineer - in - charge.				

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.

PART B.2: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SUPPLY portion of work

ST. NO	DESCRIPTION OF ITEM	UNI T	QTY	% weightage w.r.t. the total price for SUPPLY portion of work
A1501	Design and Supply of permanently color coated galvanised MS troughed metal sheet decking plate of approved colour and conforming to class3 of IS 14246 over roof purlins for cast-in-situ roof slab as per relevant IS code and specification. Bare metal thickness of deck plate shall be minimum 0.8mm with minimum trough depth of 44 mm having minimum yield strength of 250 MPa and shall serve as permanent shuttering to the roof slab 100mm thick measured over crest of metal decking & shall have adequate strength to support weight of green concrete and imposed loads of min 150 kg/sqm during construction between purlins as per manufacturer's recommendations/ calculations/ test certificates for approval including fixing of plates to purlins, side lapping, end lapping etc. all complete for below mentioned spans. The sheet shall be permanently coated with silicon modified polyster paint of minimum 20 micron DFT on exposed surface (facing operating floor) and minimum 7 micron on other face over epoxy primer applied over hot dipped galvanising @ 275 gm/sqm including fixing of sheet to purlin with self drilling white zinc plated heat treated carbon steel screws of minimum 5.6 mm dia @ 260mm c/c in the trough and stich screws between two adjacent sheets and sealing with epoxy sealant. Measurement of profile sheeting shall be of the plan area of roof covered by MS trough metal decking.			
a	Span Upto 1800mm	SQM	1900	7.71957108
1800 MISCELLANEOUS WORKS				
Miscellaneous works including all labour, material, equipment etc. at any level unless otherwise specified as per specification, drawings and as directed by engineer - in - charge.				

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana.

PART B.2: % weightage for amount of individual items of Schedule of quantity w.r.t. the total price for SUPPLY portion of work

ST. NO	DESCRIPTION OF ITEM	UNIT	QTY	% weightage w.r.t. the total price for SUPPLY portion of work
1819	Design and supply of stoplog gates in CW Pumps with embedments required, lifting beams, special tools & plants, spare parts for three years, machining, casting, all materials such as structural steel, cast steel, stainless steel, brass used for seals, rubber seals, gears, ball and roller bearing, branch bushings, greasing, bolts, nuts, lugs, threaded fastners etc., cleaning, sand blasting, hot double dip galvanised with minimum coating of zinc 750 gms/sqm., following by an application of etching primer and dipping in black bitumen as per B.S. 3416, erection along with a second stage concreting to true plumb and levels, submission of drawings / fabrication drawings for engineers approval etc all complete. The leakage through rubber seal shall not be more than 5 lit/min/metre length of seal under maximum head.(only weight of structural steel including embedments shall be considered for payment purpose)	MT	90	40.91830906
1821	Supply of bolted and / or welded structural steel work for stationary screens made out of rolled sections and / or plates including cutting, straightening if required, edge preparation, bolting / welding of joints, cleaning, sand blasting, hot double dip galvanised with minimum coating of zinc as 750 gms./sqm. followed by application of an etching primer and dipping in black bitumen as per BS 3416 etc all complete.	MT	90	37.34413469
	GRAND TOTAL Weightage (SUPPLY PORTION)			100.000

TECHNICAL CONDITIONS OF CONTRACT (TCC)
CHAPTER XI –BILL OF QUANTITIES AND % WEIGHTAGE OF
INDIVIDUAL ITEMS

PART B.3

Package-G: All Civil and Architectural work for CW Pump House, Fore Bay, CW Pipe Line, CW Chlorination & Treatment Plant, Clarified Water Storage Tank and Pump House, Side Stream Treatment Plant etc. excluding Structural fabrication and erection for Unit # 1, 2, 3 & 4 AT 4X270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana. 4 X 270 MW Thermal Power Station, Manuguru, Distt- Khammam, Telangana.

PART B.3: Percentage weightage of SERVICE portion of work (Part B.1) and SUPPLY portion of work (Part B.2) w.r.t. the Grand Total Price (as quoted by the bidder in Part C)

SL NO	DESCRIPTION	Weightage in %
1	TOTAL PRICE OF SERVICE PORTION (PART-B.1)	91.74362
2	TOTAL PRICE OF SUPPLY PORTION (PART-B.2)	8.25638
	GRAND TOTAL Weightage (SERVICE PORTION (PART B.1) & SUPPLY PORTION (PART B.2))	100.00