

PROJECTS CIVIL DEPARTMENT

Dated: 13-03-2012

Sub: Construction of Dinning Hall for ET Hostel in BHEL R&D Township.

Ref: Tender Notice No: CL/16/2011-12, dated: 11-02-12

Tenders were called for the above work, vide Tender Notice No: CL/16/2011-12, dated 11-02-12 published in news papers dated 27-02-12. In full specification abstract for item no. 22, it is observed that there is a mismatch of specification. Actual specification for that item is centering / shuttering for Shelves. In detailed estimate and single line estimate, it is printed correctly. In full specification, the quantity, rate and amounts are correct. But the description of the item needs to be corrected in estimate and in tender document. (Vide Page.34 Item No.22).

**Mismatch of specification for item 22 in Abstract Estimate as follows:**

“Reinforced cement concrete work in SHELVES excluding the cost of centering and shuttering and reinforcement with 1:2:4 (1 cement: 2 Coarse sand: 4 graded stone aggregate 20mm nominal size). Cement will be FREE supply.”

**To be replaced with following specification:**

“Providing centering and shuttering including strutting, propping etc and removal of form work after specified period as directed by the engineer-in-charge (extent possible usage of wood has to be avoided in the construction activities using only steel shuttering for shelves in cost-in-situ etc in all floors”

Necessary Corrigendum may please be issued.

(K.P.V. Rama Reddy)  
Exec. Addl. Engineer

Manager (Projects)

DGM (Projects)

AGM (Projects)

GM (MDM&P)

AGM (MM): for necessary correction in the web site for the above item.