

BHARAT HEAVY ELECTRICALS LIMITED					
RAMACHANDRAPURAM :: HYDERABAD-502032					
(TOWNSHIP ADMINISTRATION)					
PRICE BID - Part - B - Item No. 01					
Name of work: "Renovation and modification works at Geetanjali School - Civil works"					
SI. No	Description of item	Qty	Unit	Rate	Amount
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	5,300.00	Sqm	3.2	16,960.00
2	Scrapping the existing paint surface, repairing the wall surface by applying wall putty wherever required and supply and application of Two coats of Altek Superfine, One coat of Altek water based cement primer & Two coats of Altek Flora (plastic Emulsion paint) etc.complete ncluding cost of all materials all as directed by engineer-in-charge	3,300.00	Sqm	97.00	320,100.00
3	Applying two or more coats of oil bound distemper of approved brand and shade including priming coat with cement primer on new works to give an even shade including cost of all materials etc. complete .	3,300.00	Sqm	41.55	137,115.00
4	Finishing walls with Acrylic Smooth exterior paint of required shade over the New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including base coat of water proofing cement paint applied @ 2.20 kg/10sqm	2,000.00	Sqm	50.40	100,800.00
5	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed.(Ordinary rock)	125.00	Cum	152.60	19,075.00
6	Plain cement concrete 1:5:10 mix using 40 mm guage down graded machine crushed granite metal in foundation including consolidation, curing and cost of all materials etc complete.	85.00	One Cum	2079.60	176,766.00
7	Brick work with ground moulded bricks in cement mortar 1:6 (1 cement : 6 coarse sand) including curing, cost of all materials etc complete all as directed by Engineer-in-charge.	45.00	One Cum	2121.75	95,478.75

Sl. No	Description of item	Qty	Unit	Rate	Amount
8	Ellis pattern flooring 20mm thick cement concrete using 1 cement and 3 granite metal stone of chipping of 3 to 10 mm guage including fine finishing, neat thread lining, curing, cost of all materials etc complete.	1,130.00	Sqm	140.00	158,200.00
9	Applying two or more coats of synthetic enamel paint of approved shade and brand to old wood work including scraping, cost of all materials and over an under coat of suitable shade with ordinary paint/primer of approved brand and manufacture etc., complete all as directed by Engineer-in-charge.	625.00	Sqm	51.30	32,062.50
10	Repairs to the existing doors, windows, ventilators and cup boards including frame, shutters, fittings, weldmesh, T.W beadings etc., all as directed by the Engineer-in-charge. (Only labour charges).	25.00	One Sqm	144.20	3,605.00
11	Supplying and fixing of medium Indian teakwood window shutters 30 mm thick fully glazed with 3 mm thick glass of approved quality including cost and fixing of MS fixtures, fittings and furniture of superior quality etc., complete as directed by the Engineer-in-charge.	25.00	One Sqm	1,848.00	46,200.00
12	Supplying and fixing of white cleared acrylic sheet of 3 mm thick of required sizes glass putty required for fixing to the existing steel/wooden windows including removing the existing broken glass panes along with the beeding/glass putty, cost of all materials and labour etc., complete all as directed.	30.00	One Sqm	915.00	27,450.00
	Total				1,133,812.25

Tender %	In words	Figures
Excess		
Less		
Estimate		
Notes		
1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work.	
2	The tender % age quoted by the contractor shall be inclusive of all taxes and duties other than service tax as applicable from time to time.	
3	Service tax if paid by the contractor with respect to this work will be reimbursed by BHEL on production of documentary evidence for having paid the service tax by the contractor.	
4	All the bills of the contractors will be cleared subject to the production of clearance certificate by the contractors in respect of compliance of all statutory requirement, issued by IR section of HR department	
5	The agency shall submit the I.R. clearance certificate for the above work and arrange to get the final bill sent to Finance within one month from the actual date of completion of work.	
6	The maintenance period of the work is 06 months . The security deposit will be released after satisfactory completion of the work and after getting I.R clearance and payment of final bill.	