

BHARAT HEAVY ELECTRICALS LIMITED					
RAMACHANDRAPURAM :: HYDERABAD-502032					
(TOWNSHIP ADMINISTRATION)					
				Tender Notice No.	
PRICE BID - PART - B - Item No. 01				HY/TA/OT-11/2014-15	
				Date: 23.12.2014, Item. No. 01	
Name of work: "Providing Stainless Steel Kitchen Sinks to all Type-IV and Type-V quarters in NH-I, II, V and VI areas in Township.					
Sl. No	Description of item	Qty	Unit	Rate	Amount
1	Removing the existing sink and fixing stainless steel AISI 304(18/8) kitchen sink as per IS 13983 and of size 450x1040mm bowl depth 200mm with drain board,C.I brackets and stainless steel plug 40mm including painting of fitting and brackets cutting and making good i.e. replastering the walls wherever required. (Stainless sink,C.I brackets,waste water pipe, will be free issue from BHEL store).(Cement will be free issue from BHEL store).(Old sinks are to be returned to BHEL store)	393.00	Each	307.19	120,725.67
2	Fixing of GI pipes make (Class-B) with all necessary fittings including excavation, making holes, fixing clamps wherever necessary and repairing the holes, refilling the trenches, including cost of all materials etc complete as directed for 20 mm dia (3/4") dia. (G.I. pipe will be free issue from BHEL store).	500.00	One Rmt	25.38	12,690.00
3	Fixing of GI pipes make (Class-B) with all necessary fittings including excavation, making holes, fixing clamps wherever necessary and repairing the holes, refilling the trenches including cost of all materials etc complete as directed for 15 mm dia (1/2") dia. (G.I. pipe will be free issue from BHEL store)	500.00	One Rmt	25.34	12,670.00
4	Dismantling/Demolishing of items by manual or mechanical means and stacking them in 50 meter lead as per direction of the Engineer in-charge.				
a	Brick work in cement mortar	50.00	cu.m.	310.75	15,537.50
b	Plastering	200.00	Sqm	8.20	1,640.00
5	Brick work in CM 1: 6 using ground moulded bricks for all thicknesses of walls including curing, cost of all materials etc. complete. (For repair of holes in wall at all heights) all as directed by Engineer-in-charge. (Cement will be free issue from BHEL store).	50.00	cu.m.	2103.58	105,179.00
6	Plastering in cement mortar 1:6 (1 cement : 6 fine sand), 20 mm thick including curing, cost of all materials etc. complete all as directed by Engineer-in-charge. (Cement will be free issue from BHEL store)	800.00	sq. m.	65.83	52,664.00
7	Dismantling and replacing C.P. Nahani trap jalties 5" dia with new ones of approved make including cost of all materials etc complete all as directed by Engineer-in-charge.	100	Each	13.89	1,389.00
8	Supply and fixing of 8 mm thick mirror polished Granite stone of any colour and shade of required size black or other approved shade and texture laid over 12mm thick bed of cement mortar 1:3(1 white cement 3 coarse sand) including pointing in white cement with an admixture of pigment to match the stone shade including rubbing, curing grinding etc complete as directed by Engineer-in-charge	1200	Sqm	989.18	1,187,016.00
9	Extra for providing edge moulding to 18 mm thick Granite stone counters, Vanities etc. including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-charge.	1500	Rmt	97.60	146,400.00
10	Removing the existing plaster and Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS 15622 (thickness to be specified by the manufacture) of approved make in all colours, shades except burgundy bottle green black of any size as approved by engineer in charge in skirting risers of steps and dados over 12mm thick bed of cement including pigment of matching shade etc. complete as per drawing specification and direction of engineer in charge	1400	Sqm	499.88	699,832.00

11	Distempering with 1st quality acrylic washable distemper of approved manufacturer and of approved colour complete as per manufacture's specification, two or more coats on old work including scrapping the existing white washing / OBD wherever required upto satisfaction of Engineer-in-charge etc complete all as directed by Engineer-in-charge.	28000	Each	41.55	1,163,400.00
12	Fixing in position of 15 mm dia. CP bib cocks by making holes in walls with machine (Bib cocks will be supplied free of cost from Township divisional stores) including cost of jointing materials etc complete all as directed by Engineer-in-charge. Note: All fixing & cutting material cost is under contractor scope only. BHEL will only provide the CP Bibcocks.	393.00	Each	9.35	3,672.59
Total estimate cost					3,522,815.76
Tender %	In words			Figures	
Excess					
Less					
Estimate					
Notes					
1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work.				
2	The tender % age quoted by the contractor shall be inclusive of all taxes and duties other than service tax as applicable from time to time.				
3	Service tax if paid by the contractor with respect to this work will be reimbursed by BHEL on production of documentary evidence for having paid the service tax by the contractor.				
4	All the bills of the contractors will be cleared subject to the production of clearance certificate by the contractors in respect of compliance of all statutory requirement, issued by IR section of HR department (BHEL).				
5	The agency shall submit the I.R. clearance certificate for the above work and arrange to get the final bill sent to Finance within one month from the actual date of completion of work.				
6	The maintenance period of the work is 04 months . The security deposit will be released after satisfactory completion of the work and after getting I.R clearance and payment of final bill.				