



BHARAT HEAVY ELECTRICALS LIMITED
Fabrication Plant, Jagdishpur, District- Amethi

**TENDER FOR REPAIRING OF TILE FLOORING & MISC WORKS AT FP ADMIN
BUILDING**

Tender Enquiry No: BHE/FP/CVL/15-16/27

SECTION II

BILL OF QUANTITIES AND PRICE SCHEDULE

BHARAT HEAVY ELECTRICALS LIMITED
(A GOVERNMENT OF INDIA UNDERTAKING)
CSU & FP
Industrial Area
Jagdishpur (UP) 227817



BHARAT HEAVY ELECTRICALS LIMITED
FABRICATION PLANT, IA JAGDISHPUR, DISTT- AMETHI

SECTION-II: BOQ & PRICE SCHEDULE

TE No: BHE/FP/CVL/15-16/27

Dt: 16.12.2015

TENDER OF REPAIRING OF TILE FLOORING & MISC WORKS AT FP ADMIN BUILDING

S.No.	DESCRIPTION OF WORK	UNIT	QTY.	Rate Quoted (Rs.)		Amount (Rs.)
				In Figures	In words	
1	Supplinying and filling in plinth with jamuna sand including watering, raming consilidating,dressing complete.	Cum	14.60			
2	Earthwork in excavation in foundation trenches or drains (not exceeding 1.5 m in width or 10 Sqm on plain) including dressing of sides and ramming of bottom, lift up to 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m. All kinds of soil	Cum	9.00			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work up to plinth level 1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size).	Cum	4.80			
4	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in- charge.Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix).	Cum	10.60			
5	Providing and laying in position specified grade of reinforced cement concrete of mix 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size), excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level	Cum	5.20			
6	Providing and fixing Reinforcement for R.C.C. work includig , straighting, cutting, bending, placing, cleaning of rust in position and binding,all complete. TMT bars.	Kg	416.00			



BHARAT HEAVY ELECTRICALS LIMITED
FABRICATION PLANT, IA JAGDISHPUR, DISTT- AMETHI

SECTION-II: BOQ & PRICE SCHEDULE

TE No: BHE/FP/CVL/15-16/27

Dt: 16.12.2015

TENDER OF REPAIRING OF TILE FLOORING & MISC WORKS AT FP ADMIN BUILDING

S.No.	DESCRIPTION OF WORK	UNIT	QTY.	Rate Quoted (Rs.)		Amount (Rs.)
7	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc.. Size of Tile 600x600 mm complete.	Sqm	36.00			
8	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	4.14			
9	12 mm cement plaster of mix :1:6 (1 cement: 6 fine sand)	Sqm	28.60			
				Total (Exclusive of Service Tax)=		

Note:

- 1) Service tax shall be paid extra as applicable.
- 2) Evaluation of bidders shall be done based on Total quoted cost (Excluding of Service Tax) and accordingly L-1 bidder shall be decided.

(BHEL)

(Contractor)
Sign & Seal