



भारत हेवी इलेक्ट्रिकल्स लिमिटेड

(भारत सरकार का उपक्रम)

Bharat Heavy Electricals Limited

(A Govt. Of India Undertaking)

CENTRALISED STAMPING UNIT & FABRICATION PLANT

INDUSTRIAL AREA, JAGDISHPUR, DISTRICT- AMETHI (UP)

Phone: 05361-224128, FAX: 05361-224166

TENDER ENQUIRY

**TENDER FOR TILING, STONE & MISCELLEOUS WORKS IN STAFF CANTEEN AT
BHEL JAGDISHPUR**

Tender Enquiry No: BHE/FP/CVL/16-17/06

SECTION-III

BILL OF QUANTITIES & PRICE SCHEDULE

भारत हेवी इलेक्ट्रिकल्स लिमिटेड

(भारत सरकार का उपक्रम)

सेंट्रलाइज्ड स्टेपिंग इकाई एवं फेब्रिकेशन प्लांट

औद्योगिक क्षेत्र जगदीशपुर, जिला- अमेठी (उ०प्र०)-227817



Section-III: BOQ & Price Schedule for Tiling, Stone & Misc Works in Staff Canteen.

TE No: BHE/FP/CVL/16-17/06 Dated: 25.06.2016

| S. No. | Description | Unit | Qty. | Quoted Rate (In Rs.) | | Amount (Rs.) |
|--------|---|------|--------|----------------------|----------|--------------|
| | | | | In Figures | In Words | |
| 1 | Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), including pointing the joints with white cement and matching pigments etc. complete as per direction of engineer-in-charge. With Ceramic Glazed Tiles 1st quality 300 x 300 in all shades designs except White, Ivory, Grey, Fume Red Brown etc. | Sqm | 181.00 | | | |
| 2 | Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete as per direction of engineer-in-charge. With Ceramic Glazed Tiles 1st quality minimum thickness 5mm in all colours shades and designs except burgundy, bottle green, black | Sqm | 100.00 | | | |
| 3 | Marble work gang saw cut (polished and machine cut) of thickness 18 mm for wall lining (vener work), backing filled with a grout of average 12 mm thick in cement mortar 1:3 (1 cement : 3 coarse sand), including pointing with white cement mortar 1:2 (1 white cement : 2 marble dust) with an admixture of pigment to match the marble shade (To be secured to the backing by means of cramps, which shall be paid for separately). 8.1.1 Raj Nagar Plain white marble/ Udaipur green marble/ Zebra black marble Area of slab upto 0.50 sqm. as per direction of engineer-in-charge. With White marble Raj Nagar plain 18 mm thick upto 0.50 sqm area. | Sqm | 60.00 | | | |

Section-III: BOQ & Price Schedule for Tiling, Stone & Misc Works in Staff Canteen.

TE No: BHE/FP/CVL/16-17/06 Dated: 25.06.2016

| S. No. | Description | Unit | Qty. | Quoted Rate (In Rs.) | | Amount (Rs.) |
|---|---|------|--------|----------------------|----------|--------------|
| | | | | In Figures | In Words | |
| 4 | Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer- in-Charge : With Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent. | Sqm | 32.00 | | | |
| 5 | Steel work welded in built up sections/ framed work, including supply of steel, cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required as per direction of engineer-in-charge. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. | Kg | 750.00 | | | |
| Total (Rs.); Excluding of Service Tax= | | | | | | |

Note: Service Tax Shall be paid extra as applicable.

(Signature & Seal of Bidder)