



BHARAT HEAVY ELECTRICALS LIMITED

RAMACHANDRAPURAM:: HYDERABAD::502032
 FACTORY CIVIL & PROJECTS DEPARTMENT
 Phone nos: 040-23185059, 23182376 Fax: 040-23186122
 email Id: suryadevara@bhelhyd.co.in

Tender Notice No.HY/PROJ-EC/ELEC/OT-02/2015-16
 Dt.18.04.2015

SCHEDULE-A

PRICE BID

Name of the work: MISCELLANEOUS LIGHTING WORKS IN PIPE & PLATE YARD					
SCOPE OF WORK:					
(i) Supply of porcelain kit-kat type fuse units etc.					
(ii) Supply of hylam/bakelite insulating sheet etc..					
(iii) Supply of 16 amps terminal junction boxes etc.					
(iv) Assembly and fixing of smart junction box etc.					
Sl.No	Work Description	Unit	Qty	Rate / Unit in Rs.	Total Amount in Rs.
1	Supply of ISI Grade 16A, 240V (50Hz) Porcelain Kit - Kat Type Fuse Units of Anchor / Standard make with ISI Marking on Fuse Unit.	Nos.	175	46.00	8,050.00
2	Supply of Hy-Lam / Bakelite Insulating Sheet of size 10" X 12" of 3 mm Thickness (Minimum) for mounting inside the Street Light Poles.	Nos.	45	57.00	2,565.00
3	Supply of 16 Amps Stud Type Terminal Blocks with Suitable color coded Terminals (Red, Yellow, Blue & Black) on a hard Bakelite Base suitable for terminating 4C X 16 Sq.mm Aluminium Armoured Cables.	Nos.	90	97.00	8,730.00
4	Assembly and fixing of Smart Junction Box for Street Light Poles using suitable No. of Kit Kat Fuses (Depending on no. of fittings per pole), Stud Type Terminal Block on Bakelite / Hy-Lam Sheet. This also includes the cutting of the Bakelite Sheets to a suitable size, fixing of Stud Type Terminal Block on Bakelite Sheet, drilling holes for screws, supply of screws, etc., and fixing the same to the street light using the provision made in the pole.	Nos.	90	97.00	8,730.00
				TOTAL	28,075.00

Total: Rupees Twenty Eight thousand and seventy Five only

- NOTE:**
- 1) The above rates are inclusive of VAT.
 - 2) Service Tax is extra and will be released on submission of valid documentary proof.
 - 3) The Contractor has to submit separate Service tax invoice alongwith RAB (Running Account Bill)
 - 4) The quantities indicated in the schedule are tentative and may increase or decrease or delete.
 - 5) Any other works not mentioned but required for completion of the project are to be carried out by the contractor with mutually agreed rates and vetted by finance.
 - 6) The contractor shall mark with paint on all panels regarding power cables size & FROM/TO destinations.
 - 7) Contractor shall shift the materials from different locations inside the factory to the project site and return back the left over materials after completion of the work to the project stores or as per the instructions of the site engineer.
 - 8) Manpower should be at the description of the site Engineer.

Tenderer's Signature

Issuing authority Signature

- 9)The contractor should follow all the statutory requirements, Environmental Management System (EMS),Occupation Health and Safety Management System (OHSAS) while executing the work.
- 10)Contractor has to ensure neatness of the site by removing unwanted materials/scrap materials.
- 11)Safety : Contractor has to ensure usage of safety shoes, safety helmets, safety belts, safety net & anchoring rope, hand gloves etc. during erection and commissioning for all his personnel.
- 12) Penalty: 0.50 % of the gross value of work will be levied for every week's or part thereof delay by the agency subject to a maximum of 10 % gross value of the work executed after the schedule period of completion.
- 13) Payment Terms: Payment will be based on work % completion/milestone basis.
- 14) The agencies are advised to visit the site to understand the nature of work/quantum of work in its true perspective to avoid any complications.
- 15) The works are to be carried out in accordance with IE rules 1956.

Note:-The bidders are required to quote the tender value on percentage(%) basis at excess or less or on par with estimate value in figures and words.

Tender %	In Figures	In Words
Excess		
Less		
Estimated Value		