

TENDER NO. BHEL/NR/SCT/NIMOO/STORE/562

FOR OFFICIAL USE ONLY  
NOT FOR PUBLICATION

TENDERER'S COPY  
ORIGINAL COPY

## TENDER SPECIFICATION

TENDER NO. BHEL/NR/SCT/NIMOO/STORE/562

FOR

Development and construction of BHEL storage and store shed complex at site for 3x15 MW Nimoo Bazgo Hydro Electric Project site, village Alchi, District Leh, Jammu and Kashmir.

PART II – PRICE BID



भारत हैवी इलेक्ट्रिकल्स लिमिटेड  
**Bharat Heavy Electricals Limited**  
(A Govt. Of India Undertaking)  
Power Sector – Northern Region,  
Plot No. 25, Sector - 16A ,  
Distt. Gautam Budh Nagar, NOIDA – 201 301. INDIA

NMB COMPOSITE BOQn 22 SEP\_SCP

SI No	CODE	DESCRIPTION OF ITEM	UNIT	TOTAL QTY	RATE Rs	AMOUNT Rs
		<b>(A) CIVIL WORKS</b>				
		<b>EARTHWORK/SITE CLEARANCE/ROADWORK</b>				
1	C1	Clearing jungle including uprooting of rank vegetation, grass, brushwood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and disposal of rubbish upto a distance of 200 m outside the periphery of the area cleared	sqm	5050.00		
2	C2	Surfact dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50m and lift upto 1.5m in all kinds of soil.	sqm	5050.00		
3	C3	Earth work in excavation in all types of ordinary and hard soil by mechanical means (Hydraulic excavator)/manual means including stacking the excavated soil, dressing of sides and ramming of bottom, dewatering of accumulated water from any source and keeping the surface dry for subsequent works such as concreting form work etc. and disposal of surplus excavated soil as directed, disposed soil to be neatly levelled and dressed lead upto 50 meters and lift upto 1.5meter complete.	Cu.M	175.00		
4	C4	Back filling available excavated earth in trenches, plinth, slides of foundations etc., including re-excavating the deposited soil excavated earlier, breaking clods, laying at all depths and heights in layers not exceeding 20 cm indepth, consolidating each deposited layer by ramming and watering complete lead upto 50 Metre and lift upto 1.5 Meter	Cu.M	55.00		
5	C5	Disposal of surplus excavated earth and debris including re-excavating the deposited soil earlier, transportation, loading, unloading, laying at all depths and heights, leveling and dressing both the area (viz. From where earth is transported and where it is deposited) to required levels and slopes, complete with all lifts as directed.				
	a)	upto 1 km	Cu.M	110.00		
6	C6	<b>Preparation and consolidation</b> of subgrade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the subgrade and disposal of surplus earth lead upto 50 Mtrs	sqm	500.00		
7	C8	<b>Supply and Laying</b> water bound macadam with specified stone aggregate stone screening and binding material including screening, sorting, spreading to template and consolidation with power road roller of 8 to 10 tonne capacity etc. complete with <b>supply for stone aggregate, screenings, kankar, moorum and red bajri etc.</b>				
	a)	Base course with 63 mm to 45 mm size including stone screening 13.2mm size.	cum	75.00		
8	C10	<b>Providing and tilling</b> of quarry dust as levelling course compacting <b>the same with 8 to 10 ton road roller</b> complete in all respects as directed by Engineer-in Charge	cum	25.00		
9	C11	Supplying the good earth from outside the site including the cost of filling the same within the site in layer not exceeding 20cm in depth & consolidating each deposited layer by ramming and watering including all leads & lifts etc. complete.	cum	132.00		
10	C12	Providing approved quality <b>Yellow/silver sand</b> and filling the same where required under floors etc., watering, ramming, consolidating, grading and finishing to final levels and slopes for all lifts and leads involved, complete as directed (Payment to be made for solid measure of the consolidated filling)	Cu.M	44.00		
		<b>PCC</b>				

NMB COMPOSITE BOQn 22 SEP\_SCP

SI No	CODE	DESCRIPTION OF ITEM	UNIT	TOTAL QTY	RATE Rs	AMOUNT Rs
11	C14	<b>Plain cement concrete</b> of mix 1:4:8 (1 cement : 4 coarse sand and 8, 40 mm down graded stone aggregate) for column footing, levelling, floors etc., including cost of all materials, lead, lift, labour charges, consolidation, shuttering curing etc. complete	Cu. M	98.00		
12	C15	Making plinth protection 50 mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75 mm bed of dry brick ballast 40 mm nominal size well rammed and consolidated and grouted with fine sand including finishing the top smooth	sqm	82.00		
13	C16	Providing and laying and laying <b>damp proof course</b> 40 mm thick with concrete grade 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size <b>and applying a coat of residual petroleum</b> of penetration 80/100 of approved quality using 1.7 kg per sq. metre on damp proof coarse after cleaning the surface with brushes and finally with a piece of cloth lightly soaked in KEROSENE OIL.	Sq m	27.00		
14	C17	Providing and fixing at ground level precast 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)cement cement concrete reinforced with 1.6 mm MS wire in kerbs,RCC sleepers, edgings,drains,etc. as per approved pattern and placed in position wit	cum	3.50		
		<b>RR MASONRY</b>				
15	C18	<b>Random rubble masonry</b> with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 Cement : 6 coarse sand : 12 graded stone aggregate 20mm nominal size) at plinth level with : Cement mortar 1:6 (1 Cement : 6 coarse sand) complete with supply of all materials	Cu. M	68.00		
16	C19	<b>Deleted</b>				
		<b>RCC</b>				
17	C20	<b>Reinforced cement concrete</b> of mix 1:1.5:3 (1 cement, 1.5 coarse sand and ,3 :20 mm down graded aggregate) for column footing, sunshades, shelves, lintels etc. including cost of materials, lead lift, labour charges for concreting, shuttering, curing etc. complete.	Cu. M.	35.00		
18	C21	<b>Centring and shuttering including providing all shuttering material</b> , strutting, propping etc. and removal of form work for : Lintels, beams, plinth beams, girders, bressumers and cantilevers.	sqm	215.00		
19	C22	Providing and placing mild steel/ tor <b>steel reinforcement</b> for RCC work including cost of all materials, labour for cutting, bending, binding and placing in position complete as per drawing and instruction of Engineer.	MT	3.20		
20	C23	Fabricating and fixing in position, M.S.Holding down bolts with sleeves and washers, nuts and lock nuts etc. including threading of required length and type as per instructions of Engineer I/C				
	a)	Upto 20 mm dia. bolt	kg	165.00		
		<b>ROOFING</b>				
21	C24	Supply fabrication and erection of structural steel beams,channels,plates,steel tubular trusses, purlines,gates, wind ties, base plates, gusset plates, bolts, nuts etc. complete as per drawings, specifications & instructions of engineer including cost of all materials leads, lifts labour charges etc. and one coat of primer and two coats of approved enamel paint for finished products at site complete as per technical specification and direction of engineer.				
	a)	Trusses (medium grade pipes),Purlins side ties, bottom ties	MT	6.60		
	b)	structural steel for columns, crane girders,etc	MT	5.50		
	c)	Wind ties (Flats) 50 x 6 mm thick, angles,box sections,soild bars for rails etc	MT	1.00		

NMB COMPOSITE BOQn 22 SEP\_SCP

SI No	CODE	DESCRIPTION OF ITEM	UNIT	TOTAL QTY	RATE Rs	AMOUNT Rs
22	C25	Steel work in built up section/framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel for gates, railings, frames, gratings etc.	kg	650.00		
23	C26	Providing and fixing 1mm thick M.S. sheet sliding-shutters with frame and diagonal braces of 40x40x6mm angle iron, 3mm M.S. gusset plates at the junction and corners 25mm dia pulley, 40x40x6mm angle and T-iron guide at the top and bottom respectively including applying a priming coat of approved steel primer.				
	a)	Manually Operated	Sq.M	50.00		
24	C27	Providing 1 mm thick corrugated G.S. sheet roofing fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto a pitch of 60 degrees) excluding the cost of purlins, rafters and trusses.	Sq.M	1100.00		
25	C28	Providing and fixing <b>corrugated Translucent Plastic sheet</b> roofing fixed with GI J or L hooks bolts and nuts 8mm diameter with bitumen and GI limpet washer complete (upto a pitch of 60 degrees) including steel primer and 2 coats of approved paint at overlaps. as per tech. specification.	Sq.M	60.00		
26	C29	Providing .8 mm thick ridges or hips of width 60 cm over all width plain G.S. sheet fixed with polymer coated J. or L hooks, bolts and nuts 8mm dia G.I. limpet and bitumen washers complete.	RM	40.00		
26a	C31	Providing and fixing at all height false ceiling of 12.5mm thick tapered edge gypsum board conforming to IS : 2095 including providing and fixing of frame work made of special sections power pressed from M.S. sheet and galvanised in accordance with zinc coating 350 as per IS : 277 and consisting of angle cleats of size 25mm wide x 1.6mm thick with flanges of 22mm and 37mm at 1200mm centre to centre one flange fixed to the ceiling with dash fastener 12.5 mm dia x 40mm long with 6 mm dia bolts to the angle hangers of 25x25x.55 mm of reqd. length, and other end of angle hanger being fixed with nut and bolts to G.I. Channels 45x15x0.9 running at the rate of 1200 mm centre to centre to which the ceiling section 0.5 mm thick bottom wedge of 80mm with tapered flanges of				
		each having clips of 10.5mm at 450mm centre to centre shall be fixed in a direction perpendicular to G.I. Channel with connecting clips made out of 2.64mm dia x 230mm long G.I. Wire at every junction including fixing the gypsum board with ceiling section and perimeter channels 0.5mm thick 27mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450mm centre to centre with 25mm long drive-all screws @ 230mm interval including jointing and fixing to a flush finish of tapered and square edges of the gypsum board with recommended filler, paper tapes, finisher and two coats of primer suitable for gypsum board as per manufacturers specification and also including the coat of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed all complete as per drawing and specification and direction of the Engineer -in-charge but excluding the cost of painting.	sqm	25.00		
		<b>FINISHING</b>				
27	C32	50 mm thk. Ironic Topping Cement Concrete flooring consisting (1-admixture:2-stone aggregate 6mm nominal size) by volume <b>with metallic hardening compound</b> of approved quality is mixed in the ratio(4:1) (4 cement : 1 metallic floor) hardening compound of approved quality by weight including cement slurry rounding off edges and strips etc. but excluding the cost of nose of steps etc. complete.	Sq. M	480.00		
28	C33	Providing and fixing glass strips in joints of terrazo / cement concrete floors 40mm wide and 4mm thick	RM	200.00		

NMB COMPOSITE BOQn 22 SEP\_SCP

SI No	CODE	DESCRIPTION OF ITEM	UNIT	TOTAL QTY	RATE Rs	AMOUNT Rs
29	C38	<b>Plastering work</b> with cement mortar <b>1:6</b> (1 cement : 6 fine sand) 12 mm thick after scrapping and cleaning the masoary joints including scaffolding, cost of materials, labour, mixing , leads & lifts, curing etc. complete.	Sq. M	235.00		
30	C39	<b>Plastering work</b> with cement mortar <b>1:6</b> (1 cement : 6 fine sand) 15 mm thick after scrapping and cleaning the masoary joints including scaffolding, cost of materials, labour, mixing , leads & lifts, curing etc. complete.	Sq. M	245.00		
31	C46	Providing and fixing ISI marked flush door shutters non decorative type , core of block baord construction with frame of ist class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters 30 mm thick including ISI marked stainless steel butt hinges, handle,bolts, complete with necessary screws and other accessories	Sq. M	6.00		
32	C49	Providing three coats of <b>white wash</b> to give a smooth and even shade including cost of materials, cleaning and preparation of surface, scaffolding etc. complete.	sqm	120.00		
32a	C51	Distempering with <b>Oil bound washable distember</b> of approved brand and manufacture and of required shade to give an even shade on new wall ( 2 or more coats) over and including priming coat with cement primer.	sq.M	122.00		
33	C50	Finishing walls/ surfaces with <b>water proofing cement paint</b> of approved brand and manufacture and of required shade to give an even shade.	sq.M	150.00		
34	C52	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade in two or more coats on new work	sqm	10.00		
		<b>SANITARY/SEWAGE</b>				
35	S1	Providing and fixing <b>white vitreous china water closet squatting pan (Indian type / Oriss pattern WC pan)</b> size 580 x 440 mm with 100 mm sand cast iron P trap, 12.5 Lit. low level PVC flushing clastern with fittings RS or CI brackets 32 mm dia meter galvanised iron flush pipe with fitting and clamps 20 mm GI over flow pipe with special and mosquito proof coupling of approved design and GI chain and pull complete including painting of clastern and fittings, cutting and making good the walls and floors where required.	No.	1.00		
36	S2	Providing and fixing <b>white vitreous china pedestal type water closet (European type W.C. pan)</b> with seat and lid, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever), conforming to IS : 7231, Parryware/Hindware/Seabrid /Orient (Coral) with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : <b>W.C. pan with ISI marked white solid plastic seat and lid</b>	No.	1.00		
37	S3	Providing & fixing flat back <b>white vitreous china wash basin</b> 550 x 400 mm size with single 15 mm C.P.brass pillar with R.S. or C.I. brackets painted white 15 cm C.P. brass pillar taps C.P. brass chain with rubber plug, 32 mm dia CP Brass trap and M.I. unions, C.P. waste, C.P. connection, soap dish , waste pipe complete including cutting and making good the walls wherever required under counter complete in all respects	No.	2.00		
38	S7	Providing and fixing 100 mm sand cast iron gratingfor gully, floor or Nahanitrap.	each	2.00		
39	S8	Providing and fixing bevelled edge mirror of superior glass (of approved quality) complete lwith 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	sqm	0.50		
40	S9	Providing and fixing 600x120x5mm glass shelf with edges round of supported on anodised aluminium angle frame with C.P brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc. complete	each	1.00		
41	S10	Providng and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fitting arangement of approved quality colour and make (Prayag or equivalent).				

NMB COMPOSITE BOQn 22 SEP\_SCP

SI No	CODE	DESCRIPTION OF ITEM	UNIT	TOTAL QTY	RATE Rs	AMOUNT Rs
	a)	450mm long towel rail with total length of 495mm, 78mm wide and effective height of 88mm, weighing not less than 170gms.	each	1.00		
42	S12	Providing and fixing PTMT liquid soap container 109mm wide, 125mm high and 112mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality colour and make, weighing not less than 105gms (Prayag or equivalent)	each	1.00		
43	S13	Providing, laying and jointing <b>glazed stone ware pipes</b> grade A with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc., complete 100 mm dia pipe.	RM	10.00		
44	S14	Providing, laying, fitting and jointing <b>medium grade GI pipes</b> , conforming to IS 1239 for water lines at various elevations with all fittings stop cock, valve bends, elbows, tees, reducers., etc. making grooves in the brick wall, etc. (Internal work), trenching, refilling etc. (external work) including cost of all materials, labour charges etc. complete as per specifications and drawings				
	(a)	25 mm dia G.I. Pipe (External work)	RM	20.00		
	(b)	20 mm dia G.I. Pipe (Internal work)	RM	10.00		
	(c)	15 mm dia G.I. Pipe (Internal work)	RM	10.00		
45	S15	Providing and fixing <b>GM full way valve</b> with C.I wheel of approved quality etc. complete.				
	(a)	25 mm nominal bore	No.	1.00		
46	S16	Providing and fixing C.P. <b>brass 15 mm stop cock</b> of approved quality of weight not less than 250 gms.	NO	1.00		
47	S17	Providing and fixing C.P. <b>brass 15 mm bib cock</b> of approved quality of weight not less than 250 gms.	No.	1.00		
48	S19	Construction of 2.0x0.90x1.60 size <b>Septic tank</b> in all types of soil with 250 mm thick brick masonry in cement Mortar of 1:6 15 cm thick cement concrete 1:4:8 grade in bed, 75 mm thick 1:2:4 grade cement concrete flooring and 100 mm thick over RCC slab of 1:2:4 grade, 75 mm thick partition wall, 15 mm thick plaster on brick wall finished with neat cement providing M.S. rugs etc., complete as per drawing including excavation, disposal of surplus earth with a load of 50 Mtr. item includes all material, labour, leads, lifts etc., complete but excluding C.I	NO.	1.00		
49	S20	Providing and fixing <b>square mouth stone ware gully trap</b> grade'A' conforming to IS:651 complete with G.I. Grating, brick masonry chamber with bricks of class designation '50' and water tight C.I. Cover with frame of 300 x 300 mm size (inside), the weight of cover to be not less than 4.5 kgs and frame to be not less than 2.70 kg as per specification. 100x100 MM P TYPE	NO.	1.00		
50	S22	Construction <b>soak pit</b> of 2.5Mtr dia and 3 Mtr depth filled with brick bats including S.W. drain pipe 100 mm dia and 1.2 meter long complete as per standard design.	NO.	1.00		
51	S23	Providing and laying soil, waste and vent pipes, centrifugally cast (spun) iron S&S pipes				
	a)	100mm	RM	10.00		
	b)	125 mm	RM	10.00		
52	S24	Supplying and installation of HDPE cylindrical and vertical <b>water tank</b> with closed top of SINTEX or approved equivalent of undermentioned capacity with all necessary fittings including supplying and fixing input and out outlets including support of brick pillars of height of 3 Mtrs each complete				
	a)	500 Ltr. Capacity tank	per litre	500.00		

NMB COMPOSITE BOQn 22 SEP\_SCP

SI No	CODE	DESCRIPTION OF ITEM	UNIT	TOTAL QTY	RATE Rs	AMOUNT Rs
53	S25	Providing and Laying of non-Pressure NP2 class ( light duty ) RCC Pipe with collar of 250 mm dia jointed with stiff mixture of cement motar in proportion of 1:2 ( 1 cement :2 fine sand )including testing of joints etc complete	RM	10.00		
54	S26	Construction of brick masonry road gully chamber 50 cm x 45 cm x 60 cm with MPS Brick of class 75 kg in cement motar ( 1 cement : 6 fine sand) including 500 , 450 mm RCC precast horisontal with frame completed as per standard specification	EACH	1.00		
		<b>FENCING</b>				
55	F1	2.4 m high fencing with 3 m angle iron 50 x 50x 6 mm posts placed every 3 m centre to centre embedded in cement concrete block, every 15th post last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with 12 horizontal lines and two diagonals inter woven with horizontalwires of barbed wire 9.38 Kg per 100 m (min) between the two posts and fixed with GI stapies, turn buckles etc. complete. including providing and laying earth work and concrete (1:3:6)				
		With G.I. Barbed wire (Payment to be made for per metre of complete fencing)	Metre	300.00		
56	F2	Supplying at site Angle iron post & strut of required size including bottom to be split and bent at right angle in opposite directionfor 10 cm length and drilling holes upto 10 mm dia. Etc. complete including a priming coat and two coats of enamel paint	kg	2000.00		
		<b>(B) ELECTRICAL WORKS</b>				
57	E1	Providing and fixing 1 x 40 Watt Batten type <b>flourescent tube fitting</b> (Crompton / Philips / Bajaj make),fabricated from CRCA sheet steel and finished with stove enamel paint complete with Accessories like flourescent lamp,copper wound polyster choke, starter, seat, rotor holder and terminal block duly pre-wired with copper conductor, including connections, fixing on wall, false ceiling or under roof tusties with clamps as required	Nos.	17.00		
58	E2	Providing and fixing 2 x 40 Decorative type <b>flourescent tube fitting</b> (Crompton / Philips / Bajaj make),fabricated from CRCA sheet steel and finished with stove enamel paint complete with Accessories like flourescent lamp,copper wound polyster choke, starter, seat, rotor holder and terminal block duly pre-wired with copper conductor, including connections, fixing on wall, false ceiling or under roof tusties with clamps as required	Nos.	2.00		
59	E4	Providing and fixing 1 x 250 W HPSV out door type fittings (Crompton / Philips/BajaJ , complete with lamp, ballast control gear box, fixing clamp etc.	Nos.	4.00		
60	E5	Providing and fixing of following sweep <b>exhaust fan/ceiling fan/wall mounted fan</b> (Khaitan / Crompton make) single phase alongwith gravity louvers, frame / tripod for holding the motor including making necessary opening in wall, supply & fixing of assembly with grouting bolts, making connections, loop earthing etc.				
	a)	230 mm sweep	Nos.	1.00		
	b)	300 mm sweep	Nos.	1.00		
61	E8	Providing & fixing of 240 V, 5 / 15 Amp 6 <b>Pin Power socket</b> outlet point (with 15 A switch ). Switch / socket to be fitted in suitable size 20 SWG metal type box with 3mm sunmica sheet	Nos.	4.00		
62	E9	Providing & fixing of 240 V, 5A 3 <b>Pin Power socket</b> outlet point (with switch ). Switch / socket to be fitted in suitable size 20 SWG metal type box with 3mm sunmica sheet along with the piano switches and fan regulator	Nos.	2.00		

NMB COMPOSITE BOQn 22 SEP\_SCP

SI No	CODE	DESCRIPTION OF ITEM	UNIT	TOTAL QTY	RATE Rs	AMOUNT Rs
63	E14	Providing & fixing of 240 V, 20 Amp INDUSTRIAL <b>Power socket</b> outlet point (with 20 A MCB ). Switch / socket to be fitted in suitable size 20 SWG metal type box .	Nos.	2.00		
64	E15	<b>Wiring</b> of above <b>power sockets</b> with 4 Sq. mm PVC insulated Copper Conductor wires as per IS, 650 / 1100 V grade including 20 SWG GI earthing wire in PVC medium grade conduit including supply of items.				
	a)	Length per point upto 20 m	Points	1.00		
	b)	Length per point upto 30 m	Points	1.00		
65	E20	<b>Wiring</b> of the following points (including supply of Wires, conduits, clamps, boards, other misc. items) with 2.5 sq.mm colour coated PVC insulated copper conductor wires as per IS- 650/1100 volts grade in surface PVC conduits (medium grade) including laying of 20 SWG GI wire, conduit fitting. ( Fixing of piano type control switches (Anchor make) in suitable sized 20 SWG metal box with 3 mm sunmica sheet having provision for fan regulator, 5 Amp switch socket ( supplied above ) included in scope )				
	a)	Long Point ( Panel to Switch Box)	Points	10.00		
	b)	Medium Point ( Switch Box - first Point / Socket)	Points	10.00		
	c)	Short Point ( among points )	Points	10.00		
	d)	Wiring for exhaust fan.	Points	2.00		
	e)	1 x 250 W HPSV out door type fitting. One number 10 A DP switch to be used for controlling 2 fittings. D.P Switches to be fixed on outside of the store shed wall	Points	4.00		
66	E21	Providing and fixing of <b>32 Amp TPN with HRC fuses</b> along with earth wire. The TPN to be provided on one side of the shed with rain protection cover.	Nos.	1.00		
67	E22	Supply and burying of <b>earths electrods</b> 40mm dia 3 mtrs. Long including earthing upto switch board with 8 SWG GI wire.	Nos.	1.00		
68	E23	Providing , Installation and commissioning of 18 W Lighting Panel with 18 nos 16 A MCB with 63 A SFU incomer in Sheet metal housing with double door arrangement , including all earthing and statutory requirements .	Nos.	1.00		
69	E24	Supplying and laying of following type of PVC Insulated, PVC armoured standard <b>aluminium conductor cable</b> conforming to IS:1554-1976 (part 1), glanding with single compression gland, termination of both end in DB & SFU. The cable has to be laid underground on sand cushion including backfilling, suitable clamp, clamping on surface including all materials etc. complete.(Only cable will be issued by BHEL as free issue item and all other materials are to be provided by the contractor).This includes road crossing for which suitable GI Pipe to be provided by the contractor.				
	a)	3 1/2 Core x 50 / 95 Sq.mm armoured cable	RM	200.00		
	b)	2c/3c/4c upto 16 sq.mm armoured cable	RM	200.00		
70	E26	Earthing Flat 30 x 6 for Earthing	RM	20.00		
		<b>TOTAL</b>				

NOTES:

1. Incomplete offer received may not be considered for the subject work.

NMB COMPOSITE BOQn 22 SEP\_SCP

Sl No	CODE	DESCRIPTION OF ITEM	UNIT	TOTAL QTY	RATE Rs	AMOUNT Rs
-------	------	---------------------	------	-----------	---------	-----------

2. The Rate shall be entered in figures as well as in words. In case of difference in rates between words and figures THE LESSER OF THE TWO will be treated as valid rate.
3. In case of omission in quoting any rate, the evaluation will be done considering the highest quoted rate obtained against that item but the work , if awarded, will be on the lowest quoted rate obtained against that item.
4. Optional item/rates shall not be considered for evaluation purpose.