

Sub: Providing and fixing Aluminium Sliding Windows at EMRP's Tilak Nagar Township.					
PRICE SCHEDULE					
Sr. No.	Item Description	Unit	Qty	Unit Rate (In Rs.)	Amount (In Rs.)
1	2	3	4	5	6 (4X5)
1	Dismantling of existing aluminium sliding window at all height complete with shutters and frame by using appropriate tools & tackles and stacking of dismantled material at designated place inside the campus as directed by Engineer In-charge.	Sqft	1025		
2	Providing and fixing Sliding Aluminium windows at all height consisting of 3 glass shutter and 2 Mosquito Jali shutter by using suitable track system and anodised aluminium section (Jindal or equivalent make) having minimum 15 micron thickness of anodising of approved colour. The sectional thickness for outer frame and shutter should be between 1.20 mm to 1.30 mm. However, the shutter section shall not be less than 40 mm x 18 mm size. Entire fabrication is to be done by using appropriate mechanical device for ensuring smooth and neat & flush joints and fixing with suitable rawl plugs and CP/SS screws along with 5 mm thick tinted glass panes (Saint Gobian or equivalent Make) and necessary EPDM gaskets, automatic flush type lock, nylon rollers, nylon net and other hardwares etc. of good quality (duly approved) complete as directed.	Sqft	675		
3	Providing and fixing Sliding Aluminium windows at all height consisting of 2 glass shutter and 1 Mosquito Jali shutter by using suitable track system and anodised aluminium section (Jindal or equivalent make) having minimum 15 micron thickness of anodising of approved colour. The sectional thickness for outer frame and shutter should be between 1.20 mm to 1.30 mm. However, the shutter section shall not be less than 40 mm x 18 mm size. Entire fabrication is to be done by using appropriate mechanical device for ensuring smooth and neat & flush joints and fixing with suitable rawl plugs and CP/SS screws along with 5 mm thick tinted glass panes (Saint Gobian or equivalent Make) and necessary EPDM gaskets, automatic flush type lock, nylon rollers, nylon net and other hardwares etc. of good quality (duly approved) complete as directed.	Sqft	350		
4	Replacment of Cuddapa Stone in over and around windows of required size and shape in cement mortar 1:4 complete as per direction of BHEL including dismantling of existing surface and depositing dismantled material at a designated place inside the campus with all leads and lifts.	Rft	150		
Total					

Note The price is to be quoted inclusive of all taxes and duties except service tax.